# **Appendix 6**

Noise Model Worksheets

# **Curtis School Project**

# **Noise Calculation Worksheets**

Provided by Acoustical Engineering Services

# **Ambient Noise Measurements**



Location: R1 Date: 2/27/2020

Time Overload	Leq	Lmax	L10	L90	
9:47:27 AM No	53.1	64.3	56.8	48	
9:48:27 AM No	48.4	55.7	49.7	46.5	
9:49:27 AM No	47.3	49.3	48.4	46.3	
9:50:27 AM No	47.5	49.2	48.2	46.6	
9:51:27 AM No	48	52.3	49.3	46.3	
9:52:27 AM No	52.1	58.6	56.4	47.9	
9:53:27 AM No	53.2	58.5	56.7	48.5	
9:54:27 AM No	53	58	56.5	48.4	
9:55:27 AM No	52.5	59	56.3	48.4	
9:56:27 AM No	51.6	56.7	54.9	48.5	
9:57:27 AM No	50.1	55.1	52.9	47.6	
9:58:27 AM No	47	50.6	47.7	46.1	
9:59:27 AM No	51	58.2	53.9	46.7	
10:00:27 AM No	61.5	67	65.9	52	
10:01:27 AM No	52.2	56.6	55	48.3	
	F2 2				

53.3



Location: R2 Date: 2/27/2020

Time Overload	Leq	Lmax	L10	L90	
10:15:17 AM No	65.9	73	69.3	55.5	
10:16:17 AM No	63.6	71	67.6	46.9	
10:17:17 AM No	64.3	72.2	68.8	50.4	
10:18:17 AM No	65.6	75.4	67.8	56.1	
10:19:17 AM No	61.7	69	67.2	50.5	
10:20:17 AM No	64.8	71.2	69	49.8	
10:21:17 AM No	67.1	79.9	69.1	56.9	
10:22:17 AM No	65.2	72	68.8	54.1	
10:23:17 AM No	64.2	71.6	68.5	51.4	
10:24:17 AM No	63.1	68.7	66.8	54.2	
10:25:17 AM No	63.9	72	68.2	49.9	
10:26:17 AM No	63.5	70.4	67.4	48.5	
10:27:17 AM No	62.7	73.8	67.8	43.4	
10:28:17 AM No	63.9	69.8	67.8	55.3	
10:29:17 AM No	62.2	71.7	66.1	50.2	
	64.2				

64.3



Location: R3 Date: 2/27/2020

Time Overload	Leq	Lmax	L10	L90	
10:49:41 AM No	67.2	72.5	70.7	61.9	
10:50:41 AM No	69	74.5	71.1	66.2	
10:51:41 AM No	67	73	70	63.9	
10:52:41 AM No	65.4	71.4	68.6	62.6	
10:53:41 AM No	67.2	73.9	70.2	62.8	
10:54:41 AM No	64.7	70.7	67.2	61.7	
10:55:41 AM No	68.4	74.6	71.2	63.8	
10:56:41 AM No	66.8	71.1	68.9	64	
10:57:41 AM No	67.3	71.3	69.9	61.7	
10:58:41 AM No	68.3	77.2	71.4	62.1	
10:59:41 AM No	68.4	75.3	72.2	62.5	
11:00:41 AM No	67	73.9	69.1	63.5	
11:01:41 AM No	67.3	74.9	69.9	63.1	
11:02:41 AM No	66.8	75.6	69.7	60.6	
11:03:41 AM No	68.7	73.4	71.2	62.9	
	67.5				



Location:	Project Site - Future Building Location
Date:	2/27/2020

Time Overload	Leq	Lmax	L10	L90	
9:24:59 AM No	61.2	67.5	65.2	55	
9:25:59 AM No	55.1	56.3	55.7	54.5	
9:26:59 AM No	55.8	62	56.9	53.9	
9:27:59 AM No	55	58.9	56	54.3	
9:28:59 AM No	54.8	57.1	56.3	53.2	
9:29:59 AM No	54.8	56.3	55.9	54.1	
9:30:59 AM No	55.2	59.1	56.2	54.4	
9:31:59 AM No	56.5	60	58.9	54.5	
9:32:59 AM No	54.8	55.9	55.5	53.8	
9:33:59 AM No	54.5	56.5	55.5	53	
9:34:59 AM No	55.1	55.9	55.6	54.5	
9:35:59 AM No	54.1	55.7	54.9	52.9	
9:36:59 AM No	54.1	58.4	54.8	53.4	
9:37:59 AM No	55.1	55.9	55.6	54.4	
9:38:59 AM No	54.6	56	55.2	54	

55.9

# **Construction Noise Calculations**



Construction Phase: Phase 1 (Arts Building)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	325	15
	1				
Receptor:	R1				
Results:	1-hour Leq:	54.7			



## Construction Phase: Phase 2a (Additional Classroom)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	750	15
	1				
Receptor:	R1				
Results:	1-hour Leq:	47.5			



## Construction Phase: Phase 2b (New Classroom Building and Science Building)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	900	15
Receptor:	1 <b>R1</b>				
Results: 1	-hour Leq:	45.9			



# Construction Phase: *Phase 2c (Swapping Field and Parking Lot)*

## Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	650	15
Receptor:	1 <b>R1</b>				
Results: 1	-hour Leq:	48.7			



## Construction Phase: Phase 2d (Gymnasium and Athletic Buildings)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	1000	15
	1				
Receptor:	R1				
Results:	1-hour Leq:	45.0			



# Construction Phase: Phase 23 (Pavilion Back of House, Dining, and Library)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	350	15
	1				
Receptor:	R1				
Results:	1-hour Leq:	54.1			



Construction Phase: Phase 1 (Arts Building)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	1400	15
Receptor:	1 <b>R2</b>				
Results:	1-hour Leq:	42.1			



## Construction Phase: Phase 2a (Additional Classroom)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	950	15
Receptor:	1 <b>R2</b>				
-					
Results:	1-hour Leq:	45.4			



## Construction Phase: Phase 2b (New Classroom Building and Science Building)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	725	15
Receptor:	1 <b>R2</b>				
Results:	1-hour Leq:	47.8			



# Construction Phase: *Phase 2c (Swapping Field and Parking Lot)*

## Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	450	15
Receptor:	1 <b>R2</b>				
Results:	1-hour Leq:	51.9			



## Construction Phase: Phase 2d (Gymnasium and Athletic Buildings)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	550	15
Receptor:	1 <b>R2</b>				
Results:	1-hour Leq:	50.2			



# Construction Phase: Phase 23 (Pavilion Back of House, Dining, and Library)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	1350	15
Receptor:	1 <b>R2</b>				
Results:	1-hour Leq:	42.4			



Construction Phase: Phase 1 (Arts Building)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	930	15
	1				
Receptor:	<b>R</b> 3				
Results:	1-hour Leq:	45.6			



## Construction Phase: Phase 2a (Additional Classroom)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	1050	15
	1				
Receptor:	<b>R</b> 3				
Results:					
	1-hour Leq:	44.6			



## Construction Phase: Phase 2b (New Classroom Building and Science Building)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	800	15
Receptor:	1 <b>R3</b>				
Results: 1	-hour Leq:	46.9			



# Construction Phase: *Phase 2c (Swapping Field and Parking Lot)*

## Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	275	15
	1				
Receptor:	R3				
Results:	1-hour Leq:	56.2			



## Construction Phase: Phase 2d (Gymnasium and Athletic Buildings)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	675	15
	1				
Receptor:	R3				
Results:	1-hour Leq:	48.4			



# Construction Phase: Phase 23 (Pavilion Back of House, Dining, and Library)

#### Equipment

Description	No. of Equip.	Reference Noise Level at 50ft, Leq	Acoustical Usage Factor	Distance to Receptor, ft	Estimated Noise Shielding, dBA
Peak Construction	1	86	100%	925	15
	1				
Receptor:	R3				
Results:	1-hour Leq:	45.7			

INPUT: ROADWAYS									Curtis	s School			
Eyestone Environmental						2 Septen	ıber	2021					
Sean Bui						TNM 2.5							
INPUT: ROADWAYS									Average	pavement typ	e shall be ι	used unles	S
PROJECT/CONTRACT:	Curtis So	hool							a State h	ighway agend	y substant	iates the us	se
RUN:	Peak Cor	nstruction							of a different type with the approval of FHWA				
Roadway		Points											
Name	Width	Name	No.	Coor	dinates	(paveme	nt)		Flow Cor	ntrol		Segment	
				Х		Y		Z	Control	Speed	Percent	Pvmt	On
									Device	Constraint	Vehicles	Туре	Struct?
											Affected		
	ft			ft		ft		ft		mph	%		
Haul Route	12.0	point1		1	0.0		0.0	0.00	Signal	0.00	100	Average	1
		point2		2	1,000.0		0.0	0.00					

INPUT: TRAFFIC FOR LAeq1h Volumes						Cı	urtis Scho	loc				
Eyestone Environmental				2 Sept	tember 20	021						
Sean Bui	TNM 2.5											
INPUT: TRAFFIC FOR LAeq1h Volumes												
PROJECT/CONTRACT:	Curtis Scho	loo	1	1	1							
RUN:	Peak Const	truction										
Roadway	Points		_									
Name	Name	No.	Segmer	nt								
			Autos		MTruck	S	HTrucks	HTrucks			Motorcy	cles
			V	S	V	S	V	S	V	S	V	S
			veh/hr	mph	veh/hr	mph	veh/hr	mph	veh/hr	mph	veh/hr	mph
Haul Route	point1		I C	) C	0 0	0	0 20	35	0	0	C	0 0
	point2		2									

INPUT: RECEIVERS								(	Curtis Scho	ool		
Eyestone Environmental							2 Septem	ber 2021				
Sean Bui							TNM 2.5					
INPUT: RECEIVERS												
PROJECT/CONTRACT:	Curtis	Schoo	bl									
RUN:	Peak (	Peak Construction										
Receiver												
Name	No.	#DUs	Coordinates	(ground)			Height	Input Sou	nd Levels a	and Criter	ia	Active
			X	Υ	Ζ		above	Existing	Impact Cr	iteria	NR	in
							Ground	LAeq1h	LAeq1h	Sub'l	Goal	Calc.
			ft	ft	ft		ft				dB	
			n		IL		IL	dBA	dBA	dB	uD	
Along Haul Route	11	1	500.0	65.0	)	0.00	4.92	0.00	66	10.	0 8.	0 Y

RESULTS: SOUND LEVELS							C	urtis Scho	ool				
Eyestone Environmental								2 Septem	ber 2021				
Sean Bui								TNM 2.5					
								Calculate	d with TN	M 2.5			
RESULTS: SOUND LEVELS													
PROJECT/CONTRACT:		Curtis S	School										
RUN:		Peak C	onstructio	n									
BARRIER DESIGN:		INPUT	HEIGHTS						Average	pavement type	e shall be use	d unless	
									a State h	ighway agenc	y substantiate	es the use	
ATMOSPHERICS:		68 deg	F, 50% RH	1						rent type with			
Receiver													
Name	No.	#DUs	Existing	No Barrier						With Barrier			
			LAeq1h	LAeq1h			Increase over	existing	Туре	Calculated	Noise Reduc	ction	
		1		Calculated	Crit'n		Calculated	Crit'n	Impact	LAeq1h	Calculated	Goal	Calculated
								Sub'l Inc					minus
												1	Goal
			dBA	dBA	dBA		dB	dB		dBA	dB	dB	dB
Along Haul Route	11	1 1	0.0	0 61.7	7	66	61.7	1(	)	61.7	0.0	)	8 -8.
Dwelling Units		# DUs	Noise Re	duction									
			Min	Avg	Max								
			dB	dB	dB								
All Selected		1	0.0	0.0	)	0.0							
All Impacted		0	0.0	0.0	)	0.0	)						
All that meet NR Goal		0	0.0	0.0	)	0.0							