Appendix K
Water Availability and Sewer Area Study



March 11, 2019

City of Santa Clarita Attention: Hai Nguyen 23920 Valencia Boulevard, Suite 302 Santa Clarita, CA 91355

Re: Water Availability Letter for Sand Canyon Resort, MC#18-021, Assessor's Parcel Number 2840-022-025

Gentlemen:

The above-referenced **Sand Canyon Resort** ("Development") is within the service area of Santa Clarita Valley Water Agency ("Agency"). The Development consists of a 250-room hotel with an additional 70 villas as well as a spa, banquet facilities, restaurants and other amenities. The Agency is prepared to provide safe and reliable water service to the Development subject to the following terms, conditions and reservations:

- 1. Developer shall submit to Agency a set of construction improvement plans and fire department requirements for the Development. This will enable Agency to the determine distribution system and other water facilities required for the Development in accordance with Agency rules. The Development may require the installation of a reservoir, water mains, services or other appurtenances, or may require improvements to the existing source of supply, which improvements shall be the responsibility of Developer. Fire flow requirements shall be determined by the regulatory agency with applicable jurisdiction (e.g., Los Angeles County Fire Department). The size and scope of any facilities required to deliver adequate fire flow will be determined by the Agency.
- 2. Developer shall grant Agency all easements and, if necessary, sites for facilities required for water service to the Development, together with a policy of title insurance acceptable to the Agency, guaranteeing Agency's title to and interest in such easements. Developer will be responsible for all fees and charges associated with preparation and recordation of the easements.
- 3. Pursuant to the requirements of the Agency, Developer shall pay all required fees and charges, including any required deposit amounts, in order to develop planning documents, prepare or process plans and designs, and to complete construction of on-site and off-site improvements required for water service to the Development.
- 4. Developer shall comply with all of the Agency's rules and regulations governing water service and development in force at the time water service is requested, as those rules may be amended from time to time. Developer acknowledges that all water service

pursuant to this letter and to the Development shall be in accordance with Agency rules and regulations.

- 5. The provision of water service to the Development is conditioned upon the Developer meeting all requirements of any other governmental entity having jurisdiction over the Development.
- 6. Developer acknowledges and agrees that this letter is limited and exclusive to the Development and the number of units or lots described above and may not be transferred or assigned to any other person, firm or entity, or for any other purpose without the Agency's written consent.
- 7. Developer acknowledges and agrees that this letter in no way alters the settlement agreement between the prior owner, Robinson Ranch Golf, LLC and the former Castaic Lake Water Agency agreed upon on July 23, 2003.
- 8. Agency can provide safe and reliable water service to Development, and fully expects to be able to continue providing safe and reliable water service into the future. In relying upon this letter and Agency's ability to provide water service to the Development, Developer is aware of the restrictions and limitations contained in this letter and the reliance of Agency upon its wells and imported water supplied by the State Water Project to supply the water needed for domestic water purposes, both of which are subject to restriction.
- 9. At any time prior to connection to the existing water system, and upon a finding by the Board of Directors of the Agency that it is unable to serve the Development for reasons beyond Agency's control, this letter may be revoked by the Agency.
- 10. Water supply availability is further conditioned expressly upon the Development being located within the boundaries of the Agency, and to the extent necessary, effective completion of the annexation of the Development, or any portion thereof, which is not now within the boundaries of the Agency.
- 11. By issuing this letter, the Agency does not guarantee any specific quantities or quality of water, pressures or flows with respect to water service provided by the Agency.
- 12. Developer, for itself and on behalf of its successors, agrees to defend at Developer's expense, any action brought against Agency, its agents, officers or employees because of the issuance of this letter or any approvals or authorizations obtained in connection with the Development, or in the alternative, to relinquish any such approvals or authorizations. Developer shall reimburse Agency for any costs, fees or expenses Agency may incur as a result of any such legal action. Further, Developer agrees that in conducting the defense of such action, the Agency shall be entitled to engage its own attorneys, the entire expense of which shall be paid by Developer.

13. This letter and any representations or assurances made herein, shall expire and be null and void twenty-four (24) months from the date hereof if water service has not been installed to the Development. The Developer and the Development shall not be entitled to any individual water service connections not installed prior to expiration of this letter.

Very truly yours,

Santa Clarita Valley Water Agency

Dirk Marks

Director of Water Resources

Dut Marks

Sewer Area Study for Sand Canyon Country Club

County of Los Angeles

Hunsaker Project No: 0261-001-001 Revised September 28, 2018

Prepared for:

Sand Canyon Country Club 27734 Sand Canyon Road Santa Clarita, California 91387

Prepared by:



Hunsaker and Associates, LA Inc.

26074 Avenue Hall, Suite 23 Valencia, CA 91355

Telephone: (661) 294-2211 Fax: (661) 294-9890

Under the supervision of:

TABLE OF CONTENTS

1.	INTRODUCTION	Page 1
2.	PROJECT LAND USE STATISTICS	1
3.	METHODOLOGY	2
4.	CONCLUSIONS & RECOMMENDATIONS	3-4
5.	APPENDICES	
	A. Sewer Maps	

Existing Sewer Area Study Proposed Sewer Area Study Offsite Sewer Area Study

- B. FlowMaster output
- C. Reference plans/reports
 - 1. LACDPW As built PC 98-13 TR 52004
 - 2. VTTM 78248 Hunsaker & Associtates January 2018
 - 3. Santa Clarita Department of Public Works Area Study Zoning Coefficients
 - 4. Mancara (TTM063022) Sewer Area Study
 - 5. Flow Test Result
 - 6. Bonding Estimate

1. INTRODUCTION

The purpose of this report is to provide the summary of onsite sewer flow for the proposed Sand Canyon Resort (VTTM 78248) development. Offsite flows are incorporated with this report to demonstrate routing of sewer system.

The proposed project is located at the northeast corner of Sand Canyon Road and Robinson Ranch Road in the Sand Canyon area in the City of Santa Clarita. The project consists of approximately 75 acres of proposed development and open space areas. Surrounding properties are zoned UR1, NU4, NU5, OS; rural development is present.

2. PROJECT LAND USE

The proposed Sand Canyon Resort in VTTM 78248 includes resort, low density residential, industrial commercial and open space land uses. Only areas that contribute towards sewage generation were included in the sewer area study analysis.

3. METHODOLOGY

The proposed project was divided into 7 subareas that drain into existing 8" VCP per PC 98-13 in the Robinson Ranch Road. And there were 3 subareas that also drain into existing 8" VCP.

Sewer discharge rates were computed as a product of the zoning coefficients and the land use data. Land use data was compiled based on an area calculation of each tributary area for resort, low density residential and industrial commercial areas. The sewer generation factors were based upon the City of Santa Clarity zoning coefficients for private contract sewer projects. Pipe capacity analysis was calculated using Kutter's formula.

A summary table describing the land use data with its corresponding sewage discharge can be found in the Appendix in Table 1 and Table 2.

Land Use	Sewer Generation Coefficient (cfs/ac)
Residential Estate	0.00075
Residential Low Density	0.0015
Visitor Serving/Resort	0.021
Industrial Commercial	0.021

Table 1: Sewage Generation Coefficients

Sub-area	Land Use	Area (ac)	Coeff/AC	Q (cfs)
		Ai ea (ac)		` '
E1	Residential Low Density	50.5	0.0015	0.076
E2	Visitor Serving/Resort	6.3	0.021	0.132
A1	Visitor Serving/Resort	3.1	0.021	0.065
B1	Residential Low Density	3.8	0.0015	0.006
B2	Residential Low Density	1.6	0.0015	0.002
В3	Residential Low Density	2.3	0.0015	0.003
B4	Residential Low Density	1.5	0.0015	0.002
E3	Industrial Commercial	1.1	0.021	0.023
D1	Residential Estate	1.6	0.00075	0.001
D2	Residential Estate	1.9	0.00075	0.001

Table 2: Sewage Generation Calculation

4. CONCLUSIONS AND RECOMMENDATIONS

The proposed Sand Canyon Resort generates 0.074 cfs addition sewage demand to the existing system. The existing 8" VCP in Robinson Ranch Road and existing 15" VCP in Sand Canyon Road have sufficient capacity to carry the added sewer demand from Sand Canyon Resort VTTM 78248. Therefore no proposed upgrade is needed for these two existing sewer line. Table 3 below shows the minimum capacity by calculating in the flatter section and half full of the existing pipes.

Location	Pipe Size	Pipe Slope (ft/ft)	Flow at 50% depth of flow =100% capacity	Cumulative calculated Q _{TOTAL} (cfs)
Robinson Ranch Road	8	0.004	0.349	0.305
Sand Canyon Road	15	0.0064	4.652	0.848

Table 3: Capacity Vs Cumulative Q comparison table


The cumulative calculated Q_{TOTAL} for the reach with the Robinson Ranch Road is the sum of the existing Q from TR 52004 and proposed project site. The existing Q for the 15" VCP along Sand Canyon Road is calculated by delta Q from Manholes 142 and 141per the sewer area study for TM063022 (see attached map), and the existing Q is 0.774cfs.


Currently, the existing 18" VCP (P9768-R) in Lost Canyon Road between Manholes 142 to 138 is 4.257cfs. And the existing calculated Q at the segment is 6.357 cfs per Sewer Area study for TM063022. Therefore an upgraded is recommended for the proposed development per the calculation.


A flow test is performed to determine the actual flow rate in Manhole 138, and it is 2.61cfs. So the upgrade is not needed for the proposed project and upgraded will be required for future development. A fair share is calculated for the project site to pay for a portion of the upgrade. In the fair share calculation, potential development is included See Table 4.


VTTM 73858 SEWER AREA STUDY -SEWER UPGRADE(FUTURE+ PROPOSED SITE DEVELOPMENTS)							
SEWER PIPE	SEWER PIPE	Existing		Proposed Project			
SEGMENT UPGRADE	SEGMENT UPGRADE	Q (cfs)		Q _p (cfs)	Q _{total} (cfs)	%Q (Qp/Qtotal)	FAIR SHARE COST (\$)
мн то мн	COST (\$)	Sand Canyon	Lost Canyon	TR 78248			
142-138	110,131	0.774	5.82	0.074	6.668	1.11%	1,222
	•					ΤΟΤΔΙ	1 222


Table 4: Fair Share Cost Analysis





















TRACT BOUNDARY PROPOSED SEWER LINE
EXISTING SEWER LINE

PROPOSED LOT LINES
PROPOSED CURB
FLOW PATH
CONCENTRATION POINT

HUNSAKER & ASSOCIATES PLANNIC - SHCHESSING - SURVEYING 2654 Avenus Hall, Sto 25 - Valenda , CA 9055 Pro 665 204021 - Fo 666 204081

27734 SAND CANYON ROAD SANTA CLARITA, CA, 91387 TELEPHONE: (213) 700-6883 OWNER: STEVE KIM

MAJOR LAND DIVISION
VESTING TENTATIVE TRACT MAP NO. 78248

DATE: 06/13/2018
JOS No. 0261-001-001 OFFSITE SEWER AREA STUDY

IN THE UNINCORPORATED AREA OF THE COUNTY OF LOS ANGELES STATE OF CALIFORNIA 2 OF 3 SHEETS

B. FlowMaster output

	Marksh	eet for E1	F2	
	VVUIKSII	CELIUI EI	-[2	
Project Description				
Friction Method	Kutter Formula			
Solve For	Discharge			
Input Data				
Roughness Coefficient		0.013		
Channel Slope		0.00400	ft/ft	
Normal Depth		0.33	ft	
Diameter		0.67	ft	
Results				
Discharge		0.35	ft³/s	
Flow Area		0.17	ft²	
Wetted Perimeter		1.05	ft	
Hydraulic Radius		0.17	ft	
Top Width		0.67	ft	
Critical Depth		0.27	ft	
Percent Full		50.0	%	
Critical Slope		0.00814	ft/ft	
Velocity		2.00	ft/s	
Velocity Head		0.06	ft	
Specific Energy		0.40	ft	
Froude Number		0.69		
Maximum Discharge		0.76	ft³/s	
Discharge Full		0.70	ft³/s	
Slope Full		0.00104	ft/ft	
Flow Type	SubCritical			
GVF Input Data				
Downstream Depth		0.00	ft	
Length		0.00	ft	
Number Of Steps		0	••	
GVF Output Data				
		0.00	f.	
Upstream Depth		0.00	ft	
Profile Description		0.00		
Profile Headloss		0.00	ft	
Average End Depth Over Rise		0.00	%	

49.99 %

Infinity ft/s

Normal Depth Over Rise

Downstream Velocity

Worksheet for E1-E2

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.33
 ft

 Critical Depth
 0.27
 ft

 Channel Slope
 0.00400
 ft/ft

 Critical Slope
 0.00814
 ft/ft

Worksheet for E2-A1					
Project Description					
Friction Method	Kutter Formula				
Solve For	Discharge				
Input Data					
Roughness Coefficient		0.013			
Channel Slope	(0.00400	ft/ft		
Normal Depth		0.33	ft		
Diameter		0.67	ft		
Results					
Discharge		0.35	ft³/s		
Flow Area		0.17	ft²		
Wetted Perimeter		1.05	ft		
Hydraulic Radius		0.17	ft		
Top Width		0.67	ft		
Critical Depth		0.27	ft		
Percent Full		50.0	%		
Critical Slope	(0.00814	ft/ft		
Velocity		2.00	ft/s		
Velocity Head		0.06	ft		
Specific Energy		0.40	ft		
Froude Number		0.69			
Maximum Discharge		0.76	ft³/s		
Discharge Full		0.70	ft³/s		
Slope Full	(0.00104	ft/ft		
Flow Type	SubCritical				
GVF Input Data					
Downstream Depth		0.00	ft		
Length		0.00	ft		
Number Of Steps		0			
GVF Output Data					
Upstream Depth		0.00	ft		
Profile Description					
Profile Headloss		0.00	ft		
Average End Depth Over Rise		0.00	%		
Normal Depth Over Rise		49.99	%		
Downstream Velocity		Infinity	ft/s		

Worksheet for E2-A1

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.33
 ft

 Critical Depth
 0.27
 ft

 Channel Slope
 0.00400
 ft/ft

 Critical Slope
 0.00814
 ft/ft

Worksheet for E3-D1					
Project Description					
Friction Method Solve For	Kutter Formula Discharge				
Input Data					
Roughness Coefficient Channel Slope Normal Depth Diameter	0	0.013 0.00400 0.33 0.67	ft/ft ft ft		
Results					
Discharge Flow Area Wetted Perimeter Hydraulic Radius Top Width Critical Depth Percent Full Critical Slope Velocity Velocity Head Specific Energy Froude Number Maximum Discharge Discharge Full Slope Full	0	0.35 0.17 1.05 0.17 0.67 0.27 50.0 0.00814 2.00 0.06 0.40 0.69 0.76 0.70 0.00104	ft³/s ft² ft ft/ft ft/s ft/ft ft/s ft ft ft		
Flow Type	SubCritical				
GVF Input Data					
Downstream Depth Length Number Of Steps		0.00 0.00 0	ft ft		
GVF Output Data					
Upstream Depth Profile Description Profile Headloss		0.00	ft ft		
Average End Depth Over Rise		0.00	%		
Normal Depth Over Rise		49.99	%		

Infinity ft/s

Downstream Velocity

Worksheet for E3-D1

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.33
 ft

 Critical Depth
 0.27
 ft

 Channel Slope
 0.00400
 ft/ft

 Critical Slope
 0.00814
 ft/ft

	Worksheet	for E10-E	11_RRR	
Project Description				
Friction Method	Kutter Formula			
Solve For	Discharge			
Input Data				
Roughness Coefficient		0.013		
Channel Slope		0.01880	ft/ft	
Normal Depth		0.94	ft	
Diameter		1.25	ft	
Results				
Discharge		7.99	ft³/s	
Flow Area		0.99	ft²	
Wetted Perimeter		2.62	ft	
Hydraulic Radius		0.38	ft	
Top Width		1.08	ft	
Critical Depth		1.11	ft	
Percent Full		75.0	%	
Critical Slope		0.01391	ft/ft	
Velocity		8.09	ft/s	
Velocity Head		1.02	ft	
Specific Energy		1.95	ft	
Froude Number		1.49		
Maximum Discharge		9.40	ft³/s	
Discharge Full		8.64	ft³/s	
Slope Full		0.01607	ft/ft	
Flow Type	SuperCritical			
GVF Input Data				
Downstream Denth		0.00	ft	

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Average End Depth Over Rise	0.00	%
Normal Depth Over Rise	75.00	%
Downstream Velocity	Infinity	ft/s

Worksheet for E10-E11_RRR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 1.11
 ft

 Channel Slope
 0.01880
 ft/ft

 Critical Slope
 0.01391
 ft/ft

	Worksheet for E11-E2	12_RRR
Project Description		
Friction Method	Kutter Formula	
Solve For	Discharge	
Input Data		
Roughness Coefficient	0.013	
Channel Slope	0.02000	ft/ft
Normal Depth	0.94	ft
Diameter	1.25	ft
Results		
Discharge	8.24	ft³/s
Flow Area	0.99	ft²
Wetted Perimeter	2.62	ft
Hydraulic Radius	0.38	ft
Top Width	1.08	ft
Critical Depth	1.13	ft
Percent Full	75.0	%
Critical Slope	0.01466	ft/ft
Velocity	8.34	ft/s
Velocity Head	1.08	ft
Specific Energy	2.02	ft
Froude Number	1.54	
Maximum Discharge	9.69	ft³/s
Discharge Full	8.91	ft³/s
Slope Full	0.01710	ft/ft
Flow Type	SuperCritical	
GVF Input Data		
Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	
GVF Output Data		
Upstream Depth	0.00	ft

GVF Output Data			
Upstream Depth	0.00	ft	
Profile Description			
Profile Headloss	0.00	ft	
Average End Depth Over Rise	0.00	%	
Normal Depth Over Rise	75.00	%	
Downstream Velocity	Infinity	ft/s	

Worksheet for E11-E12_RRR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 1.13
 ft

 Channel Slope
 0.02000
 ft/ft

 Critical Slope
 0.01466
 ft/ft

Worksheet for E12-E13_RRR

Friction Method Kutter Formula Solve For Discharge

Input Data

Roughness Coefficient	0.013	
Channel Slope	0.01560	ft/ft
Normal Depth	0.94	ft
Diameter	1.25	ft

Results

Discharge		7.27	ft³/s
Flow Area		0.99	ft²
Wetted Perimeter		2.62	ft
Hydraulic Radius		0.38	ft
Top Width		1.08	ft
Critical Depth		1.08	ft
Percent Full		75.0	%
Critical Slope		0.01199	ft/ft
Velocity		7.37	ft/s
Velocity Head		0.84	ft
Specific Energy		1.78	ft
Froude Number		1.36	
Maximum Discharge		8.56	ft³/s
Discharge Full		7.87	ft³/s
Slope Full		0.01336	ft/ft
Flow Type	SuperCritical		

GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

GVF Output Data

Upstream Depth

Profile Description		
Profile Headloss	0.00	ft
Average End Depth Over Rise	0.00	%
Normal Depth Over Rise	75.00	%
Downstream Velocity	Infinity	ft/s

0.00 ft

Worksheet for E12-E13_RRR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 1.08
 ft

 Channel Slope
 0.01560
 ft/ft

 Critical Slope
 0.01199
 ft/ft

Worksheet for E13-E14_RRR

Project Description	
Friction Method	Kutter Formula
Solve For	Discharge

	In	put	Data
--	----	-----	------

Roughness Coefficient	0.013	
Channel Slope	0.01560	ft/ft
Normal Depth	0.94	ft
Diameter	1.25	ft

Results

Discharge		7.27	ft³/s
Flow Area		0.99	ft²
Wetted Perimeter		2.62	ft
Hydraulic Radius		0.38	ft
Top Width		1.08	ft
Critical Depth		1.08	ft
Percent Full		75.0	%
Critical Slope		0.01199	ft/ft
Velocity		7.37	ft/s
Velocity Head		0.84	ft
Specific Energy		1.78	ft
Froude Number		1.36	
Maximum Discharge		8.56	ft³/s
Discharge Full		7.87	ft³/s
Slope Full		0.01336	ft/ft
Flow Type	SuperCritical		

GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Average End Depth Over Rise	0.00	%
Normal Depth Over Rise	75.00	%
Downstream Velocity	Infinity	ft/s

Worksheet for E13-E14_RRR

GVF Output Data

Upstream Velocity Infinity ft/s Normal Depth 0.94 ft Critical Depth 1.08 ft Channel Slope 0.01560 ft/ft Critical Slope 0.01199 ft/ft

	Worksheet for	or E14-E1	15_RRR
Project Description			
Friction Method	Kutter Formula		
Solve For	Discharge		
Input Data			
Roughness Coefficient		0.013	
Channel Slope		0.00940	ft/ft
Normal Depth		0.94	ft
Diameter		1.25	ft
Results			
Discharge		5.64	ft³/s
Flow Area		0.99	ft²
Wetted Perimeter		2.62	ft
Hydraulic Radius		0.38	ft
Top Width		1.08	ft
Critical Depth		0.96	ft
Percent Full		75.0	%
Critical Slope		0.00886	ft/ft
Velocity		5.72	ft/s
Velocity Head		0.51	ft
Specific Energy		1.45	ft
Froude Number		1.06	
Maximum Discharge		6.64	ft³/s
Discharge Full		6.10	ft³/s
Slope Full		0.00804	ft/ft
Flow Type	SuperCritical		
GVF Input Data			
Downstream Depth		0.00	ft
Length		0.00	ft
Number Of Steps		0	
GVF Output Data			
Upstream Depth		0.00	ft
Destile Description			

GVF Output Data			
Upstream Depth	0.00	ft	
Profile Description			
Profile Headloss	0.00	ft	
Average End Depth Over Rise	0.00	%	
Normal Depth Over Rise	75.00	%	
Downstream Velocity	Infinity	ft/s	

Worksheet for E14-E15_RRR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 0.96
 ft

 Channel Slope
 0.00940
 ft/ft

 Critical Slope
 0.00886
 ft/ft

	Worksheet for	E15-E1	16_RRR
Project Description			
Friction Method	Kutter Formula		
Solve For	Discharge		
Input Data			
Roughness Coefficient		0.013	
Channel Slope		0.00640	ft/ft
Normal Depth		0.94	ft
Diameter		1.25	ft
Results			
Discharge		4.65	ft³/s
Flow Area		0.99	ft²
Wetted Perimeter		2.62	ft
Hydraulic Radius		0.38	ft
Top Width		1.08	ft
Critical Depth		0.87	ft
Percent Full		75.0	%
Critical Slope		0.00762	ft/ft
Velocity		4.71	ft/s
Velocity Head		0.35	ft
Specific Energy		1.28	ft
Froude Number		0.87	
Maximum Discharge		5.47	ft³/s
Discharge Full		5.03	ft³/s
Slope Full		0.00547	ft/ft
Flow Type	SubCritical		
GVF Input Data			
Downstream Depth		0.00	ft
Length		0.00	ft
Number Of Steps		0	
GVF Output Data			
Upstream Depth		0.00	ft
Profile Description			
Profile Headloss		0.00	ft

75.00 %

Infinity ft/s

Average End Depth Over Rise

Normal Depth Over Rise

Worksheet for E15-E16_RRR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 0.87
 ft

 Channel Slope
 0.00640
 ft/ft

 Critical Slope
 0.00762
 ft/ft

Project Description Friction Method		
Eriction Mothod		
Friction Metriod	Kutter Formula	
Solve For	Discharge	
Input Data		
Roughness Coefficient	0.013	
Channel Slope	0.01360	ft/ft
Normal Depth	0.94	ft
Diameter	1.25	ft
Results		
Discharge	6.79	ft³/s
Flow Area	0.99	ft²
Wetted Perimeter	2.62	ft
Hydraulic Radius	0.38	ft
Top Width	1.08	ft
Critical Depth	1.05	ft
Percent Full	75.0	%
Critical Slope	0.01090	ft/ft
Velocity	6.88	ft/s
Velocity Head	0.74	ft
Specific Energy	1.67	ft
Froude Number	1.27	
Maximum Discharge	7.99	ft³/s
Discharge Full	7.34	ft³/s
Slope Full	0.01164	ft/ft
Flow Type	SuperCritical	
GVF Input Data		
Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	
GVF Output Data		
Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft

Infinity ft/s

75.00 %

Average End Depth Over Rise

Normal Depth Over Rise

Worksheet for E16-E17_RRR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 1.05
 ft

 Channel Slope
 0.01360
 ft/ft

 Critical Slope
 0.01090
 ft/ft

Worksheet for E17-E18_RRR

Friction Method Kutter Formula
Solve For Discharge

Input Data

Roughness Coefficient	0.013	
Channel Slope	0.02920	ft/ft
Normal Depth	0.94	ft
Diameter	1.25	ft

Results

Discharge		9.96	ft³/s
Flow Area		0.99	ft²
Wetted Perimeter		2.62	ft
Hydraulic Radius		0.38	ft
Top Width		1.08	ft
Critical Depth		1.18	ft
Percent Full		75.0	%
Critical Slope		0.02113	ft/ft
Velocity		10.09	ft/s
Velocity Head		1.58	ft
Specific Energy		2.52	ft
Froude Number		1.86	
Maximum Discharge		11.71	ft³/s
Discharge Full		10.77	ft³/s
Slope Full		0.02497	ft/ft
Flow Type	SuperCritical		

GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Average End Depth Over Rise	0.00	%
Normal Depth Over Rise	75.00	%
Downstream Velocity	Infinity	ft/s

Worksheet for E17-E18_RRR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 1.18
 ft

 Channel Slope
 0.02920
 ft/ft

 Critical Slope
 0.02113
 ft/ft

	Worksheet for E18-E19_RRR			
Project Description				
Friction Method	Kutter Formula			
Solve For	Discharge			
Input Data				
Roughness Coefficient		0.013		
Channel Slope		0.03440	ft/ft	
Normal Depth		0.94	ft	
Diameter		1.25	ft	
Results				
Discharge		10.81	ft³/s	
Flow Area		0.99	ft²	
Wetted Perimeter		2.62	ft	
Hydraulic Radius		0.38	ft	
Top Width		1.08	ft	
Critical Depth		1.20	ft	
Percent Full		75.0	%	
Critical Slope		0.02519	ft/ft	
Velocity		10.95	ft/s	
Velocity Head		1.86	ft	
Specific Energy		2.80	ft	
Froude Number		2.02		
Maximum Discharge		12.72	ft³/s	
Discharge Full		11.69	ft³/s	
Slope Full		0.02943	ft/ft	
Flow Type	SuperCritical			
GVF Input Data				
Downstream Depth		0.00	ft	
Length		0.00	ft	
Number Of Steps		0		

Number Of Steps	0		
GVF Output Data			
Upstream Depth	0.00	ft	
Profile Description			
Profile Headloss	0.00	ft	
Average End Depth Over Rise	0.00	%	
Normal Depth Over Rise	75.00	%	

Infinity ft/s

Worksheet for E18-E19_RRR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 1.20
 ft

 Channel Slope
 0.03440
 ft/ft

 Critical Slope
 0.02519
 ft/ft

	Worksheet for E19-E20	_RRR
Project Description		_
Friction Method	Kutter Formula	
Solve For	Discharge	
Input Data	·	
Roughness Coefficient	0.013	
Channel Slope	0.01000 ft/ft	ft
Normal Depth	0.94 ft	
Diameter	1.25 ft	
Results		
Discharge	5.82 ft ³ /:	le.
Flow Area	0.99 ft ²	
Wetted Perimeter	2.62 ft	
Hydraulic Radius	0.38 ft	
Top Width	1.08 ft	
Critical Depth	0.98 ft	
Percent Full	75.0 %	
Critical Slope	0.00913 ft/ft	ft
Velocity	5.90 ft/s	S
Velocity Head	0.54 ft	
Specific Energy	1.48 ft	
Froude Number	1.09	
Maximum Discharge	6.85 ft ³ /	/s
Discharge Full	6.29 ft ³ /	/s
Slope Full	0.00855 ft/ft	ft
Flow Type	SuperCritical	
GVF Input Data		
Downstream Depth	0.00 ft	
Length	0.00 ft	
Number Of Steps	0	
GVF Output Data		
Upstream Depth	0.00 ft	
Profile Description		
5 (1) 11	0.00	

0.00 ft

0.00 %

Infinity ft/s

75.00 %

Profile Headloss

Average End Depth Over Rise

Normal Depth Over Rise

Worksheet for E19-E20_RRR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 0.98
 ft

 Channel Slope
 0.01000
 ft/ft

 Critical Slope
 0.00913
 ft/ft

Worksheet for E20-E21_RRR

Project Description		
Friction Method	Kutter Formula	
Solve For	Discharge	
Input Data		
input Data		
Roughness Coefficient	0.013	
Channel Slope	0.01880	ft/ft
Normal Depth	0.94	ft
Diameter	1.25	ft
Results		
Discharge	7.99	ft³/s
Flow Area	0.99	ft²
Wetted Perimeter	2.62	ft
Hydraulic Radius	0.38	ft
Top Width	1.08	ft
Critical Depth	1.11	ft
Percent Full	75.0	%
Critical Slope	0.01391	ft/ft
Velocity	8.09	ft/s
Velocity Head	1.02	ft
Specific Energy	1.95	ft
Froude Number	1.49	

Flow Type SuperCritical

GVF Input Data

Maximum Discharge

Discharge Full

Slope Full

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

GVF Output Data

Upstream Depth

Profile Description		
Profile Headloss	0.00	ft
Average End Depth Over Rise	0.00	%
Normal Depth Over Rise	75.00	%
Downstream Velocity	Infinity	ft/s

9.40 ft³/s

8.64 ft³/s

0.01607 ft/ft

0.00 ft

Worksheet for E20-E21_RRR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 1.11
 ft

 Channel Slope
 0.01880
 ft/ft

 Critical Slope
 0.01391
 ft/ft

	Worksheet fo	r E21-E	22_LCR
Project Description			
Friction Method	Kutter Formula		
Solve For	Discharge		
Input Data			
Roughness Coefficient		0.013	
Channel Slope		0.00200	ft/ft
Normal Depth		1.50	ft
Diameter		2.00	ft
Results			
Discharge		9.31	ft³/s
Flow Area		2.53	ft²
Wetted Perimeter		4.19	ft
Hydraulic Radius		0.60	ft
Top Width		1.73	ft
Critical Depth		1.09	ft
Percent Full		75.0	%
Critical Slope		0.00502	ft/ft
Velocity		3.68	ft/s
Velocity Head		0.21	ft
Specific Energy		1.71	ft
Froude Number		0.54	
Maximum Discharge		10.96	ft³/s
Discharge Full		10.11	ft³/s
Slope Full		0.00170	ft/ft
Flow Type	SubCritical		
GVF Input Data			
Downstream Depth		0.00	ft
Length		0.00	ft
Number Of Steps		0	
GVF Output Data			
Upstream Depth		0.00	ft
Profile Description			
Profile Headloss		0.00	ft

75.00 %

Infinity ft/s

Average End Depth Over Rise

Normal Depth Over Rise

Worksheet for E21-E22_LCR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 1.50
 ft

 Critical Depth
 1.09
 ft

 Channel Slope
 0.00200
 ft/ft

 Critical Slope
 0.00502
 ft/ft

	Worksheet for E22-E23_LCR			
Project Description				
Friction Method	Kutter Formula			
Solve For	Discharge			
Input Data				
Roughness Coefficient		0.013		
Channel Slope		0.00200	ft/ft	
Normal Depth		1.50	ft	
Diameter		2.00	ft	
Results				
Discharge		9.31	ft³/s	
Flow Area		2.53	ft²	
Wetted Perimeter		4.19	ft	
Hydraulic Radius		0.60	ft	
Top Width		1.73	ft	
Critical Depth		1.09	ft	
Percent Full		75.0	%	
Critical Slope		0.00502	ft/ft	
Velocity		3.68	ft/s	
Velocity Head		0.21	ft	
Specific Energy		1.71	ft	
Froude Number		0.54		
Maximum Discharge		10.96	ft³/s	
Discharge Full		10.11	ft³/s	
Slope Full		0.00170	ft/ft	
Flow Type	SubCritical			
GVF Input Data				
Downstream Depth		0.00	ft	
Length		0.00	ft	
Number Of Steps		0		
GVF Output Data				
Upstream Depth		0.00	ft	
Profile Description				
Profile Headloss		0.00	ft	
Average End Depth Over Rise		0.00	%	

Infinity ft/s

Normal Depth Over Rise

Worksheet for E22-E23_LCR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 1.50
 ft

 Critical Depth
 1.09
 ft

 Channel Slope
 0.00200
 ft/ft

 Critical Slope
 0.00502
 ft/ft

	Worksheet for	E23-E2	24_LCR
Project Description			
Friction Method	Kutter Formula		
Solve For	Discharge		
Input Data			
Roughness Coefficient		0.013	
Channel Slope		0.00200	ft/ft
Normal Depth		1.50	ft
Diameter		2.00	ft
Results			
Discharge		9.31	ft³/s
Flow Area		2.53	ft²
Wetted Perimeter		4.19	ft
Hydraulic Radius		0.60	ft
Top Width		1.73	ft
Critical Depth		1.09	ft
Percent Full		75.0	%
Critical Slope		0.00502	ft/ft
Velocity		3.68	ft/s
Velocity Head		0.21	ft
Specific Energy		1.71	ft
Froude Number		0.54	
Maximum Discharge		10.96	ft³/s
Discharge Full		10.11	ft³/s
Slope Full		0.00170	ft/ft
Flow Type	SubCritical		
GVF Input Data			
Downstream Depth		0.00	ft
Length		0.00	ft
Number Of Steps		0	
GVF Output Data			
Upstream Depth		0.00	ft
Profile Description			
•			

0.00 ft

0.00 %

Infinity ft/s

75.00 %

Profile Headloss

Average End Depth Over Rise

Normal Depth Over Rise

Worksheet for E23-E24_LCR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 1.50
 ft

 Critical Depth
 1.09
 ft

 Channel Slope
 0.00200
 ft/ft

 Critical Slope
 0.00502
 ft/ft

	Worksheet for E24-E	25_LCR
Project Description		
Friction Method	Kutter Formula	
Solve For	Discharge	
Input Data		
Roughness Coefficient	0.013	
Channel Slope	0.00200	ft/ft
Normal Depth	1.50	ft
Diameter	2.00	ft
Results		
Discharge	9.31	ft³/s
Flow Area	2.53	ft²
Wetted Perimeter	4.19	ft
Hydraulic Radius	0.60	ft
Top Width	1.73	ft
Critical Depth	1.09	ft
Percent Full	75.0	%
Critical Slope	0.00502	ft/ft
Velocity	3.68	ft/s
Velocity Head	0.21	ft
Specific Energy	1.71	ft
Froude Number	0.54	
Maximum Discharge	10.96	ft³/s
Discharge Full	10.11	ft³/s
Slope Full	0.00170	ft/ft
Flow Type	SubCritical	
GVF Input Data		
Downstream Depth	0.00	ft
Length	0.00	
Number Of Steps	0	
GVF Output Data		
Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Average End Depth Over Rise	0.00	%
Normal Depth Over Rise	75.00	%

Infinity ft/s

Worksheet for E24-E25_LCR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 1.50
 ft

 Critical Depth
 1.09
 ft

 Channel Slope
 0.00200
 ft/ft

 Critical Slope
 0.00502
 ft/ft

Worksheet for E25-E26_LCR

Project Description	

Friction Method Kutter Formula Solve For Discharge

Input Data

Roughness Coefficient	0.013	
Channel Slope	0.02000	ft/ft
Normal Depth	0.94	ft
Diameter	1.25	ft

Results

Discharge		8.24	ft³/s
Flow Area		0.99	ft²
Wetted Perimeter		2.62	ft
Hydraulic Radius		0.38	ft
Top Width		1.08	ft
Critical Depth		1.13	ft
Percent Full		75.0	%
Critical Slope		0.01466	ft/ft
Velocity		8.34	ft/s
Velocity Head		1.08	ft
Specific Energy		2.02	ft
Froude Number		1.54	
Maximum Discharge		9.69	ft³/s
Discharge Full		8.91	ft³/s
Slope Full		0.01710	ft/ft
Flow Type	SuperCritical		

GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Average End Depth Over Rise	0.00	%
Normal Depth Over Rise	75.00	%
Downstream Velocity	Infinity	ft/s

Worksheet for E25-E26_LCR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 1.13
 ft

 Channel Slope
 0.02000
 ft/ft

 Critical Slope
 0.01466
 ft/ft

	Worksheet for	r E26-E2	27_LCR
Project Description			
Friction Method	Kutter Formula		
Solve For	Discharge		
Input Data			
Roughness Coefficient		0.013	
Channel Slope		0.02000	ft/ft
Normal Depth		0.94	ft
Diameter		1.25	ft
Results			
Discharge		8.24	ft³/s
Flow Area		0.99	ft²
Wetted Perimeter		2.62	ft
Hydraulic Radius		0.38	ft
Top Width		1.08	ft
Critical Depth		1.13	ft
Percent Full		75.0	%
Critical Slope		0.01466	ft/ft
Velocity		8.34	ft/s
Velocity Head		1.08	ft
Specific Energy		2.02	ft
Froude Number		1.54	
Maximum Discharge		9.69	ft³/s
Discharge Full		8.91	ft³/s
Slope Full		0.01710	ft/ft
Flow Type	SuperCritical		
GVF Input Data			
Downstream Depth		0.00	ft
Length		0.00	ft
Number Of Steps		0	
GVF Output Data			
Upstream Depth		0.00	ft
Profile Description			
Profile Headloss		0.00	ft

Normal Depth Over Rise	75.00	%	
Downstream Velocity	Infinity	ft/s	

Average End Depth Over Rise

Worksheet for E26-E27_LCR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 1.13
 ft

 Channel Slope
 0.02000
 ft/ft

 Critical Slope
 0.01466
 ft/ft

	Worksheet	for E27-E2	28_LCR	
Project Description			_	
Friction Method	Kutter Formula			
Solve For	Discharge			
Input Data				
Roughness Coefficient		0.013		
Channel Slope		0.02000	ft/ft	
Normal Depth		0.94	ft	
Diameter		1.25	ft	
Results				
Discharge		8.24	ft³/s	
Flow Area		0.99	ft²	
Wetted Perimeter		2.62	ft	
Hydraulic Radius		0.38	ft	
Top Width		1.08	ft	
Critical Depth		1.13	ft	
Percent Full		75.0	%	
Critical Slope		0.01466	ft/ft	
Velocity		8.34	ft/s	
Velocity Head		1.08	ft	
Specific Energy		2.02	ft	
Froude Number		1.54		
Maximum Discharge		9.69	ft³/s	
Discharge Full		8.91	ft³/s	
Slope Full		0.01710	ft/ft	
Flow Type	SuperCritical			
GVF Input Data				
Downstream Depth		0.00	ft	
Length		0.00	ft	
Number Of Steps		0		
GVF Output Data				
Upstream Depth		0.00	ft	
Profile Description				
Profile Headloss		0.00	ft	

75.00 %

Infinity ft/s

Downstream Velocity

Average End Depth Over Rise Normal Depth Over Rise

Worksheet for E27-E28_LCR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 1.13
 ft

 Channel Slope
 0.02000
 ft/ft

 Critical Slope
 0.01466
 ft/ft

	Worksheet t	for E28-E2	29_LCR	
Project Description				
Friction Method	Kutter Formula			
Solve For	Discharge			
Input Data				
Roughness Coefficient		0.013		
Channel Slope		0.02000	ft/ft	
Normal Depth		0.94	ft	
Diameter		1.25	ft	
Results				
Discharge		8.24	ft³/s	
Flow Area		0.99	ft²	
Wetted Perimeter		2.62	ft	
Hydraulic Radius		0.38	ft	
Top Width		1.08	ft	
Critical Depth		1.13	ft	
Percent Full		75.0	%	
Critical Slope		0.01466	ft/ft	
Velocity		8.34	ft/s	
Velocity Head		1.08	ft	
Specific Energy		2.02	ft	
Froude Number		1.54		
Maximum Discharge		9.69	ft³/s	
Discharge Full		8.91	ft³/s	
Slope Full		0.01710	ft/ft	
Flow Type	SuperCritical			
GVF Input Data				
Downstream Depth		0.00	ft	
Length		0.00	ft	
Number Of Steps		0		
GVF Output Data				
Upstream Depth		0.00	ft	
Profile Description				
Profile Headloss		0.00	ft	

75.00 %

Infinity ft/s

Downstream Velocity

Average End Depth Over Rise Normal Depth Over Rise

Worksheet for E28-E29_LCR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 0.94
 ft

 Critical Depth
 1.13
 ft

 Channel Slope
 0.02000
 ft/ft

 Critical Slope
 0.01466
 ft/ft

Kutter Formula Discharge	
Discharge	
0.013	
0.01760	ft/ft
1.13	ft
1.50	ft
12.71	ft³/s
1.42	ft²
3.14	ft
0.45	ft
1.30	ft
1.34	ft
75.0	%
0.01298	ft/ft
8.94	ft/s
1.24	ft
2.37	ft
1.51	
14.96	ft³/s
13.78	ft³/s
0.01499	ft/ft
SuperCritical	
0.00	ft
0.00	ft
0	
0.00	ft
0.00	ft
	%
	1.50 12.71 1.42 3.14 0.45 1.30 1.34 75.0 0.01298 8.94 1.24 2.37 1.51 14.96 13.78 0.01499 SuperCritical 0.00 0.00 0

Infinity ft/s

Normal Depth Over Rise

Worksheet for E29-E30_LCR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 1.13
 ft

 Critical Depth
 1.34
 ft

 Channel Slope
 0.01760
 ft/ft

 Critical Slope
 0.01298
 ft/ft

	Worksheet for E30-E31_LCR	
Project Description		
Friction Method	Kutter Formula	
Solve For	Discharge	
Input Data		
Roughness Coefficient	0.013	
Channel Slope	0.00800 ft/ft	
Normal Depth	1.13 ft	
Diameter	1.50 ft	
Results		
Discharge	8.56 ft³/s	
Flow Area	1.42 ft ²	
Wetted Perimeter	3.14 ft	
Hydraulic Radius	0.45 ft	
Top Width	1.30 ft	
Critical Depth	1.13 ft	
Percent Full	75.0 %	
Critical Slope	0.00787 ft/ft	
Velocity	6.02 ft/s	
Velocity Head	0.56 ft	
Specific Energy	1.69 ft	
Froude Number	1.01	
Maximum Discharge	10.08 ft³/s	
Discharge Full	9.28 ft³/s	
Slope Full	0.00682 ft/ft	
Flow Type	SuperCritical	
GVF Input Data		
Downstream Depth	0.00 ft	
Length	0.00 ft	
Number Of Steps	0	
GVF Output Data		
Upstream Depth	0.00 ft	
Profile Description		
Profile Headloss	0.00 ft	

Infinity ft/s

75.00 %

Average End Depth Over Rise

Normal Depth Over Rise

Worksheet for E30-E31_LCR

GVF Output Data

 Upstream Velocity
 Infinity
 ft/s

 Normal Depth
 1.13
 ft

 Critical Depth
 1.13
 ft

 Channel Slope
 0.00800
 ft/ft

 Critical Slope
 0.00787
 ft/ft


C.	Reference plans/reports


1. LACDPW As built PC 98-13 – TR 52004


PROFILE, ALIGNMENT AND GRADE OF PAGE 1 PRIVATE ENGINEER'S NOTICE TO CONTRACTORS GENERAL NOTES: BENCH MARK NO PP #533919E MKD (BM 203-3A 1971) 2IN 1. ELEVATIONS ARE IN FEET ABOVE U.S.C. & G.S. SEA LEVEL DATUM OF 1928. ERODED SEDIMENTS AND OTHER POLLUTANTS MUST BE RETAINED ON SITE TRANSPORTED FROM THE SITE WA SHEETILOW, SWALES, AREA DRAINS, NATURAL DRAINAGE COURSES OR WIND. D REVISIONS SHALL BE MADE IN THESE PLANS WITHOUT THE APPROVAL OF THE CITY ENGINEER SANITARY SEWERS TATIVE OF THE CITY OF SANTA CLARITA WILL SURVEY OR LAY OUT ANY PORTION OF THE WORK. CRACES TO MICH THIS IMPROVABENT IS TO BE CONSTRUCTED HE SHOWN ON FLAME HID PROFILES GRACE POINTS ALL POINTS BETWEEN ESSENATED POINTS HE GRACE SHALL BE ESTABLISHED SO AS TO CONFORM TO A STRANGHT UNDER DAMAN BETWEEN ESSENATED POINTS. IP 3FT UP 2FT W/O MON ELEV. 1585.560 B.M. NO. L 3819 TRACT NO. 52004 5. THE PRIVATE DIGINEER SMALL PURPOSED THE SURDIVISION SECTION WITH GRADE SHEETS AND STATIONING TOR ALL HOUSE LATERACKS AND "YO N" IT BRANCHES AND SHALL PROVIDE STAKES FOR THEM AT THEM PROPERLY AND SHALL PROVIDE STAKES FOR THEM AT STANDARD AND ADDRESS OF THE STANDARD AND ADDRESS OF 6. THE PRIVATE ENGINEER SHALL FURNISH THE HOUSE LATERAL BEPTH AT THE PROPERTY LINE BELOW THE TOP OF CURB ELEVATION FOR EACH HOUSE LATERAL ON THE GRADE SHEET. PRIVATE CONTRACT NO. 98-13 . Before work can be started, the contractor haist obtain a permit to excavate in city streets from The city of santa clarita building and safety division NO CONNECTION FOR THE DISPOSAL OF INDUSTRIAL WASTE SHALL BE MADE TO SENERS SHOWN ON THESE DRAWNOS UNTIL A PERMIT FOR INDUSTRIAL WASTE WATER DISCHARGE HAS BEEN ISSUED BY THE SANTATION DISTRICTS FOR SAID CONNECTION. TRASH AND CONSTRUCTION RELATED SOLD WASTES MUST BE DEPOSITED INTO A COVERED RECEPTACLE TO PREVENT CONTAMINATION RAINWATER AND DISPESSAL BY WIND. INDEX: B. IF NORK IS TO DONE IN A STATE HIGHWAY. A PERMIT MUST BE OBTAINED FROM THE STATE OF CALIFORNIA, DIVISION OF HIGHWAYE, 120 SOUTH SPRING STREET, LOS ANGELES, CALIFORNIA. ...7. SHEETS; ...14 PAGES BEFORE BREAKING INTO OR CONSTRUCTION ON A COUNTY SANITATION SCALE: VERT.: 1"= 8' HORIZ.: 1"=40' OCT., 1996 DISTRICT SEMER AND PRIOR TO FINAL ACCEPTANCE OF THE PROJECT, A SANITATION DISTRICT INSPECTOR SHALL BE NOTIFIED BY PHONE AT (805) 266–4683 SO THAT REQUIRED INSPECTION CAN BE MADE. ANY SLOPES WITH DISTURBED SOILS OR DENUDED OF VEGETATION MUST BE STABILIZED SO AS TO INHIBIT EROSION BY WIND AND WATER. No. 55069 PREPARED IN THE OFFICES OF THE FOLLOWING BUIPS AS OUTLINED IN, BUT NOT LIMITED TO, THE BEST MANAGEMENT PRACTICE HANDBOOK, CALIFORNIA STORMINATER QUALITY TASK FORCE, SACRAMENTO, CALIFORNIA 1993, OR THE LATEST REVISED LAND DESIGN CONSULTANTS, INC. Bo. Lake Aver-Suite 600 Pasadena, Califor PH(626) 578-7000 FAX(626) 578-7373 DIAPPROPRIATE BY COUNTY):


DOWN TERMS COPPA TONE
PANNE CREATIONS
STRUCTURE CONSISTEM AND PARTIN
STRUCTURE CONSISTEM AND PARTIN
SOLD MASTE WANAGEMENT
CONCRETE MASTE WANAGEMENT
VENCE AND COUPPORT MARTEMANCE
PRESERVATION OF DIRETTO WEET THAN
STEDEN AND FASTEMENT
CONTRIBUTED
CONTRIBUTED
CONTRIBUTED
THE PROPRIETY OF THE MASTEMENT
TRANSPORT THE MASTEMENT
TRANSPORT
TRA BY: Jamy Man — REG. C.E. NO. 55069 EXP. 6-30-00 EX. 15" V.C.P. SEWER PER P.C. 9768 R CONSTRUCTION NOTES. CA001 CA003 CA010 CA020 CA021 CA023 CA024 CA030 CA031 ESC01 ESC10 ESC10 ESC21 WORK SHALL BE CONSTRUCTED ACCORDING TO THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION (1998 EDYTOH) AND LA. COUNTY DEPARTMENT OF PUBLIC WORKS SPECIAL PROVISIONS FOR THE CONSTRUCTION OF SAMFAY SENERS DATED JULY 31, 1988 AND SHALL BE PROSECUTED ONLY IN THE PRESENCE OF THE CITY THE FOLLOWING LATEST REVISED STANDARD PLANS ON FILE IN THE OFFICE OF THE CML ENGINEER SHALL APPLY IN THE CONSTRUCTION OF THIS PROJECT: 2. THE CONTRACTOR SHALL NOTIFY THE PUBLIC WORKS INSPECTOR BY TELEPHONE, (808) 258-4748, AT LEAST 24 HOUR BEFORE STARTING ANY WORK UNDER THIS CONTRACT LEGEND MINIMUM PUBLIC SAFETY REQUIREMENTS... MINIMUM PUBLIC SAFETY NEURO BRICK MANHOLE STEP_ STANDARD MANHOLE STEP_ BEDDING FOR SEWER, PIPE_ CRADLING AND ENCASEMENT_ WYE OR TEE SUPPORT LOCKING IMMHOLE FRAME AND COVER NON-RENFORCED PREAST CONCRETE IMMN BREAK INTO EXISTING MANHOLE SPECIAL HOUSE LATERAX SECOND PROTECTION IN STEEP SLOPES ANCHOR BLOCKS JACKING SEWER CASING FOR SEWER PIPE. COUNTY REVISION KEY MAP SCALE 1" = 600' 9. IF A POWER POLE IS WITHIN THREE FEET OF THE SENIER, THE SENIER SHALL SE ENCASED PER LACIDLY. STD. PLAN NO. 2023—0, CASE IL TWO FEET ON EACH SIDE FROM THE POINT OF INTERFERENCE. MOTICE TO CONTRACTOR SEWER SERVICE MUST BE MAINTAINED AT ALL TIMES. P.C. 98-13 TRACT NO. 52004 2 M THOMAS GUIDE PAGE. 4552 D, 3 & 4 TRACT BOUNDARY -* REFERS TO A.P.W.A. STD. DRAWING NO.

* REFER TO SANITARY SEWER PROCEDURAL MANUAL DRAWING SANITARY SEWER IN THE VALUETY OF TREASURE MATTER. TE: NUMBERS IN CIRCLE INDICATES PAGE NUMBERS All Joint's Between Cast from PIPE and Withfield Clay PIPE shall be made with a rubber sleeve Joint Type "C" or "D". (with Bushing if Necessary) per Standard Specifications. Section 208—2. CITY OF SANTA CLARITA STORMWATER POLLUTION CONTROL CITY OF BANTA CLARITA, CALIFORNIA REQUIREMENTS FOR SEWER CONSTRUCTION
SEE SHEET NO. 3, PAGE NO. 6 ##STREET RIW & STREET NAME REVISED PER STREET ANTHONY J. NISICH DIRECTOR OF TRANSPORTATION NEERING SERVICES / CITY ENG CHARLES W. CARR CHIEF ENGINEER CO. SAN DIET. NO. 20 APPROVED TO LE EN CONSTRUCTION LE CONSTRUCTION LE EN CONSTRUCTION LE CONSTRUCTION LE EN C LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS CONSOLIDATED SEWER MAINTENA REVIEWED FOR MAINTENANCE ADD OFFSET CUES OFT. SHT. 0) REVISIONS PER STORET MAN DEVISIONS CHECKED (12.42-93 8. ALL WYES AND/OR HOUSE LATERALS ARE TO BE LOCATED AT LEAST FIVE FEET APART AND NOT CLOSER THAN FIVE FEET TO ANY MANHOLE.










<u>E</u> 98 O ۵.





2.	LACDPW As built PC 9768R



GENERAL NOTES:

FLEVATIONS ARE IN FEET ABOVE U.S.C. & G.S. SEA LEVEL DATUM OF 1929.

REVAILORS ARE IN FEET AROVE U.S.C. & G.S. SEA LEVEL DATUM OF 1929.

NO REVISIONS SHALL BE MADE IN THESE PLANS WITHOUT THE APPROVIL OF THE COUNTY ENGINEER.

NO REPRESENTATIVE OF THE COUNTY ENGINEER WILL SURVEY OR LAY OUT ANY PORTION OF THE WORK.

GRADES TO WHICH THIS IMPROVEMENT IS TO BE CONSTRUCTED ARE SHOWN ON NAMS AND PROFILES. ARE POINTS FOR TOP OF
CHARS. CENTER UNE OF STREETS, OR CENTER UNE OF ALIESTS ARE SHOWN OF IT CRUESTS OR PROFILES. AT ALL POINTS BETWEEN DESIGNATED POINTS THE GRADE SHALL BE ESTABLISHED SO AS TO CONFORM TO A STRAIGHT LINE DRAWN BETWEEN SAID DESIGNATED
FOINTS.

DOUBLE SCALE

- POINTS.

 THE PRIVATE ENGINEER SHALL FURNISH THE COUNTY ENGINEER WITH GRADE SHEETS AND STATIONING FOR ALL HOUSE LATERALS
 AND "" OR "" BARNCHEE AND SHALL PROVIDE STAKES FOR THEM AT THEIR PROPER LOCATIONS WITH STATIONING HER
 ARED. ALL HOUSE LATERALS SHALL BE CONSTRUCTED IN A STRAIGHT AIGNISHMENT AT BEINGT ANGLES FROM THE MAIN LIME SEWER
 EXCEPT AS SHOWN ON THE FLANTS, HOUSE LATERALS FROM CHIMMETS SHALL NOT HAVE AN ANGLE OF LESS THAN 3" WITH THE
 MAIN LIME SEWER ANY CHANGE "IN AUGMENTS SHALL BE REQUISED IN WRITTING BY THE PRIVATE REPURENCE.
- THE PRIVATE ENGINEER SHALL FURNISH THE HOUSE LATERAL DEPTH AT THE PROPERTY LINE BELOW THE TOP OF CURB ELEVATION FOR EACH HOUSE LATERAL ON THE GRADE SHEET.
- Before work can be stated, the contractor must obtain a permit to excavate in county streets from the LA county koad dept. District office no 5 and day a fee to the county enginee. 550 JORGE VERMONE AVE. A ROBLES TO COVER the Cost of construction inspection and become plans.
- IF WORK IS TO BE DONE IN A STATE HIGHWAY, A PERMIT MUST BE OBTAINED FROM THE STATE OF CALIFORNIA, DIVISION OF HIGH WAYS, 120 SOUTH SPRING STREET, LOS ANGELES, CALIFORNIA
- 9. APPROVAL OF THIS PLAN BY THE COUNTY OF LOS ANGELES DOES NOT CONSTITUTE A REPRESENTATION AS TO THE ACCURACY OF THE LOCATION OF OR THE EXISTENCE OR NON-EXISTENCE OF ANY UNDERGROUND UTILITY PIPE, OR STRUCTURE WITHIN THE LIMITS OF

10. REFER TO SECTION 7-10.4.1 OF THE STANDARD SPECIFICATIONS, REGARDING SAFETY ORDERS

PRIOR TO THE ISSUANCE OF THE REQUIRED SEWER CONSTRUCTION PERMIT, THE CONTRACTOR SHALL OBTAIN AND FILE WITH THE COUNTY ENGINEER COPIES OF A PERMIT TO EXCAUNTE IN COUNTY STREETS FROM THE LIDS ANGELES COUNTY ROAD PEPARTMENT, A PERMIT FOR EVCAUNTIONS AND TREVCHES FROM THE STATE OF CALIFORNIA, DIVISION OF INDUSTRIAL SAFETY AND A CERTIFICATE OF WARKER'S COMPENSATION INSURANCE WITH THE DEPARTMENT OF COUNTY ENGINEER, 550 SOUTH VERMONT AVE, ROOM 405. LOS ANGELES, CALIFORNIA 90020, NAMED AS THE CERTIFICATE HOLDER TO BE NOTIFIED 30 DAYS PRIOR TO CANCELLATION OF POLICY.

CONSTRUCTION NOTES:

- HOUSE LATERALS TO BE CONSTRUCTED WITH INVESTS AT PROPERTY LINE 6 FEET BELOW CURB GRADE EXCEPT AS NOTED.

 WYE ON THE REALMORES MAY BE USED FOR CONNECTIONS TO MAINHUME SEWESS EXCEPT AS NOTED.

 ALL STRUCTURES SHALL BE STITKE BRICK MAINHOLES FEE S-J OR PRECAST CONCRETE MAINHOLES FEE S-J4, EXCEPT AS NOTED. PROVIDE STAKES ON THE PROPERTY LINE OR PROPERTY LINES PRODUCED AT RIGHT ANGLES TO THE SEWER LINE AT THE CENTER LINE OF EACH MANHOLE.
- 7. MANHOLE TOPS IN UNIMPROYED RIGHTS OF WAY TO BE SIX INCHES ABOYE FINISHED GRADE.
- WINDING LOTS IN OWNER FOR SHALL BE THE "D", OR "G" PER STANDARD SPECIFICATIONS SECTION 280-2.

 IF A DOWNER FOLE IS WITHIN THERE FEET OF THE SEWER, THE SEWER SHALL BE ENCASED, FER 5-23, CASE II, TWO RET ON EACH SIDE A PERMIT FROM THE FOLIO OF INTERSERVER.
- 10. IF DUILING THE COURSE OF CONSTRUCTION IT IS DETERMINED THAT THERE IS LESS THAN FOUR PET OF COVER OWER THE TOP OF A MAIN LINE OR HOUSE LATERAL V.C.P. SEWER WHICH IS NOT INDICATED ON THE PLANS, THE PIPE SHALL BE ENCASED PER \$-23, CASE II UNICES OF THE REPORT FROMERS. ALL JOINTS BETWEEN CAST IRON PIPE AND VITRIFIED CLAY PIPE SHALL BE MADE WITH A RUBBER SLEEYE JOINT, TYPE "C" OR "D", IWITH BUSHING IF NECESSARY) PER STANDARD SPECIFICATIONS, SECTION 208-2.
- THIND BANGHOW IT RELEASANT FEE STANDARD STRUCTURATIONS, SECTION 100-2.

 SEWEST OF BETSTEE FOR LEAKAGE FEE SECTION 306-7. OF THE STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.

 RESURACE ALL TERNICES WITHIN FAYED AREAS TO MEET LA. COUNTY ROAD UPFT, OR CAUFORNIA STATE HIGHWAY REQUIREMENTS IN ACCORDANCE WITH PERMIT PROVINCES.

IN ACCORDANCE WITH PREMITS.

If JULI COMMINICE WITH SCICTION 306-93-8 OF THE SPECIAL PROVISIONS WILL BE REQUIRED FOR BACKFILL IN STREETS. CERTIFICATION OF BACKFILL COMMINION AND BOUNDAINTS BY A QUALIFIED, REGISTERED TESTING LABOLATON SHALL BE PROVIDED BY THE FREMITTES FOR TOTAL TO THE THING TO THE HISTORY OF PARTIAL ACCOPTANCE.

15. IN CASE OF 15" DIAMETER PIPES OR SMALLER, ALB.S. COMPOSITE PYPE MATE BE USED.

14. LIELU OF V.C.P. IF IT COMPOSITES TO THE CONDITIONS OF USEGE CONTAINED.

18. IN PART IV OF THE SPECIAL PROVISIONS FOR THE CONSTRUCTION OF SAN SENERS. CASES WHEREA. B.S. COMPOSITE PIPE CANNOT BE USED ARE BETWEEN STATIONS 25+50 + 92+50 AND BET. STATIONS 1+00 + 4+00 ON PAGES 7 + 8 RESPECTIVE

2614161 258H161 2644157

PROFILE, ALIGNMENT AND GRADE OF 0-143 PAGE 1 SANITARY SEWERS

TO BE CONSTRUCTED IN

TRACT No. 37572 AND LOST CANYON ROAD AND OTHER RIWS

PRIVATE CONTRACT NO. 9768 R

W.S. 62 9 SHEETS: 18 PAGES

(49293

SCALE: VERT. 1"-8" NOVEMBER , 1979

PREPARED IN THE OFFICES OF
ENGINEERING SERVICE CORPORATION
4676 ADMINALTY WAY, SUITE 933 MARKINA DEL REY, CA. 90291
TEL 213/822-9049
BY:

REG. C. E. No. 13095

IF CONCRETE MANNOLE

STAGE
BEFORE BREAKING INTO OR CONTINUETON OH A QUINTY
SANIETION DESTROT SEWER AND PRIOR TO FINE MODERNAME
OF THE PROJECT SAVINATION DISTRICT INSPECTION—SHALL BE
NOTHER BY THOME 962-8595, SO THAT REQUIRED INSPECTION
CAN BE WIST. NO CONTECT IN FOR THE DISTOSAL OF INDUSTRIAL WASTES SHALL BE THEN TO SEWERS BUTTON OF THE DESTRUCTIONS UNTIL A PERMIT OF NOWSTRIAL WASTE WATER BOSCH WISE HAS BEEN ISSUED BY EAS ANITATION DISTRICTS FOR DATE OCNNECTION

COUNTY OF LOS ANGELES, CALIFORNIA

STEPHEN J. KOONCE, COUNTY ENGINEER WALTER E. GARRISON, CHIEF ENGINEER


APPROVED Martin & Murphy 6-12-80 APPROVED


CHECKED Ralph David Sevent 6/10/80 REG. C.E. NO. 16883


NEWHALL COUNTY WATER DISTRICT


Dean Intula 6417/80


SANTA CLARITA VALLEY BLDG DIST. 8.2
















































3. VTTM 78248 – Hunsaker & Associates – January 2018





LEGEND:

5000 SF - LOT AREA (SQUARE FEET)
PAD=1210.0 - PAD ELEVATION
OS. OR LOT TYPE VTTM 78248 BOUNDAR PROPOSED PRIVATE DRIVE

67' PROPOSED LOT LINE

EXISTING EASEMENTS
IDENTIFIED BY 3

PROPOSED CONTOUR __ # _ _ # _ _ DAYLIGHT LINE STORM DRAIN CULVERT ——SD——— STORM DRAIN __ S _____ SANITARY SEWER (SERVICE -FM----- SEWER FORCE MAIN

100 - LOT NO.

RW RECYCLED WATER
----W EXISTING WATER LINE ----E--- EXISTING POWER LINE FIRE DEPARTMENT ACCESS GATE

LOW FLOW DIVERSION
DEBRIS RISER
ORIGINAL
RISER

LOW FLOW DIVERSION DEBRIS RISER RISER CATCH BASIN SURVEYOR'S NOTES PER "EXCEPTIONS", PER SHT 2 **√**3

IMPACTED OAK TREE HERITAGE SIZE LABELED WITH "H"

ENCROACHED OAK TREE
 HERITAGE SIZE LABELED WITH "H"

O PRESERVED OAK TREE
HERITAGE SIZE LABELED WITH "H" EXISTING POWER POLE PROPOSED DRIVEWAY

WATER TANK & STORM DRAIN ACCESS ROAD TRAIL, CONC OR DG PER PLAN

● · · · · · · · · · · · · · · sight distance line (415')

GENERAL NOTES:

- AND THE PARKS AND RECREATION DEPARTMENT.

 BUILDING FOOTBRITS SHOWN ON THE TENTATIVE MAP OR ACCOMPANYING SITE PLAN EXHIBIT MAPS ARE ONLY FOR ELUSTRATIVE PURPOSES. PELOCATION OF BUILDINGS, OR DEPARTMENT OF THE PARTMENT OF THE PARTMENT OF THE PARTMENT OF THE PARTMENT OF THE SHORT OF THE SHORT
- 6. THE RECORDATION OF A TABLED LOT PREC DOUNT SUBDONSON CODE.

 6. THE RECORDATION OF A TABLED LOT PRINCE USE SHALL BE CONSIDERED THE FLUX OF THE FIRST UNIT FOR THE PURPOSE OF TIME EXTENSION PURSUANT TO THE SUBDONSON DO A TABLED LOT PRINCE THE RECORDANT OF A TABLED LOT PRINCE WITH THE COUNTY SUBDONSON ORDINANCE—NOR THE DEDICATION OF PARKLAND OR ST PERMISSION IS REQUESTED TO COMBINE LOTS TO THE SATISFACTION OF DRP AND PUBLIC WORKS.
- 7. PERMISSION IS REQUESTED TO COMBINE LOTS TO THE SATISFACTION OF DRP AND PUBLIC WORKS.
 8. PERMISSION IS REQUESTED FOR UNIT PHASING TO THE SATISFACTION OF DRP AND PUBLIC WORKS.
 9. PERMISSION IS REQUESTED TO RECORD ADDITIONAL OPEN SPACE LOTS TO THE SATISFACTION OF DRP AND PUBLIC WORKS.
- . PERMISSION IS REQUESTED TO RECORD ADDITIONAL UTILITY LOTS PROVIDED MAINTENANCE EASEMENTS ARE GRANTED TO THE SATISFACTION OF THE DRP.
- MAINTENANCE EASEMENTS ARE GHOWLED IN THE SHITEMENT OF THE THE LOCATIONS OF APPURITEMENT STRUCTURES (E.G., PASEOS, PEDESTRIAN BRIDGES, TRANSIT SHILTERS, WATER QUALITY BASINS, WATER TANKS, ETC.) MAY BE RELOCATED TO THE SATISFACTION OF DPW AND DRP.

 PERMISSION TO RECORD JOINT ACCESS EASEMENTS (20' WIDE) AS LOTS REQUESTED.
- REQUEST PERMISSION TO PHASE MASS GRADE TO THE SATISFACTION OF DRP AND DPW AND THE PROVISIONS OF THE COUNTY CODE, APPROVED PROJECT CONDITIONS AND MITIGATION MEASURES.
- MEASURES.

 A PROPOSED STREET GRADING IS APPROXIMATE ONLY AND SUBJECT TO ADJUSTMENTS PENDING DETERMINATION OF FINAL DEVELOPMENT LAYOUT AND PLANS.

 5. PROPERTY USE RETURN ADDI OF 15 FL. AT ALL LOCAL STREET INTERSECTIONS AND 27 FL AT THE INTERSECTION OF LOCAL STREETS WITH PLANNED HIGHWAYSTERS OF THE ATTEMPT OF PUBLIC WORKS.

- MODIFIED STREET PROSES SECTIONS AS SHOWN ON VESTING TRAINING TRACT MAP
 PORE REQUESTED. HOWEVER, PROMISSION IS SOUGH TO CONSTRUCT STANDARD STREET
 CROSS-SECTIONS AT THE DESCRIPTION OF THE SUBDIMPER.
 ALD DIMENSION SHOWN ARE APPROXIMATE.
 TOPOGRAPHY PROVIDED BY: CITY OF SANTA CLARITA
 DATE OF TOPOGRAPHY: 2006
 ALL DEMANGE TO BE MANTANICD BY LACTCO, LINLESS OTHERWISE NOTED ON PLAN.
 ALL DEMANGE TO BE MANTANICD BY LACTCO, LINLESS OTHERWISE NOTED ON PLAN.
 SCHIEST CEREST EPONIAGE. MANNE DOE JOSS EPONIMA, ON DRIVAT STREETS AND DE
 PORTIEST CEREST EPONIAGE. MANNE DOE JOSS EPONIMA, ON DRIVAT STREETS AND DE

- REQUEST STREET FRONTAGE WAIVER FOR LOTS FRONTING ON PRIVATE STREETS AND PRIVATI DRIVES PER CONDITIONS OF APPROVAL. 21. PERMISSION IS REQUESTED TO ALLOW FLAG LOTS PER CONDITIONS OF APPROVAL

SPECIAL NOTES:

1. WATER QUALITY BASINS WILL PROVIDE FOR TREATMENT OF STORM WATER RAN OFT.

2. THE WATER QUALITY BASINS SHALL BE DEDUCATED TO THE COUNTY WHICH COMPLETED AND ACCEPTED.

3. PROPOSED RECLAMED WATER LINES WILL BE LOCATED IN PUBLIC STREETS AND TRAILS.

UTILITY PROVIDERS

VILLII FOYTH-LE
PHONE: ATAT
SCHOOLS: SULPHUR SPRING UNION SCHOOL DISTRICT
SCHOOLS: SULPHUR SPRING UNION SCHOOL DISTRICT
SCHOOLS: SULPHUR SAUTATION DISTRICT
GAS: SOULHERN CALIFORNA GAS COMPANY
WATER: SANTA CLARITA WATER DIVISION
POLICE PROTICTION: LA COUNTY SHEEF
FIRE PROTICTION: LA COUNTY FIRE

SURVEY NOTES:

AFRICAL DATUM:

BENCH MARK: B.M. NO. L7143

LA CO BM BR DISK MRKD 7143, N. E.

LOS ANGLES CO. ELEV. 1573.388

ACHINA USED FOR FIELD REFERENCE AND VE AERUL PLANIMETRY:
TOPOGRAPHY PROVIDED BY: CITY OF SANTA CLARITA
DATE OF TOPOGRAPHY: 2006
PHONE: N/A

LEGAL DESCRIPTION:

REAL PROPERTY IN THE CITY OF SANTA CLARITA, COUNTY OF LOS ANGELES, STATE OF CALIFORNIA, DESCRIBED AS FOLLOWS:

OFFICE OF THE COUNTY RECORDED OF SAID LAND LYING WITHIN THAT PORTION OF THE SOUTHWEST QUARTER OF THE SOUTHWEST QUARTER OF SECTION 2.3. THE SOUTHWEST QUARTER OF SECTION 2.3. THE SOUTHWEST WASHING AND ADDRESS AND RESONANCE OF THE SOUTHWEST OF A THORN AND THE SOUTHWEST OF THE SOUTHWEST ON THE SOUTHWEST OF THE SOUTHWEST OF THE SOUTHWEST ON THE SOUTHWEST OF THE SOUTHWEST OF THE SOUTHWEST ON THE SOUTHWEST OF THE SOUT

PROJECT SUMMARY:

GROSS AREA — 74.9 AC
TOTAL LOTS — 4 TOTAL D.U. — 392
EXISTING ZONING — OPEN SPACE
PROPOSED ZONING — REGIONAL COMMERCIAL
GENERAL PLAN LAND USE — VISITOR SERVING / RESORT

ASSESSOR'S PARCEL NUMBER (APN)

APPROXIMATE EARTHWORK QUANTITIES:
VTTM 78248: (WITHIN TRACT BOUNDARY)

CUT FILL NET

RAW VOLUME= 241,000 CY 201,500 CY 39,500 CY CUT

*TOTAL EXCAVATION= 511,000 CY 510,000 CY +1000 CY CUT


LOT NUMBERS	TYPE (USE)	DWELLING UNITS OR NON-RESIDENTIAL	DEVELOPED ACRES	OPEN SPACE ACRES	TOTAL ACRES
1	PARK	0	0	7.1	7.1
2	1-STORY SINGLE FAMILY, OAK TREE PRESERVE & OPEN SPACE	10	5.7	12.5	18.2
3	HOTEL, RESORT SPA, RESTAURANTS, 2-STORY MULTI-FAMILY & OPEN SPACE	382	26.0	11.0	37.0
4	9 HOLE GOLF COURSE, TENNIS/PICKLE COURTS, RECREATION AREA & OPEN SPACE	000	0	12.6	12.6
		700	71.7	47.0	740

JHF, PDO

PDO

				OWNER DEVELOPER:	
				SAND CANYON	1000
				COUNTRY CLUB	
				27734 SAND CANYON ROAD	No. 40695 €
				SANTA CLARITA, CA, 91387 TELEPHONE: (213) 700-6883	CIVIL
ο.	REVISIONS	DATE	BY	OWNER: STEVE KIM	














WE ALSO HEREBY DEDICATE TO THE CITY OF SANTA CLARITA THE RIGHT TO RESTRICT RESIDENTIAL CONSTRUCTION OVER ALL OPEN SPACE.

DRAINAGE NOTES: LOT OWNERS IN THIS SUBDIVISION SHALL NOT INTERFERE WITH THE ESTABLISHED DRAINAGE OF THIS SUBDIVISION. OWNERS OF LOTS SHALL NOT ERECT WALLS OR OTHER SOLID CONSTRUCTION WHICH WILL OBSTRUCT DRAINAGE EXCEPT AS APPROVED BY THE CITY ENGINEER.

OPEN SPACE GOLF COURSE NOTE: IF ANY OF THE GOLF COURSE LOTS ARE CONVEYED, ACCESS SHALL BE AFFORDED BY MEANS OF RESERVATION OF GRANT IN THE DEEDS OR DEEDS OF CONVEYANCE. SURVEYOR'S NOTE: GEOLOGICAL RESTRICTED USE AREA IS BLANKET OVER LOT 79


SURVEYOR'S NOTE: FLOOD HAZARD AREA IS PLOTTED HEREON AS (6)

7. AL ESSEMENT FOR FLOOD CONTROL PURPOSES AND INCORDENTAL PURPOSES, RECORDED OCTOBER 10, 2000 IN PROTECTION OF CONTROL PURPOSES, RECORDED OCTOBER 10, 2000 IN PAGING OF; LOS ANGELES COUNTY FLOOD CONTROL DISTRICT, A BODY CORPORATE AND POLITIC AFFECTISAS DESCRIBED THEREON

DOCUMENT RE-RECORDED JULY 30, 2002 AS INSTRUMENT NO. 02-1777823 OF OFFICIAL RECORDS. surveyor's note: flood control easement plotted hereon as \bigcirc surveyor's note: temporary construction easements plotted hereon as \bigcirc


- 8. THE TERMS, PROVISIONS AND EASEMENT(S) CONTAINED IN THE DOCUMENT ENTITLED "ROAD EASEMENT AND MAINTENANCE AGREEMENT" RECORDED OCTOBER 31, 2000 AS INSTRUMENT NO. 00-1700352 OF OFFICIAL RECORDS.
- AN EASEMENT FOR WATER LINE AND INCIDENTAL PURPOSES, RECORDED DECEMBER 11, 2000 AS INSTRUMENT NO. 00-1923801 OF OFFICIAL RECORDS.


 IN FANCR OF-SANTA CLARITA WATER COMPANY, A CORPORATION, ITS SUCCESSORS AND ASSIGNS AFFECTISAS DESCRIBED THEREIN. surveyor's note: plotted hereon as $\left\langle 9\right\rangle$




4 PRIVATE DRIVE 34'

'A', 'B', 'C', 'D', 'E' AND 'F' DRIVES










NED:					OWNER DEVELOPER:
JHF, PDO					SAND CANYON
ED:					COUNTRY CLUB
PDO					27734 SAND CANYON ROAD
EO:					SANTA CLARITA, CA, 91387 TELEPHONE: (213) 700-6883
JHF	NO.	REVISIONS	DATE	BY	OWNER: STEVE KIM






MAJOR LAND DIVISION VESTING TENTATIVE TRACT MAP NO. 78248 EASEMENT DESCRIPTION DETAILS AND SECTIONS

09/05/2018 JOB No. 0261-001-001 SHEET THE UNINCORPORATED AREA OF THE COUNTY OF LOS ANGELES STATE OF CALIFORNIA





4.	Santa Clarita Department Coe	of Public efficients	Works Area	Study Zoning




City of Santa Clarita Engineering Services Division


SEWAGE FLOW COEFFICIENTS


ZONING		DESCRIPTION	COEFFICIENT
			(cfs/gross acreage)
		Residential Estate – large custom single family homes on uniquely configured lots	0.00075
_	RVL	Residential Very Low Density - 1 DU/AC	0.001
Residential	RL	Residential Low Density – 2.2 DU/AC	0.0015
side	RS	Residential Suburban - 5 DU/AC	0.005
Res	RM	Residential Moderate – 11 DU/AC	0.012
		Residential Medium High – 20 DU/AC	0.015
	RH	Residential High – 28 DU/AC	0.023
developed lar	nd, and for e	all be used for undeveloped land, land that is not entitled, and intitled residential developments (except apartment complexes) used in lieu of the above coefficients. Agricultural - 1 single family home/ legal lot	
M <mark>ixed-Use</mark>	MU		existing zone coefficient 0.016
9 0		Open Space - Natural / Unimproved	0
Open Space	00	Open Space - Parks	0.0002
en 8	os	Community Rooms	0.0005
Community Pool Facilities		0.001	
<u>a</u>	CTC	Commercial Town Center	
Commercial	CC	Community Commercial	0.015
mu	CN	Commercial Neighborhood	0.015
ŏ	CO	Commercial Office	
al	VSR	Visitor Serving/Resort	
Industrial	BP	Business Park	0.021
npu	IC	Industrial Commercial	0.021
=	1	Industrial	
_	UG1	Urban General 1	0.0 <mark>05</mark>
SP 3: Newhall Specific Plan	UG2	Urban General 2	0.012
SP 3: Newhal Specific Plan	UC	Urban Center	0.015
3: I ecif	COR	Corridor	0.021
SP Sp	CD	Creative District	0.021
	OS	Open Space	0
			(gal/student)
		Elementary & Junior High Schools	25
Schools		High School	37.5
Ę,		University & College	50
(/)			


5.	Mancara (TTM063022) Sewer Area Study	














9/13/2018 thru 9/21/2018









9/13/2018 thru 9/21/2018



7. Bonding Estimate	

City of Santa Clarita Department of Public Works - Engineering Services Division

Updated September, 2017

Bond & Fee Calculation Sheet - Sewer

Instructions:

- Complete fields below highlighted in yellow
- On Line B1, using the drop-down arrow, select "Y" or "N" as applicable
- All bond and fee amounts will automatically calculate and be summarized below

Notes:

- Inspection fees calculated below are an estimated amount and subject to change. The fee is based on the final approved plan and date of payment. Verify fee amount with Engineering Services Division prior to payment.

Prepared by:				
Heidy Siles		٦	Fract / Parcel Map #	78248
Name			Lot #	
(661)705-2203		Address	27734 Sand Canyor	n Road
Phone			Master Case #	
hsiles@hunsaker.com			ENG	
Email			STD	
9/27/2018			SS	
Date prepared			PC	
(place Engineer's seal, exp.date & signature below)				
	Approved by:			
	Name			
	Signature			
	Date			
SUMMARY				

Valuation	\$145,002.75	(A)
Bonds		
Sewer - Faithful Performance	\$153,700.00	(G)
Sewer - Labor & Materials	\$76,850.00	(G/2)
Bond Processing Fee	\$237.00	
Plan Review Fee	\$1,822.84	(1)
Record Management Fee	\$47.24	
Encroachment Permit - Sewer		
Inspection Fee	\$4,723.54	(F)
Permit Issuance Fee	\$45.00	
Total =	\$4,768.54	

SEWER - CONSTRUCTION COST							
Item Quantity Unit Cost Total (

Sewer Pipe - Vitrified Clay Pipe					
4" VCP		\$ 93.29	/ LF	\$	-
6" VCP		\$ 95.77	/ LF	\$	-
8" VCP		\$ 101.76	/ LF	\$	-
10" VCP		\$ 107.74	/ LF	\$	-
12" VCP		\$ 113.73	/ LF	\$	-
15" VCP		\$ 119.71	/ LF	\$	-
18" VCP	638	\$ 125.71	/ LF	\$	80,201.72
Manhole					
Manhole	5	\$ 5,985.92	each	\$	29,929.60
Break into Existing Manhole	- C	\$ 2,394.36		\$	-
Extra Depth Construction					
Extra Depth Construction (10' - 12')		\$ 12.57	/IF	\$	-
Extra Depth Construction (12' - 14')		\$ 18.55		\$	-
Extra Depth Construction (14' - 16')		\$ 31.14		\$	_
Extra Depth Construction (16' - 18')		\$ 37.12		\$	_
Extra Depth Construction (18' - 20')		\$ 43.69		\$	-
Miscellaneous Items					
4" Ductile Iron Pipe		\$ 43.56	/ LF	\$	_
6" Ductile Iron Pipe		\$ 53.69	/ LF	\$	_
8" Ductile Iron Pipe		\$ 70.91	/ LF	\$	-
10" Ductile Iron Pipe		\$ 74.96	/ LF	\$	-
12" Ductile Iron Pipe		\$ 86.11	/ LF	\$	-
14" Ductile Iron Pipe		\$ 92.18	/ LF	\$	-
16" Ductile Iron Pipe		\$ 97.25	/ LF	\$	-
≥ 18" Ductile Iron Pipe		\$ 108.39	/ LF	\$	-
Concrete Encasement or Cradle		\$ 31.14	/ LF	\$	-
Special Encasement or Cradle		\$ 61.66	/ LF	\$	-
Excavation in Rock Areas		\$ 31.14	/ LF	\$	-
Unstable Bedding		\$ 25.15	/ LF	\$	-
Jacking Steel Casing		\$ 677.62	/ LF	\$	-
Breaking Pavement & Resurfacing - AC		\$ 7.78		\$	-
Breaking Pavement & Resurfacing - Concrete		\$ 13.77		\$	-
Backflow Preventer		\$ 436.97	each	\$	-
Cleanout (6")		\$ 875.14		\$	-
Cast Iron Pipe		\$ 7.87	/ in / ft	\$	-
Join Existing VCP		\$ 281.21	each	\$	-
Lump Sum <i>(enter dollar amount)</i>			each	\$	-
				TOTAL = \$	110,131.32

SEWER - BOND							
(B1) Traffic Control Plan required? (click in cell and	Υ	Traffic Control Plan (5% x A) =	\$	5,506.57			
use drop-down arrow to select 'Y' for Yes or 'N' for No)		Contingency [15% x (A+B)] =	\$	17,345.68			
		Inflation $[12\% \times (A+B+C)] =$	\$	15,958.03			
		Improvement Total (A+B+C+D) =	\$	148,941.60			
		Inspection (Use Table 1) =	\$	4,723.54			
		Sewer Bond Amount (E+F) =	\$	153,700.00			
		round up to	near	rest hundred			

PLAN REVIEW FEE	
Valuation for Plan Review Fee (A+D+15% Contingency) =	\$ 145,002.75
*Plan Review Fee (Use Table 2) =	\$ 1,822.84

*Plan Reviews beyond 3rd submittal will require payment of an additional review fee in the amount of 15% of original plan review fee.

TABLE 1: Inspection Fee Calculation*							
<u>Valuation</u>	Total (E)						
\$1 to \$10,0	000	10% of valuation					
\$10,000 to	\$20,000	\$	1,000.00	+	5.0%	over	\$10,000
\$20,001 to	\$200,000	\$	1,500.00	+	2.5%	over	\$20,000
\$200,000	and over	\$	6,000.00	+ _	2.0%	over	\$200,000

TABLE 2: Plan Review Fee Calculation						
	Valuation Total (H)	Plan Check Fee (I)				
	\$5,000 or less	\$371				
	\$5,001 to \$25,000	\$388				
	\$25,001 to \$100,000	\$388	+	\$	13.52	per \$1,000 over \$25,000
	\$100,000 and over	\$1,401.61	+	\$	9.36	per \$1,000 over \$100,000



COUNTY SANITATION DISTRICTS OF LOS ANGELES COUNTY

1955 Workman Mill Road, Whittier, CA 90601-1400 Mailing Address: P.O. Box 4998, Whittier, CA 90607-4998 Telephone: (562) 699-7411, FAX: (562) 699-5422 www.lacsd.org

GRACE ROBINSON HYDE Chief Engineer and General Manager

July 3, 2019

Ref. DOC 4999798

Mr. Hai Nguyen City of Santa Clarita 23920 Valencia Boulevard Suite 302 Santa Clarita, CA 91355

Dear Mr. Nguyen:

Revised Response to the Revised NOP for Sand Canyon Resort Project

The Santa Clarita Valley Sanitation District (District) responded to a Revised Notice of Preparation of a Draft Environmental Impact Report (NOP) for the subject project on May 2, 2019 (copy enclosed). The proposed project is located within the jurisdictional boundaries of the District. We offer the following amendment:

• The District determined the wastewater originating from the proposed project site will discharge to a local sewer line, which is not maintained by the Districts, for conveyance to the Districts' Soledad Canyon Section 5 Trunk Sewer, located in Soledad Canyon Road at Los Canyon Road. The Districts' 18-inch diameter trunk sewer has a capacity of 5.7 million gallons per day (mgd) and conveyed a peak flow of 2.2 mgd when last measured in 2018.

The previous response letter misidentified wastewater flow tributary to the Soledad Canyon Section 4 Trunk Sewer. As a result of the amendment provided herein, the developer is no longer required to submit a build-out schedule. If you have any questions, please contact the undersigned at (562) 908-4288, extension 2717.

Very truly yours,

Adriana Raza

Customer Service Specialist Facilities Planning Department

AR:ar

Enclosure

cc: A. Schmidt

A. Howard



COUNTY SANITATION DISTRICTS OF LOS ANGELES COUNTY

1955 Workman Mill Road, Whittier, CA 90601-1400 Mailing Address: P.O. Box 4998, Whittier, CA 90607-4998 Telephone: (562) 699-7411, FAX: (562) 699-5422 www.lacsd.org

GRACE ROBINSON HYDE Chief Engineer and General Manager

May 2, 2019

Ref. DOC: 4999798

Mr. Hai Nguyen City of Santa Clarita 23920 Valencia Boulevard Suite 302 Santa Clarita, CA 91355

Dear Mr. Nguyen:

Response to Revised NOP for the Sand Canyon Resort Project

The Santa Clarita Valley Sanitation District (District) received a Revised Notice of Preparation of a Draft Environmental Impact Report (NOP) for the subject project on April 4, 2019. The proposed project is located within the jurisdictional boundaries of the District. Previous comments submitted by the District in correspondence dated November 15, 2018 (copy enclosed) still apply the subject project with the following updated information:

- 1. The Districts' 15-inch diameter Soledad Canyon Section 4 Trunk Sewer, located in a private right of way in the Santa Clara River southeast of the south terminus of Hidaway Avenue, is at capacity. Please submit a copy of the project's build-out schedule to the undersigned to ensure the project is considered when planning future sewerage system relief and replacement projects.
- 2. The expected increase in average wastewater flow from the revised project scope, described in the notice as a total of 392 hotel rooms, including the view villas, 25,000 square feet of Dining area, and a 33,000 square-foot Spa/Gym/Salon, is 95,970 gallons per day.

If you have any questions, please contact the undersigned at (562) 908-4288, extension 2717.

Very truly yours,

Adriana Raza

Customer Service Specialist Facilities Planning Department

AR:ar

Enclosure

cc:

A. Schmidt

A. Howard

DOC 5081736.SCVD



COUNTY SANITATION DISTRICTS OF LOS ANGELES COUNTY

1955 Workman Mill Road, Whittier, CA 90601-1400 Mailing Address: P.O. Box 4998, Whittier, CA 90607-4998 Telephone: (562) 699-7411, FAX: (562) 699-5422 www.lacsd.org

GRACE ROBINSON HYDE Chief Engineer and General Manager

November 15, 2018

Ref. Doc. No.: 4817284

Mr. Hai Nguyen City of Santa Clarita 23920 Valencia Boulevard Suite 302 Santa Clarita, CA 91355

Dear Mr. Nguyen:

NOP Response for the Sand Canvon Resort Project

The Santa Clarita Valley Sanitation District (District) received a Notice of Preparation of a Draft Environmental Impact Report for the subject project on October 18, 2018. The proposed project is located within the jurisdictional boundaries of the District. We offer the following comments regarding sewerage service:

- 1. The wastewater flow originating from the proposed project will discharge to a local sewer line, which is not maintained by the District, for conveyance to the District's Soledad Canyon Trunk Sewer Section 4, located in a private right of way in the Santa Clara River southeast of the terminus of Hidaway Avenue. The District's 15-inch diameter trunk sewer has a capacity of 2.7 million gallons per day (mgd) and conveyed a peak flow of 1.5 mgd when last measured in 2012.
- Availability of sewer capacity depends upon project size and timing of connection to the sewerage system. Because there are other proposed developments in the area, the availability of trunk sewer capacity should be verified as the project advances. Please submit a copy of the project's build-out schedule to the undersigned to ensure the project is considered when planning future sewerage system relief and replacement projects.
- 3. The District operates two water reclamation plants (WRPs), the Saugus WRP and the Valencia WRP, which provide wastewater treatment in the Santa Clarita Valley. These facilities are interconnected to form a regional treatment system known as the Santa Clarita Valley Joint Sewerage System (SCVJSS). The SCVJSS has a capacity of 28.1 mgd and currently produces an average recycled water flow of 18.4 mgd.
- 4. The expected average wastewater flow from the project, described in the notice as a total of 322 hotel rooms and 25 villas, is 44,150 gallons per day. For a copy of the District's average wastewater generation factors, go to www.lacsd.org, Wastewater & Sewer Systems, click on Will Serve Program, and click on the Table 1, Loadings for Each Class of Land Use link.

- The District is empowered by the California Health and Safety Code to charge a fee for the privilege of connecting (directly or indirectly) to the District's Sewerage System for increasing the strength or quantity of wastewater discharged from connected facilities. This connection fee is a capital facilities fee that is imposed in an amount sufficient to construct an incremental expansion of the Sewerage System to accommodate the proposed project. Payment of a connection fee will be required before a permit to connect to the sewer is issued. For more information and a copy of the Connection Fee Information Sheet, go to www.lacsd.org, Wastewater & Sewer Systems, click on Will Serve Program, and search for the appropriate link. In determining the impact to the Sewerage System and applicable connection fees, the Districts' Chief Engineer and General Manager will determine the user category (e.g. Condominium, Single Family home, etc.) that best represents the actual or anticipated use of the parcel or facilities on the parcel. For more specific information regarding the connection fee application procedure and fees, please contact the Connection Fee Counter at (562) 908-4288, extension 2727.
- 6. In order for the District to conform to the requirements of the Federal Clean Air Act (CAA), the capacities of District wastewater treatment facilities are based on the regional growth forecast adopted by the Southern California Association of Governments (SCAG). Specific policies included in the development of the SCAG regional growth forecast are incorporated into clean air plans, which are prepared by the South Coast and Antelope Valley Air Quality Management Districts in order to improve air quality in the South Coast and Mojave Desert Air Basins as mandated by the CCA. All expansions of District facilities must be sized and service phased in a manner that will be consistent with the SCAG regional growth forecast for the counties of Los Angeles, Orange, San Bernardino, Riverside, Ventura, and Imperial. The available capacity of District treatment facilities will, therefore, be limited to levels associated with the approved growth identified by SCAG. As such, this letter does not constitute a guarantee of wastewater service, but is to advise you that the District intends to provide this service up to the levels that are legally permitted and to inform you of the currently existing capacity and any proposed expansion of District facilities.

If you have any questions, please contact the undersigned at (562) 908-4288, extension 2717.

Very truly yours,

Adriana Raza

Customer Service Specialist Facilities Planning Department

AR:ar

cc: A. Schmidt

A. Howard