



LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS

Limited Hazardous Materials Survey

Little Tujunga Canyon Road Bridge Replacement over Buck Canyon Creek Project

Prepared by
Los Angeles County Department of Public Works
Construction Division
Environmental Compliance Unit
November 14, 2017

Project No. RDC0014790

PCA No. D250000323

Table of Contents

1.	INTRODUCTION.....	2
2.	SITE DESCRIPTION.....	2
3.	OBJECTIVE.....	2
4.	METHODOLOGY	3
5.	RESULTS.....	3
6.	CONCLUSIONS AND RECOMMENDATIONS.....	6

Attachment 1 – Site Photos

Attachment 2 – Lead, Analytical Report and Chain-of-Custody Record

Attachment 3 – Asbestos, Analytical Report and Chain-of-Custody Record

Attachment 4 – LACDPW 60% Preliminary Plan Drawings dated 9/15/16

1. INTRODUCTION

This letter report summarizes the hazardous materials sampling conducted for the Little Tujunga Canyon Road Bridge Replacement over Buck Canyon Creek Project located at 14465 Little Tujunga Canyon Road, Sylmar in Los Angeles County, California 91342.

The Los Angeles County Department of Public Works (LACDPW) is proposing to remove and replace the existing bridge structure.

In order to prepare specific project bid specifications, a limited structure survey for potentially hazardous materials including asbestos, lead based paint (LBP), and Treated Wood Waste (TWW) was conducted for suspect materials impacted by the proposed project. The sampling was conducted on October 31, 2017 by Construction Division – Environmental Compliance Unit (CON-ECU), Marie Tullai, a California Division of Occupational Safety and Health (DOSH) Certified Asbestos Consultant (CAC) and California Department of Public Health Certified Lead Inspector/Assessor (CDPH I/A) and David Simon, a DOSH CAC and Certified Lead Project Monitor (CDPH PM).

Sampling was limited to the items impacted by the “Little Tujunga Canyon Road Bridge Replacement over Buck Canyon Creek” 60% Preliminary Plan Drawings dated September 15, 2016 provided by LACDPW Design Division (Attachment 4).

2. SITE DESCRIPTION

The Little Tujunga Canyon Road Bridge over Buck Canyon Creek is located at 14465 Little Tujunga Canyon Road, Sylmar, in Los Angeles County, California. The project consists of removing and replacing the existing bridge structure.

3. OBJECTIVE

The purpose of the field sampling activities was to determine if lead, asbestos, or any other suspected regulated hazardous materials will be impacted by the proposed project referenced above.

4. METHODOLOGY

Lead Surface Coatings

Samples were collected, labeled, and delivered under strict chain of custody to AETL, in Burbank, California who subcontracted the analysis to LA Testing Laboratories, an Environmental Lead Laboratory Accreditation Program (ELLAP) accredited laboratory. The paint chip samples were analyzed for lead by Environmental Protection Agency (EPA) method 7420.

Asbestos Containing Materials (ACM)

The sample was collected, labeled, and delivered under strict chain of custody to AETL who subcontracted the analysis to LA Testing Laboratories, a National Voluntary Laboratory Accreditation Program (NVLAP) accredited laboratory in South Pasadena, California. Analysis for asbestos was conducted by EPA method 600/R-93/116 using polarized light microscopy.

Treated Wood Waste (TWW)

According to Title 22, California Code of Regulations (CCR), Section 67386 "Alternative Management Standards for Treated Wood Waste" generators of TWW can presume their TWW to be hazardous waste and bypass the laboratory analysis. Pressure treated wood was observed and presumed to be TWW for handling and disposal purposes.

5. RESULTS

Lead Surface Coatings

A list of suspect lead-based paints sampled and their results are presented in Table 1.

Table 1 Lead Analytical Results						
Sample No.	Substrate	Location	Color	Lead Concentration (parts per million [ppm])	Classification*	Photo No.
103101	Metal	Beam (underside of bridge, near center)	Grey	290	LCP	3

Table 1 Lead Analytical Results						
Sample No.	Substrate	Location	Color	Lead Concentration (parts per million [ppm])	Classification*	Photo No.
103102	Metal	Beam (underside of bridge at northwest corner)	Grey (shiny) with Orange under layer	170,000	LBP	4
103103	Metal	"A" Frame Beam (southeast portion of bridge)	Grey	160	LCP	5
103104	Metal	Pole at apex of "A" Frame (east side of bridge)	Black with Orange under layer	89,000	LBP	6
103105	Asphalt	Traffic Striping Paint (center of bridge)	Yellow	None Detected <100	Non-Lead	7
103106	Asphalt	Traffic Striping Paint (east side of bridge)	White	None Detected <100	Non-Lead	8

Sample results in bold exceeded the concentrations that qualify as lead containing or lead based paint.

*LBP = Lead Based Paint

LCP = Lead Containing Paint

LBP is defined by the CDPH, Title 17, CCR, Division 1, Chapter 8, as paint containing 5,000 ppm, 0.5 percent by weight, or 1 milligram per square centimeter (mg/cm²) by X-Ray Fluorescence (XRF) analysis or greater. LCP is paint that does not qualify as LBP, but still contains detectable quantities of lead.

The State of California, Department of Occupational Safety and Health (Cal/OSHA), Title 8, California Code of Regulations (CCR) 1532.1 applies to all construction work where an employee may be occupationally exposed to lead. Where lead is present in any quantity, (Title 8, CCR 1532.1 Appendix B) Cal/OSHA requires an initial determination of whether any worker's exposure to lead exceeds the Action Level (AL) of 30 micrograms per cubic meter ($\mu\text{g}/\text{m}^3$) averaged over an 8-hour day.

When conducting activities defined by Title 8, CCR 1532.1 (d)(2)(A) as "trigger tasks", such as manual demolition, manual scraping, manual sanding, heat gun applications, abrasive blasting, cutting, welding, or torch burning, the employer shall treat the employee as if the employee were exposed to lead above the Permissible Exposure Limit (PEL) of $50 \mu\text{g}/\text{m}^3$ averaged over an 8-hour day, and implement employee protective measures per Title 8, CCR 1532.1(d)(2)(E). Required employee protection measures include appropriate respiratory protection, personal protective clothing, change areas, hand washing facilities, biological monitoring, and training.

Sample No. 103102 (Photo No. 4) and Sample No. 103104 (Photo No. 6) had lead concentrations that met or exceeded the 5,000 ppm threshold to be defined as a LBP. These samples were collected from the grey (shiny) paint with orange under layer on the metal beams supporting the bridge and the black paint with the orange under layer on the metal poles at the apex of the timber "A" frame on the sides of the bridge.

Sample No. 103101 (Photo No. 3) and Sample No. 103103 (Photo No. 5) had detectable lead concentrations below 5,000 ppm. These samples were collected from the grey paint on the metal beams supporting the bridge and the grey paint on the metal beams of the "A" frame on the sides of the bridge.

No lead was detected in Sample No. 103105 (Photo No. 7) and Sample No. 103106 (Photo No. 8) which were collected from the yellow and white paint striping on the road surface of the bridge based on the limitations of the analysis method.

The laboratory results and chain of custody record for the lead-paint chip samples are included as Attachment 2.

Asbestos Containing Materials (ACM)

A list of suspect asbestos containing materials sampled and their results are presented in Table 2.

Table 2 Asbestos Analytical Results						
Sample No.	Location	Material	Asbestos Type and Content	Friability	Classification	Photo No.
103107	Wood "A" Frame (northwest portion of bridge)	Grey Mastic	10% Chrysotile	No	ACM	9

ACM is defined by the Occupational Safety and Health Administration (OSHA) 29 CFR 1001 and Cal/OSHA Title 8, Section 1529 as any material containing greater than 1% asbestos. Cal/OSHA further defines an asbestos containing construction material (ACCM) as any manufactured construction material which contains more than 1/10th of 1% asbestos by weight.

Sample No. 103107 (Photo No. 9) which was collected from the grey mastic on the "A" frame timber was found to contain asbestos at a concentration that defines this material as ACM. The analytical laboratory report and chain of custody record are included as Attachment 3.

Treated Wood Waste

The pressure treated timber observed on the exterior of the Headworks structure is assumed to contain creosote (Photo Nos. 9, 10, and 11). Based on this assumption the timber is regulated under Title 22, CCR, Section 67386 "Alternative Management Standards for Treated Wood Waste".

6. CONCLUSIONS AND RECOMMENDATIONS

Lead Surface Coatings

The grey (shiny) paint with the orange under layer on the metal beams supporting the bridge and the black paint with the orange under layer on the metal poles at the apex of the timber

“A” frame on the sides of the bridge contain concentrations of lead greater than the regulatory level of 5,000 ppm of lead and are considered LBP.

The grey paint on the metal beams supporting the bridge and the grey paint on the metal beams of the “A” frame on the sides of the bridge contain detectable levels of lead below 5,000 ppm. Although these paints did not meet or exceed the level of 5,000 ppm for LBP, these surface coatings contain detectable levels of lead and are regulated by Cal/OSHA. Any areas of peeling or deteriorating paint shall be stabilized to prevent loose and flaking paint from becoming detached and impacting the surrounding environment. The paint shall be abated in any areas that may require cutting.

Cal/OSHA, Title 8, CCR 1532.1 requires the employer to treat any employee conducting any of several “trigger tasks” commonly associated with renovation and demolition activities such as torching, manual demolition, or using non-HEPA (high-efficiency particulate air) equipped tools or vacuums as if they were exposed above the PEL of $50 \mu\text{g}/\text{m}^3$ until an exposure assessment shows otherwise. Renovation or demolition of components coated with LBP or other lead-containing materials will require workers who are appropriately certified, trained, and employ proper work methods and protective equipment to minimize exposure to themselves and the surrounding environment.

Painted surfaces in areas not accessible, and which were not tested for lead content, cannot be presumed to be free of lead. Therefore, if renovation or demolition activities reveal paint types that were not sampled, additional sampling would be required prior to activities that would disturb the painted surfaces unless those surfaces are presumed to contain lead.

Asbestos

The grey mastic on the “A” frame timber contains asbestos and is considered to be ACM. Suspect asbestos materials in areas not accessible at the time of the hazardous materials survey, and which were not tested for asbestos content, cannot be presumed to be free of asbestos. Therefore, if renovation or demolition activities reveal suspect asbestos materials that were not sampled, additional sampling would be required prior to activities that would disturb the suspect asbestos materials unless those surfaces are presumed to contain asbestos.

Other Hazardous Materials

The existing timber to be removed from the bridge structure is categorized as TWW and shall be removed and disposed of per Title 22, CCR, Section 67386 "Alternative Management Standards for Treated Wood Waste". This regulation also requires the employer to provide training for all employees handling TWW and all employees that may reasonably be expected to contact TWW.

Prepared By:



✓ Marie Tullai, CIH
CAC #92-0219
CDPH Lead I/A #11088


Reviewed By:



David Simon
CAC #92-0005
CDPH Lead PM #24204

Attachments:

- Attachment 1 – Site Photos
- Attachment 2 – Lead, Analytical Report and Chain-of-Custody Record
- Attachment 3 – Asbestos, Analytical Report and Chain-of-Custody Record
- Attachment 4 – LACDPW 60% Preliminary Plan Drawings dated 9/15/16

Approved By	Construction Division	Date
	Environmental Compliance Unit	1-2-18

Attachment 1

Site Photos



LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS
CONSTRUCTION DIVISION
PHOTOGRAPHIC RECORD

PROJECT NAME	PROJECT No.	SHEET	1	OF	6
Little Tujunga Canyon Road Bridge Replacement over Buck Canyon Creek	D250000323				



PROJECT PHOTOGRAPHIC NUMBER		1	
DESCRIPTION	View of the bridge looking toward the northwest.		
PHOTOGRAPHED BY	D. Simon	DATE	09/20/2017



PROJECT PHOTOGRAPHIC NUMBER		2
DESCRIPTION	View looking up at the bridge from the bed of Buck Canyon Creek.	
PHOTOGRAPHED BY	D. Simon	DATE 09/20/2017



LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS
CONSTRUCTION DIVISION
PHOTOGRAPHIC RECORD

PROJECT NAME	Little Tujunga Canyon Road Bridge Replacement over Buck Canyon Creek	PROJECT No.	D250000323	SHEET	2	OF	6
--------------	---	----------------	------------	-------	---	----	---



PROJECT PHOTOGRAPHIC NUMBER		3
DESCRIPTION	Underside of beam with grey paint under bridge.	
Lead Paint Sample No. 103101. 290 ppm, LCP		
PHOTOGRAPHED BY	D. Simon	DATE
		10/31/2017



PROJECT PHOTOGRAPHIC NUMBER		4
DESCRIPTION	Underside of beam with grey (shiny) paint with orange under layer. Lead Paint Sample No. 103102. 170,000 ppm, LBP	
PHOTOGRAPHED BY	D. Simon	DATE 10/31/2017



LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS
CONSTRUCTION DIVISION
PHOTOGRAPHIC RECORD

PROJECT NAME	Little Tujunga Canyon Road Bridge Replacement over Buck Canyon Creek	PROJECT No.	D250000323	SHEET	3	OF	6
--------------	---	----------------	------------	-------	---	----	---



PROJECT PHOTOGRAPHIC NUMBER		5
DESCRIPTION	"A" Frame Beam with grey paint. Lead Paint	
Sample No. 103103. 160 ppm, LCP.		
PHOTOGRAPHED BY	D. Simon	DATE
		10/31/2017




PROJECT PHOTOGRAPHIC NUMBER		6
DESCRIPTION	Black paint with orange under layer on metal pole at apex of "A" Frame. Lead Paint Sample No. 103104. 89,000 ppm, LBP.	
PHOTOGRAPHED BY	D. Simon	DATE 10/31/2017



LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS
CONSTRUCTION DIVISION
PHOTOGRAPHIC RECORD

PROJECT NAME	Little Tujunga Canyon Road Bridge Replacement over Buck Canyon Creek	PROJECT No.	D250000323	SHEET	4	OF	6
--------------	---	----------------	------------	-------	---	----	---



PROJECT PHOTOGRAPHIC NUMBER		7
DESCRIPTION	Yellow Road Striping. Lead Paint Sample	
No. 103105. No lead detected.		
PHOTOGRAPHED BY	D. Simon	DATE
		10/31/2017




PROJECT PHOTOGRAPHIC NUMBER		8
DESCRIPTION	White Road Striping. Lead Paint Sample No. 103106.	
No lead detected.		
PHOTOGRAPHED BY	D. Simon	DATE
		10/31/2017




LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS
CONSTRUCTION DIVISION
PHOTOGRAPHIC RECORD

PROJECT NAME	Little Tujunga Canyon Road Bridge Replacement over Buck Canyon Creek	PROJECT No.	D250000323	SHEET	5	OF	6
--------------	---	----------------	------------	-------	---	----	---



PROJECT PHOTOGRAPHIC NUMBER		9
DESCRIPTION	Grey Mastic. Asbestos Sample No. 103107.	
10% chrysotile asbestos, ACM.		
PHOTOGRAPHED BY	D. Simon	DATE
		10/31/2017



PROJECT PHOTOGRAPHIC NUMBER		10	
DESCRIPTION	Treated Wood Timber at underside of bridge.		
PHOTOGRAPHED BY	D. Simon	DATE	09/20/2017



LOS ANGELES COUNTY DEPARTMENT OF PUBLIC WORKS
CONSTRUCTION DIVISION
PHOTOGRAPHIC RECORD

PROJECT NAME	Little Tujunga Canyon Road Bridge Replacement over Buck Canyon Creek	PROJECT No.	D250000323	SHEET	6	OF	6
--------------	---	----------------	------------	-------	---	----	---



PROJECT PHOTOGRAPHIC NUMBER		11
DESCRIPTION	Treated Wood Timber railing.	
PHOTOGRAPHED BY	D. Simon	DATE
		09/20/2017



PROJECT PHOTOGRAPHIC NUMBER		12	
DESCRIPTION	Treated Wood Timber at bridge abutments.		
PHOTOGRAPHED BY	D. Simon	DATE	09/20/2017

Attachment 2

Lead, Analytical Report and Chain-of-Custody Record



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181
Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

Ordered By

LA County Dept. of Public Works
GMED Materials Lab 900 S. Fremont Ave,
4th Floor
Alhambra, CA 91803-

Telephone: (626) 458-5100
Attention: Robert Larson

Number of Pages 3
Date Received 10/31/2017
Date Reported 11/09/2017

Job Number	Order Date	Client
90055	10/31/2017	LACDPW

Project ID: RDC0014790
Project Name: Little Tujunga Rd.
Site: Little Tujunga Canyon Rd.
Sylmar, CA

Enclosed please find results of analyses of 6 solid samples which were analyzed as specified on the attached chain of custody. If there are any questions, please do not hesitate to call.

Attachment: 3 pages

Checked By: _____

Approved By: _____

Cyrus Razmara, Ph.D.
Laboratory Director



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street, Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181
Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

CHAIN OF CUSTODY RECORD

103206

AETL JOB NO. **90055** Page **1** of **1**

COMPANY LHC DPW		PROJECT MANAGER Robert Larson / Marie Tullai	
COMPANY ADDRESS 9005 Fremont Ave, Alhambra, CA 91803		PHONE / FAX (310) 850-4458	
PROJECT NAME Little Tujunga Overlook Canyon		PROJECT # RDC0014790	
SITE NAME AND ADDRESS Little Tujunga Canyon Rd, Sylmar, CA 91781		PCA No. D250000333	
		BO# EN00000000000000000000	

SAMPLE ID	LAB ID	DATE	TIME	MATRIX	CONTAINER NUMBER/SIZE	PRES.
103101	90055-01	10/31/17	1100	bulk	1 bag	N/A
103102	90055-02	10/31/17	1100	bulk	1 bag	N/A
103103	90055-03	10/31/17	1100	bulk	1 bag	N/A
103104	90055-04	10/31/17	1100	bulk	1 bag	N/A
103105	90055-05	10/31/17	1100	bulk	1 bag	N/A
103106	90055-06	10/31/17	1100	bulk	1 bag	N/A

SAMPLE RECEIPT - TO BE FILLED BY LABORATORY		RELINQUISHED BY SAMPLER:		RELINQUISHED BY:	
TOTAL NUMBER OF CONTAINERS 6		PROPERLY COOLED Y / N / NA		1.	
CUSTODY SEALS (1) NA		SAMPLES INTACT Y / N / NA		2.	
RECEIVED IN GOOD COND. Y / N		SAMPLES ACCEPTED Y / N		3.	
TURN AROUND TIME		DATA DELIVERABLE REQUIRED			
<input checked="" type="checkbox"/> NORMAL <input type="checkbox"/> RUSH		<input type="checkbox"/> HARD COPY <input checked="" type="checkbox"/> PDF			
<input type="checkbox"/> SAME DAY <input type="checkbox"/> NEXT DAY		<input type="checkbox"/> GEOTRACKER (GLOBAL ID)			
<input type="checkbox"/> 2 DAYS <input type="checkbox"/> 3 DAYS		<input type="checkbox"/> OTHER (PLEASE SPECIFY)			

ANALYSIS REQUESTED		TEST INSTRUCTIONS & COMMENTS	
7430 lead		Email results to: rlarson@dpw.lacounty.gov mtullai@dpw.lacounty.gov (Report Results) 1 PPM	
X		Grey paint (shiny)	
X		Grey paint	
X		Black w/ orange paint	
X		Yellow paint stripe	
X		White paint stripe	

DISTRIBUTION: WHITE - Laboratory, CANARY - Laboratory, PINK - Project/Account Manager, YELLOW - Sampler/Originator



American Environmental Testing Laboratory Inc.

2834 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181
Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

COOLER RECEIPT FORM

Client Name: <u>LACDPW</u>		
Project Name:		
AETL Job Number: <u>90055 & 90056</u>		
Date Received: <u>10/31/12</u> Received by: <u>Juan Larde</u>		
Carrier: <input type="checkbox"/> AETL Courier <input checked="" type="checkbox"/> Client <input type="checkbox"/> GSO <input type="checkbox"/> FedEx <input type="checkbox"/> UPS		
<input type="checkbox"/> Others:		
Samples were received in: <input checked="" type="checkbox"/> Cooler (<u>1</u>) <input type="checkbox"/> Other (Specify):		
Inside temperature of shipping container No 1: <u>3.5</u> , No 2: , No 3:		
Type of sample containers: <input type="checkbox"/> VOA, <input type="checkbox"/> Glass bottles, <input type="checkbox"/> Wide mouth jars, <input type="checkbox"/> HDPE bottles, <input type="checkbox"/> Metal sleeves, <input checked="" type="checkbox"/> Others (Specify): <u>Plastic bag</u>		
How are samples preserved: <input type="checkbox"/> None, <input type="checkbox"/> Ice, <input checked="" type="checkbox"/> Blue Ice, <input type="checkbox"/> Dry Ice		
<input checked="" type="checkbox"/> None, <u>HNO₃</u> , <u>NaOH</u> , <u>ZnOAc</u> , <u>HCl</u> , <u>Na₂S₂O₃</u> , <u>MeOH</u>		
Other (Specify):		
	No, explain below	Name, if client was notified.
1. Are the COCs Correct?	<input checked="" type="checkbox"/>	
2. Are the Sample labels legible?	<input checked="" type="checkbox"/>	
3. Do samples match the COC?	<input checked="" type="checkbox"/>	
4. Are the required analyses clear?	<input checked="" type="checkbox"/>	
5. Is there enough samples for required analysis?	<input checked="" type="checkbox"/>	
6. Are samples sealed with evidence tape?	<u>NA</u>	
7. Are sample containers in good condition?	<input checked="" type="checkbox"/>	
8. Are samples preserved?	<input checked="" type="checkbox"/>	
9. Are samples preserved properly for the intended analysis?	<input checked="" type="checkbox"/>	
10. Are the VOAs free of headspace?	<u>NA</u>	
11. Are the jars free of headspace?	<u>↓</u>	

Explain all "No" answers for above questions:



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181

Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

Page: 1 A

Ordered By

LA County Dept. of Public Works
GMED Materials Lab 900 S. Fremont Ave,
4th Floor
Alhambra, CA 91803-

Telephone: (626) 458-5100

Attention: Robert Larson

Project ID: RDC0014790

Date Received 10/31/2017

Date Reported 11/09/2017

Job Number	Order Date	Client
90055	10/31/2017	LACDPW

CERTIFICATE OF ANALYSIS

CASE NARRATIVE

AETL received 6 samples with the following specification on 10/31/2017.

Lab ID	Sample ID	Sample Date	Matrix	Quantity Of Containers
90055.01	103101	10/31/2017	Solid	1
90055.02	103102	10/31/2017	Solid	1
90055.03	103103	10/31/2017	Solid	1
90055.04	103104	10/31/2017	Solid	1
90055.05	103105	10/31/2017	Solid	1
90055.06	103106	10/31/2017	Solid	1

Method ^ Submethod	Req Date	Priority	TAT	Units
(7420)	11/07/2017	2	Normal	mg/Kg

The samples were analyzed as specified on the enclosed chain of custody.
No analytical non-conformances were encountered.

Unless otherwise noted, all results of soil and solid samples are based on wet weight.

Checked By: _____

Approved By: _____

Cyrus Razmara, Ph.D.
Laboratory Director



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181

Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

ANALYTICAL RESULTS

Ordered By

LA County Dept. of Public Works
GMED Materials Lab
900 S. Fremont Ave, 4th Floor
Alhambra, CA 91803-

Telephone: (626)458-5100

Attn: Robert Larson

Page: 2

Project ID: RDC0014790

Project Name: Little Tujunga Rd.

Site

Little Tujunga Canyon Rd.
Sylmar, CA

AETL Job Number	Submitted	Client
90055	10/31/2017	LACDPW

Method: (7420), Total Lead

QC Batch No: 321725758

Our Lab I.D.			Method Blank	90055.01	90055.02	90055.03	90055.04
Client Sample I.D.				103101	103102	103103	103104
Date Sampled				10/31/2017	10/31/2017	10/31/2017	10/31/2017
Date Prepared			11/02/2017	11/02/2017	11/02/2017	11/02/2017	11/02/2017
Preparation Method			3050B	3050B	3050B	3050B	3050B
Date Analyzed			11/02/2017	11/02/2017	11/02/2017	11/02/2017	11/02/2017
Matrix			Solid	Solid	Solid	Solid	Solid
Units			mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg
Dilution Factor			1	1	1	1	1
Analytes	MDL	PQL	Results	Results	Results	Results	Results
Lead	100	100	ND	290	170,000	160	89,000



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181
Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

ANALYTICAL RESULTS

Ordered By

LA County Dept. of Public Works
GMED Materials Lab
900 S. Fremont Ave, 4th Floor
Alhambra, CA 91803-

Site

Little Tujunga Canyon Rd.
Sylmar, CA

Telephone: (626)458-5100

Attn: Robert Larson

Page: 3

Project ID: RDC0014790

Project Name: Little Tujunga Rd.

AETL Job Number	Submitted	Client
90055	10/31/2017	LACDPW

Method: (7420), Total Lead

QC Batch No: 321725758

Our Lab I.D.			90055.05	90055.06			
Client Sample I.D.			103105	103106			
Date Sampled			10/31/2017	10/31/2017			
Date Prepared			11/02/2017	11/02/2017			
Preparation Method			3050B	3050B			
Date Analyzed			11/02/2017	11/02/2017			
Matrix			Solid	Solid			
Units			mg/Kg	mg/Kg			
Dilution Factor			1	1			
Analytes	MDL	PQL	Results	Results			
Lead	100	100	ND	ND			



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street, Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181
Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

Data Qualifiers and Descriptors

Data Qualifier:

#:	Recovery is not within acceptable control limits.
*:	In the QC section, sample results have been taken directly from the ICP reading. No preparation factor has been applied.
B:	Analyte was present in the Method Blank.
D:	Result is from a diluted analysis.
E:	Result is beyond calibration limits and is estimated.
H:	Analysis was performed over the allowed holding time due to circumstances which were beyond laboratory control.
J:	Analyte was detected. However, the analyte concentration is an estimated value, which is between the Method Detection Limit (MDL) and the Practical Quantitation Limit (PQL).
M:	Matrix spike recovery is outside control limits due to matrix interference. Laboratory Control Sample recovery was acceptable.
MCL:	Maximum Contaminant Level
NS:	No Standard Available
S6:	Surrogate recovery is outside control limits due to matrix interference.
S8:	The analysis of the sample required a dilution such that the surrogate concentration was diluted below the method acceptance criteria.
X:	Results represent LCS and LCSD data.

Definition:

%Limi:	Percent acceptable limits.
%REC:	Percent recovery.
Con.L:	Acceptable Control Limits
Conce:	Added concentration to the sample.
LCS:	Laboratory Control Sample
MDL:	Method Detection Limit is a statistically derived number which is specific for each instrument, each method, and each compound. It indicates a distinctively detectable quantity with 99% probability.



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street, Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181
Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

Data Qualifiers and Descriptors

MS:	Matrix Spike
MS DU:	Matrix Spike Duplicate
ND:	Analyte was not detected in the sample at or above MDL.
PQL:	Practical Quantitation Limit or ML (Minimum Level as per RWQCB) is the minimum concentration that can be quantified with more than 99% confidence. Taking into account all aspects of the entire analytical instrumentation and practice.
Recov:	Recovered concentration in the sample.
RPD:	Relative Percent Difference

**LA Testing**

520 Mission Street, South Pasadena, CA 91030

Phone/Fax: (323) 254-9960 / (323) 254-9982

<http://www.LATesting.com>pasadenalab@lateesting.com

LA Testing Order: 321725758

CustomerID: 32AETL21

CustomerPO: 22394-SUB

ProjectID:

Attn: **Jim Lin****American Environmental Testing Lab, Inc.**
2834 North Naomi Street**Burbank, CA 91504**

Phone: (818) 845-8200

Fax: (818) 845-8840


Received: 11/01/17 12:50 PM

Collected: 10/31/2017

Project: 90055

Test Report: Lead in Paint Chips by Flame AAS (SW 846 3050B/7000B)*

<i>Client Sample Description</i>	<i>Lab ID</i>	<i>Collected</i>	<i>Analyzed</i>	<i>Lead Concentration</i>
90055-01	321725758-0001	10/31/2017	11/2/2017	
Site: Solid				290 ppm
90055-02	321725758-0002	10/31/2017	11/2/2017	
Site: Solid				170000 ppm
90055-03	321725758-0003	10/31/2017	11/2/2017	
Site: Solid				160 ppm
90055-04	321725758-0004	10/31/2017	11/2/2017	
Site: Solid				89000 ppm
90055-05	321725758-0005	10/31/2017	11/2/2017	
Site: Solid				<100 ppm
90055-06	321725758-0006	10/31/2017	11/2/2017	
Site: Solid				<100 ppm


Jerry Drapala Ph.D, Laboratory Manager
or other approved signatory

*Analysis following Lead in Paint by EMSL SOP/Determination of Environmental Lead by FLAA. Reporting limit is 0.010 % wt based on the minimum sample weight per our SOP. Unless noted, results in this report are not blank corrected. This report relates only to the samples reported above and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities. Samples received in good condition unless otherwise noted. "<" (less than) result signifies that the analyte was not detected at or above the reporting limit. Measurement of uncertainty is available upon request. The QC data associated with the sample results included in this report meet the recovery and precision requirements unless specifically indicated otherwise. Definitions of modifications are available upon request.

Samples analyzed by LA Testing South Pasadena, CA CA ELAP 2283, AIHA-LAP, LLC ELLAP 102814

Initial report from 11/02/2017 15:29:37

Test Report ChmSnglePrm/nQC-7.32.3 Printed: 11/9/2017 3:10:46 PM

Page 1 of 1



Chain of Custody

EMSL Order Number (Lab Use Only):

321725758#

LATESTING
520 MISSION STREET
S. PASADENA, CA 91030
PHONE: (800) 303-0047
FAX: (323) 254-9982

Company: <u>AETL</u>		EMSL-Bill to: <input type="checkbox"/> Same <input type="checkbox"/> Different if Bill to is Different note Instructions in Comments**	
Street: <u>2834 N. Naomi St.</u>		Third Party Billing requires written authorization from third party	
City: <u>Burbank</u>	State/Province: <u>CA</u>	Zip/Postal Code: <u>91504</u>	Country: <u>USA</u>
Report To (Name): <u>Jim Lin</u>		Fax #: <u>818-845-8200</u>	Purchase Order: <u>22394-SUB</u>
Telephone #: <u>818-845-8200</u>		Email Address: <u>Jim.Lin@AETLAB.COM</u>	
Project Name/Number: <u>90055</u>		Please Provide Results: <input type="checkbox"/> Fax <input checked="" type="checkbox"/> Email <input type="checkbox"/> Mail	
U.S. State Samples Taken: <u>CA</u>		Connecticut Samples: <input type="checkbox"/> Commercial <input type="checkbox"/> Residential	
Turnaround Time (TAT) Options* - Please Check			
<input type="checkbox"/> 3 Hour <input type="checkbox"/> 6 Hour <input type="checkbox"/> 24 Hour <input type="checkbox"/> 48 Hour <input type="checkbox"/> 72 Hour <input type="checkbox"/> 96 Hour <input checked="" type="checkbox"/> 1 Week <input type="checkbox"/> 2 Week			
*For RUSH TATs Please Call Ahead to Confirm Lab Hours and Availability. Not all TAT options are valid for every test. Materials Science and IAQ TATs are in Business Days rather than Hours (i.e. 24 Hour = End of Next Business Day)			
Asbestos			
PCM - Air <input type="checkbox"/> NIOSH 7400 <input type="checkbox"/> w/8hr. TWA TEM - Air <input checked="" type="checkbox"/> 4-4.5hr TAT (AHERA ONLY) <input type="checkbox"/> AHERA 40 CFR, Part 763 <input type="checkbox"/> NIOSH 7402 <input type="checkbox"/> EPA Level II <input type="checkbox"/> ISO 10312 TEM - Water Fibers $\geq 10\mu m$ <input type="checkbox"/> Waste <input type="checkbox"/> Drinking All Fiber Sizes <input type="checkbox"/> Waste <input type="checkbox"/> Drinking		PLM - Bulk <input type="checkbox"/> PLM EPA 600/R-93/116 <input type="checkbox"/> PLM EPA NOB (<1%) <input type="checkbox"/> NYS 198.1 (friable-NY) <input type="checkbox"/> NYS 198.6 (non-friable-NY) Point Count <input type="checkbox"/> 400 (<0.25%) <input type="checkbox"/> 1000 (<0.1%) <input type="checkbox"/> 400 (<0.25%) <input type="checkbox"/> 1000 (<0.1%) TEM - Dust <input type="checkbox"/> Microvac - ASTM D 5755 <input type="checkbox"/> Wipe-ASTM D6480	
Flame Atomic Absorption <input checked="" type="checkbox"/> Chips SW846-7000B or AOAC 974.02 <input type="checkbox"/> Soil SW846-7000B/7420 <input type="checkbox"/> Air NIOSH 7082 <input type="checkbox"/> Wastewater SM3111B or SW846-7000B/7420 <input type="checkbox"/> ASTM Wipe SW846-7000B/7420 <input type="checkbox"/> non ASTM Wipe SW846-7000B/7420 <input type="checkbox"/> TCLP SW846-1311/7420/SM 3111B		ICP <input type="checkbox"/> Air NIOSH 7300 Modified <input type="checkbox"/> non ASTM Wipe SW846-6010B or C <input type="checkbox"/> ASTM Wipe SW846-6010B or C <input type="checkbox"/> Soil SW846-6010 B or C <input type="checkbox"/> Waste Water SW846-6010B or C <input type="checkbox"/> TCLP SW846-6010B or C	
Graphite Furnace Atomic Absorption <input type="checkbox"/> Soil SW846-7421 <input type="checkbox"/> Wastewater EPA 200.9 <input type="checkbox"/> Air NIOSH 7105 <input type="checkbox"/> Drinking Water EPA 200.9		Other: <input type="checkbox"/>	
Lead (Pb)			
Microbiology Wipe and Bulk Samples <input type="checkbox"/> Mold & Fungi - Direct Examination <input type="checkbox"/> Mold & Fungi Culture (Genus Only) <input type="checkbox"/> Mold & Fungi Culture (Genus & Species) <input type="checkbox"/> Bacterial Count & ID (Up to Three Types) <input type="checkbox"/> Bacterial Count & ID (Up to Five Types) <input type="checkbox"/> MRSA <input type="checkbox"/> Pseudomonas aeruginosa Water Samples <input type="checkbox"/> Total Coliform & E.coli (P/A) <input type="checkbox"/> Fecal Coliform (SM 9222D) <input type="checkbox"/> Sewage Screen <input type="checkbox"/> Heterotrophic Plate Count (SM 9215)		Air Samples <input type="checkbox"/> Mold & Fungi (Spore Trap) <input type="checkbox"/> Mold & Fungi Culture (Genus Only) <input type="checkbox"/> Mold & Fungi (Genus & Species) <input type="checkbox"/> Bacterial Culture & ID (Up to Three Types) <input type="checkbox"/> Bacterial Culture & ID (Up to Five Types) <input type="checkbox"/> Endotoxin Testing Real Time Q-PCR (See Analytical Guide for Code) Code: _____ Legionella <input type="checkbox"/> Level 1 <input type="checkbox"/> Level 2 <input type="checkbox"/> Level 3 <input type="checkbox"/> Level 4 Other: <input type="checkbox"/>	
**Comments/Special Instructions: _____		Materials Science <input type="checkbox"/> Common Particle ID (large particles) <input type="checkbox"/> Full Particle ID (environmental dust) <input type="checkbox"/> Basic Material ID (solids) <input type="checkbox"/> Advanced Material ID <input type="checkbox"/> Physical Testing (Tensile, Compression) <input type="checkbox"/> Combustion-by-products (soot, char, etc.) <input type="checkbox"/> X-Ray Fluorescence (elem. analysis) <input type="checkbox"/> X-Ray Diffraction (Crystalline Part.) <input type="checkbox"/> MMVFs (Fibrous glass, RCF's) <input type="checkbox"/> Particle Size (sieve/microscopy/laser) <input type="checkbox"/> Combustible Dust <input type="checkbox"/> Petrographic Examination Other: <input type="checkbox"/>	
Client Sample #s <u>90055-2</u> → <u>90055-06</u>		Total # of Samples: <u>SIX</u>	
Relinquished (Client) <u>Steve Kim</u>		Date: <u>11-1-17</u>	
Received (Lab): <u>OTI (WAT)</u>		Date: <u>11-1-17</u>	
Analysis Completed In Accordance with EMSL's Terms and Conditions located in the Analytical Price Guide		Time: <u>12:50pm</u>	



Chain of Custody
EMSL Order Number (Lab Use Only):

LATESTING
520 MISSION STREET
S. PASADENA, CA 91030
PHONE: (800) 303-0047
FAX: (323) 254-9982

[illegible]

Attachment 3

Asbestos, Analytical Report and Chain-of-Custody Record



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181
Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

Ordered By

LA County Dept. of Public Works
GMED Materials Lab 900 S. Fremont Ave,
4th Floor
Alhambra, CA 91803-

Telephone: (626) 458-5100
Attention: Robert Larson

Number of Pages 2

Date Received 10/31/2017

Date Reported 11/09/2017

Job Number	Order Date	Client
90056	10/31/2017	LACDPW

Project ID: RDC0014796
Project Name: Little Tujunga Canyon Rd.
Site: Little Tujunga Canyon Rd.
Sylmar, CA

Enclosed please find results of analyses of 1 solid sample which was analyzed as specified on the attached chain of custody. If there are any questions, please do not hesitate to call.

Attachment: 3 pages

Checked By: _____

Approved By: _____

Cyrus Razmara, Ph.D.
Laboratory Director



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street, Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181
Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

CHAIN OF CUSTODY RECORD

No 89087

COMPANY
LAEPDW

COMPANY ADDRESS

900 S. Fremont Ave, Alhambra, CA 91803

PROJECT NAME

Little Tujunga Canyon Rd over Buck Canyon

SITE NAME AND ADDRESS

Little Tujunga Canyon Rd over Buck Canyon, Encombrance No. 1, Little Tujunga Canyon Rd, Sylmar, CA 91789

PROJECT MANAGER

Rob Larson / Marie Tulai

PHONE

(312) 850-4488

FAX

PROJECT # RDC0014796

PO # 355000000000

AETL JOB No.

90056

Page 1 of 1

ANALYSIS REQUESTED

TEST INSTRUCTIONS & COMMENTS

Email Results to:
marson@epw.lacounty.ca
mtulai@epw.lacounty.ca

Grey Mastic

SAMPLE RECEIPT - TO BE FILLED BY LABORATORY

TOTAL NUMBER OF CONTAINERS 1
CUSTODY SEALS Y/N/NA
RECEIVED IN GOOD COND. Y/N

PROPERLY COOLED Y/N/NA
SAMPLES INTACT Y/N/NA
SAMPLES ACCEPTED Y/N

TURN AROUND TIME

☒ NORMAL ☐ RUSH
☐ SAME DAY ☐ NEXT DAY
☐ 2 DAYS ☐ 3 DAYS

DATA DELIVERABLE REQUIRED

☐ HARD COPY
☒ PDF
☐ GEOTRACKER (GLOBAL ID)
☐ OTHER (PLEASE SPECIFY)

RELINQUISHED BY SAMPLER

Signature Marie Tulai
Printed Name Marie Tulai
Date 10/31/17

RECEIVED BY

Signature
Printed Name
Date

RELINQUISHED BY

Signature
Printed Name
Date

2.

RELINQUISHED BY

Signature
Printed Name
Date

3.

1.

2.

3.

DATA DELIVERABLE REQUIRED

Signature
Printed Name
Date

2.

3.

DISTRIBUTION: WHITE - Laboratory, CANARY - Laboratory, PINK - Project/Account Manager, YELLOW - Sampler/Originator



American Environmental Testing Laboratory Inc.

2834 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181
Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

COOLER RECEIPT FORM

Client Name: <u>LACDPW</u>			
Project Name:			
AETL Job Number: <u>90055 & 90056</u>			
Date Received: <u>10/31/12</u>		Received by: <u>Jean Claude</u>	
Carrier: <input checked="" type="checkbox"/> AETL Courier <input checked="" type="checkbox"/> Client <input type="checkbox"/> GSO <input type="checkbox"/> FedEx <input type="checkbox"/> UPS			
<input type="checkbox"/> Others:			
Samples were received in: <input checked="" type="checkbox"/> Cooler (<u>1</u>) <input type="checkbox"/> Other (Specify):			
Inside temperature of shipping container No 1: <u>3.5</u> , No 2: , No 3:			
Type of sample containers: <input type="checkbox"/> VOA, <input type="checkbox"/> Glass bottles, <input type="checkbox"/> Wide mouth jars, <input type="checkbox"/> HDPE bottles,			
<input type="checkbox"/> Metal sleeves, <input checked="" type="checkbox"/> Others (Specify): <u>Plastic Jar</u>			
How are samples preserved: <input type="checkbox"/> None, <input type="checkbox"/> Ice, <input checked="" type="checkbox"/> Blue Ice, <input type="checkbox"/> Dry Ice			
<input checked="" type="checkbox"/> None, <u>HNO₃</u> , <u>NaOH</u> , <u>ZnOAc</u> , <u>HCl</u> , <u>Na₂S₂O₃</u> , <u>MeOH</u>			
Other (Specify):			
	Yes	No, explain below	Name, if client was notified
1. Are the COCs Correct?	<input checked="" type="checkbox"/>		
2. Are the Sample labels legible?	<input checked="" type="checkbox"/>		
3. Do samples match the COC?	<input checked="" type="checkbox"/>		
4. Are the required analyses clear?	<input checked="" type="checkbox"/>		
5. Is there enough samples for required analysis?	<input checked="" type="checkbox"/>		
6. Are samples sealed with evidence tape?	<u>NA</u>		
7. Are sample containers in good condition?	<input checked="" type="checkbox"/>		
8. Are samples preserved?	<input checked="" type="checkbox"/>		
9. Are samples preserved properly for the intended analysis?	<input checked="" type="checkbox"/>		
10. Are the VOAs free of headspace?	<u>NA</u>		
11. Are the jars free of headspace?	<u>NA</u>		

Explain all "No" answers for above questions:



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181

Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

Page: 1 A

Ordered By

LA County Dept. of Public Works
GMED Materials Lab 900 S. Fremont Ave,
4th Floor
Alhambra, CA 91803-

Telephone: (626) 458-5100
Attention: Robert Larson

Project ID: RDC0014796
Date Received 10/31/2017
Date Reported 11/09/2017

Job Number	Order Date	Client
90056	10/31/2017	LACDPW

CERTIFICATE OF ANALYSIS CASE NARRATIVE

AETL received 1 samples with the following specification on 10/31/2017.

Lab ID	Sample ID	Sample Date	Matrix	Quantity Of Containers
90056.01	103107	10/31/2017	Solid	1
Method ^ Submethod	Req Date	Priority	TAT	Units
EPA-600R-93/116	11/07/2017	2	Normal	Percent

The samples were analyzed as specified on the enclosed chain of custody.
No analytical non-conformances were encountered.

Unless otherwise noted, all results of soil and solid samples are based on wet weight.

Checked By: _____

Approved By: _____

Cyrus Razmara, Ph.D.
Laboratory Director



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street, Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181
Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

ANALYTICAL RESULTS

Ordered By

LA County Dept. of Public Works
GMED Materials Lab
900 S. Fremont Ave, 4th Floor
Alhambra, CA 91803-

Site

Little Tujunga Canyon Rd.
Sylmar, CA

Telephone: (626)458-5100

Attn: Robert Larson

Page: 2

Project ID: RDC0014796

Project Name: Little Tujunga Canyon Rd.

AETL Job Number	Submitted	Client
90056	10/31/2017	LACDPW

Method: EPA-600R-93/116, Asbestos by Polarized Light Microscopy Analysis (PLM)

Our Lab I.D.		90056.01				
Client Sample I.D.		103107				
Date Sampled		10/31/2017				
Date Prepared		10/31/2017				
Preparation Method		EPA600R93				
Date Analyzed		11/07/2017				
Matrix		Solid				
Units		Percent				
Dilution Factor		1				
Analytes	MDL	PQL	Results			
Asbestos, Total	1.0	1.0	10.0			



LA Testing

520 Mission Street South Pasadena, CA 91030

Tel/Fax: (323) 254-9960 / (323) 254-9982

http://www.LATesting.com / pasadenalab@latesting.com

LA Testing Order: 321726114

Customer ID: 32AETL21

Customer PO:

Project ID:

Attention: Jim Lin

American Environmental Testing Lab, Inc.

2834 North Naomi Street

Burbank, CA 91504

Phone: (818) 845-8200

Fax: (818) 845-8840

Received Date: 10/31/2017 1:50 PM

Analysis Date: 11/07/2017

Collected Date:

Project: 90056

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
90056.01	Solid	Black Fibrous		90% Non-fibrous (Other)	10% Chrysotile
321726114-0001		Homogeneous			

Analyst(s)

Rosa Mendoza (1)


Jerry Drapala Ph.D, Laboratory Manager
or Other Approved Signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%

Samples analyzed by LA Testing South Pasadena, CA NVLAP Lab Code 200232-0, CA ELAP 2283

Initial report from: 11/07/2017 12:21:46



Chain of Custody

EMSL Order Number (Lab Use Only):

#321726114

LATESTING
520 MISSION STREET
S. PASADENA, CA 91030
PHONE: (800) 303-0047
FAX: (323) 254-9987

Company: <u>AETC</u>		EMSL-Bill to: <input checked="" type="checkbox"/> Same <input type="checkbox"/> Different If Bill to is Different note instructions in Comments**	
Street: <u>2834 N. Naomi St.</u>		Third Party Billing requires written authorization from third party	
City: <u>Burbank</u>	State/Province: <u>CA</u>	Zip/Postal Code: <u>91504</u>	Country: <u>USA</u>
Report To (Name): <u>Jim Lin</u>		Fax #: <u>818-245-8840</u>	Purchase Order: <u>22340-543</u>
Telephone #: <u>818-245-8200</u>		Email Address: <u>JimL@ASTLAB.COM</u>	
Project Name/Number: <u>90056</u>		Please Provide Results: <input checked="" type="checkbox"/> Fax <input checked="" type="checkbox"/> Email <input type="checkbox"/> Mail	
U.S. State Samples Taken: <u>CA</u>		Connecticut Samples: <input type="checkbox"/> Commercial <input type="checkbox"/> Residential	
Turnaround Time (TAT) Options* - Please Check			
<input type="checkbox"/> 3 Hour <input type="checkbox"/> 6 Hour <input checked="" type="checkbox"/> 24 Hour <input type="checkbox"/> 48 Hour <input type="checkbox"/> 72 Hour <input checked="" type="checkbox"/> 96 Hour <input checked="" type="checkbox"/> 1 Week <input type="checkbox"/> 2 Week			
*For RUSH TATs Please Call Ahead to Confirm Lab Hours and Availability. Not all TAT options are valid for every test. Materials Science and IAQ TATs are in Business Days rather than Hours (i.e. 24 Hour = End of Next Business Day)			
Asbestos			
PCM - Air <input checked="" type="checkbox"/> NIOSH 7400 <input type="checkbox"/> w/8hr. TWA TEM - Air <input type="checkbox"/> 4-4.5hr TAT (AHERA ONLY) <input type="checkbox"/> AHERA 40 CFR, Part 763 <input checked="" type="checkbox"/> NIOSH 7402 <input checked="" type="checkbox"/> EPA Level II <input type="checkbox"/> ISO 10312 TEM - Water Fibers >10µm <input type="checkbox"/> Waste <input type="checkbox"/> Drinking All Fiber Sizes <input type="checkbox"/> Waste <input checked="" type="checkbox"/> Drinking		PLM - Bulk <input checked="" type="checkbox"/> PLM EPA 600/R-93/116 <input type="checkbox"/> PLM EPA NOB (<1%) <input checked="" type="checkbox"/> NYS 198.1 (friable-NY) <input checked="" type="checkbox"/> NYS 198.6 (non-friable-NY) Point Count <input type="checkbox"/> 400 (<0.25%) <input type="checkbox"/> 1000 (<0.1%) Point Count w/ Gravimetric <input type="checkbox"/> 400 (<0.25%) <input type="checkbox"/> 1000 (<0.1%) TEM - Dust <input type="checkbox"/> Microvac - ASTM D 5755 <input type="checkbox"/> Wipe-ASTM D6480	
Flame Atomic Absorption <input checked="" type="checkbox"/> Chips SW846-7000B or AOAC 974.02 <input type="checkbox"/> Soil SW846-7000B/7420 <input type="checkbox"/> Air NIOSH 7082 <input type="checkbox"/> Wastewater SM3111B or SW846-7000B/7420 <input checked="" type="checkbox"/> ASTM Wipe SW846-7000B/7420 <input type="checkbox"/> non ASTM Wipe SW846-7000B/7420 <input type="checkbox"/> TCLP SW846-1311/7420/SM 3111B Graphite Furnace Atomic Absorption <input checked="" type="checkbox"/> Soil SW846-7421 <input type="checkbox"/> Wastewater EPA 200.9 <input type="checkbox"/> Air NIOSH 7105 <input type="checkbox"/> Drinking Water EPA 200.9		ICP <input checked="" type="checkbox"/> Air NIOSH 7300 Modified <input checked="" type="checkbox"/> non ASTM Wipe SW846-6010B or C <input type="checkbox"/> ASTM Wipe SW846-6010B or C <input type="checkbox"/> Soil SW846-6010 B or C <input type="checkbox"/> Waste Water SW846-6010B or C <input checked="" type="checkbox"/> TCLP SW846-6010B or C Other:	
Microbiology		Materials Science	
Wipe and Bulk Samples <input checked="" type="checkbox"/> Mold & Fungi - Direct Examination <input checked="" type="checkbox"/> Mold & Fungi Culture (Genus Only) <input type="checkbox"/> Mold & Fungi Culture (Genus & Species) <input type="checkbox"/> Bacterial Count & ID (Up to Three Types) <input type="checkbox"/> Bacterial Count & ID (Up to Five Types) <input type="checkbox"/> MRSA <input type="checkbox"/> <i>Pseudomonas aeruginosa</i> Water Samples <input type="checkbox"/> Total Coliform & E.coli (P/A) <input checked="" type="checkbox"/> Fecal Coliform (SM 9222D) <input type="checkbox"/> Sewage Screen <input checked="" type="checkbox"/> Heterotrophic Plate Count (SM 9215)		<input type="checkbox"/> Common Particle ID (large particles) <input checked="" type="checkbox"/> Full Particle ID (environmental dust) <input type="checkbox"/> Basic Material ID (solids) <input checked="" type="checkbox"/> Advanced Material ID <input checked="" type="checkbox"/> Physical Testing (Tensile, Compression) <input checked="" type="checkbox"/> Combustion-by-products (soot, char, etc.) <input type="checkbox"/> X-Ray Fluorescence (elem. analysis) <input checked="" type="checkbox"/> X-Ray Diffraction (Crystalline Part) <input checked="" type="checkbox"/> MMVFs (Fibrous glass, RCF's) <input checked="" type="checkbox"/> Particle Size (sieve/microscopy/laser) <input type="checkbox"/> Combustible Dust <input checked="" type="checkbox"/> Petrographic Examination Other:	
Air Samples <input checked="" type="checkbox"/> Mold & Fungi (Spore Trap) <input type="checkbox"/> Mold & Fungi Culture (Genus Only) <input type="checkbox"/> Mold & Fungi (Genus & Species) <input checked="" type="checkbox"/> Bacterial Culture & ID (Up to Three Types) <input checked="" type="checkbox"/> Bacterial Culture & ID (Up to Five Types) <input type="checkbox"/> Endotoxin Testing Real Time Q-PCR (See Analytical Guide for Code) Code: Legionella <input type="checkbox"/> Level 1 <input type="checkbox"/> Level 2 <input checked="" type="checkbox"/> Level 3 <input type="checkbox"/> Level 4 Other:		IAQ	
**Comments/Special Instructions:		Nuisance Dust NIOSH <input checked="" type="checkbox"/> 0500 <input checked="" type="checkbox"/> 0600 Airborne Dust <input checked="" type="checkbox"/> PM10 <input type="checkbox"/> TSP Silica Analysis: <input type="checkbox"/> All Species Silica Analysis - Single Species <input checked="" type="checkbox"/> Alpha Quartz <input checked="" type="checkbox"/> Cristobalite <input checked="" type="checkbox"/> Tridymite <input checked="" type="checkbox"/> HVAC Efficiency <input checked="" type="checkbox"/> Carbon Black <input checked="" type="checkbox"/> Airborne Oil Mist Radon Testing: Call for Kit and COC Other:	
Client Sample #s: <u>90056.01</u>		Total # of Samples: <u>one</u>	
Relinquished (Client): <u>Alison K. Brown</u>		Date: <u>10-31-17</u>	
Received (Lab): <u>ASTLAB</u>		Date: <u>10/31/17</u>	
		Time: <u>1:35C</u>	
		Time: <u>1:350</u>	

Analysis Completed in Accordance with EMSL's Terms and Conditions located in the Analytical Price Guide



#3. 25114

#32172611

Analysis Completed in Accordance with EMSL's Terms and Conditions located in the Analytical Price Guide



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street, Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181
Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

Data Qualifiers and Descriptors

Data Qualifier:

#:	Recovery is not within acceptable control limits.
*:	In the QC section, sample results have been taken directly from the ICP reading. No preparation factor has been applied.
B:	Analyte was present in the Method Blank.
D:	Result is from a diluted analysis.
E:	Result is beyond calibration limits and is estimated.
H:	Analysis was performed over the allowed holding time due to circumstances which were beyond laboratory control.
J:	Analyte was detected . However, the analyte concentration is an estimated value, which is between the Method Detection Limit (MDL) and the Practical Quantitation Limit (PQL).
M:	Matrix spike recovery is outside control limits due to matrix interference. Laboratory Control Sample recovery was acceptable.
MCL:	Maximum Contaminant Level
NS:	No Standard Available
S6:	Surrogate recovery is outside control limits due to matrix interference.
S8:	The analysis of the sample required a dilution such that the surrogate concentration was diluted below the method acceptance criteria.
X:	Results represent LCS and LCSD data.

Definition:

%Limi:	Percent acceptable limits.
%REC:	Percent recovery.
Con.L:	Acceptable Control Limits
Conce:	Added concentration to the sample.
LCS:	Laboratory Control Sample
MDL:	Method Detection Limit is a statistically derived number which is specific for each instrument, each method, and each compound. It indicates a distinctively detectable quantity with 99% probability.



American Environmental Testing Laboratory Inc.

2834 & 2908 North Naomi Street, Burbank, CA 91504 • DOHS NO: 1541, LACSD NO: 10181
Tel: (888) 288-AETL • (818) 845-8200 • Fax: (818) 845-8840 • www.aetlab.com

Data Qualifiers and Descriptors

MS:	Matrix Spike
MS DU:	Matrix Spike Duplicate
ND:	Analyte was not detected in the sample at or above MDL.
PQL:	Practical Quantitation Limit or ML (Minimum Level as per RWQCB) is the minimum concentration that can be quantified with more than 99% confidence. Taking into account all aspects of the entire analytical instrumentation and practice.
Recov:	Recovered concentration in the sample.
RPD:	Relative Percent Difference


Attachment 4

LACDPW 60% Preliminary Plan Drawings
Dated 9/15/16


COUNTY OF LOS ANGELES
DEPARTMENT OF PUBLIC WORKS
LITTLE TUJUNGA CANYON ROAD

BRIDGE REPLACEMENT OVER

BUCK CANYON CREEK
PROJECT ID NO. RDC0014790



LOCATION MAP



INDEX TO PLANS

SHEET	TITLE
<u>PLAN B</u>	
1.	TITLE SHEET
2.	GENERAL PLAN
3.	REMOVAL PLAN
4.	REMOVAL DETAILS
5.	DECK CONTOURS
6.	FOUNDATION PLAN
7.	TYPICAL SECTION
8.	PRESTRESSED GIRDER DETAILS
9.	TUBULAR HAND RAILING

DRAFTER L. BRADLEY	DESIGNER L. BRADLEY	CHECKER B. FATHOLLAHI	CADD PROJECT FILE NAME RDC0014790.dgn
-----------------------	------------------------	--------------------------	--



Los Angeles County
Department of Public Works

The Information Shown Hereon is
60% PLAN DISTRIBUTION
Unofficial and Subject to Change
Date 9/15/16

[illegible]


Los Angeles County
Department of Public Works
The Information Shown Hereon is
Unofficial and Subject to Change
Date 9/15/16
60% PLAN DISTRIBUTION

PROFILE GRADE
NOT TO SCALE




ELEVATION
SCALE 1" = 10'-0"

GENERAL PLAN
SCALE 1" = 10'-0"




THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD
DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

TYPICAL SECTION
SCALE 1/2" = 1'-0"



STAGE TWO CONSTRUCTION
SCALE 1/2" = 1'-0"




STAGE ONE CONSTRUCTION
SCALE 1/2" = 1'-0"


DATE		REVISIONS	PROJECT NUMBER		BRS. NO.	PCA	X250000323	DWG	PB2	SHEET	2	OF	X

LITTLE TUUNGA CANYON ROAD
OVER
BUCK CANYON
GENERAL PLAN
RDC0014790

PLAN B



- Removal Notes:**
- The existing paint system on structural steel contains lead based paint. The Contractor shall refer to the Special Provisions for requirements regarding lead based paint.
 - The existing timber throughout the bridge and wingwalls contains creosote. The Contractor shall refer to the Special Provisions for requirements regarding creosote.
 - Removal limits are indicated thus:
 - Removal of the existing bridge structure shall not begin until the temporary shoring for the roadway and the temporary shoring for the superstructure is installed.
 - The temporary shoring to support the roadway is shown schematically. The Contractor shall determine the type of shoring, shoring dimensions, and layout necessary to support the roadway during the construction operations. The temporary shoring shall follow the requirements listed in the Temporary Supports, Excavations, and Shoring Notes. The Contractor shall submit the details of the temporary roadway shoring for both Stage One and Stage Two removal to the Engineer to review and approve prior to the start of removal activities.
 - With the approval of the Engineer, the existing deadmen and deadmen rods may remain in place where the deadmen do not interfere with the new structure, and where the deadmen do not interfere with construction operations.
 - The temporary roadway shoring located adjacent to the new abutment during the Stage Two removal shall not interfere with the Stage Two construction operations. The shoring shall be configured in such a way that will allow the Stage Two portion of the abutment stem wall and footing to be joined to the Stage One portion of the abutment.
 - The Contractor shall provide temporary shoring to support the existing commercial driveway during Stage One removal and construction operations.
 - The Contractor shall refer to the Traffic Control Plans for additional requirements and clearances that apply to the portions of the roadway and commercial driveway to remain open to traffic. These requirements may impose additional limitations to the removal limits shown.
- Temporary Supports, Excavations, and Shoring Notes:**
- The temporary superstructure shoring shall be designed to support the dead load of the existing superstructure and a minimum live loading of HS20-44 truck.
 - The Contractor shall refer to the Geotechnical Report for additional requirements for temporary supports, excavations, and shoring.



Los Angeles County
Department of Public Works
60% PLAN DISTRIBUTION
The Information Shown Hereon Is
Unofficial and Subject to Change
Date 9/15/16

PLAN B


COUNTY OF LOS ANGELES DEPARTMENT OF PUBLIC WORKS
LITTLE TUJUNGA CANYON ROAD
OVER
BUCK CANYON
REMOVAL PLAN
RDC0014790




DATE	BY	DESCRIPTION

THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD
DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.


DRAFTER L. BRADLEY	DESIGNER L. BRADLEY	CHECKER B. FATHOLLAHI	CADD PROJECT FILE NAME RDC0014790.dgn	REVIEWED BY	DATE
-----------------------	------------------------	--------------------------	--	-------------	------




SECTION A1-A1
SCALE 1/2" = 1'-0"




SECTION A2-A2
SCALE 1/2" = 1'-0"



SECTION A3-A3
SCALE 1/2" = 1'-0"



SECTION A4-A4
SCALE 1/2" = 1'-0"



SECTION A5-A5
SCALE 1/2" = 1'-0"

- Notes:**
1. The existing paint system on structural steel contains lead based paint. The Contractor shall refer to the Special Provisions for requirements regarding lead based paint.
 2. The existing timber throughout the bridge and wingwalls contains creosote. The Contractor shall refer to the Special Provisions for requirements regarding creosote.
 3. Removal limits are indicated thus:
 4. The temporary shoring to support the superstructure is shown schematically. The Contractor shall determine the type of shoring, shoring dimensions, and layout necessary to support the remaining portion of the existing superstructure during the Stage One construction operations. The temporary shoring shall follow the requirements listed in the Temporary Supports, Excavations, and Shoring Notes on Sheet 3.

Los Angeles County
Department of Public Works
The Information Shown Hereon is
60% PLAN DISTRIBUTION
Unofficial and Subject to Change
Date 9/15/16

DRAFTER	DESIGNER	CHECKER	CADD PROJECT FILE NAME	REVIEWED BY	DATE
L. BRADLEY	L. BRADLEY	B. FATHOLLAHI	RDC0014790.dgn		

THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD
DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DATE	BY	DESCRIPTION




COUNTY OF LOS ANGELES DEPARTMENT OF PUBLIC WORKS
LITTLE TUJUNGA CANYON ROAD
OVER
BUCK CANYON
REMOVAL DETAILS
RDC0014790

PROJECT NUMBER: BR. NO. 0592 P A 0000 D PB4 SHEET 4 OF X

PLAN B

GENERAL NOTES
LOAD AND RESISTANCE
FACTOR DESIGN

DESIGN: AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, FOURTH EDITION WITH 2011 CALIFORNIA AMENDMENTS.
DEAD LOAD: INCLUDES 35 PSF FOR FUTURE WEARING SURFACE.
LIVE LOADING: HL 93 AND PERMIT DESIGN VEHICLE
SEISMIC DESIGN: CALTRANS SEISMIC DESIGN CRITERIA (SDC), VERSION 1.7, APRIL 2013
SEISMIC LOADING: NA
REINFORCED CONCRETE: $f_y = 60,000$ psi
 $f_c = 4,000$ psi
 $n = 8$
DESIGN SOIL PRESSURE: Active pressure xx.pdf
PILE DESIGN LOAD: NA
PRESTRESSED CONCRETE: See "Prestressing Notes" on "Prestressed Girder Details" Sheet
CONSTRUCTION: (MATERIALS & METHODS) STANDARD SPECIFICATIONS - STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION, 2010.



DECK CONTOUR PLAN

SCALE 1/4" = 1'-0"

- Notes:
1. X = 10' intervals along station line
 2. Contours are at top of deck and do not include camber.
 3. Contours are for bridge construction only.
 4. See Plan R beyond bridge.

STANDARD PLANS

2010 California Department of Transportation (Caltrans) Standard Plans
A62C Units of Payment for Excavation and Backfill-Bridge
B0-1 Bridge Details
B0-3 Bridge Details
B0-5 Bridge Details
B0-13 Bridge Details
B6-10 Utility Openings
B6-21 Joint Seats
B11-55 Concrete Barrier Type 732


Caltrans Standard Plan Sheet No.
Detail No.

Los Angeles County
Department of Public Works
60% PLAN DISTRIBUTION
The Information Shown Hereon is
Unofficial and Subject to Change
Date 9/15/16

COUNTY OF LOS ANGELES DEPARTMENT OF PUBLIC WORKS
PLAN B
LITTLE TUJUNGA CANYON ROAD
OVER
BUCK CANYON
DECK CONTOURS
RDC0014790

DRAFTER	DESIGNER	CHECKER	CADD PROJECT FILE NAME	REVIEWED BY	DATE
L. BRADLEY	L. BRADLEY	B. FATHOLLAHI	RDC0014790.dgn		

DATE	BY	DESCRIPTION	PROJECT ENGINEER	DATE	BR. NO.	PCA	DWG	SHEET	OF
					0592	X250000323	PBS	5	X



DRAFTER	DESIGNER	CHECKER	CADD PROJECT FILE NAME	REVIEWED BY	DATE
L. BRADLEY	L. BRADLEY	B. FATHOLLAHI	RDC0014790.dgn		

- Notes:
- Existing topography shall be verified in the field by the Contractor.
 - Existing contours and elevations are based on a Los Angeles County, Department of Public Works survey of Little TuJunga Canyon Road dated September 2011.
 - Contractor shall remove the existing bridge foundation according to the removal plan and details on Sheets 3 and 4.
 - Bottom of footing elevations indicated thus: **XXX.XX**

CURVE DATA					
CURVE	RADIUS	CENTRAL ANGLE	LENGTH	TANGENT	
	FT.	DEG. MIN. SEC.	FT.	FT.	
(A)	130	50	33	52	114.73
(B)	250	4	53	49	21.37

FOUNDATION PLAN

Scale: 1" = 10'-0"

BENCHMARK

NAD 83 CA ZONE 5 COORDS. EPOCH 2007.0
VERT. DATUM = NGVD 1929, 1980 ADJ
PWFB 2318 Pg. 140-155

THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DATE	REV	DESCRIPTION




LITTLE TUJUNGA CANYON ROAD

OVER
BUCK CANYON
FOUNDATION PLAN
RDC0014790


PLAN B

PROJECT NUMBER	DATE	BR. NO. 0592	P.C. X25000323	DWG. P36	SHEET 6 OF X
----------------	------	--------------	----------------	----------	--------------

Los Angeles County
Department of Public Works
The Information Shown Hereon is
60% PLAN DISTRIBUTION
Unofficial and Subject to Change
Date 9/15/16




TYPICAL SECTION




ELEVATION

- Notes:
1. Galvanize rail assembly after fabrication.
 2. Post shall be normal to railing.
 3. Rail tubes shall be shop bent fabricated to fit horizontal curve when radius is less than 950'.
 4. Tube splices shall be located in tubes spanning deck or wall joints. Increase joint width in tubes to match expansion joint width and increase sleeve length correspondingly.
 5. Top rail tube shall be continuous over and less than two posts except a short post spacing is permitted near deck or wall joints or other rail discontinuities as noted.
 6. For details and reinforcement not shown, see Caltrans Standard Plan B11-55.
 7. Post spacing shall be even across the bridge within the allowances shown herein. Submit final layout for Engineers approval prior to fabrication.



SECTION A-A




VIEW G-G

VIEW H-H


SLEEVE

TUBE SPLICE DETAILS

Note:
3/8" DIA nut tack welded to sleeve and drilled and tapped hole in sleeve.



SECTION



SECTION B-B

ELEVATION

RAIL CONNECTION DETAILS

Los Angeles County
Department of Public Works
The Information Shown Hereon is
60% PLAN DISTRIBUTION
Unofficial and Subject to Change
Date 9/15/16

THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DATE	BY	DESCRIPTION

COUNTY OF LOS ANGELES DEPARTMENT OF PUBLIC WORKS

LITTLE TUJUNGA CANYON ROAD

OVER
BUCK CANYON
TUBULAR HAND RAILING
RDC0014790

PROJECT NUMBER: BR-NO 0592 PCA X25000323 DWG PB9 SHEET 9 OF X