

STORM DRAIN LEACH TRENCH TYPICAL SECTION

NOTES

- 1.) INSTALL APPROXIMATELY 1,410 FEET OF STORM DRAIN LEACH TRENCH BELOW THE SIDEWALK ALONG THE SUBDIVISION STREET RIGHT OF WAY TO COLLECT AND PERCOLATE STORM WATER RUNOFF FROM THE SUBDIVISION IMPROVEMENTS.
- 2.) INCREASED RUNOFF FROM THE DEVELOPMENT OF THE LOTS WILL BE COLLECTED AND PERCOLATED USING STORM DRAIN LEACH TRENCHES ON EACH INDIVIDUAL LOT.

