Print Form

Form F

Sample Summary for Electronic Document Submittal

15 copies of this document may be included when a Lead Agency is submitting electronic copies of environmental impact reports, negative declarations, mitigated negative declarations, or notices of preparation to the SCH. The SCH will still accept other summaries, such as an EIR summary prepared pursuant to CEQA Guidelines Section 15123, attached to the electronic copies of the document.

SCH # _____

Lead Agency: Sausalito-Marin City Sanitary District

Project Title: Coloma Pump Station Improvements Project

Project Location: Sausalito (*City*) Marin (*County*)

Please provide a Project Decription (Proposed Actions, location, and/or consequences).

The Sausalito-Marin City Sanitary District (SMCSD) Coloma Pump Station Improvements Project would demolish the existing Scotties pump station and Whiskey Springs pump station and replace both with the new Coloma pump station. The project is adjacent to the intersection of Bridgeway and Coloma Street in Sausalito. The goal of this proposed project is to increase the reliability of the wastewater conveyance system and provide sufficient capacity to convey peak wet weather flows. All construction described below would use open trenching methods.

Scotties Pump Station
The SMCSD-owned and -operated Scotties pump station is at the northwest corner of the intersection of Coloma Street and Bridgeway in Sausalito. As a wet weather pump station, it is active only during peak wet weather events. Constructed in 1955 and rebuilt in 1987, it is an aging subsurface pump station with limited access for maintenance. The Scotties pump station is upstream of the Locust Street pump station and provides wet weather relief when flows in a nearby gravity interceptor are greater than 6 million gallons per day.

To the extent possible, the pump station equipment would be disassembled and removed from the ground for recycling and disposal. The top 3 feet of the wet well would be removed, the remaining void would be filled with lightweight concrete backfill, and the disturbed area would be topped with 3 feet of topsoil and re-vegetated. The abandoned force main, sewer, and vent would be capped and filled with controlled, low-strength material (CLSM). The existing influent sewer manhole would be demolished and replaced with a new manhole and pipeline routed to the new pump station. Any damage to

Please identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

While there are potentially significant adverse impacts to Cultural and Paleontological Resources, Hazards and Hazardous Materials, Noise, and Tribal Cultural Resources, those impacts would be mitigated to less than significant levels.

Mitigation Measure Cultural Resources-1. The SMCSD must inform all personnel connected with excavation and grading operations of the possibility of encountering archaeological resources. If such resources are encountered during construction, all work would cease within the area of the discovery, and a qualified archaeologist would evaluate the nature of the discovery and its significance and provide proper management recommendations. Project personnel must not collect cultural materials discovered on the site.

Mitigation Measure Cultural Resources-2. If paleontological resources are encountered during project construction, the SMCSD would cease all construction, and a qualified paleontologist would evaluate the nature of the discovery and its significance and provide proper management recommendations. Personnel must not collect paleontological resources that are discovered on the site.

Mitigation Measure Cultural Resources-3. If human remains of Native American origin are discovered during excavation or construction, the SMCSD would comply with state laws relating to the disposition of Native American burials, which fall under the jurisdiction of the Native American Heritage Commission (Public Resources Code Section 5097). In addition, state law (CEQA Guidelines Section 15064.5 and the Health and Safety Code Section 7050.5) requires that if human remains are found during project demolition and construction, the project proponent must contact the Marin County Coroner, who in turn must contact the Native American Heritage Commission within 24 hours following a determination that the finds are of

If applicable, please describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

There are no known areas of controversy associated with this project, and no known issues have been raised by agencies or the public.

Please provide a list of the responsible or trustee agencies for the project.

There are no responsible or trustee agencies for this project.