outh of Campus Improvement Project itial Study/Mitigated Negative Declaration	
	Appendix
	Geology and Soils Supporting Information

La Cañada Unified School District—New Outdoor Pool Facility and



La Candad Unified School District—New Outdoor Pool Facility and South of Campus Improvement Project Initial Study/Mitigated Negative Declaration
E.1 - Geotechnical and Geohazards Investigation Report





GEOTECHNICAL AND GEOHAZARDS INVESTIGATION REPORT

PROJECT:

NEW OUTDOOR POOL FACILITY AND SOUTH CAMPUS IMPROVEMENTS
LA CAÑADA HIGH SCHOOL
4463 OAK GROVE DRIVE
LA CAÑADA, CALIFORNIA 91011

FOR:

4490 CORNISHON AVENUE LA CAÑADA, CALIFORNIA 91011



PREPARED BY: GEO-ADVANTEC, INC. 457 W. ALLEN AVENUE, SUITE 113 SAN DIMAS, CALIFORNIA 91773 PROJECT NO. 19-1093(R.01) OCTOBER 10, 2019

TABLE OF CONTENTS

Su	<u>bject</u>	<u>Page</u>
1.	INTRODUCTION	1
2.	SITE CONDITIONS	2
3.	PROPOSED DEVELOPMENTS	2
4.	SCOPE OF SERVICES	3
5.	FIELD EXPLORATORY WORKS	3
6.	SUBSURFACE CONDITIONS	4
7.	LABORATORY TESTING	
8.	GROUNDWATER	
9.	SITE GEOLOGY	
	SEISMIC CONSIDERATIONS	
	10.1. General	
	10.2. Landsliding and Slope Stability	8
	10.3. Liquefaction	8
	10.4. Earthquake-Induced Dry Settlement	9
	10.5. Flooding	9
	10.6. Oil Wells	
11.	CONCLUSIONS AND RECOMMENDATIONS	10
	11.1. General	10
	11.2. Grading Requirements	
	11.2.1. Peripheral Buildings	
	11.2.2. Swimming Pool	
	11.2.3. Demolition of Old Swimming Pool and Grading for New Basketball Court	
	11.3. General Grading Requirements	12
	11.4. Fill Materials and Import	
	11.5. Seismic Coefficients	
	11.6. Foundations	
	11.6.1. General	
	11.6.2. Peripheral Buildings	
	11.6.3. Swimming Pool	
	11.7. Floor Slab	16
	11.8. Basketball Court Slab	
	11.9. Concrete Flatwork	
	11.10. Pavement for Parking Lot	
	•	
	11.11. Utility Trench Backfilling	
	11.12. Excavations	
	11.12.1. General	
	11.12.2. Excavations of Contaminated Soils	21

12.	INFIL	TRATION RATE DETERMINATION	.21
	12.1.	General	21
	12.2.	Test Procedure	22
	12.3.	Results and Feasibility	23
		CORROSIVITY	
14.	SOIL	EXPANSIVITY	.24
15.	OBSE	RVATION AND TESTING	.24
16.	CLOS	SURE	.25

Mr. Harold J. Pierre, P.E. Program Manager Linik CORP. Builders Management 25239 Avenue Tibbitts Valencia, California 91355 October 10, 2019 Project No. 19-1093(R.01)

Subject: Geotechnical and Geohazards Investigation Report,

New Outdoor Pool Facility and South Campus Improvements at

La Cañada High School 4463 Oak Grove Drive La Cañada, California 91011

1. INTRODUCTION

This report presents the results of a Geotechnical and Geohazards Investigation performed by Geo-Advantec, Inc. (GAI) for the proposed New Outdoor Pool Facility and South Campus Improvements project for the La Cañada High School located within the City of La Cañada, California. This geotechnical and geohazard investigation was performed to provide geotechnical information for the design and construction of the proposed developments, as described in the forthcoming sections of this report. This report also includes our recommendations for the design and construction of the proposed developments from a geotechnical standpoint.

The recommendations provided within this submittal are based on the results of our field exploration, laboratory testing, engineering analyses, and our experience from similar projects. Our services were performed in general accordance with our Proposal No. 19-1093(R.01), dated July 2, 2019.

A vicinity map is presented as Figure A-1 within Appendix A. An aerial photo of the site, presented as Figure A-2 within Appendix A, has been used as the base map to depict the approximate locations of the proposed developments, the borings, and the percolation tests performed.

Our professional services have been performed using the degree of care and skill ordinarily exercised, under similar circumstances, by reputable geotechnical consultants practicing in this or similar localities. No other warranty, expressed or implied, is made as to the professional advice included in this report. This report has been prepared for Linik CORP ("Client"), La Cañada Unified School District ("District"), and their design consultant for the subject project. The report has not been prepared for use by other parties and may not contain sufficient information for other parties or the purposes of other uses. The Geotechnical Engineer of Record should be allowed to

review the plans for the proposed developments and perform such additional geotechnical analyses as may be required to confirm the applicability of the recommendations contained in this report to the final design.

2. SITE CONDITIONS

The site of the existing La Cañada High School is located in the City of La Cañada, California. The entire campus is bounded by Interstate 210, Oak Grove Drive, and Berkshire Place on the west, east, and south side, respectively. The campus is also bordered with a learning center (Child Education Center) and another high school (St. Francis High School) to the north side. The proposed developments area focuses on the south part of campus, which currently consist of the Spartan Pool, South Gym, Basketball Court, Junior Varsity Baseball Field, and Student Parking Lot. It should be noted that an old leach field (abandoned in 1997) lies beneath part of the existing basketball court and baseball field, where the new proposed swimming pool will be built. The site is relatively flat (roughly 1 percent north to south descending slope) with an approximate elevation of 1,090 feet above mean sea level (AMSL). More detailed information about the location of the subject project is presented on Figures A-1, A-2a, and A-2b within Appendix A of this report.

3. PROPOSED DEVELOPMENTS

Based on the plan and information provided by the Client, it is our understanding that the proposed developments at La Cañada High School includes:

- 1. Construction of new basketball courts on the footprint of the existing swimming pool.
- 2. Construction of a new 40-meter swimming pool.
- 3. Construction of two new buildings ("peripheral buildings") adjacent to the 40-meter swimming pool. The northern building will be utilized for restroom, locker, and office purposes. The smaller southern building will be utilized for restroom, pool equipment storage, and tickets/announcer booth purposes.
- 4. Expansion of the south parking area to the west side partially into the baseball fields.

Our understanding of the proposed developments is based on the plan and information provided by the Client, and it is the basis for the geotechnical recommendations provided in this submittal.

4. SCOPE OF SERVICES

Our scope of services for this project included the followings:

• Performing a site reconnaissance, evaluating the general site conditions, and marking the

proposed boring locations for the purpose of underground utility clearance.

• Conducting six exploratory borings at the proposed locations within vicinity of the

proposed developments using truck-mounted hollow-stem drilling rig and sampling at 5

feet intervals.

• Conducting three falling head borehole percolation tests for the proposed on-site

stormwater infiltration system.

Performing laboratory testing on selected soil samples obtained from our exploratory

borings.

• Reviewing the field data and laboratory test results and performing engineering analyses.

• Preparing a final geotechnical evaluation report for the site, which includes our findings

and recommendations for the design and construction of the proposed developments from

a geotechnical point of view.

5. FIELD EXPLORATORY WORKS

GAI conducted field exploratory program using One Way Drilling as the drilling contractor on

July 27, 2019, and it consisted of performing a total of six 8-inch diameter borings and three falling

head borehole percolation tests. Figure A-2 within Appendix A presents the approximate locations

of the borings and percolation tests performed plotted on an aerial photo of the site along with the

approximate footprint of the proposed developments.

The borings were conducted using a truck-mounted hollow-stem drilling rig and were drilled down

to the planned depths. The borings were located at the vicinity or within the footprint of the

proposed developments considering accessibility limitations. Table 5.1 summarizes the area,

depth, and samples collected for each boring. Standard Penetration Test (SPT) and Modified California Sampler samples were taken starting at 5 to 7 feet below the ground surface (bgs) and alternating every 5 feet thereafter until the planned depths for Borings B-2 to B-6.

Table 5.1. Borings and Percolation Tests Summary

Boring ID	Developments	Depth (ft)	Sample ^a
B-1	Parking Lot	5.0	Bulk
B-2	Parking Lot	8.5	Bulk, MC
B-3	Peripheral Buildings	8.5	Bulk, SPT
B-4	Peripheral Buildings	41.0	Bulk, SPT, MC
B-5	Peripheral Buildings	41.0	Bulk, SPT, MC
B-6	Demolition Area	7.5	Bulk, MC
P-1	Infiltration System	7.0	Bulk
P-2	Infiltration System	7.0	Bulk
P-3	Infiltration System	7.0	Bulk

^aSPT: Standard Penetration Test

MC: Modified California (Thick wall) Driven Sampler

6. SUBSURFACE CONDITIONS

The soil encountered in our exploratory work was predominantly silty sand with varying amounts of gravel throughout the entire depths. Boring B-4 encountered a thin layer of silty gravel at approximately 15 feet bgs. Clay traces were also encountered in Boring B-4 at 10 feet bgs and Boring B-5 at 40 feet bgs.

The silty sand layers in the upper 10 feet bgs were generally loose to medium dense except for Borings B-3 and B-6, which were medium dense to very dense. From 15 feet bgs to the maximum depth explored (i.e. 41 feet bgs), the silty sand layers were dense to very dense. The encountered soils were generally dry to slightly moist and becoming moist at approximately 25 feet bgs in Boring B-4 and at 35 feet bgs in Boring B-5.

Variations in the soil layer conditions, as well as more detailed information, are indicated on the attached boring logs in Appendix B. Approximate locations of the borings are shown on the boring locations plan, Figure A-2a and A-2b within Appendix A.

The soil conditions described in this report are based on the soils observed in the borings drilled for this investigation and the laboratory test results. It is possible that soil conditions could vary in areas other than the boring locations.

7. LABORATORY TESTING

Laboratory testing, including moisture content, unit weight, gradation, and plasticity index (Atterberg limits) tests were performed on selected samples obtained from the site investigation to aid in the classification of the encountered layers and to evaluate their engineering properties. Also, direct shear, consolidation, R-Value, expansion index, sulfates, chlorides, resistivity, and pH tests (corrosivity tests) have been conducted on selected samples. The following is the list of tests performed:

- Density of Soil in Place by the Drive-Cylinder Method (ASTM D 2937)
- Particle Size Analysis (ASTM D 422)
- Liquid Limit, Plastic Limit, and Plasticity Index (ASTM D 4318)
- Direct Shear Test (ASTM D 3080)
- One-Dimensional Consolidation Properties (ASTM D 2435)
- Resistance R-value and Expansion Pressure (ASTM D 2844)
- Expansion Index (ASTM D 4829)
- Sulfate Content and Chloride Content (CT 417 and CT 422)
- Resistivity and pH Measurements (CT 643)

The results of our laboratory tests are provided in Appendix C, and selected results are shown on the boring logs in Appendix B.

8. GROUNDWATER

As mentioned above, the subject site has an approximate elevation of about 1,090 feet AMSL. We have reviewed the historically highest groundwater contour map (Figure D-2 within Appendix D) excerpted from the *Seismic Hazard Zone Report 014 for the Pasadena 7.5-Minute Quadrangle*

published by the California Department of Conservation. Historically highest groundwater depth

is noted to be at approximately 40 to 50 feet bgs. Additionally, groundwater was not encountered

during our exploratory works to a maximum depth of 41 feet bgs.

Based on the site topography, historically highest groundwater contour map, and data obtained

from the exploratory borings conducted at the site, it is our opinion that the groundwater depth at

the site is lower than 40 feet from the existing grade, and it is unlikely that groundwater would be

encountered during the course of construction for the proposed developments.

9. SITE GEOLOGY

The site is located in the Cresenta Valley, which is bounded by the San Gabriel Mountains to the

north and the Verdugo Mountains to the south. The San Fernando Valley is to the west and the

San Gabriel Valley is to the east. The Cresenta Valley is part of the Transverse Ranges Geomorphic

Province.

The Transverse Ranges Geomorphic Province extends from the Santa Ynez Mountains on the west

to the Little San Bernardino Mountains on the east and consists of east west trending mountains

and valleys. The Transverse Ranges are formed by a step in the San Andreas Fault, which produces

the mountains as a result of the compression from movement on the fault.

Dibblee (1989) showed the site to be underlain by alluvial unconsolidated floodplain deposits of

silts, sand, and gravel of the Holocene age. The borings conducted during our site investigation,

on July 25, 2019 showed that the site, at the explored locations, is generally underlain by silty

sands with varying amounts of gravels to the maximum depth explored. The boring logs are

presented within Appendix B of this report, and the site geologic map is presented in Figure G-1.

10. SEISMIC CONSIDERATIONS

10.1. General

The subject site, like the rest of Southern California, is located within a seismically active region

as a result of being located near the active margin between the North American and Pacific tectonic

plates. The principal source of seismic activity is movement along the northwest-trending regional

faults such as the San Andreas, San Jacinto, Newport-Inglewood, and Whittier-Elsinore fault zones.

By definition of the California Geological Survey (CGS), an active fault is one which has had surface displacement within the Holocene Epoch (roughly the last 11,000 years). The CGS has defined a potentially active fault as any fault which has been active during the Quaternary Period (approximately the last 1,600,000 years). These definitions are used in delineating Earthquake Fault Zones as mandated by the Alquist-Priolo Geologic Hazard Zones Act of 1972 and as subsequently revised in 1997 as the Alquist-Priolo Earthquake Fault Zones. The intent of the act is to require fault investigations on sites located within Special Studies Zone to preclude new construction of certain inhabited structures across the trace of active faults. The subject site is not located within an Alquist-Priolo Earthquake Fault Zone. The nearest active fault is the Sierra Madre Fault. The fault is located approximately 1.19 miles (1.92 km) northeast of our investigation location. No evidence of active or potentially active faulting was observed on the subject site during our investigation. Surface rupture is not considered to be a potential hazard to the site.

Table 10.1 below tabulates the faults, their corresponding maximum magnitude, and distances to the site. Figure G-2 in Appendix G illustrates the fault activity map at the vicinity of the project.

Table 10.1. Active Faults at the Vicinity of the Site

Fault Name	Maximum Magnitude	Distance to the Site (km)
Sierra Madre fault zone (Sierra Madre B)	7.2	1.92
Verdugo-Eagle Rock	6.8	4.63
Raymond	6.7	7.85
Hollywood	6.7	9.27
Santa Monica	7.3	13.31
Elysian Park (Upper)	6.6	13.73
Clamshell-Sawpit	6.6	16.58
San Gabriel	7.2	16.93
Puente Hills (LA)	6.9	22.63

Historic seismicity on the site was evaluated from earthquakes listed in the USGS database and is included in Figure G-3 within Appendix G. From historical records, the site has experienced moderate to severe ground shaking in the past. There are no records of any failures due to historic

earthquakes for the site. No evidence of active or potentially active faulting was observed on the

subject site during our investigation. Surface rupture is not considered to be a potential hazard to

the site.

Probably the most important fault to the site from a seismic shaking standpoint is the northwest

trending Sierra Madre Fault, located approximately 1.19 miles (1.92 kilometers) northeast of the

site. The Sierra Madre Fault is zoned as an active fault in the Alquist-Priolo Fault Zoning Act.

Based on the information available at this time, it is our opinion that a M7.2 earthquake may occur

on the Sierra Madre Fault. Large earthquakes could occur on other faults in the general area, but

because of their greater distance and/or lower probability of occurrence, they are less important to

the site from a seismic shaking standpoint.

Due to the proximity of the site to the Sierra Madre Fault, near field effects from strong ground

motion associated with a large earthquake along this fault may occur at the site. These near field

effects, including "fling" and directivity of strong ground motion, may result in significantly higher

accelerations at the site.

10.2. Landsliding and Slope Stability

As mentioned above the site is relatively flat. Based on the Earthquake Zones of Required

Investigation – Pasadena Quadrangle map, published by the California Geological Survey, the

site is not located in an earthquake-induced landslide zone, as shown in Figure D-1 within

Appendix D. No evidence for landsliding was observed on or in the immediate vicinity of the site.

Therefore, it is our opinion that landsliding is not a potential hazard on the site.

10.3. Liquefaction

Liquefaction may occur when saturated, loose to medium dense, cohesionless soils are densified

by ground vibrations. If the soils are not sufficiently permeable to dissipate these pressures during

and immediately following an earthquake, the densification will result in increased pore water

pressures. When the pore water pressure is equal to or exceeds the overburden pressure,

liquefaction of the affected soil layers occurs. For liquefaction to occur, three conditions are

required:

• ground shaking of sufficient magnitude and duration;

• a ground water level at or above the level of the susceptible soils during the ground shaking;

and

soils that are susceptible to liquefaction.

Based on the Earthquake Zones of Required Investigation – Pasadena Quadrangle map, published

by the California Geological Survey, the site does not lie in a seismic hazard zone of liquefaction

as shown in Figure D-1 within Appendix D. Therefore, due to the zoning of the site, it is our

opinion that liquefaction is not a potential hazard at the subject site.

10.4. Earthquake-Induced Dry Settlement

Strong ground motion during an earthquake will reduce the pore space between soils particles, and

it is well known that loose sands tend to compress during dynamic shaking. Soils underlying the

site and to the maximum depth explored include some coarse-grained layers of silty sands and

well-graded sands with silt. The dry settlement analysis was performed with groundwater level at

approximately 40 feet bgs. The results of our analyses are provided in Figures E-1a and E-1b

within Appendix E of this report, and it indicates that a maximum total earthquake-induced dry

settlement of about $1\frac{1}{2}$ inches is expected to occur at the site.

10.5. Flooding

The site does not lie within a Special Flood Hazard Area (SFHA), i.e. 100-year flood area, nor in a

dam inundation area, as shown on the FEMA Flood Map #06037C1375F (Figure A-3 within

Appendix A). Therefore, flooding is not considered to be a potential hazard to the site.

10.6. Oil Wells

The project site is not located within any oil and/or gas field, and the search result on the oil wells at

the vicinity of the site on the Department of Conservation's Division of Oil, Gas, and Geothermal

Resources (DOGGR) is presented in Figure A-4 within Appendix A. The DOGGR records indicate

that there are no wells within a one-mile radius of the site. Therefore, it is our opinion that no

hazardous materials associated with any oil well/field is expected on the site.

Project No. 19-1093(R.01) October 10, 2019 Geo-Advantec, Inc.

Page 9 of 26

11. CONCLUSIONS AND RECOMMENDATIONS

11.1. General

Based on our understanding of the project, we have determined that the planned developments are feasible from a geotechnical engineering point of view provided the geotechnical recommendations presented in this report are followed. The shallow on-site soils from below the ground surface consist of loose to medium dense silty sands followed by dense to very dense silty sand. Therefore, to reduce any potential future damages, due to likelihood of excessive total and differential settlement under the anticipated loads, the following recommendations should be incorporated into design and construction of the proposed on-site developments. As discussed in the following sections of this report, conventional shallow footings are recommended for the proposed peripheral buildings adjacent to the new 40-meter pool.

It is recommended that a formal review of foundation plans be performed by GAI, when plans become available, to verify the applicability of the recommendations contained herein.

11.2. Grading Requirements

11.2.1. <u>Peripheral Buildings</u>

As discussed, the upper soils strata underlying the site predominantly consists of loose to medium dense silty sands followed by dense to very dense silty sand. Therefore, to provide a more uniform bearing stratum and to minimize any potential settlement to a tolerable level, over-excavation and compaction of the on-site soil below the designated areas for the proposed peripheral buildings is recommended.

It is recommended that the on-site soils below the footprint of proposed buildings be over-excavated, moisture-conditioned, and recompacted, so that the new conventional shallow footings consisting of spread-strip footings be supported entirely on at least 7 feet of compacted fill or engineered fill that extends to 9 feet below the existing grade, whichever provides the deeper fill. As an alternative to conventional shallow footings, the proposed building foundations may also be mat-type foundation supported entirely on at least 3 feet of compacted fill or engineered fill that extends to 5 feet below the existing grade, whichever provides the deeper fill. The over-excavation shall laterally extend at least 5 feet from the outer faces of the perimeter footings in all directions. The over-excavated area shall be backfilled to the designated grade. Adjacent to existing structures, over-excavation shall be performed by employing slot-cut (A-B-C) method.

The backfilled materials shall comply with the requirements outlined in Section 11.4 of this report and shall be moisture-conditioned to a moisture content between the optimum and 3 percent above the optimum moisture content and compacted to at least 95 percent of the maximum dry density obtained per ASTM D1557. Prior to placement of backfill, the bottom of removal shall be observed and confirmed to be competent by the Geotechnical Engineer of Record.

Following the over-excavation, we recommend that the areas to receive engineered fill be scarified to a minimum depth of 8 inches, moisture-conditioned to a moisture content between the optimum and 3 percent above the optimum moisture content, and compacted to at least 90 percent of the maximum dry density obtained per ASTM D1557.

11.2.2. Swimming Pool

The proposed development area for the new swimming pool is within the footprint of an old leach field that was abandoned in 1997 (as mentioned in Section 2). Based on the drawings available to us, the leaching trenches are expected to be about 5 feet deep from the ground surface. The excavation for the swimming pool is expected to be at deeper depth than the bottom of the leaching field trenches. However, contaminated soils are likely to be encountered during excavation and the contractor shall follow the recommendations outlined is Section 11.12.2, and all applicable codes and regulations.

It is recommended that the on-site soils below the footprint of the proposed swimming pool be over-excavated, moisture-conditioned, and recompacted, so that the swimming pool will be supported entirely on at least 2 feet of compacted fill. The over-excavated area shall be backfilled to the designated grade. Adjacent to existing structures, over-excavation shall be performed by employing slot-cut (A-B-C) method.

The backfilled materials shall comply with the requirements outlined in Section 11.4 of this report and shall be moisture-conditioned to a moisture content between the optimum and 3 percent above the optimum moisture content and compacted to at least 95 percent of the maximum dry density obtained per ASTM D1557. Prior to placement of backfill, the bottom of removal shall be observed and confirmed to be competent by the Geotechnical Engineer of Record.

Following the over-excavation, we recommend that the areas to receive engineered fill be scarified to a minimum depth of 8 inches, moisture-conditioned to a moisture content between the optimum and 3 percent above the optimum moisture content, and compacted to at least 90 percent of the maximum dry density obtained per ASTM D1557.

11.2.3. <u>Demolition of Old Swimming Pool and Grading for New Basketball Court</u>

The new basketball court will be built within the footprint of the existing (old) swimming pool. It is recommended that the concrete floor slabs, sidewalls, and other pool construction materials be completely removed during the demolition process. After demolition, the empty swimming pool area shall be backfilled to the designated grade and compacted in layers which, when loose, shall not exceed 8 inches per layer. The backfilled materials shall be compacted to at least 90 percent of the maximum dry density obtained per ASTM D1557.

The top 12 inches of the backfill supporting slab-on-grade for the basketball court shall be compacted to 95 percent of the maximum dry density obtained per ASTM D1557.

The backfilled materials shall comply with the requirements outlined in Section 11.4 of this report and shall be moisture-conditioned to a moisture content between the optimum and 3 percent above the optimum moisture content and compacted to at least 90 percent of the maximum dry density obtained per ASTM D1557.

11.3. General Grading Requirements

All fills, unless otherwise specifically stated in the report, shall be compacted to at least 90 percent of the maximum dry density obtained per ASTM D1557 Method of Soil Compaction. The moisture content during compaction shall be as stated in items 5 and 6 below, unless otherwise specifically stated in the report.

- 1. No fill shall be placed until the area to receive the fill has been adequately prepared and approved by the Geotechnical Consultant or their representative.
- 2. Fill soils should be kept free of debris and organic material.
- 3. Rocks or hard fragments larger than 3 inches may not be placed in the fill without approval of the Geotechnical Consultant or their representative, and in a manner specified for each occurrence.

- 4. The fill material shall be placed in layers which, when loose, shall not exceed 8 inches per layer. Each layer shall be spread evenly and shall be thoroughly mixed during the spreading to insure uniformity of material and moisture.
- 5. When the moisture content of the fill material is too low to obtain adequate compaction, water shall be added and thoroughly dispersed until the soil has a moisture content between the optimum and 3 percent above the optimum moisture content.
- 6. When the moisture content of the fill material is too high to obtain adequate compaction, the fill material shall be aerated by blading or other satisfactory methods until the soil has a moisture content between the optimum and 3 percent above the optimum moisture content.
- 7. Permanent fill and cut slopes should not be constructed at gradients steeper than 2:1 (H:V).

11.4. Fill Materials and Import

In general, the on-site silty sand soils have been determined to have a very low expansion potential and are suitable for backfilling purpose. On-site uncontaminated native soils or imported materials could be used for backfilling purpose. On-site soils or import materials, if used, should have an expansion index (EI) of less than 30 and should contain sufficient fines (binder material) so as to be relatively impermeable and result in a stable subgrade when compacted. The material being used for backfilling purpose should be free of organic materials, debris, and cobbles larger than 3 inches, with no more than 25 percent of the materials being larger than 2 inches in size and no more than 35 percent passing #200 sieve. A bulk sample of potential backfill/import material, weighing at least 30 pounds, should be submitted to the Geotechnical Consultant at least 72 hours before fill operations. Upon approval of the potential backfill earth materials, the contractor will be allowed to start importing/hauling process. All backfill materials should be approved by the Geotechnical Consultant prior to being placed at the site.

11.5. Seismic Coefficients

Under the Earthquake Design Regulations of Chapter 16A, Section 1613A of the CBC 2016, and using the mapped acceleration parameters obtainable from the program available in the Structural Engineers Association of California (SEAOC) website, the following coefficients and factors tabulated in Table 11.1 apply to lateral-force design for structures at the site. Figures G-4 and G-5

within Appendix G show the PSHA Deaggregation at PGA for 2475 years return period and design maps summary report for the site respectively, obtained from the USGS and SEAOC websites.

Table 11.1. ASCE 7 Mapped Seismic Coefficients

Site Parameters	Value
Site Class (CBC 2016 – 1613A.3.2)	D (Stiff Soil)
Seismic Design Category based on Risk Category II (CBC 2016-Table 1604A.5 & 1613A.3)	E
Mapped Acceleration Parameter for Short Period (0.2 Second), S _S	2.708
Mapped Acceleration Parameter for 1.0 Second, S ₁	0.968
Adjusted Maximum Spectral Response Parameter for Short Period (0.2 Second), S_{MS}	2.708
Adjusted Maximum Spectral Response Parameter for 1.0 Second Period, $S_{\rm M1}$	1.453
Design Spectral Response Acceleration Parameter, S _{DS}	1.805
Design Spectral Response Acceleration Parameter, S _{D1}	0.968
Mapped Peak Ground Acceleration, PGA	1.007

Longitude: W 118.179020° Latitude: N 34.190908°

11.6. Foundations

11.6.1. General

By the time of preparation of this report, we had not been provided with the order of the anticipated structural loads applicable on the foundations for the proposed buildings. For the purpose of preparing this report, we assumed that the proposed structures will impose column loads of less than 30 kilo-pounds (kips) and continuous footing loads of less than 3 kips per foot (kpf). As recommended, the proposed footings should be founded entirely within the engineered fills. All footings shall be underlain by compacted fill as addressed in grading section of this report (Section 11.2.). GAI should be notified if the final structural loads increase by more than 10 percent of the above-assumed loads, and to reevaluate our analyses and provide revised recommendations, if necessary. The project's Structural Engineer should design foundations and floor slabs in accordance with the requirements of the applicable building code.

11.6.2. <u>Peripheral Buildings</u>

The proposed locker room, restroom and office buildings may be supported on conventional shallow spread/strip footings designed using a bearing value of 2,000 pounds per square foot (psf) provided that the recommendations addressed in the grading section of this report (Section 11.2.)

are strictly followed and observed by the project's Geotechnical Engineer at the time of construction. Spread and strip footings supporting the proposed structures should have a minimum width of 24 and 18 inches, respectively. The bottom of footings shall be located at least 2 feet below the lowest adjacent finish grade, embedded into the recommended compacted fill and underlain by compacted fill extended to the depth recommended. The recommended allowable bearing capacity should not be increased for any additional footing embedment depth or width.

Also, mat-type foundation may be chosen to support the proposed buildings and may be designed using a bearing value of 1,500 pounds per square foot (psf) provided that the recommendations addressed in the grading section of this report (Section 11.2.) are strictly followed and observed by the project's Geotechnical Engineer at the time of construction.

The recommended bearing value is a net value and the weight of concrete in the footings may be taken as 50 pounds per cubic foot (pcf). The weight of soil backfill may be neglected when determining the downward loads from the footings. A one-third increase in the bearing value may be used when considering wind or seismic loads provided the load reduction factor of 0.75 is not applied to wind or seismic loads for load combinations.

Lateral Resistance: Lateral loads may be resisted by soil friction and by the passive resistance utilized by the compacted on-site granular fill. A coefficient of friction of 0.35 may be used between the footings, floor slabs, and the supporting soils comprised of compacted on-site material, as recommended. The passive resistance of level properly compacted on-site material in direct contact with the footings may be assumed to be equal to the pressure developed by a fluid with a density of 300 pcf, to a maximum pressure of 3,000 psf. A one-third increase in the passive value may be used for wind or seismic loads. The frictional resistance and the passive resistance of the soils may be combined provided that the passive resistance is reduced by one-third.

Settlement: Provided that the proposed footings are constructed per the recommendations provided in preceding sections of this report and have been designed using bearing values recommended herein, we estimate that the total maximum static settlement would be less than about ½ inches and ½ inches for conventional spread/strip footings and mat-foundation system, respectively. Additionally, the effect of excess settlement due to earthquake motions was evaluated and it was concluded that the earthquake-induced dry settlement at the site would be about 1½ inches. However, the over-excavation and recompaction of the loose layers under the proposed foundations will mitigate earthquake-induced dry settlements to a tolerable level of less than 1 inch for conventional spread/

strip footings (Figure E-1b within Appendix E). Therefore, for both spread/strip foundations and mat-foundation system, a combined static plus seismic differential settlement of ½ inches within a horizontal distance of 30 feet may be used for the design purpose.

<u>Modulus of Subgrade Reaction:</u> A modulus of subgrade reaction equal to 120 pounds per cubic inch may be used in design of mat foundation supported on compacted and improved soils, as recommended in section 11.2.1.

11.6.3. Swimming Pool

Bearing Capacity: The swimming pool should be designed as a freestanding structure, where the pool sidewalls can support a pool filled with water, without soil supports. An allowable bearing capacity of 1,500 psf may be used for the base slab of the pool underlain by a minimum of 2 feet of compacted fill. A one-third increase in the bearing value may be used when considering seismic loads provided the load reduction factor of 0.75 is not applied to seismic loads for load combinations.

Lateral Loading: The active pressure acting on the inner wall of the shell from the swimming pool water may be assumed to be 62 psf per foot of depth. The active pressure of drained soils acting on the outer wall of the shell may be assumed to be 45 psf per foot of depth for leveled backfill condition. A drainage system should be provided behind the wall to reduce the potential for development of hydrostatic pressure. If a drainage system is not installed, the walls should be designed to resist a combined soils and hydrostatic pressure equal to that developed by a fluid with a density of 90 pcf for the full height of the wall. A coefficient of friction of 0.35 may be used for resisting lateral loads at the contact surface between the concrete and foundation soils.

Modulus of Subgrade Reaction: A modulus of subgrade reaction equal to 120 pounds per cubic inch may be used in design of mat foundation/floor slab of the proposed swimming pool supported on compacted and improved soils, as recommended in section 11.2.1.

11.7. Floor Slab

Interior slab-on-grade within the building footprints shall be supported on the graded building pads of compacted fill as recommended in the grading section of this report (Section 11.2.1). The building floor slabs should have a nominal thickness of 4 inches and should contain as a minimum No. 4 bars spaced a maximum of 18 inches on center, in both directions. Thicker slabs and additional

reinforcement may be required depending on the floor loads and the structural requirements. These conditions are referred to the project's Structural Engineer.

Perimeter grades around the buildings should be sloped in a manner allowing water to drain away from the structures and not pond next to the foundations. Roof down drains should be connected to underground pipes carrying water away from the building areas or have extenders so water does not drain and pond next to the buildings.

11.8. Basketball Court Slab

The slab-on-grade for the proposed basketball court shall be supported on the graded and compacted fill of the demolished old swimming pool area (Section 11.2.3). The slabs should have a nominal thickness of 4 inches and should contain as a minimum No. 4 bars spaced a maximum of 18 inches on center, in both directions.

11.9. Concrete Flatwork

It is recommended that the upper 12 inches of soils below concrete flatwork or hardscapes located around and within the vicinity of the proposed developments, and subjected to pedestrian loads only, be over-excavated, reworked, and recompacted. The backfilled materials shall comply with the requirements outlined in Section 11.4 of this report and shall be moisture-conditioned to a moisture content between the optimum and 3 percent above the optimum moisture content and compacted to at least 90 percent of the maximum dry density obtained per ASTM D1557. The slabs for concrete flatwork or hardscape subjected to pedestrian loads only should have a nominal thickness of 4 inches.

11.10. Pavement for Parking Lot

Traffic Index (TI) values for the parking lot were not provided at the time of preparation of this report. The new pavement sections recommendations presented in the following sections are based upon assumed TI values of 4, 5, and 6. GAI does not take responsibility for the numerical determination of the TI values or the areas where they apply within the project limits. However, for light and regular conventional parking area, we recommend pavement sections for TI value of 4 or 5. For fire lanes and slightly heavier vehicular traffic, we recommend pavement sections for TI value of 6. We would be pleased to provide additional pavement section recommendations for different TI values upon request. Samples of the subgrade soils were obtained within the parking area and one sample was selected and tested for its R-Value.

The pavement section recommendations provided in the following sections are based on the on-site subgrade soils having a design R-Value of 29. Two different options are recommended and provided in Table 11.2 for pavement section thicknesses depending on whether base course will be used.

- Option 1 consists of constructing the pavement section by placing layers of Hot Asphalt Concrete Mix (ACM) over reworked/recompacted subgrade materials.
- Option 2 consists of constructing the pavement section by placing layers of ACM over compacted base materials over reworked/recompacted subgrade materials.

It is recommended that the upper 12 inches of the subgrade soils below the pavement structural section (i.e. below asphalt concrete for Option 1, and below base course for Option 2) be scarified, moisture-conditioned, and recompacted. The subgrade soils shall be moisture-conditioned to a moisture content between the optimum and 3 percent above the optimum moisture content and compacted to at least 95 percent of the maximum dry density obtained per ASTM D1557.

Table 11.2. Asphalt Concrete Pavement Sections

Traffic		M	Minimum Course Thicknesses (in)		
Index	Option	Asphalt Concrete	Aggregate Base ^a	Reworked Subgrade ^b	
4	1	4.5		8.0	
	2	3.0	4.0	8.0	
5	1	6.0		8.0	
	2	3.5	5.0	8.0	
6	1	7.5		8.0	
	2	4.0	6.5	8.0	

^aOption 1 is full depth asphalt concrete and does not utilize aggregate base. For Option 2, the base course shall be compacted to at least 95 percent of the maximum dry density obtained per ASTM D1557.

The base course material shall comply with Crushed Aggregate Base (CAB) as defined by *Standard Specifications for Public Works Construction* (SSPWC) Section 200-2.2. In lieu of CAB material, Crushed Miscellaneous Base (CMB) material, as defined by SSPWC Section 200-2.4, may be used. The base course material should be compacted to at least 95 percent of the maximum dry density of that material. The assumed R-Value in design of the pavement sections above for the base material is 78.

^bThe reworked/recompacted subgrade shall be compacted to at least 95 percent of the maximum dry density obtained per ASTM D1557.

11.11. Utility Trench Backfilling

When required, bedding material shall be first placed below the bottom of the utility line, on a firm and unyielding subgrade so the pipe is supported for the full-length of the barrel. The minimum dimensions of bedding material below the bottom of the utility line shall conform to the specification in SSPWC Section 306-6. Bedding material shall also be placed immediately around a utility line extending to a point 12 inches above the top of the line. The bedding material should consist of sand, fine-grained gravel, or cement slurry to support the line and protect it, and shall meet the specification in SSPWC Section 217. Sand or gravel should be compacted in accordance with SSPWC specifications. No jetting or pounding is permitted.

Above the bedding material and up to the finished ground surface, utility trench backfills may consist of low-expansive material (EI less than 30) and should be mechanically compacted to at least 90 percent of the maximum dry density of the soils obtained per ASTM D1557, except below pavements or within the areas with a higher relative compaction such as building pads. A minimum relative compaction of 95 percent will be required in the upper 8 inches of the backfill underneath the pavement areas and the minimum required relative compaction for the upper 2 feet within the building pads shall be as set forth for the building pads. Prior to backfilling, the gradation and expansivity of the backfill material shall be tested, reviewed, and approved by the soils engineer. Both bedding and backfilling materials should be placed in accordance with Sections 306-6 and 306-12 of the SSPWC.

When adjacent to any footings, utility trenches and pipes should be located above an imaginary line measured at a gradient of 1:1 (H:V) projected down from the bottom edges of any footings. Otherwise the pipe should be designed to accept the lateral effect from the footing load, or the footing bottom should be deepened as needed to comply with this requirement, into competent materials.

For bedding and backfilling of trenches and upon approval of the soils engineer, controlled low strength material (CLSM) may be used. CLSM shall comply with the requirements of SSPWC Section 201-6. The backfill material shall be observed, tested, and approved by the Geotechnical Engineer.

11.12. Excavations

11.12.1. **General**

In general, the on-site earth materials can be excavated using conventional heavy-duty earthmoving equipment and the materials are not expected to pose a rippability problem. However, large cobbles and rocks are expected within the excavations and the contractor should employ proper means to remove all large-size pieces so the materials being used in backfilling complies with the requirement of Section 11.4. Based on the grading recommendations provided, it is expected that the excavation be as deep as about 9 feet bgs for the grading and construction of the peripheral buildings and about 10 feet bgs for the swimming pool. Excavation sloping and benching shall be done in accordance with soil Type C as classified in Chapter 4, Subchapter 4, Article 6, Appendix A of the California Occupational Safety and Health Administration (Cal/OSHA) Title 8 Regulations. For excavation less than 5 feet in depth, the excavation may be performed to a maximum vertical cut of 5 feet without the use of a protective system (e.g. sloping, benching, shoring). For excavation less than 20 feet in depth, the soils at the site are expected to be temporarily stable when excavated at a gradient of 1.5:1 (H:V).

The top of slopes should be barricaded to prevent vehicles and storage loads within 0.7H feet of the top of the slopes, where H is the total depth. A greater setback may be necessary when considering heavy vehicles (e.g. concrete trucks and cranes) and we should be advised of such heavy vehicle loadings so that specific setback requirements can be established. When excavating adjacent to footings of existing buildings, proper means should be employed to prevent any possible damage to the existing structures. Un-shored excavations that are adjacent to existing buildings should not extend below a 1:1 (H:V) plane extending downward from the lower edge of adjacent footings. All regulations of State or Federal OSHA should be followed.

Temporary excavations are assumed to be those that will remain un-shored for a period not exceeding 10 days. In dry weather, the excavation slopes should be kept slightly moist, but not saturated. If excavations are made during the rainy season (normally from November through April), particular care should be taken to protect slopes against erosion. Mitigative measures, such as installation of berms, plastic sheeting, or other devices, may be warranted to prevent surface water from flowing over or ponding at the top of excavations.

11.12.2. Excavations of Contaminated Soils

Any soils which have visible staining or detectable odors should be tested in the field by the contractor or qualified environmental subcontractor with an organic vapor analyzer (OVA) for volatile components, which requires additional considerations in their handling. The stockpiles should be barricaded near the excavation area, away from drainage areas or catch basins, on an impermeable plastic liner (6 mil nominal thickness and tested at 100 psi strength). Caution must be taken to separate contaminated soils from the remainder of the excavated material. If only small amounts of contaminated soils are encountered, it may be stored in 55-gallon steel drums with seal lids.

Any contaminated material (soil, asphalt, railroad ballast, concrete, or debris) that is to be hauled off the site is considered a "waste product" and must be classified as hazardous or nonhazardous waste under all criteria by both State and Federal codes prior to disposal. If the waste soils or other material are determined hazardous, a hazardous waste manifest will be prepared by the contractor or its qualified representative, and the material shall be transported to an appropriate class of facility for recycling or landfill disposal by a registered hazardous material transporter. The project contractor is responsible for conducting all necessary tests on the export soils.

12. INFILTRATION RATE DETERMINATION

12.1. General

We have been requested to perform three percolation tests to determine the infiltration rates within the proposed developments. The locations of the percolation tests were chosen by the Client and are shown on Figure A-2a and A-2b within Appendix A. The depths were chosen based on the subsurface conditions, considering the most permeable layer at the practical depths.

In general, percolation tests are used for design and construction of subsurface sewage disposal system and/or on-site storm drain infiltration system, and the test procedure for these purposes varies in different localities. For the purpose of obtaining an infiltration rate at the subject site, borehole percolation tests were performed following the procedure from the Los Angeles County *Guidelines for Design, Investigation, and Reporting Low Impact Developments Stormwater Infiltration* (Reference 10). The following sections of the report are devoted to providing information regarding the employed test method and the concluded infiltration rate.

12.2. Test Procedure

The borings for the percolation tests were drilled using a hollow-stem truck-mounted drill rig down to a depth determined based on the subsurface profile from other borings within vicinity. Falling head borehole percolation tests were employed to determine the infiltration rates of the soils. Falling head borehole percolation tests include measurements of change in water levels in an open standpipe or hole over consistent time periods.

The procedure for performing a falling head borehole percolation test is summarized below:

- 1. Drill or auger an 8-inch diameter hole to the depth at which the test is to be executed.
- 2. Set a 2- to 4-inch-diamter observation (perforated) pipe with a solid end cap.
- 3. Fill the anulus spaces between the perforated PVC pipe and the native material with well-draining material up to the desired test section.
- 4. Perform two presoak tests to determine duration of presoaking required. For each presoak test, fill the hole with at least 12 inches of water. If the water seeps completely away within 30 minutes of filling the hole two consecutive times, presoaking can be considered complete and testing can proceed. Otherwise, presoak the hole for at least 4 hours before conducting the infiltration test.
- 5. Perform a time interval test to determine the duration of each time interval that will be used to measure the water drop readings. Fill the hole with at least 12 inches of water and observe the drop in the water during the next 30 minutes. If no water remains in the hole, the time interval between readings shall be 10 minutes. Otherwise, the time interval between readings shall be 30 minutes.
- 6. Pour at least 12 inches of water into to the casing, but less than the water level used to presoak the hole. For each successive percolation test reading, the starting water level must be at this approximate initial water depth.
- 7. Conduct the percolation test by taking readings of the water drop from the initial depth for each time interval (as determined in step 5). After each reading, fill the hole with water back to the approximate initial water depth.
- 8. Repeat the percolation test readings a minimum of 8 times or until a stabilized rate of drop is obtained, whichever occurs first. This preadjusted rate is then reduced with a factor

accounting for discharging of water from both the sides and bottom of the boring (i.e. non-vertical flow).

12.3. Results and Feasibility

The data and results of the field percolation tests are provided in Figures E-2a to E-2c within Appendix E. A summary of the infiltrate rates, as calculated from Los Angeles County guidelines (Reference 10) and Porchet method (Reference 13) for each test location are provided in Table 12.1. Additional safety factor (e.g. site variability, number of tests, long-term siltation, plugging, and maintenance) was not utilized into the reported infiltration rates. Correction factors or safety factors should be chosen at the design engineer's discretion, considering the entire project scope and guidelines from the requesting agency.

Table 12.1. Summary of Infiltration Tests

			Infiltration Rate (in/hr)	
Test	Test Depth (ft)	Subsurface Material	LA County ^a	Porchet ^b
P-1	7.0	Silty Sand with Gravel	1.90	0.98
P-2	7.0	Silty Sand with Gravel	1.24	0.64
P-3	7.0	Silty Sand with Gravel	1.68	0.87

^aCounty of Los Angeles, Department of Public Works, Geotechnical and Materials Engineering Division, December 31, 2014. Guidelines for Design, Investigation, and Reporting Low Impact Developments Stormwater Infiltration. GS200.1. (Reference 10)

According to guidelines of the Los Angeles County *Guidelines for Design, Investigation, and Reporting Low Impact Developments Stormwater Infiltration* (Reference 10), soils with a corrected in-situ infiltration rate of 0.3 inch/hour or greater are considered feasible for retention-based storm water quality control measures.

The subsurface material at the site and to the maximum depth of exploration is relatively similar throughout the entire depth and, therefore, the infiltration rates obtained from the percolation tests at 7 feet bgs may be used for the purposes of drywell at deeper depth. Considering the historically highest groundwater depth at the site at about 40 bgs, the maximum allowable depth for infiltration using deep drywells should not exceed 30 feet bgs in order to provide at least a 10 feet separation between the infiltration depth and the groundwater table.

^bOrange County, December 20, 2013. Technical Guidance Document (TGD) for the Preparation of Conceptual/Preliminary and/or Project Water Quality Management Plans (WQMPs). Exhibit 7.III. (Reference 13)

13. SOIL CORROSIVITY

Corrosivity tests were performed on one sample of on-site soils, and the results of the tests are presented in Appendix C of this report. It is concluded that the amount of sulfate in tested soils in the upper 5 feet bgs is less than 0.1 percent by weight (water soluble sulfate). The resistivity test result indicates existence of a severely corrosive condition. Further interpretation of the corrosivity test results (including the resistivity value) and recommendations for corrosion design and construction are referred to corrosion specialists/consultants and design engineers.

14. SOIL EXPANSIVITY

We have performed one expansivity test on selected soil sample to determine the expansion characteristics of the on-site soils. The sample was obtained from on-site soils in the upper 5 feet bgs, which are susceptible to expansion when facing seasonal cycles of saturation/desiccation. The test results are presented in Table 14.1 below.

Table 14.1. Expansion Test Summary

Sample Location	Sample Depth (ft)	Expansion Index (EI)	Expansion Potential (ASTM D4829)
B-1	1 – 5	0	Very Low

The above tabulated test result on the sample obtained from on-site soil within the footprint of the proposed developments indicate a very low expansion potential (based on ASTM D4829).

15. OBSERVATION AND TESTING

This final report has been prepared assuming that GEO-ADVANTEC, INC. will perform all geotechnical-related field observations and testing. If the recommendations presented in this report are utilized, and observation of the geotechnical work is performed by others, the party performing the observations must review this report and assume responsibility for recommendations contained herein. That party would then assume the title "Geotechnical Consultant of Record".

A representative of the Geotechnical Consultant should be present to observe all grading operations as well as all footing excavations. Upon the Client's request, a report or final

verification letter presenting the results of these observations and related testing should be issued

upon completion of the grading operations.

16. CLOSURE

The findings and recommendations presented in this final report were based on the results of our

field and laboratory investigations, combined with professional engineering experience and

judgment. The report was prepared in accordance with generally accepted engineering principles

and practice. We make no other warranty, either expressed or implied.

The soils encountered in the boreholes are believed to be representative of the total under

consideration area for the subject proposed developments; however, soil characteristics can vary

throughout the site. GAI should be notified if subsurface conditions are encountered which differ

from those described in this report.

Samples secured for this investigation will be retained in our laboratory for a period of 45 days

from the date of this report and will be disposed after this period unless other arrangements are

made.

Should you have any questions concerning this submittal, or the recommendations contained herewith, please do not hesitate to call our office.

Respectfully submitted, GEO-ADVANTEC, INC.



Giang (Jack) Lee, P.E. Senior Project Engineer



Ronald C. Hanson, P.G., C.E.G. Principal Engineering Geologist



Shawn Ariannia, Ph.D., P.E., G.E. Principal Geotechnical Engineer

Distribution:

- 1. Addressee (3 wet stamped copy + pdf copy via e-mail)
- 2. File

APPENDICES

Appendix A: Maps and Plans and Figures

Figure A-1: Vicinity Map

Figure A-2a: Boring Locations Plan on Aerial Photo Figure A-2b: Boring Locations Plan on Partial Site Plan

Figure A-3: FEMA Flood Map Figure A-4: DOGGR Oil Well Map

Appendix B: Field Exploratory Logs

Keys to Logs

Borings B-1 to B-6

Appendix C: Laboratory Test Results

Sieve Analysis

Plasticity Chart

Direct Shear Test

Consolidation Test

R-Value Test

Corrosivity Test

Appendix D: Quadrangle Maps

Figure D-1: Seismic Hazard Zones Map

Figure D-2: Historically highest Groundwater Map

Appendix E: Engineering Analyses Results

Figure E-1a to E-1b: Seismic Settlements

Figure E-2a to E-2c: Percolation Test Data

Appendix G: Geologic and Seismic Data

Figure G-1: Geologic Map

Figure G-2: Fault Activity Map

Figure G-3: Historical Earthquakes

Figure G-4: PSHA Deaggregation at PGA

Figure G-5: SEAOC Seismic Design Map


REFERENCES

- 1. American Society for Testing and Materials (ASTM), 2017, Annual Book of ASTM Standards, Volume 04.08 and 04.09 Soil and Rock.
- 2. Building News, 2018, The Greenbook: Standard Specifications for Public Works Construction.
- 3. California Department of Conservation, Division of Mines and Geology, 1998, *Seismic Hazard Zone Report for the Pasadena 7.5-Minute Quadrangle, Los Angeles County, California,* Seismic Hazard Zone Report 014.
- 4. California Department of Conservation, Division of Mines and Geology, March 25, 1999, Earthquake Zones of Required Investigation, Pasadena 7.5 Minute Quadrangle.
- 5. California Department of Transportation (Caltrans), 2018, Highway Design Manual Sixth Edition.
- 6. California Department of Transportation (Caltrans), Division of Engineering Services, June 2007, *Method for Determining Field and Laboratory Resistivity and pH Measurements for Soil and Water*, California Test 643.
- 7. California Department of Transportation (Caltrans), Division of Engineering Services, June 2014, *Method of Testing Soils, Concrete Patching Materials and Waters for Chloride Content*, California Test 422.
- 8. California Department of Transportation (Caltrans), Division of Engineering Services, June 2014, *Method of Testing Soils, Concrete Patching Materials and Waters for Sulfate Content*, California Test 417.
- 9. California Geological Survey, 2010, Fault Activity Map of California by Charles W. Jennings and William A. Bryant.
- 10. County of Los Angeles, Department of Public Works, Geotechnical and Materials Engineering Division, December 31, 2014. *Guidelines for Design, Investigation, and Reporting Low Impact Developments Stormwater Infiltration*. GS200.1.
- 11. Dibblee, Thomas W. Jr., 1989, *Geologic Map of the Pasadena Quadrangles, Los Angeles County, California*, Dibblee Geology Center Map #DF-23.
- 12. Federal Emergency Management Agency, September 26, 2008, *Flood Insurance Rate map of Los Angeles County, California and Incorporated Areas*, Map Number 06037C1075F.
- 13. Orange County, December 20, 2013. Technical Guidance Document (TGD) for the Preparation of Conceptual/Preliminary and/or Project Water Quality Management Plans (WOMPs). Exhibit 7.III.


APPENDICES


APPENDIX A


MAPS, PLANS AND FIGURES



Geo-Adva	antec, Inc.	VICINITY MAP	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	A-1
DATE	08-23-2019	South Campus Improvements - La Canada Flintridge, CA	







LEGEND

SPECIAL FLOOD HAZARD AREAS (SFHAS) SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD

Applies of 1 to 3 feet (usually areas of ponding); Base

with velocity hazard (wave action); no Base Floor

with velocity

ay is the channel of a stream plus any adjacent floodplain areas that must be if encroachment so that the 1% annual chance flood can be carried without increases in flood heights. FLOODWAY AREAS IN ZONE AE

OTHER FLOOD AREAS

Area of 0.2% amual chance flood; areas of 1% amual chance flood with average depths of less than 1 foot or with drainage areas less than 1 square mile; and areas protected by levels from 1% amual chance.

Areas determined to be outside the 0.2% annual chance floor OTHER AREAS

COASTAL BARRIER RESOURCES SYSTEM (CBRS) AREAS

OTHERWISE PROTECTED AREAS (OPAS)

PANEL 1375F

FIRM

FLOOD INSURANCE RATE MAP LOS ANGELES COUNTY, CALIFORNIA

AND INCORPORATED AREAS

PANEL 1375 OF 2350 (SEE MAP INDEX FOR FIRM PANEL LAYOUT) CONTAINS:

COMMUNITY

MAP NUMBER 06037C1375F

Federal Emergency Management Agency

Geo-Advantec, Inc. 19-1093 PROJECT NO.

08-23-2019

DATE

METERS

MAP SCALE


South Campus Improvements - La Canada Flintridge, CA La Cañada High School New Pool and

FEMA FLOOD MAP

Program flood maps check the FEMA Flood Map Store at www.msc.fema.go. This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood insurance

FIGURE A-3

EFFECTIVE DATE SEPTEMBER 26, 2008



0336



DOGGR OIL WELL MAP

La Cañada High School New Pool and South Campus Improvements - La Canada Flintridge, CA

FIGURE A-4

antec, inc.	19-1093	08-23-2019
Geo-Advantec,	PROJECT NO.	DATE

APPENDIX B FIELD EXPLORATORY BORING LOGS

SOILS CLASSIFICATION										
	MAJOR DIVISIONS	S	GRAPH LOG	USCS SYMBOL		ТҮРІ	CAL NAMES			
	GRAVELS	CLEAN GRAVELS		GW	WELL-GRADED GRAVELS, GRAVEL-SAND MIXTURE LITTLE OR NO FINES					
COARSE GRAINED	GRAVELS	LESS THAN 5% FINES	0.00	GP	POORLY-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES					
SOILS	MORE THAN 50% OF COARSE FRACTION IS	GRAVELS WITH FINES	0000	GM	SILTY GRAVE	ELS, GRAVEL-	SAND-SILT MIXTU	JRES		
	LARGER THAN NO. 4 SIEVE	MORE THAN 12% FINES		GC	CLAYEY GRA	VELS, GRAVE	L-SAND-CLAY MI	XTURES		
	SANDS	CLEAN SANDS		sw	WELL-GRADI FINES	ED SANDS, GF	RAVELLY SANDS,	LITTLE OR NO		
MORE THAN 50% OF MATERIAL IS	SANDS	LESS THAN 5% FINES		SP	POORLY-GRADED SANDS, GRAVELLY SANDS, LITTLE OF NO FINES					
LARGER THAN NO. 200 SIEVE SIZE	50% OR MORE OF COARSE FRACTION IS		H	SM	SILTY SANDS, SAND-SILT MIXTURES					
	SMALLER THAN NO. 4 SIEVE	MORE THAN 12% FINES	6	sc	CLAYEY SANDS, SAND-CLAY MIXTURES					
	SILTS AN	ID CLAYS		ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY					
FINE GRAINED SOILS		S LESS THAN 50		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS					
	EIQOID EIIIII II	S ELOO TIAN OU		OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY					
	SILTS AN	ID CLAYS		МН	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR GRAVELLY ELASTIC SILTS					
50% OR MORE OF MATERIAL IS SMALLER THAN NO. 200 SIEVE SIZE	LIQUIDLIMIT	IS 50 OR MORE		СН	INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS					
	EIQOID EIIVIIT	IO 30 OIN WORLE		ОН		ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS				
HIGH	LY ORGANIC S	SOILS		V PT	PEAT AND O	THER HIGHLY	ORGANIC SOILS			
			GRA	AIN SIZES						
SILT AN	D CLAY		SAND	T		GRAVEL		BOULDERS		
		#400 #40	MEDIUM	COARSE	FINE	COARSE 4		5.		
# # # # # # # # # # # # # # # # # # #										

Bulk Bag Sample

Standard Penetration Test (SPT)

California Modified Sampler

▼ Water Level After Specified Hours

Water Level at End of Change in material cannot be accurately located due to limitations in the drilling/sampling methods used

Geo-Adva	antec, Inc.	KEY TO LOGS	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	
DATE	08-23-2019	South Campus Improvements - La Canada Flintridge, CA	

KEY TO LOGS

SPT/CD BLOW COUNTS VS. CONSISTENCY/DENSITY										
FINE-GRAINED S	OILS (SILT	S, CLAYS, etc.)	GRANULAR SOILS (S.	ANDS, GRAVELS	S, etc.)					
CONSISTENCY	*BLC	DWS/FOOT	RELATIVE DENSITY	*BLOWS/F	TOOT					
CONSISTENCY	SPT	CD	RELATIVE DENSITY	SPT	CD					
SOFT	0-4	0-4	VERY LOOSE	0-4	0-8					
FIRM	5-8	5-9	LOOSE	5-10	9-18					
STIFF	9-15	10-18	MEDIUM DENSE	11-30	19-54					
VERY STIFF	16-30	19-39	DENSE	31-50	55-90					
HARD	over 30	over 39	VERY DENSE	over 50	over 90					

^{*} CONVERSION BETWEEN CALIFORNIA DRIVE SAMPLERS (CD) AND STANDARD PENETRATION TEST (SPT) BLOW COUNT HAS BEEN CALCULATED USING "FOUNDATION ENGINEERING HAND BOOK" BY H.Y. FANG. (VALUES ARE FOR 140 Lbs HAMMER WEIGHT ONLY)

DESCRIPTIVE ADJECTIVE VS. PERCENTAGE								
DESCRIPTIVE ADJECTIVE	PERCENTAGE REQUIREMENT							
TRACE	1 - 10%							
LITTLE	10 - 20%							
SOME	20 - 35%							
AND	35 - 50%							

^{*}THE FOLLOWING "DESCRIPTIVE TERMINOLOGY/ RANGES OF MOISTURE CONTENTS" HAVE BEEN USED FOR MOISTURE CLASSIFICATION IN THE LOGS.

	APPROXIMATE MOIST	URE CONTENT DEFINI	TION
	MOISTURE CON		
DEFINITION	FINE-GRAINED SOILS (SILTS, CLAYS, etc.)	GRANULAR SOILS (SANDS, GRAVELS, etc.)	DESCRIPTION
DRY	<10	2 - 4	Dry to the touch; no observable moisture
SLIGHTLY MOIST	15-24	6-8	Some moisture but still a dry appearance
MOIST	24-28	10-13	Damp, but no visible water
VERY MOIST	30-38	15-20	Enough moisture to wet the hands
WET	>40	20-25	Almost saturated; visible free water

Geo-Adva	antec, Inc.	KEY TO LOGS	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	
DATE	08-23-2019	South Campus Improvements - La Canada Flintridge, CA	

PAGE 1 OF 1

GEOTECH BH COLUMNS - GINT STD US LAB. GDT - 8/28/19 08:23 - M:\PROJECTS\Z019\19-1093-SI-LA CANADA USD_SWIMMING POOL AND SITE IMPROVEMENT AT LCHS\1-MAPS-LOGS-APPENDICES\APPENDIX B\19-1093 BORING LOGS. GP.					nified So	chool D	District	PROJECT LOCATION La Cañada HS			mprove	ements		
ING L				7/25/1	9-1093			PROJECT LOCATION La Cañada Flintridge, CA GROUND ELEVATION 1090 ft						
BOR						ne Way	/ Drilling	GROUND WATER LEVELS:						
1093					Hollow S			FIRST ENCOUNTER						
B\19-					ay			AFTER STABILIZED						
XIQNE					-		der). No Groundwater Encountered		LO	NGITUI	DE -1	18.1789	 932 °	
\APP											AT	TERBE	RG	
SICES	드		<u></u>	Blow Counts (N Value)	go.				Dry Unit Weight (pcf)	Moisture Content (%)		LIMITS		Fines Content (%)
PEN	Elevation (ft)	Depth (ft)	Sampler	Cor /alu	Gaphic Log	uscs	Description / I	nterpretation	Init W (pcf)	e Cc (%)	Liquid Limit	Plastic Limit	<u>lud</u>	SG (%
S-AP	Ele	Δ	Sa	<u>%</u> (N	Gapl	Ď	·) y	istur (bin	stic	licity	unes (
3-LOG	1090	0		ш					<u> </u>	Мо	ij	Pla	Plasticity Index	<u> </u>
MAP					7 1/1 1/1 1/1 1/1 1/1 1/1 1/1 1/1 1/1 1/	SM	3" Grass over 5" Topsoil							
HS/1-	-	_				Sivi	ARTIFICIAL FILL (SM) Silty SAND with gravel: col	oble (4") loose to medium						
AT LC	_	_				SM	dense, slightly moist, brown		-					
ENT /	_ 1085	- 5					NATIVE - ALLUVIUM (SM) Silty SAND with gravel: col	oble (4"), loose to medium						
OVEM							dense, slightly moist, brown							
MPR							Bottom of bore	hole at 5.0 feet.						
SITE														
AND														
00 00														
ING P														
MIMM														
SD_S\														
DA US														
SANA														
I-LA														
393-S														
119-1														
3/2018														
ECTS														
PROJ														
3 - M:\														
08:23														
28/19														
)T - 8/														
AB.GE														
US L/														
STD														
GINT														
- SNV														
OLUN														
BHC														
TECH														
GEO.														

Geo-Advantec, Inc.

103.7

7.2

25

Geo-Advantec, Inc.

SM

1085

<u>1</u>080

5

7-6-7

CLIENT La Cañada Unified School District PROJECT NAME La Cañada HS Pool and Site Improvements PROJECT NUMBER 19-1093 PROJECT LOCATION La Cañada Flintridge, CA DATE DRILLED 7/25/19 **GROUND ELEVATION** 1088 ft **DRILLING CONTRACTOR** One Way Drilling **GROUND WATER LEVELS:** DRILLING METHOD Hollow Stem Auger FIRST ENCOUNTER _---GEOTECH BH COLUMNS - GINT STD US LAB GDT - 8/28/19 08:23 - M:\PROJECTS/2019/19-1093-SI-LA CANADA USD SWIMMING POOL AND SITE IMPROVEMENT AT LCHS/1-MAPS-LOGS-APPENDICES/APPENDICE LOGGED BY S. Noorzay CHECKED BY J. Lee AFTER STABILIZED ---NOTES No Groundwater Encountered **LATITUDE** _34.189718 ° **LONGITUDE** _-118.178695 ° **ATTERBERG** Moisture Content (%) Fines Content (%) Dry Unit Weight <u>IMITS</u> Blow Counts (N Value) Elevation (ft) Gaphic Log Sampler lasticity Index **USCS** Depth (ft) Liquid Limit Plastic Limit (bct) Description / Interpretation 6" Asphalt Concrete SM **ARTIFICIAL FILL**

Silty SAND: fine to medium sand, trace fine gravel, loose, slightly Bottom of borehole at 8.5 feet.

(SM) Silty SAND with gravel: cobble, loose to medium dense,

(SM) Silty SAND with gravel: cobble, loose to medium dense,

slightly moist, gray to brown

NATIVE - ALLUVIUM

slightly moist, brown

moist, dark brown

PENDIX B/19-1093 BORING LOGS.GPJ	CLIENT La Cañada Unified School District PROJECT NUMBER 19-1093 DATE DRILLED 7/25/19 DRILLING CONTRACTOR One Way Drilling DRILLING METHOD Hollow Stem Auger LOGGED BY S. Noorzay CHECKED BY J. Lee NOTES No Groundwater Encountered						y Drilling uger CHECKED BY J. Lee	PROJECT LOCATION La Cañad GROUND ELEVATION 1090 ft GROUND WATER LEVELS: FIRST ENCOUNTER AFTER STABILIZED	la Flintric	lge, CA		
'S-LOGS-APPENDICES\APP	DE Elevation (ft)	o Depth (ft)	Sampler	Blow Counts (N Value)	Gaphic Log	SOSN	·	Interpretation	Dry Unit Weight (pcf)	Moisture Content (%)	Plastic Limit WBB	Fines Content (%)
SITE IMPROVEMENT AT LCHS/1-MAF	_ - - _ 1085 - -	_ _ _ _ 5		12-13- 21 (34)		SM	NATIVE - ALLUVIUM (SM) Silty SAND with gravel: no brown to orange brown dense, brown to gray	nedium dense, slightly moist, gray nedium dense, slightly moist,				
GEOTECH BH COLUMNS - GINT STD US LAB. GDT - 8/28/19 08:23 - M:NPROJECTS/2019/19-1093-SI-LA CANADA USD_SWIMMING POOL AND SITE IMPROVEMENT AT LCHS/1-MAPS-LOGS-APPENDICES/APPENDIX B1/9-1093 BORING LOGS. GPJ												

Geo-Advantec, Inc.

Geo-Advantec, Inc.

	NT <u>La</u>	Car	iada H	nified S	chool D	istrict	PROJECT NAME La Cañada HS	Pool an	ıd Sita I	mprove	mente			
SS PRO	JECT N					100100	PROJECT LOCATION La Cañada							
DAT	E DRILL						GROUND ELEVATION 1091 ft							
b DRIL					ne Way	Drilling								
DRIL	LING N						FIRST ENCOUNTER							
LOG	GGED BY S. Noorzay CHECKED BY J. Lee						AFTER STABILIZED							
Î NOT	NOTES No Groundwater Encountered						LATITUDE 34.190689 °	LC	NGITU	DE 1	18.178	859°		
APP.								1_		AT				
Color Colo	ے	er	Blow Counts (N Value)	Log	w			Dry Unit Weight (pcf)	Moisture Content (%)	LIMITS			Fines Content (%)	
S-APPENDIC Elevation (ft)	Depth (ft)	Sampler	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	Gaphic Log	nscs	Description /	Interpretation	nit M (pcf)	(%)	Ë	Lin (y Z	ပ္စိုင္တိ	
ese di Se-A		Š		Gap	ر			Γ	oistu	Liquid Limit	Plastic Limit	Plasticity Index	ine	
07-5	0								Š	=	ā	Plas		
<u>₹</u> 1090	-				SM	3" Grass/Topsoil ARTIFICIAL FILL								
HS!	-					(SM) Silty SAND: some gravel	(3"), loose, dry, brown							
ATLC	-				SM	NATIVE - ALLUVIUM								
EN L	_ 5					(SM) Silty SAND with gravel: fir gravel, loose, dry, brown to dark	ne to medium sand, fine to coarse							
<u> </u> _1085	-	M	7-18- 14			medium dense, slightly moist to			8.7					
MPR -	-		(32)											
	-													
	10													
ਰੂ 1080		X	3-3-5 (8)			trace clay, loose				NP	NP	NP	28	
하- 편	-		(0)											
<u> </u>	-													
8S-	15													
5 1075	_	M	15-23- 34		GМ	(GM) Silty GRAVEL with sand:	dense, dry, brown	134.8	3.1					
NAD/	-		54 (57)	Paras										
	-													
	20			200										
6 1070			7-30-		SM	(SM) Silty SAND with gravel: fir							15	
19/18			34 (64)			slightly moist to moist, gray to be	prown							
TS/2(-													
	25													
½ 1065		M	5-29-			dense, moist, light tan brown		107.7	11.9					
23 - 1			50 (79)											
	-													
1/28/1	-													
	_30		20-50			very dense, gray to brown								
BB.G														
US [
STD -	-													
	35		4-34-			some cementation with fine gra	vel. caliche, dense, brown							
^{ဗု} 1055	<u> </u>		50 (84)				,,,							
			(04)											
표 -	-													
H 1050	_40	\searrow	31-50			no cementation, more fine, very	dense, gray to brown							
) <u>1050</u>	'	$V \setminus$	01-00	[mlmlið:			chole at 41.0 feet.					I	I	

Geo-Advantec, Inc.

19-1093 BORING LOGS.GP. PROJECT NAME La Cañada HS Pool and Site Improvements **CLIENT** La Cañada Unified School District PROJECT NUMBER 19-1093 PROJECT LOCATION La Cañada Flintridge, CA DATE DRILLED 7/25/19 **GROUND ELEVATION** 1094 ft **DRILLING CONTRACTOR** One Way Drilling **GROUND WATER LEVELS:** DRILLING METHOD Hollow Stem Auger FIRST ENCOUNTER _---LOGGED BY S. Noorzay CHECKED BY J. Lee AFTER STABILIZED ---NOTES No Groundwater Encountered **LATITUDE** _34.191015 ° **LONGITUDE** _-118.179334 ° **ATTERBERG** Moisture Content (%) Fines Content (%) Dry Unit Weight <u>IMITS</u> Blow Counts (N Value) Elevation (ft) Gaphic Log Sampler lasticity Index **USCS** Depth (ft) Liquid Limit (bct) Plastic Limi Description / Interpretation 2" Grass over 4" Topsoil SM **ARTIFICIAL FILL** (SM) Silty SAND: some gravel, loose to medium dense, slightly moist, brown 1090 SM **NATIVE - ALLUVIUM** 5 (SM) Silty SAND with gravel: medium dense, slightly moist, 8-3-7 107.4 13.4 (10)Silty SAND: loose, moist, dark brown 1085 SWIMMING POOL AND 10 10-13-Silty SAND with gravel: fine to coarse sand, fine gravel, medium 17 dense to dense, slightly moist, brown (30)1080 15 GEOTECH BH COLUMNS - GINT STD US LAB.GDT - 8/28/19 08:23 - M:\PROJECTS\2019\19-1093-SI-LA CANADA USD 15-33₋ Silty SAND: some cementation, very dense, slightly moist to 134.7 8.9 50/5" moist, brown <u>1</u>075 20 20-20trace gravel, dense, reddish brown 20 (40)1070 25 20-37-Silty SAND with gravel: fine to coarse sand, fine gravel, very 118.4 7.1 50/5" dense, slightly moist, orange brown 1065 30 16-27 tan to yellow brown 20 (56)1060 35 10-32moist, orange brown 50/5" 1055 40 37-50 trace clay Bottom of borehole at 41.0 feet.

Geo-Advantec, Inc.

S.GP	CLIEN	IT <u>L</u> a				chool C	District	PROJECT NAME La Cañada HS	Pool an	d Site Iı	mprove	ements		
LOG	PROJECT NUMBER 19-1093				PROJECT LOCATION La Cañada									
RING		DRILL						GROUND ELEVATION 1095 ft						
3 BO						ne Way	/ Drilling	GROUND WATER LEVELS:						
-1093		DRILLING METHOD Hollow Stem Auger				_	-	FIRST ENCOUNTER						
B\19					zay									
XIQN					ter Enc			 _ LATITUDE _34.19171 °			DE -1	18.1793	373 °	
APPE												TERBE		<u> </u>
CES	_			ts (l g				ight	Moisture Content (%)		LIMITS		Fines Content (%)
END	Elevation (ft)	Depth (ft)	Sampler	Blow Counts (N Value)	Gaphic Log	nscs	Description	[/] Interpretation	cf. ×	° Co	init	Plastic Limit	Inde	 Sont
-APF) He		San	%Z.	aph	SN	Description	merpretation	Ling G	sture (9	Liquid Limit	tic L	city) sai
LOGS				⊞)	0				Dry Unit Weight (pcf)	Mois	Liqu	Plas	Plasticity Index	造
APS-	1095	0			0,144,144	SM	4" Asphalt Concrete	/					<u> </u>	
S/1-M	_	_				SIVI	ARTIFICIAL FILL							
LCH	_						│ (SM) Silty SAND with gravel: o ├── moist, tan brown	cobble (6"), medium dense, slightly						
IT AT	_	_				SM	NATIVE - ALLUVIUM							
EMEN	<u>1</u> 090	_ 5					(SM) Silty SAND with gravel: of dense, dry to slightly moist, br							
ROVI	_	_					defice, dry to diightly molet, or							
= IMP		_	$oldsymbol{\boxtimes}$	50	4 (444)		very dense, dry, orange brown		118.9	2.7				
SIT							Bottom of bo	rehole at 7.5 feet.						
GEOTECH BH COLUMNS - GINT STD US LAB. GDT - 8/28/19 08:23 - M:\PROJECTS\2019\19-1093-SI-LA CANADA USD_SWIMMING POOL AND SITE IMPROVEMENT AT LCHS\1-MAPS-LOGS-APPENDICES\APPENDIX B\19-1093 BORING LOGS.GP														
NG PC														
MMI														
SWI														
N USE														
VADA														
4 CA														
-SI-L														
-1093														
19/19														
-S\20														
JECT														
\PRC														
3 - M														
9 08:2														
/28/19														
JT - 8														
\B.G														
US L/														
STD														
SINT														
NS - C														
LUMI														
SH CO														
SCHE														
EOTE														

APPENDIX C LABORATORY TEST RESULTS

Project: La Cañada HS Pool & Improvements
Site: La Cañada Flintridge


Project No. <u>19-1093</u> Date: 8/15/2019

Tech: CC

Test Specification: ASTM D422

Sample B-2@7'
Material Silty SAND (SM)

	Mesh	Percent
Sieve	Opening	Passing
	(mm)	(%)
1 1/2 in	38.1	100.0 %
1 in	25.4	100.0 %
3/4 in	19.0	98.9 %
3/8 in	9.51	95.9 %
No. 4	4.75	93.1 %
No. 10	2.00	88.1 %
No. 40	0.425	69.4 %
No. 100	0.150	42.7 %
No. 140	0.106	34.4 %
No. 200	0.075	25.4 %



Geo-Adva	antec, Inc.	SIEVE ANALYSIS	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	
DATE	08-23-2018	South Campus Improvements - La Canada Flintridge, CA	


Project: La Cañada HS Pool & Improvements Site:

Project No. <u>19-1093</u> La Cañada Flintridge Date: 8/15/2019

Tech: CC

Test Specification: ASTM D422 Sample B-4@10'

	Mesh	Percent
Sieve	Opening	Passing
	(mm)	(%)
1 1/2 in	38.1	100.0 %
1 in	25.4	100.0 %
3/4 in	19.0	92.1 %
3/8 in	9.51	89.7 %
No. 4	4.75	83.5 %
No. 10	2.00	76.5 %
No. 40	0.425	57.5 %
No. 100	0.150	41.4 %
No. 140	0.106	35.3 %
No. 200	0.075	28.1 %



Geo-Adva	antec, Inc.	SIEVE ANALYSIS		
PROJECT NO.	19-1093	La Cañada High School New Pool and		
DATE	08-23-2018	South Campus Improvements - La Canada Flintridge, CA		


Project: La Cañada HS Pool & Improvements Site:

Project No. <u>19-1093</u> La Cañada Flintridge Date: 8/15/2019

Tech: CC

Test Specification: ASTM D422 Sample B-4@20'

	Mesh	Percent
Sieve	Opening	Passing
	(mm)	(%)
1 1/2 in	38.1	100.0 %
1 in	25.4	97.8 %
3/4 in	19.0	96.3 %
3/8 in	9.51	88.4 %
No. 4	4.75	76.8 %
No. 10	2.00	63.5 %
No. 40	0.425	36.9 %
No. 100	0.150	21.7 %
No. 140	0.106	18.6 %
No. 200	0.075	15.1 %



Geo-Adva	antec, Inc.	SIEVE ANALYSIS		
PROJECT NO.	19-1093	La Cañada High School New Pool and		
DATE	08-23-2018	South Campus Improvements - La Canada Flintridge, CA		

Project: <u>La Cañada HS Pool & Improvements</u>
Site: <u>La Cañada Flintridge</u>

Project No. <u>19-1093</u>


Date: <u>8/15/2019</u>

Site: La Caña
Tech: CC

Sample B-5@10'

Test Specification: ASTM D422

	Mesh	Percent
	IVIESIT	reiceill
Sieve	Opening	Passing
	(mm)	(%)
1 1/2 in	38.1	100.0 %
1 in	25.4	100.0 %
3/4 in	19.0	100.0 %
3/8 in	9.51	89.5 %
No. 4	4.75	83.2 %
No. 10	2.00	71.7 %
No. 40	0.425	40.9 %
No. 100	0.150	19.3 %
No. 140	0.106	18.0 %
No. 200	0.075	17.3 %



	Geo-Adva	antec, Inc.	SIEVE ANALYSIS		
	PROJECT NO.	19-1093	La Cañada High School New Pool and	1	
Г	DATE	08-23-2018	South Campus Improvements - La Canada Flintridge, CA		


Project: La Cañada HS Pool & Improvements Site:

Project No. <u>19-1093</u> La Cañada Flintridge Date: 8/15/2019

Tech: CC


Test Specification: ASTM D422 Sample B-5@30'

	Mesh	Percent
Sieve	Opening	Passing
	(mm)	(%)
1 1/2 in	38.1	100.0 %
1 in	25.4	100.0 %
3/4 in	19.0	100.0 %
3/8 in	9.51	92.9 %
No. 4	4.75	83.7 %
No. 10	2.00	70.8 %
No. 40	0.425	43.5 %
No. 100	0.150	27.6 %
No. 140	0.106	24.0 %
No. 200	0.075	19.9 %



	Geo-Adva	antec, Inc.	SIEVE ANALYSIS	FIGURE
	PROJECT NO.	19-1093	La Cañada High School New Pool and	1
ı	Geo-Advantec, Inc. PROJECT NO. 19-1093 DATE 08-23-2018		South Campus Improvements - La Canada Flintridge, CA	

PLASTICITY CHART (ASTM D4318)



Liquid Limit (LL)

Symbol	Source	Depth (ft)	Classification	Natural M.C.	Liquid Limit (LL)	Plasticity Index (PI)	%Passing #200 Sieve
×	B-4	10	Silty SAND with gravel (SM)	-	NP	NP	28

Geo-Adva	antec, Inc.	PLASTICITY CHART	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	
DATE	08-23-2018	South Campus Improvements - La Canada Flintridge, CA	

DIRECT SHEAR TEST (ASTM D3080)

Project La Cañada HS Pool & Site Improvement
Project No. 19-1093
Date Tested 8/16/2019


Site Location
La Cañada Flintridge
Tested by AP


Boring No. B-5
Depth 5 ft
Sample Type Intact CD

Soil Description Silty SAND with gravel (SM)

Test Condition Inundated

	Wet Unit Weight (pcf)	Dry Unit Weight (pcf)	Moisture Content (%)	Void Ratio	Saturation (%)	Normal Stress (psf)	Peak Shear Stress (psf)	Ultimate Shear Stress (psf)
Initial	133.6	117.8	13.4	0.43	84.1	500	718	510
Preshear	136.5	117.7	16.0	0.43	100.0	1000	1236	996
						2000	2100	1936





STRENGTH TYPE	COHESION (psf)	FRICTION ANGLE (degrees)
Peak Strength	300	42
Ultimate Strength	120	42

Geo-Adva	antec, Inc.	DIRECT SHEAR TEST RESULTS	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	
DATE	08-23-2018	South Campus Improvements - La Canada Flintridge, CA	

CONSOLIDATION TEST (Consolidation Curve)

Project La Cañada HS Pool & Site Improvement

Project No. 19-1093

Date Tested 8/14/2019

Site Location La Cañada Flintridge


Tested by AP

Boring No. B-5 Sample No. Depth 5 ft Frame No. Sample Type Intact CD

Soil Description Silty SAND with gravel (SM)

Water added 800 psf

CONSOLIDATION CURVE



Initial Moisture Content 13.4% Final Moisture Content 19.3% Initial Dry Unit Weight, pcf 118.5 Final Dry Unit Weight, pcf 110.8 Initial Void Ratio 0.42 Final Void Ratio 0.52 85.7% Initial Degree of Saturation Final Degree of Saturation 100.0% Assumed Specific Gravity 2.7

Remarks Collapse = 0.04 % upon inundation

Geo-Advantec, Inc.		ONE-DIMENSIONAL CONSOLIDATION TEST	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	l
DATE	08-23-2018	South Campus Improvements - La Canada Flintridge, CA	

R-VALUE TEST DATA

Project La Cañada HS Pool & Improvements
Project No. 19-1093
Date Tested


Site Location
La Cañada Flintridge
Test Specification
CT 301

Boring No. B-3 Sample Depth 1 - 5 ft
Test Performed by AP

Soil Description Silty Sand with gravel (SM)

Mold Number	А	В	С	
Exudation Pressure, psi	710	124	102	
Prepared Weight, g	1100	1100	1100	
Final Water Added, g	0	20	25	
Weight, Soil & Mold, g	3156	3174	3177	
Weight, Mold, g	2095	2096	2100	
Height, in	2.42	2.46	2.45	
Expansion, x10-4 inches	0	0	0	
Stability 1,000 (80 psi)	0	0	0	
Stability 2,000 (160 psi)	95	106	118	
Turns Displacement	3.09	3.88	4.2	
(2.5/d)*((Pv/Ph)-1)+1	1.55	1.33	1.21	
100/Above	64	75	83	
R-Value Uncorrected	36	25	17	
R-Value Corrected	36	25	17	

R-VALUE	By Exudation (Uncorrected)	29
R-VA	By Exudation (Corrected)	29
Remarks	Moisture: 9.1%	⁄6



Geo-Adva	antec, Inc.	R-VALUE TEST RESULTS	
PROJECT NO.	19-1093	La Cañada High School New Pool and	
DATE	08-23-2018	South Campus Improvements - La Canada Flintridge, CA	

CORROSION TEST RESULTS

Project / Client	La Cañada HS Pool & Improvements	Project No.	19-1093	Date Tested	8/15/2019
Site Location	La Cañada Flintridge	Test Specification		_ (See notes)
		Tested by	 ΔΡ	Sample Type	bulk

Boring No.	Depth (feet)	Soil Type	Minimum Resistivity (ohm-cm)*	рН	Sulfate Content (ppm)	Chloride Content (ppm)
B-6	1-5	SM	1317	7.20	290	176

^{*}Minimum Resistivty values have been normalized to standard ground temperature of 15.5 Cper CT-643

NOTES: Resistivity Test and pH: California Test Method 643

Sulfate Content: California Test Method 417


Chloride Content: California Test Method 422


Geo-Adva	antec, Inc.	CORROSIVITY TEST RESULTS	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	
DATE	08-23-2018	South Campus Improvements - La Canada Flintridge, CA	

^{**}Temperature of soil sample collected from final resistance measurement per CT-643 $\,$

APPENDIX D

QUADRANGLE MAP





Earthquake Zones of Required Investigation Pasadena Quadrangle

California Geological Survey

This Map Shows Seismic Hazard Zones Alquist-Priolo Earthquake Fault Zones Have Not Been Prepared For The Pasadena Quadrangle

MAP EXPLANATION SEISMIC HAZARD ZONES




Liquefaction Zones
Areas where historical occurrence of liquefaction, or local geological, geotechnical and ground water conditions indicate a potential for permanent ground displacements such that mitigation as defined in Public Resources Code Section 2693(c) would be required.




Earthquake-Induced Landslide Zones
Areas where previous occurrence of landslide movement, or local topographic, geological, geotechnical and subsurface water conditions indicate a potential for permanent ground displacements such that mitigation as defined in Public Resources Code Section 2693(c) would be required.

Geo-Advantec, Inc.		SEISMIC HAZARD ZONES MAP	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	D-1
DATE	08-23-2019	South Campus Improvements - La Canada Flintridge, CA	




APPENDIX E ENGINEERING ANALYSES RESULTS



South Campus Improvements - La Canada Flintridge, CA LIQUEFACTION & SEISMIC SETTLEMENTS La Cañada High School New Pool and Geo-Advantec, Inc. 10-10-2019 19-1093 PROJECT NO. DATE

E-1a

FIGURE



FIGURE

E-1b

South Campus Improvements - La Canada Flintridge, CA

La Cañada High School New Pool and

LIQUEFACTION & SEISMIC SETTLEMENTS

Geo-Advantec, Inc.

10-10-2019

19-1093

PROJECT NO.

DATE

Project La Canada HS Pool and Site Improvements

Test Hole P-1	Depth of Test Hole (ft) 7.00	Pipe Height Above Grade (ft) 3.00	Diameter of Test Hole (ft) 0.667	Soil Classification SM w/ Gravel
CA	19-1093	7/29/2019	MN	Sunny / Hot
Location La Canada, CA	Project No	Date Tested	Tested By	Weather

Sandy	Sandy Soil Criteria Test	est							
									Greater than
		Initial		Final		Initial	Final	Change in	or equal to 12
Trial	Start	Depth to	Stop	Depth to	Time Diff.	Height of	Height of	Water	inch in 30
No	Minute	Water (ft)	Minute	Water (ft)	(min)	Water (in)	Water (in)	Level (in)	minutes?
1	0	5.29	10	5.69	10	56.50	51.75	4.75	n/a
2	0	5.17	10	5.71	10	58.00	51.50	6.50	n/a

Test Data	ta											
		Initial		Final		Initial	Final	Change in		LA County	LA County	Porchet
Trial	Start	Depth to	Stop	Depth to	Time Diff.	Height of	Height of	Water	Percolation	Reduction	Infiltration	Infiltration
No	Minute	Water (ft)	Minute	Water (ft)	(min)	Water (in)	Water (in)	Level (in)	Rate (in/hr)	Factor ^a	Rate ^b (in/hr)	Rate ^c (in/hr)
1	0	5.46	10	5.90	10	54.50	49.25	5.25	31.5	13.97	2.26	1.17
2	0	5.13	10	5.52	10	58.50	53.75	4.75	28.5	15.03	1.90	96.0
3	0	5.54	10	6.04	10	53.50	47.50	00.9	36.0	13.63	2.64	1.37
4	0	5.21	10	2.60	10	57.50	52.75	4.75	28.5	14.78	1.93	1.00
2	0	5.35	10	5.75	10	55.75	51.00	4.75	28.5	14.34	1.99	1.03
9	0	5.54	10	80.9	10	53.50	47.00	6.50	39.0	13.56	2.88	1.49
7	0	5.56	10	00.9	10	53.25	48.00	5.25	31.5	13.66	2.31	1.20
										minimum >	1.90	0.98
										average >	2.27	1.18

^aAdditional safety factor (e.g. site variability, number of tests, long-term siltation, plugging, and maintenance) was not utilized into the above reported rates.

Orange County, December 20, 2013. Technical Guidance Document (TGD) for the Preparation of Conceptual/Preliminary and/or Project Water Quality Management Plans (WQMPs). Exhibit 7.III.

Geo-Adva	intec, Inc.	PERCOLATION TEST DATA	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	E-2a
DATE	08-23-2019	South Campus Improvements - La Canada Flintridge, CA	

^bCounty of Los Angeles, Department of Public Works, Geotechnical and Materials Engineering Division, December 31, 2014. Guidelines for Design, Investigation, and Reporting Low Impact Development Stormwater Infiltration. GS200.1.

Project La Canada HS Pool and Site Improvements

Test Hole P-2	Depth of Test Hole (ft) 7.00	Pipe Height Above Grade (ft) 3.25	Diameter of Test Hole (ft) 0.667	Soil Classification SM w/ Gravel
QA	19-1093	7/29/2019	MM	Sunny / Hot
Location La Canada, CA	Project No	Date Tested	Tested By	Weather

Sandy	Sandy Soil Criteria Test	est							
									Greater than
		Initial		Final		Initial	Final	Change in	or equal to 12
Trial	Start	Depth to	Stop	Depth to	Time Diff.	Height of	Height of	Water	inch in 30
No	Minute	Water (ft)	Minute	Water (ft)	(min)	Water (in)	Water (in) Level (in)	Level (in)	minutes?
1	0	4.13	10	4.52	10	73.50	68.75	4.75	n/a
2	0	4.33	10	4.77	10	71.00	65.75	5.25	n/a

Test Data	ata											
		Initial		Final		Initial	Final	Change in		LA County	LA County	Porchet
Trial	Start	Depth to	Stop	Depth to	Time Diff.	Height of	Height of	Water	Percolation	Reduction	Infiltration	Infiltration
No	Minute	Water (ft)	Minute	Water (ft)	(min)	Water (in)	Water (in)	Level (in)	Rate (in/hr)	Factor ^a	Rate ^b (in/hr)	Rate ^c (in/hr)
1	0	4.46	10	4.92	10	69.50	64.00	5.50	33.0	17.69	1.87	96.0
2	0	4.10	10	4.48	10	73.75	69.25	4.50	27.0	18.88	1.43	0.73
3	0	4.46	10	4.81	10	69.50	65.25	4.25	25.5	17.84	1.43	0.74
4	0	3.17	10	3.54	10	85.00	80.50	4.50	27.0	21.69	1.24	0.64
2	0	4.13	10	4.50	10	73.50	00.69	4.50	27.0	18.81	1.44	0.74
9	0	3.65	10	4.00	10	79.25	75.00	4.25	25.5	20.28	1.26	0.64
										minimum >	1.24	0.64
										average >	1.44	0.74

^aAdditional safety factor (e.g. site variability, number of tests, long-term siltation, plugging, and maintenance) was not utilized into the above reported rates.

^bCounty of Los Angeles, Department of Public Works, Geotechnical and Materials Engineering Division, December 31, 2014. Guidelines for Design, Investigation, and Reporting Low Impact Development Stormwater Infiltration. GS200.1.

MPs).	
ns (WQ	
nent Pla	
Aanager	
\uality N	
Water C	
Project	
and/or a	
liminary	
tual/Pre	
f Concep	
ration o	
ie Prepa	
D) for th	
nent (TGD	
e Docun	
Guidanc	
echnical	
, 2013. Те	
nber 20,	
y, Decen	
ge Count	t 7.III.
Orang	Exhibi

Geo-Advante	intec, Inc.	PERCOLATION TEST DATA	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	E-2b
DATE	08-23-2019	South Campus Improvements - La Canada Flintridge, CA	

Project La Canada HS Pool and Site Improvements

Test Hole P-3	Depth of Test Hole (ft) 7.00	Pipe Height Above Grade (ft) 3.42	Diameter of Test Hole (ft) 0.667	Soil Classification SM w/ Gravel
CA	19-1093	7/29/2019	MN	Sunny / Hot
Location La Canada, CA	Project No	Date Tested	Tested By	Weather

	Sandy Soil Criteria Test	st							
									Greater than
		Initial		Final		Initial	Final	Change in	or equal to 12
Trial	Start	Depth to	Stop	Depth to	Time Diff.	Height of	Height of	Water	inch in 30
No	Minute	Water (ft)	Minute	Water (ft)	(min)	Water (in)	Water (in) Level (in)	Level (in)	minutes?
1	0	80.9	10	6.63	10	52.00	45.50	6.50	n/a
2	0	6.21	10	09.9	10	50.50	45.75	4.75	n/a

Test Data	ıta											
		Initial		Final		Initial	Final	Change in		LA County	LA County	Porchet
Trial	Start	Depth to	Stop	Depth to	Time Diff.	Height of	Height of	Water	Percolation	Reduction	Infiltration	Infiltration
No	Minute	Water (ft)	Minute	Water (ft)	(min)	Water (in)	Water (in)	Level (in)	Rate (in/hr)	Factor ^a	Rate ^b (in/hr)	Rate ^c (in/hr)
1	0	6.38	10	6.81	10	48.50	43.25	5.25	31.5	12.47	2.53	1.32
2	0	6.50	10	7.02	10	47.00	40.75	6.25	37.5	11.97	3.13	1.63
3	0	5.75	10	6.23	10	26.00	50.25	5.75	34.5	14.28	2.42	1.25
4	0	5.83	10	6.17	10	55.00	51.00	4.00	24.0	14.25	1.68	0.87
2	0	6.17	10	6.63	10	51.00	45.50	5.50	33.0	13.06	2.53	1.31
9	0	5.75	10	6.13	10	56.00	51.50	4.50	27.0	14.44	1.87	0.97
7	0	5.96	10	6.52	10	53.50	46.75	6.75	40.5	13.53	2.99	1.55
8	0	6.52	10	7.06	10	46.75	40.25	6.50	39.0	11.88	3.28	1.71
										minimum >	1.68	0.87
										average >	2.55	1.33


^aAdditional safety factor (e.g. site variability, number of tests, long-term siltation, plugging, and maintenance) was not utilized into the above reported rates.

^bCounty of Los Angeles, Department of Public Works, Geotechnical and Materials Engineering Division, December 31, 2014. Guidelines for Design, Investigation, and Reporting Low Impact Development Stormwater Infiltration. GS200.1.

s).	
VQMPs	
lans (V	
nent P	
anager	
ility Mi	
er Qua	
ct Wat	
r Proje	
and/o	
ninary	
I/Prelir	
ceptua	
of Con	
ration	
Prepa	
for the	
(TGD)	
ument	
ce Docı	
uidan	
nical G	
3. Tech	
0, 2013. Te	
mber 20	
, Decer	
County,	=
range (hibit 7.
ō	Ĕ

	IC. PERCOLATION LEST DATA	FIGURE
PROJECT NO. 19-1093	13 La Cañada High School New Pool and	E-2c
DATE 08-23-2019	319 South Campus Improvements - La Canada Flintridge, CA	

APPENDIX G GEOLOGIC AND SEISMIC DATA



PASADENA QUADRANGLE LOS ANGELES COUNTY, CALIFORNIA GEOLOGIC MAP OF THE

BY THOMAS W. DIBBLEE, JR., 1989 EDITED BY HELMUT E. EHRINSPECK, 1989 EDITED BY JOHN A. MINCH, 2010

LEGEND



SURFICIAL SEDIMENTS

Ols

LANDSLIDE AND TALUS DEBRIS

OLDER DISSECTED SURFICIAL SEDIMENT

UNCONFORMITY

CRYSTALLINE BASEMENT ROCKS



<u>Р</u>


South Campus Improvements - La Canada Flintridge, CA

08-23-2019 19-1093

PROJECT NO. DATE

La Cañada High School New Pool and

State of California Department of Conservation



2010 FAULT ACTIVITY MAP OF CALIFORNIA

California Geological Survey, Geologic Data Map No. 6

Compilation and Interpretation by: Charles W. Jennings and William A. Bryant

Graphics by: Milind Patel, Ellen Sander, Jim Thompson, Barbara Wanish and Milton Fonseca

SYMBOL EXPLANATION

Fault traces on land are indicated by solid lines where well located, by dashed lines where approximately located or inferred, and by dotted lines where concealed by younger rocks or by lakes or bays. Fault traces are queried where continuation or existence is uncertain. All offshore faults based on seismic reflection profile records are shown as solid lines where well defined, dashed where inferred, queried where uncertain.

FAULT CLASSIFICATION COLOR CODE (Indicating Recency of Movement)

Fault along which historic (last 200 years) displacement has occurred.

1906 ▶ ◀ 1906

A triangle to the right or left of the date indicates termination point of observed surface displacement. Solid red triangle indicates known location of rupture termination point. Open black triangle indicates uncertain or estimated location of rupture termination point.

Date bracketed by triangles indicates local fault break.

No triangle by date indicates an intermediate point along faultbreak.

CREEP

Fault that exhibits fault creep slippage. Hachures indicate linear extent of fault creep. Annotation (creep with leader) indicates representative locations where fault creep has been observed and recorded.

1968

Square on fault indicates where fault creep slippage has occured that has been triggered by an earthquake on some other fault. Date of causative earthquake indicated. Squares to right and left of date indicate terminal points between which triggered creep slippage has occurred (creep either continuous or intermittent between these end points).

Holocene fault displacement (during past 11,700 years) without historic record.

Late Quaternary fault displacement (during past 700,000 years).

Quaternary fault (age undifferentiated).

Pre-Quaternary fault (older that 1.6 million years) or fault without recognized Quaternary displacement.

ADDITIONAL FAULT SYMBOLS

Bar and ball on downthrown side (relative or apparent).

Arrows along fault indicate relative or apparent direction of lateral movement.

Arrow on fault indicates direction of dip.

Low angle fault (barbs on upper plate).

OTHER SYMBOLS

Numbers refer to annotations listed in the appendices of the accompanying report.

Structural discontinuity (offshore) separating differing Neogene structural domains. May indicate discontinuities between basement rocks

Geo-Advantec, Inc.

FAULT ACTIVITY MAP

FIGURE

PROJECT NO. 19-1093

DATE 08-23-2019

La Cañada High School New Pool and South Campus Improvements - La Canada Flintridge, CA


G-2



Time	Latitude	Longitude	Depth	Mag	MagType	Place
1994-01-17T12:31:58.120Z	34.275	-118.493	5.3	5.9	ml	1km ENE of Granada Hills, California
1994-01-17T12:30:55.390Z	34.213	-118.537	18.2	6.7	mw	1km NNW of Reseda, CA
1991-06-28T14:43:54.660Z	34.270	-117.993	8.0	5.8	mw	13km NNE of Sierra Madre, CA
1987-10-01T14:42:20.020Z	34.061	-118.079	8.9	5.9	mw	2km SSW of Rosemead, CA
1971-02-09T14:02:45.740Z	34.416	-118.370	6.0	5.8	mh	10km SSW of Agua Dulce, CA
1971-02-09T14:01:12.450Z	34.416	-118.370	6.0	5.8	mh	10km SSW of Agua Dulce, CA
1971-02-09T14:00:41.920Z	34.416	-118.370	9.0	6.6	mw	10km SSW of Agua Dulce, CA
1933-03-11T01:54:10.660Z	33.631	-118.000	6.0	6.4	mw	Long Beach, California Earthquake
1899-07-22T20:32:00.000Z	34.300	-117.500		6.4	mw	Southern California
1894-07-30T05:12:00.000Z	34.300	-117.600		5.9	ml	Southern California
1858-12-16T10:00:00.000Z	34.200	-117.400		6.0	ml	Near San Bernardino, California
1855-07-11T04:15:00.000Z	34.100	-118.100		6.0	ml	Greater Los Angeles area, California
1812-12-08T15:00:00.000Z	34.370	-117.650		6.9	ml	Southern California



Geo-Advantec, Inc.		HISTORICAL EARTHQUAKES	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	G-3
DATE	08-23-2019	South Campus Improvements - La Canada Flintridge, CA	







OSHPD

Latitude, Longitude: 34.190908, -118.179020



Туре	Value	Description	Date	8/7/2019, 2:57:26 PM
S _S	2.708	MCER ground motion. (for 0.2 second period)	Design Code	ASCE7-10
S ₁	0.968	MCER ground motion. (for 1.0s period)	Risk Category	II
S _{MS}	2.708	Site-modified spectral acceleration value	Site Class	D - Stiff Soil
S _{M1}	1.453	Site-modified spectral acceleration value		
S _{DS}	1.805	Numeric seismic design value at 0.2 second SA		
S _{D1}	0.968	Numeric seismic design value at 1.0 second SA		
SDC	E	Seismic design category		
Fa	1	Site amplification factor at 0.2 second		
F_v	1.5	Site amplification factor at 1.0 second		
PGA	1.007	MCEG peak ground acceleration		
F _{PGA}	1	Site amplification factor at PGA		
PGA _M	1.007	Site modified peak ground acceleration		





Geo-Advantec, Inc.		SEISMIC DESIGN MAP	FIGURE
PROJECT NO.	19-1093	La Cañada High School New Pool and	G-5
DATE	08-23-2019	South Campus Improvements - La Canada Flintridge, CA	



La Cañada Unified School District—New Outdoor Pool Fo South of Campus Improvement Project Initial Study/Mitigated Negative Declaration	
	E.2 - Paleontological Records Search Results





Natural History Museum of Los Angeles County 900 Exposition Boulevard Los Angeles, CA 90007

tel 213.763.DINO www.nhm.org

Vertebrate Paleontology Section Telephone: (213) 763-3325

e-mail: smcleod@nhm.org

28 May 2020

FirstCarbon Solutions 250 Commerce, Suite 250 Irvine, CA 92602

Attn: Brittany Hagen, Environmental Services Analyst II

re: Paleontological resources for the proposed New Outdoor Pool Facility and South of Campus Improvement Project, FCS Project # 5153.0002, in the City of La Cañada Flintridge, Los Angeles County, project area

Dear Brittany:

I have conducted a thorough search of our paleontology collection records for the locality and specimen data for the proposed New Outdoor Pool Facility and South of Campus Improvement Project, FCS Project # 5153.0002, in the City of La Cañada Flintridge, Los Angeles County, project area as outlined on the portion of the Pasadena USGS topographic quadrangle map that you sent to me via e-mail on 14 May 2020. We do not have any vertebrate fossil localities that lie directly within the proposed project boundaries, but we do have localities somewhat nearby from sedimentary deposits similar to those that may occur at depth in the proposed project area.

In the entire proposed project area the surficial deposits consist of younger Quaternary Alluvium, derived as alluvial fan deposits from the San Gabriel Mountains to the northeast. These sedimentary deposits typically do not contain significant vertebrate fossils, at least in the uppermost layers, but underlying older and perhaps finer-grained Quaternary deposits may well contain significant vertebrate fossils. Our closest vertebrate fossil locality in older Quaternary deposits is LACM 2027, southeast of the proposed project area, south of Washington Boulevard and west of Allen Avenue near the western end of Brigden Road, that produced a fossil specimen of mastodon, *Mammut*, at unstated depth. Further to the southwest of the proposed project area, in Eagle Rock east of the Pasadena Freeway (I-110) and Eagle Rock Boulevard just south of York Boulevard, our

older Quaternary locality LACM (CIT) 342 produced fossil specimens of turkey, *Parapavo californicus*, and mammoth, *Mammuthus*, at a depth of 14 feet below the surface. The fossil turkey specimen from locality LACM (CIT) 342 was published in the scientific literature by L.H. Miller in 1942 (A New Fossil Bird Locality. Condor, 44(6):283-284) and the mammoth specimen was a rare, nearly complete skeleton and was published in the scientific literature by V.L. Roth in 1984 (How Elephants Grow: Heterochrony and the Calibration of Developmental Stages in Some Living and Fossil Species. Journal of Vertebrate Paleontology, 4(1):126-145).

Shallow excavations in the younger Quaternary Alluvium exposed throughout the proposed project area are unlikely to uncover significant vertebrate fossils. Deeper excavations that extend down into older and perhaps finer-grained Quaternary deposits, however, may well uncover significant fossil vertebrate specimens. Any substantial excavations in the proposed project area, therefore, should be monitored closely to quickly and professionally recover any fossil remains discovered while not impeding development. Also, sediment samples should be collected and processed to determine the small fossil potential in the proposed project area. Any fossils recovered during mitigation should be deposited in an accredited and permanent scientific institution for the benefit of current and future generations.

This records search covers only the vertebrate paleontology records of the Natural History Museum of Los Angeles County. It is not intended to be a thorough paleontological survey of the proposed project area covering other institutional records, a literature survey, or any potential on-site survey.

Sincerely,

Samuel A. McLeod, Ph.D. Vertebrate Paleontology

Summel a. M. Leod

enclosure: invoice