



GEOTECHNICAL INVESTIGATION

BOUTIQUE HOTEL

160 EL CAMINO REAL

SAN BRUNO, CALIFORNIA 94066

Prepared for

Shanghai Dowell Group

1799 Bayshore Highway, Suite 208

Burlingame, California 94010

June 2017

Project No. 4078-1



June 5, 2017

4078-1

Shanghai Dowell Group
1799 Bayshore Highway, Suite 208
Burlingame, California 94010

**RE: GEOTECHNICAL INVESTIGATION
BOUTIQUE HOTEL
160 EL CAMINO REAL
SAN BRUNO, CALIFORNIA**

Attention: Mr. Chen Cu Wu

Gentlemen:


As requested, we have performed a geotechnical investigation for the proposed boutique hotel to be constructed at 160 El Camino Real in San Bruno, California. The accompanying report summarizes the results of our field exploration, laboratory testing, and engineering analysis, and presents geotechnical recommendations for the proposed project.


We refer you to the text of our report for specific recommendations.

Thank you for the opportunity to work with you on this project. If you have any questions or comments about our findings or recommendations for the project, please call.

Very truly yours,

ROMIG ENGINEERS, INC.


Tom W. Porter, P.E.

A circular professional engineer seal for Thomas W. Porter, No. 77883, Civil Engineer, State of California. The seal includes the text 'REGISTERED PROFESSIONAL ENGINEER', 'THOMAS W. PORTER', 'No. 77883', 'CIVIL', and 'STATE OF CALIFORNIA'.


Glenn A. Romig, P.E., G.E.

A circular professional engineer seal for Glenn A. Romig, No. 002157, Geotechnical Engineer, State of California. The seal includes the text 'REGISTERED PROFESSIONAL ENGINEER', 'GLENN A. ROMIG', '002157', 'GEOTECHNICAL', and 'STATE OF CALIFORNIA'.

Copies: Addressee (1)
RYS Architects, Inc. (4)
Attn: Mr. Jim Rato
Hohbach-Lewin, Inc. (via email)
Attn: Mr. Michael Morgan

GAR:TWP:dr

**GEOTECHNICAL INVESTIGATION
BOUTIQUE HOTEL
160 EL CAMINO REAL
SAN BRUNO, CALIFORNIA 94066**

**PREPARED FOR:
SHANGHAI DOWELL GROUP
1799 BAYSHORE HIGHWAY, SUITE 208
BURLINGAME, CALIFORNIA 94010**

**PREPARED BY:
ROMIG ENGINEERS, INC.
1390 EL CAMINO REAL, SECOND FLOOR
SAN CARLOS, CALIFORNIA 94070**

JUNE 2017



TABLE OF CONTENTS

	Page No.
Letter of transmittal	
Title Page	
TABLE OF CONTENTS	
INTRODUCTION.....	1
Project Description	1
Scope of Work	1
Limitations.....	2
SITE ENVIRONMENTAL DOCUMENTATION.....	2
SITE EXPLORATION AND RECONNAISSANCE.....	3
Previous Geotechnical Investigation	3
Surface Conditions	4
Subsurface Conditions.....	4
Ground Water	4
GEOLOGIC SETTING.....	5
Faulting and Seismicity	5
Table 1. Earthquake Magnitudes and Historical Earthquakes	6
Earthquake Design Parameters	7
Table 2. 2016 CBC Seismic Design Data	7
Geologic Hazards	7
Dynamic Densification	8
CONCLUSIONS.....	9
FOUNDATIONS	10
Mat Foundation	10
Lateral Loads for Basement Mat	11
Basement Water Proofing.....	11
Settlement	11
SLABS-ON-GRADE.....	12
General Slab Considerations	12
Exterior Flatwork.....	12
Basement Mat	12
Moisture Considerations.....	13
BASEMENT WALLS	13
TEMPORARY BASEMENT EXCAVATION SHORING.....	14
Tie Backs	16
VEHICLE PAVEMENTS.....	16
Asphalt Concrete Pavements	16
Table 3. Pavement Sections	16
Portland Cement Concrete Pavements	17
EARTHWORK.....	18
Clearing and Subgrade Preparation	18
Existing Fill Recommendations	18

TABLE OF CONTENTS

(Continued)

Material For Fill.....	19
Temporary Slopes and Excavations.....	19
Compaction.....	19
Table 4. Compaction Recommendations	20
Surface Drainage	20
FUTURE SERVICES	21
Plan Review	21
Construction Observation and Testing	21

REFERENCES

FIGURE 1 - VICINITY MAP

FIGURE 2 - SITE PLAN

FIGURE 3 - VICINITY GEOLOGIC MAP

FIGURE 4 - REGIONAL FAULT AND SEISMICITY MAP

APPENDIX A - FIELD INVESTIGATION

Figure A-1 - Key to Exploratory Boring Logs

Exploratory Boring Log EB-1 and EB-2

APPENDIX B - SUMMARY OF LABORATORY TESTS

APPENDIX C - PREVIOUS EXPLORATION LOGS

Boring Logs EB-1 through EB-4 (Romig Engineers, Inc., 2002)

APPENDIX D - SELECTED SITE PLANS FROM ENVIRONMENTAL REPORTS

Figure 3 - Groundwater Analytical Results (TEC Accutite, 2001)

Figure 4 - Horizontal Extent of the Existing Impacted Soil (TEC Accutite, 1999)

Figure 2 - Site Map (TEC Accutite, 2014)

**GEOTECHNICAL INVESTIGATION
FOR
BOUTIQUE HOTEL
160 EL CAMINO REAL
SAN BRUNO, CALIFORNIA**

INTRODUCTION

This report presents the results of our geotechnical investigation for the proposed boutique hotel to be constructed at 160 El Camino Real in San Bruno, California. The location of the site is shown on the Vicinity Map, Figure 1. The purpose of this investigation was to evaluate subsurface conditions at the site and to provide geotechnical recommendations for design and construction of the proposed project.

Project Description

The project consists of constructing an approximately 19,500 square-foot, three-story hotel complex at the referenced site in San Bruno. The building is expected to have one level of basement parking below the entire footprint of the site and extend about 12 feet below grade. The basement will be accessed through a ramp at the northeast side of the site. The ground floor will consist of the hotel lobby, business center, coffee shop, and street level parking with guest rooms at the second and third floors. Structural loads are expected to be relatively light to moderate as is typical for this type of construction.

Scope of Work

Our scope of work for this investigation was presented in our agreement with Shanghai Dowell Group dated April 20, 2017. In order to complete our investigation, we performed the following work.

- Review of geologic and geotechnical literature in our files pertinent to the general area of the site including our previous August 26, 2002 geotechnical report for the site.
- Subsurface exploration consisting of drilling, sampling, and logging two exploratory borings in the area of the proposed building.
- Laboratory testing of selected soil samples to aid in soil classification and to help evaluate the engineering properties of the soils encountered at the site.



- Engineering analysis and evaluation of the surface and subsurface data to develop earthwork guidelines and foundation design criteria for the proposed building.
- Preparation of this report presenting our findings and geotechnical recommendations for the proposed construction.

Limitations

This report has been prepared for the exclusive use of Shanghai Dowell Group for specific application to developing geotechnical design criteria for the proposed boutique hotel to be constructed at 160 El Camino Real in San Bruno, California. We make no warranty, expressed or implied, except that our services are performed in accordance with the geotechnical engineering principles generally accepted at this time and location. This report was prepared to provide engineering opinions and recommendations only. In the event there are any changes in the nature, design, or location of the project, or if any future improvements are planned, the conclusions and recommendations presented in this report should not be considered valid unless 1) the project changes are reviewed by us, and 2) the conclusions and recommendations presented in this report are modified or verified in writing.

The analysis, conclusions, and recommendations presented in this report are based on site conditions as they existed at the time of our investigation; the currently planned improvements; review of previous reports relevant to the site conditions; and laboratory test results. In addition, it should be recognized that certain limitations are inherent in the evaluation of subsurface conditions, and that certain conditions may not be detected during an investigation of this type. Changes in the information or data gained from any of these sources could result in changes in our conclusions or recommendations. If such changes occur, we should be advised so that we can review our report in light of those changes.

SITE ENVIRONMENTAL DOCUMENTATION

We briefly reviewed the tank closure report prepared by TEC Accutite, Inc., dated January 10, 2002; ground water monitoring report prepared by TEC Environmental, Inc., dated May 5, 2014; and site closure report prepared by the San Mateo County Department of Environmental Health, dated August 12, 2015, and other relevant documents available on the State Geotracker website. Our primary concern in reviewing these documents was the location of the former tanks and excavations related to environmental remediation work (specific environmental testing results were not reviewed). A brief summary of these documents is presented below.



The documents indicate that the property was formerly an Olympic Service Station which closed in 1999. A total of 10 underground storage tanks were removed from the site in 1999. Subsequent environmental soil sampling and testing indicated that petroleum hydrocarbon impacted soil existed below the former tank locations. In 2000, the impacted soil was excavated from a majority of the site within about 3 to 4 feet of the sidewalks to a depth of about 20 feet below existing grades. According to previous discussions with TEC Accutite, the tank removal contractor, the excavation was backfilled in 1 to 2 foot lifts and compacted with a vibratory roller, however no compaction testing or geotechnical observation was performed during the backfill operations. Our previous geotechnical investigation included four exploratory borings advanced at the northwest half of the site, which encountered poorly to marginally compacted fill to a depth of about 18.5 feet. The exact limits of the former excavation is unknown, however the rough limits of the impacted soil is shown on Site Plan, Figure 2.

The San Mateo County closure report confirmed the completion of the tank removal, soil sampling, and site closure activities related to the underground storage tanks formerly located at the site. No further corrective action was required.

Selected site plans showing the locations of former structures, excavations, and soil sampling and monitoring well locations from the previous environmental work documented by TEC Environmental are attached in Appendix D.

SITE EXPLORATION AND RECONNAISSANCE

Site reconnaissance and subsurface exploration were performed on May 16, 2017. Subsurface exploration was performed using a Mobile B-40 truck-mounted drill equipped with 8-inch diameter hollow-stem augers. Two exploratory borings were advanced to depths of 30 to 45 feet. The approximate locations of the borings are presented on the Site Plan, Figure 2. The boring logs and the results of our laboratory tests are attached in Appendices A and B, respectively.

Previous Geotechnical Investigation

We performed a geotechnical investigation at the site for a previously planned office building; the results were presented in our report dated August 26, 2002. The site investigation included advancing four exploratory borings to depths ranging between 10 to 40 feet. At the location of Borings EB-1, EB-2, and EB-3, which were advanced within the previous environmental remediation area, we encountered approximately 13.5 to 18.5 feet of fill which consisted of loose to medium dense clayey sand, underlain by dense to very dense poorly graded sand and silty sand which extended to the maximum

depth explored. In Boring EB-4 which was advanced outside of the fill area, we encountered medium dense to very dense clayey sand, silty sand, and poorly graded sand that extended to the maximum depth explored. Ground water was not encountered in the borings during the investigation. The locations of the borings from the previous investigation are shown on the Site Plan, Figure 2 and the boring logs are attached in Appendix C.

Surface Conditions

The rectangular shaped site is located in a commercial area at the southeast corner of the intersection of El Camino Real and San Luis Avenue. At the time of our investigation, the site was a relatively flat, undeveloped lot surrounded by chain-link fencing. The gently sloping site generally had an exposed soil surface covered with areas of native vegetation.

Subsurface Conditions

At the location of Boring EB-1, we encountered approximately 18.5 feet of loose to medium clayey sand underlain by approximately 4.5 feet of very stiff to hard sandy silt with clay. We then encountered approximately 5 feet of stiff sandy silt/sandy lean clay of low plasticity underlain by medium dense to very dense silty sand that extended to a depth of about 42 feet. Beneath the silty sand, we encountered dense poorly graded sand that extended to the maximum depth explored of 45 feet.

In Boring EB-2, we encountered approximately 4.5 feet of soft sandy silt/sandy lean clay of low plasticity underlain by approximately 14 feet of medium dense to very dense clayey sand. We then encountered medium dense to very dense silty sand which extended to the maximum boring depth of 30 feet.

Ground Water

Free ground water was not encountered in our borings during or immediately following our field exploration. The borings were backfilled with grout shortly after drilling, therefore a stabilized ground water level may not have been obtained. Ground water was also not encountered during our previous investigation in 2002.

The semi-annual ground water monitoring report prepared by TEC Environmental, dated May 5, 2014, presented ground water depth measurements from seven monitoring wells which were measured between 2001 and 2014. During that time period, the measurements indicated a low ground water elevation of -10.1 feet in February 2009 and a high ground water elevation of 16.9 feet in September 2009. However there appeared to be significant fluctuations in the ground water data in the 2008 to 2009 time period.

Between 2010 to 2014 (the last five years of data), the ground water was generally measured between elevations of -1.1 to -6.6 feet. Based on the elevation of the site of about 42 to 49 feet, over the last five years of data the depth to ground water would be approximately 43.8 to 54.3 feet below existing grades. These ground water measurements are relative to approximate existing site grades and have not been correlated to any specific survey datum.

Based on the findings from our investigation, our local experience, and our analysis of the nearby ground water elevation trends over the last 16 years, in our opinion, for design purposes the highest projected ground water depth would be approximately 25 feet below the existing ground surface, however the current ground water level is expected to be approximately 43 feet or deeper. Please be cautioned that fluctuations in the level of ground water can occur due to variations in rainfall, landscaping, surface and subsurface drainage patterns, and other factors.

GEOLOGIC SETTING

As part of our investigation, we briefly reviewed our local experience and geologic information in our files pertinent to the general area of the site. The information reviewed indicates the site is located in an area underlain by Pliocene age bedrock of the Colma Formation, Qc (Pampeyan, 1994). The unit is expected to consist of weakly consolidated, moderately well bedded, yellowish gray and tan sandy clay and silty sand, and friable light to reddish brown, poorly sorted to well sorted sand and gravel. The geology of the site vicinity is shown on the Vicinity Geologic Map, Figure 3.

The lot and immediate site vicinity are located in an area that slopes gently to the northeast (approximately 10 feet vertically per 500 feet laterally, although locally the topography may be steeper). The site is located at an elevation of approximately 45 feet above sea level.

Faulting and Seismicity

There are no mapped through-going faults within or adjacent to the site and the site is not located within a State of California Earthquake Fault Zone (formerly known as a Special Studies Zone), an area where the potential for fault rupture is considered probable. The closest active fault is the San Andreas fault, located approximately 1.5 miles southwest of the property. Thus, the likelihood of surface rupture occurring from active faulting at the site is remote.

The San Francisco Bay Area is an active seismic region. Earthquakes in the region result from strain energy constantly accumulating because of the northwestward movement of

the Pacific Plate relative to the North American Plate. On average about 1.6-inches of movement occur per year. Historically, the Bay Area has experienced large, destructive earthquakes in 1838, 1868, 1906, and 1989. The faults considered most likely to produce large earthquakes in the area include the San Andreas, San Gregorio, Hayward, and Calaveras faults. The San Gregorio fault is located approximately 7 miles southwest of the site. The Hayward and Calaveras faults are located approximately 17 and 26 miles northeast of the site, respectively. These faults and significant earthquakes that have been documented in the Bay Area are listed in Table 1 below and are shown on the Regional Fault and Seismicity Map, Figure 4.

**Table 1. Earthquake Magnitudes and Historical Earthquakes
Boutique Hotel
San Bruno, California**

<u>Fault</u>	<u>Maximum Magnitude (Mw)</u>	<u>Historical Earthquakes</u>	<u>Estimated Magnitude</u>
San Andreas	7.9	1989 Loma Prieta	6.9
		1906 San Francisco	7.9
		1865 N. of 1989 Loma Prieta Earthquake	6.5
		1838 San Francisco-Peninsula Segment	6.8
		1836 East of Monterey	6.5
Hayward	7.1	1868 Hayward	6.8
		1858 Hayward	6.8
Calaveras	6.8	1984 Morgan Hill	6.2
		1911 Morgan Hill	6.2
		1897 Gilroy	6.3
San Gregorio	7.3	1926 Monterey Bay	6.1

In the future, the subject property will undoubtedly experience severe ground shaking during moderate and large magnitude earthquakes produced along the San Andreas fault or other active Bay Area fault zones. The Working Group On California Earthquake Probabilities, a panel of experts that are periodically convened to estimate the likelihood of future earthquakes based on the latest science and ground motion prediction modeling, concluded there is a 72 percent chance for at least one earthquake of Magnitude 6.7 or larger in the Bay Area before 2045. The Hayward fault has the highest likelihood of an earthquake greater than or equal to magnitude 6.7 in the Bay Area, estimated at 14 percent, while the likelihood on the San Andreas and Calaveras faults is estimated at approximately 6 and 7 percent, respectively (Working Group, 2015).

Earthquake Design Parameters

The State of California currently requires that buildings and structures be designed in accordance with the seismic design provisions presented in the 2016 California Building Code and in ASCE 7-10, “Minimum Design Loads for Buildings and Other Structures.” Based on site geologic conditions and on information from our subsurface exploration at the site, the site may be classified as Site Class D, stiff soil, in accordance with Chapter 20 of ASCE 7-10. Spectral acceleration response parameters S_S and S_1 , site coefficients F_a and F_v , spectral response values S_{MS} and S_{M1} , and design spectral response parameters S_{DS} and S_{D1} listed on Table 2 are based on the figures and tables in the 2016 California Building Code and in the lookup tables at the U.S.G.S. website based on the latitude (37.617) and longitude (-122.4076) of the site.

Table 2. 2016 CBC Seismic Design Data
Boutique Hotel
San Bruno, California

<u>Design Category</u>		<u>Design Value</u>
Site Class -		D
Spectral Response Parameter for Short Period -	S_S	2.387
Spectral Response Parameter for 1-s Period -	S_1	1.147
Site Coefficient -	F_a	1.0
Site Coefficient -	F_v	1.5
Spectral Response Value -	S_{MS}	2.387
Spectral Response Value -	S_{M1}	1.720
Design Spectral Acceleration Parameter -	S_{DS}	1.592
Design Spectral Acceleration Parameter -	S_{D1}	1.147

Geologic Hazards

As part of our investigation, we reviewed the potential for geologic hazards to impact the site and the proposed building, considering the geologic setting and the soils encountered during our investigation. The results of our review are presented below and in the following sections of our report.

- **Fault Rupture** - The site is not located in a State of California Earthquake Fault Zone or area where fault rupture is considered likely. Therefore, active faults are not believed to exist beneath the site and the potential for fault rupture at the site is considered low.

- Ground Shaking - The site is located in an active seismic area. Moderate to large earthquakes are probable along several active faults in the greater Bay Area over a 30 to 50 year design life. Strong ground shaking should therefore be expected several times during the life of the building, as is typical for sites throughout the Bay Area. The building should be designed in accordance with current earthquake resistance standards.
- Liquefaction - Liquefaction occurs when saturated sandy soils lose strength during earthquake shaking. Ground settlement often accompanies liquefaction. Soils most susceptible to liquefaction are saturated, loose, sandy silts, silty sands, and uniformly graded sands. Since saturated loose sands and soft silts and other types of soil prone to liquefaction were not encountered in our borings below the highest projected ground water depth, the likelihood of liquefaction occurring within the soils encountered within the depth of our borings is low. The site is also not located within a currently published State liquefaction hazard zone.

Dynamic Densification

Dynamic densification occurs during moderate and large earthquakes when soft or loose, natural or fill soils densify and settle, often unevenly across a site. To evaluate the potential for earthquake-induced dynamic densification of the sandy and silty soils encountered at the site, we performed a settlement analysis of the data from our boring following the methods presented in the US Army Corps of Engineers EM1110-1-1904.

The existing fill and medium dense sandy and silty soils encountered above the expected depth of the basement foundation were not included in our analysis since these soils will be removed during excavation for the basement and any remaining fill will be removed and replaced with compacted fill below the basement mat following the recommendations in our report.

Soils potentially prone to dynamic densification were encountered between depths of approximately 20 to 23 feet and 32 to 40 feet in Boring EB-1, and between depths of approximately 14 to 22 feet in Boring EB-2. Our analysis also included the borings from our previous investigation (2002) which encountered soils potentially prone to dynamic densification between depths of approximately 18.5 to 26 feet in Boring EB-1; between depths of approximately 14 to 17 feet in Boring EB-2; and between depths of approximately 14 to 17 feet in Boring EB-4. These sands and silts are potentially prone to dynamic densification when subjected to the maximum considered earthquake acceleration (PGA_M) of 0.919g based on the Probabilistic Seismic Hazards Mapping Ground Motion Page (CGS, 2017).

Based on the results of our analysis, we estimate that settlement of about ¼- to ½-inches could occur during major earthquake shaking. In our opinion, differential settlement of about ¼- to ½-inches across the basement mat is estimated from dynamic densification of these silts and sands during seismic shaking. This differential settlement would not be expected to significantly affect the proposed building supported on a structural mat at the proposed basement level designed and constructed in accordance with the recommendations presented in this report.

CONCLUSIONS

From a geotechnical viewpoint, the site is suitable for the proposed boutique hotel provided the recommendations presented in this report are followed during design and construction. Specific geotechnical recommendations for the project are presented in the following sections of this report.

The primary geotechnical concerns for the proposed hotel are the presence of 18.5 to 20 feet of loose to medium dense undocumented backfill which was placed during the previous environmental remediation work, the medium dense native sand strata which are subject to dynamic densification, and the potential for severe ground shaking during a major earthquake. Based on the proposed basement elevation, the basement foundation is expected to span across areas of the existing loose to medium dense undocumented fill and medium dense to very dense native soil. The existing deep fuel storage tank related backfill does not appear to have been compacted to current engineering standards.

In our opinion, any existing fill not removed during excavation for the basement should be excavated and compacted below the footprint of the proposed basement. Based on the depth of fill encountered in our borings and review of the available environmental reports, we expect that approximately 4.5 to 7 feet of fill will remain below the bottom of the basement foundation. The reworking of the fill and subgrade preparation should proceed as recommended in the section of this report titled “Earthwork.”

In our opinion, the building may be supported on a mat foundation bearing on medium dense to dense native soil and/or properly compacted fill at the basement level. Prior to mat construction, the mat subgrade should be prepared and compacted as recommended in the “Earthwork” section of this report. At this time, building loads are not available. During design, our office should be retained to finalize the preliminary foundation design and building settlement criteria presented in this report.

We note that portions of the clayey sand strata encountered in the borings within the basement excavation depth were judged to have limited cohesion and may be prone to sloughing and/or caving if excavated near-vertical. Temporary basement excavation shoring should be designed and installed accordingly. This information should be considered by the contractor when establishing temporary shoring/sloping criteria for basement excavation, as needed.

Because subsurface conditions may vary from those encountered at the location of our borings, and to observe that our recommendations are properly implemented, we recommend that we be retained to: 1) review the grading and foundation plans for conformance with the recommendations presented in this report and; 2) observe and test during earthwork, foundation, shoring, drainage and slab construction.

FOUNDATIONS

Mat Foundation

In our opinion, the proposed building and basement walls may be supported on a reinforced concrete mat foundation bearing in undisturbed native soil and properly compacted fill. On a preliminary basis, the mat may be designed for an average allowable bearing pressure of up to 3,000 pounds per square foot for dead plus live loads with a one-third increase allowed when considering additional short-term wind or seismic loading. A maximum localized bearing pressure of 3,500 pounds per square foot from dead plus live loads may be used at concentrated column or wall loads.

The mat should be reinforced to provide structural continuity and to permit spanning of local irregularities. On a preliminary basis, a modulus of subgrade reaction (K_v) of 100 pounds per cubic inch may be assumed for the mat subgrade. This value is based on a 1-foot square bearing area and should be scaled to account for mat foundation size effects. Alternatively, once building loads and estimated post construction differential settlement are available, a modulus of subgrade reaction (K_v) may be estimated for the mat subgrade (typically on the order of 15 to 25 pci). The mat should also be designed with sufficient depth and reinforcing to span over localized weak compressible areas.

The bottom of the excavation for the basement mat should be cleaned of all loose or relatively soft soil and debris. A member of our staff should observe the excavation and evaluate whether scarification and compaction or proof rolling of the bottom of the excavation is needed. If desired, a 6-inch section of crushed rock or a thin working slab could be placed as a working surface on the prepared and approved mat subgrade.

Lateral Loads for Basement Mat

Lateral loads may be resisted by friction between the bottom of the mat and the supporting subgrade, and by passive soil pressure acting against the mat or basement walls cast neat in foundation excavations or backfilled with properly compacted structural fill. The below values given for coefficient of friction and passive soil resistance are ultimate values. We recommend that a factor of safety of 1.5 be applied.

An ultimate coefficient of friction of 0.375 may be assumed for the mat bearing directly on native soil. An ultimate coefficient of friction of 0.45 may be assumed for the mat foundation bearing directly on a crushed rock section. However, since it is likely that a water-proofing membrane will be installed between the bottom of the mat and subgrade soil, the structural engineer should consult with the water-proofing consultant for the coefficient of friction between the membrane and subgrade soil.

Ultimate passive soil resistance may be simulated by an equivalent fluid pressure of 450 pounds per cubic foot beginning at the ground surface, where appropriate. The ultimate passive soil resistance acting on the mat foundation should be limited to 3,000 pounds per square foot. This passive pressure assumes lateral deflection at the top of the mat foundation on the order of 1/4- to 1/2-inch.

Basement Water Proofing

We have not provided recommendations regarding the method or details for basement damp-proofing since design of damp-proofing systems is outside of our scope of services and expertise. Installing adequate damp-proofing below and behind the edges of the basement floor and behind the basement walls is essential for the success of the basement structure. Placing concrete with a low water cement ratio should be considered as one step of good damp-proofing as discussed below. The damp-proofing system below the basement mat may be placed directly on a layer of 3/4-inch crushed rock or a thin working slab (as discussed previously), or alternative methods as determined by the water-proofing consultant and/or contractor.

Settlement

On a preliminary basis, 30-year post construction total settlement due to static loads is not expected to exceed approximately 1-inch across the mat foundation. We estimate post construction differential settlement of about 3/4-inch between interior columns and perimeter basement walls across the mat foundation. Once the range of dead and live loads and the foundation configuration have been developed, we should update the magnitude of total and differential foundation settlement to help establish if an

adjustment should be made to the allowable bearing capacity values and/or differential settlement.

SLABS-ON-GRADE

General Slab Considerations

To reduce the potential for movement of the slab subgrade, at least the upper 6-inches of subgrade soil should be scarified and compacted at a moisture content above the laboratory optimum. The soil subgrade should be kept moist up until the time the non-expansive fill, aggregate base, and/or vapor barrier is placed. Slab subgrades and non-expansive fill should be prepared and compacted as recommended in the section of this report titled "Earthwork." Overly soft or moist soils should be removed from slab-on-grade areas. Exterior flatwork and interior slabs-on-grade should be underlain by a layer of non-expansive fill as recommended below. The non-expansive fill should consist of Class 2 aggregate base or clayey soil with a Plasticity Index of 15 or less.

Considering the potential for some differential movement of the surface and near-surface soils, we expect that reinforced slabs will perform better than unreinforced slabs. Consideration should be given to using a control joint spacing on the order of 2 feet in each direction for each inch of slab thickness.

Exterior Flatwork

Concrete walkways and exterior flatwork should be at least 4 inches thick and should be constructed on at least 6 inches of Class 2 aggregate base. For improved performance, exterior slabs-on-grade, such as for patios, may constructed with a thickened edge to improve edge stiffness and to reduce the potential for water seepage under the edge of the slabs and into the underlying base and subgrade.

Basement Mat

In our opinion, the basement mat and parking ramp (prior to installation of the water proofing) may be placed directly on a 6-inch thick layer of $\frac{3}{4}$ -inch crushed rock or a thin working slab, or alternative methods as determined by the water-proofing consultant and/or contractor. A member of our staff should observe the excavation and evaluate whether or not scarification and compaction or proof rolling of the bottom of the excavation below the basement mat and ramp is needed.

As discussed previously, installing adequate damp-proofing below and behind the edges of the basement floor and behind the basement walls is essential for the success of the basement structure.

Moisture Considerations

The permeability of concrete is affected significantly by the water:cement ratio of the mix, with lower water:cement ratios producing more damp-resistant slabs (or basement retaining walls) and higher strength. Where moisture protection is important and/or where the concrete will be placed directly on the damp-proofing, the water:cement ratio should be 0.45 or less. To increase the workability of the concrete, mid-range plasticizers may be added to the mix. Water should not be added to the mix unless the slump is less than specified and the water:cement ratio will not exceed 0.45. Other steps that may be taken to reduce moisture transmission through concrete slabs-on-grade include moist curing for 5 to 7 days and allowing the slab to dry for a period of two months or longer prior to placing floor coverings. Prior to installation of floor coverings, it may be appropriate to test the slab moisture content for adherence to the manufacturer's requirements to determine whether a longer drying time is necessary.

BASEMENT WALLS

We recommend that retaining walls with level backfill that are not free to deflect or rotate, such as the basement walls, be designed to resist an equivalent fluid pressure of 40 pounds per cubic foot plus an additional uniform lateral pressure of $8H$ pounds per square foot, where H is the height of the wall in feet. Although a deep ground water condition is expected, if the basement walls will be designed as undrained, some provision should be made in basement wall design for at least locally undrained wall backfill conditions. To account for approximately 6 feet of perched ground water behind the basement walls, we recommend adding a line load surcharge of 680 pounds per lineal foot behind the basement walls. Since perched water conditions could develop at various depths behind the basement walls, we recommend the line load surcharge be applied at various depths to check the wall design for perched water conditions. Where retaining walls will be subjected to surcharge loads, such as from foundations, construction loading, or traffic on adjacent streets, the walls should also be designed for an additional uniform lateral pressure equal to one-half of the surcharge pressure.

Based on the site peak ground acceleration (PGA), on Seed and Whitman (1970); Al Atik and Sitar (2010); and Lew et al. (2010); seismic loads on retaining walls that can yield may be simulated by a line load of $10H^2$ (in pounds per foot, where H is the wall height in feet). Seismic loads on walls that cannot yield may be subjected to a seismic load as high as about $16H^2$. This seismic surcharge line load should be assumed to act at $1/3H$ above the base of the wall (in addition to the active wall design pressure of 40 pounds per cubic foot).

As noted above, a reliable water-proofing system should be installed below and around the edges of the foundation and slab floor as well as behind the basement walls.

If the basement is designed for drained conditions, in order to prevent buildup of water pressure from surface water infiltration, a subsurface drainage system should be installed behind the walls (and the perched ground water condition recommended above may be eliminated). The drainage system should consist of a 4-inch diameter perforated pipe (perforations placed down) embedded in a section of 1/2- to 3/4-inch, clean, crushed rock at least 12 inches wide. Backfill above the perforated drain line should also consist of 1/2- to 3/4-inch, clean, crushed rock to within about 1½ to 2 feet below exterior finished grade. A filter fabric should be wrapped around the crushed rock to protect it from infiltration of native soil. The upper 1½ to 2 feet of backfill should consist of compacted native soil. The perforated pipe should discharge into a sump that pumps to a suitable location. Damp-proofing of the walls should be included in areas where wall dampness and efflorescence would be undesirable.

Miradrain, Enkadrain or other drainage fabrics approved by our office may also be used for wall drainage as an alternative to the gravel drainage system described above. If used, the drainage fabric should extend from a depth of about 1 foot below the top of the wall backfill down to the drain pipe or to a manufacturer specified collector pipe at the base of the wall. If a perforated drainpipe is installed, a minimum 12-inch wide section of ½-inch to ¾-inch clean crushed rock and filter fabric should be placed around the drainpipe, as recommended previously.

Backfill (if any) behind the retaining walls should be compacted to at least 90 percent relative compaction using light compaction equipment. If heavy equipment is used for compaction of wall backfill, the walls may need to be temporarily braced.

The basement retaining walls should be supported on a structural mat foundation designed in accordance with the recommendations presented previously.

TEMPORARY BASEMENT EXCAVATION SHORING

We understand that stitch piers with wood lagging possibly with tie-backs, as needed, could be used for support of the temporary basement excavation and required excavations to properly compact the existing fill below the building area. The following preliminary geotechnical design parameters are provided for conventional concrete filled soldier beams and lagging basement shoring and support. The shoring engineer and contractor who are responsible for performance of the shoring system may recommend alternative

values based on their experience and the allowable deflection needed for the site, adjacent structures, and surface features.

In our opinion, the temporary stitch piers may be designed to support an active lateral soil pressure of at least 38 pounds per cubic foot across the entire vertical excavation cut. This design soil pressure assumes that drainage can occur between shimmed wood lagging resulting in a drained soil pressure on the shoring system. Where vehicle traffic or construction loads, will be applied on the soil surface behind the back of the shoring, a lateral surcharge pressure equal to 50 percent of the vertical surcharge pressure should be included in the shoring design.

Passive soil resistance of 375 pounds per cubic foot may be assumed to act on the stitch piers over 2 pier diameters when calculating the minimum depth of the piers required to resist lateral loads; at least the upper foot of passive resistance should be neglected in design. A skin friction of 350 pounds per square foot may be assumed for the stitch piers when calculating the allowable vertical capacity of the piers.

Some vertical and lateral deflection of the temporary shoring should be expected to occur in the planned cantilever shoring system which could result in ground settlement adjacent to the shoring. The amount of vertical and lateral deflection at the shoring face is typically on the order of $\frac{1}{2}$ to $1\frac{1}{2}$ -percent of the total excavation depth (H) (reducing to ground settlement on the order of about $\frac{1}{8}$ to $\frac{1}{4}$ percent of H within a lateral distance of about twice the total excavation depth). If this amount of deflection and settlement is not tolerable, the shoring system should be designed for a higher active or at-rest pressure in order to limit the potential deflections.

Larger deflections than estimated above are possible depending upon how the shoring is constructed and/or backfilled. The contractor should monitor vertical and lateral deflections as the basement excavation, shoring installation and building construction proceeds and modify the design as needed to control deflections to acceptable amounts. In addition, it should be the contractor's responsibility to undertake a preconstruction survey with benchmarks and photographs of the adjacent properties.

Concrete should be placed in the pier excavations as soon as practical after drilling. Ground water seepage may be encountered during pier drilling and it is possible that ground water seepage could cause some sloughing or caving of the pier holes. This can be further evaluated during drilling of the initial piers. If ground water cannot be effectively pumped from the pier holes, concrete will need to be placed in the pier holes by the tremie method.

Tie Backs

Tie backs may be installed to laterally support the shoring system as needed. The tie backs may be designed with allowable bond strength between the native soil and the anchors of 1,100 pounds per square foot. This bond strength (with a factor of safety of at least 1.5) should be confirmed in the field during the initial stages of construction with proof load testing as required by the shoring designer. The actual bond strength and pull-out capacity of the tie back is dependent upon the installation method and should be confirmed in the field during construction with performance and proof load testing; our representative should observe the testing to verify that the needed capacities are obtained.

The design bond length will depend on the anchor spacing and desired capacity, however we suggest a minimum bond length of 10 feet beyond the active soil wedge behind the shoring walls would generally be appropriate. We suggest that the minimum unbonded length within the active zone of the tie-backs be assumed to be the length in front of a 60 degree slope (from horizontal) projected up from the base of the retaining wall.

VEHICLE PAVEMENTS**Asphalt Concrete Pavements**

Based on the anticipated composition of the surface soils, and an estimated traffic index for the proposed pavement loading conditions, we developed the minimum pavement sections presented in Table 3 below based on Procedure 630 of the Caltrans Highway Design Manual.

**Table 3. Pavement Sections
Boutique Hotel
San Bruno, California**

Traffic Loading Condition	Design Traffic Index	Asphalt Concrete (inches)	Aggregate Base* (inches)	Total Thickness (inches)
Automobile Parking	4.0	3.0	6.0	9.0
Automobile Access	4.5	3.0	8.0	11.0
Light Truck Traffic	5.0	3.0	10.0	13.0
Moderate Truck Traffic	6.0	4.0	11.0	13.0
Heavy Truck Traffic	7.0	4.0	15.0	19.0

*Caltrans Class 2 Aggregate Base (minimum R-value = 78).

The Traffic Indices used in our pavement thickness calculations are considered reasonable values for this development and are based on engineering judgment rather than on detailed traffic projections. Asphalt concrete and aggregate base should conform to and be placed in accordance with the requirements of the Caltrans Standard Specifications, latest edition, except that compaction should be based on ASTM Test D1557.

We recommend that measures be taken to limit the amount of surface water that seeps into the aggregate base and subgrade below vehicle pavements, particularly where the pavements are adjacent to landscape areas. Seepage of water into the pavement base material tends to soften the subgrade, increasing the amount of pavement maintenance that is required and shortening the pavement service life. Deepened curbs extending 4-inches below the bottom of the aggregate base layer are generally effective in limiting excessive water seepage. Other types of water cutoff devices or edge drains may also be considered to maintain pavement service life.

Portland Cement Concrete Pavements

If Portland Cement Concrete (PCC) pavements are to be used on portions of the site, the minimum required thickness of the PCC pavements should be based on the anticipated traffic loading, the modulus of rupture of the concrete that will be used for pavement construction, and the composition and supporting characteristics of the soil subgrade below the pavement section.

To provide a general guideline for the minimum required thickness of PCC pavements, we used information in the Portland Cement Association publication titled “Thickness Design for Concrete Highway and Street Pavements.” We assumed “low” subgrade support from the on-site soils, considering typical residential street traffic (up to 25 daily trucks with maximum single axle loads of 22 kips and maximum tandem axle loads of 36 kips), aggregate-interlock joints (i.e. no dowels), no concrete shoulder or curb, a modulus of rupture of concrete of 550 psi (which correlates to a concrete compressive strength of approximately 3,700 psi), at least 10 inches of Class 2 aggregate base below the PCC pavement, and 20-year pavement service life. Sufficient control joints should be incorporated in the design and construction to limit and control cracking.

Based on the design assumptions described above, a PCC pavement with a thickness of at least 6 inches would be adequate for average daily truck traffic (ADTT) of one; a thickness of at least 6.5 inches would be adequate for ADTT of 13; and a thickness of at least 7 inches would be adequate for ADTT of 110.

EARTHWORK

Clearing and Subgrade Preparation

All deleterious materials, such utilities to be abandoned, vegetation, root systems, surface fills, topsoil, etc. should be cleared from areas of the site to be built on or paved. The actual stripping depth should be determined by a member of our staff in the field at the time of construction. Excavations that extend below finished grade should be backfilled with structural fill that is water-conditioned, placed, and compacted as recommended in the section of this report titled "Compaction."

After the site has been properly cleared, stripped, and excavated to the required grades, exposed soil surfaces in areas to receive structural fill or slabs-on-grade should be scarified to a depth of 6 inches, moisture conditioned, and compacted as recommended for structural fill in the section of this report titled "Compaction." On-site soils, foundation and utility trench excavations, and slab and pavement subgrades should be kept in a moist condition throughout the construction period.

A member of our staff should observe the basement excavation to evaluate whether scarification and compaction or proof rolling of the excavation bottom is needed.

If a temporary ramp is constructed to access portions of the basement excavation, the ramp should be properly backfilled with compacted on-site soil as recommended in this report for structural fill. A member of our staff should observe and test during backfilling of the temporary entrance ramp and basement walls.

Existing Fill Recommendations

In our opinion, after excavation of the proposed basement, any remaining fill should be excavated and compacted below the mat foundation. The approximate limits of the existing fill are roughly shown on Figure 2 and is expected to extend to a depth of approximately 18.5 to 20 feet below existing site grades. The fill should be excavated down to dense native soil and the resulting excavations backfilled with on-site inorganic non-expansive material, imported non-expansive fill, or Class 2 aggregate base placed in lifts no thicker than 8-inches and compacted as recommended below. Proposed backfill materials should be approved by a member of our staff prior to delivery to the site. The backfill should be moisture conditioned, and compacted as recommended in the section of this report titled "Compaction." Near-vertical excavation sidewalls should be cut (benched) at a projected plane approximating a 1:1 (horizontal:vertical) to the mat subgrade. Benching should begin about 2 feet above the bottom of the excavation. A

member of our staff should observe and test during benching, backfilling, and compaction of the pool on nearly a full time basis.

Material For Fill

All on-site soil containing less than 3 percent organic material by weight (ASTM D2974) may be suitable for use as structural fill. Structural fill should not contain rocks or pieces larger than 6 inches in greatest dimension and no more than 15 percent larger than 2.5 inches. Imported, non-expansive fill should have a Plasticity Index no greater than 15, should be predominately granular, and should have sufficient binder so as not to slough or cave into foundation excavations or utility trenches. A member of our staff should approve proposed import materials prior to their delivery to the site.

Temporary Slopes and Excavations

The contractor should be responsible for the design and construction of all temporary slopes and any required shoring. Shoring and bracing should be provided in accordance with all applicable local, state, and federal safety regulations, including current OSHA excavation and trench safety standards.

Temporary excavations and slopes less than 4 feet deep excavated in the native soils should be capable of standing near-vertical for short construction periods with minimal bracing. Due to the potential for variation of the on-site soil, field modification of temporary cut slopes may be required. Unstable materials encountered on excavations and slopes during and after excavation should be trimmed off even if this requires cutting the slopes back to a flatter inclination.

Portions of the clayey sands or silty sands encountered at the site were judged to have limited cohesion and will be prone to sloughing and/or caving if excavated near-vertical. This information should be considered by the contractor when establishing temporary shoring/sloping criteria for basement excavation.

Compaction

Scarified soil surfaces and all structural fill should be compacted in uniform lifts no thicker than 8-inches in uncompacted thickness, conditioned to the appropriate moisture content, and compacted as recommended for structural fill in Table 4 on the following page. The relative compaction and moisture content recommended in Table 4 is relative to ASTM Test D1557, latest edition.

**Table 4. Compaction Recommendations
Boutique Hotel
San Bruno, California**

	<u>Relative Compaction*</u>	<u>Moisture Content*</u>
<u>General</u>		
• Scarified subgrade in areas to receive structural fill.	90 percent	Above optimum
• Structural fill composed of native soil.	90 percent	Above optimum
• Structural fill composed of non-expansive fill.	90 percent	Above optimum
• Structural fill below a depth of 5 feet.	92 percent	Above optimum
<u>Pavement Areas</u>		
• Upper 6-inches of soil below aggregate base.	95 percent	Near optimum
• Aggregate base.	95 percent	Near optimum
<u>Utility Trench Backfill</u>		
• On-site soil.	90 percent	Near optimum
• Imported sand	95 percent	Near optimum

* Relative to ASTM Test D1557, latest edition.

Surface Drainage

Finished grades should be designed to prevent ponding and to drain surface water away from foundations and edges slabs and pavements, and toward suitable collection and discharge facilities. Slopes of at least 2 percent are recommended for flatwork and pavement areas with 5 percent preferred in landscape areas within 8 feet of the structures, where possible. At a minimum, splash blocks should be provided at the ends of downspouts to carry surface water away from perimeter foundations. Preferably, downspout drainage should be collected in a closed pipe system that is routed to a storm drain system or other suitable discharge outlet.

Drainage facilities should be observed to verify that they are adequate and that no adjustments need to be made, especially during first two years following construction. We recommend that an as-built plan be prepared to show the locations of all surface and subsurface drain lines and clean-outs. Drainage facilities should be periodically checked

to verify that they are continuing to function properly. The drainage facilities will probably need to be periodically cleaned of silt and debris that may build up in the lines.

FUTURE SERVICES

Plan Review

Romig Engineers should review the completed grading and foundation plans for conformance with the recommendations presented in this report. We should be provided with these plans as soon as possible upon their completion in order to limit the potential for delays in the permitting process that might otherwise be attributed to our review. In addition, it should be noted that many of the local building and planning departments now require “clean” geotechnical plan review letters prior to acceptance of plans for their final review. Since our plan reviews typically result in recommendations for modification of the plans, our generation of a “clean” review letter often requires two iterations. At a minimum, we recommend the following note be added to the plans.

“Earthwork, foundation construction, pier drilling, tie-back and/or soil nail installation, mat and/or slab subgrade preparation, utility trench backfill, basement wall drainage and backfill, pavement construction, and site drainage should be performed in accordance with the geotechnical report prepared by Romig Engineers, Inc., dated June 5, 2017. Romig Engineers should be notified at least 48 hours in advance of any earthwork or foundation construction and should observe and test during earthwork and foundation construction as recommended in the geotechnical report.”

Construction Observation and Testing

The earthwork and foundation phases of construction should be observed and tested by us to 1) confirm that subsurface conditions are compatible with those used in the analysis and design; 2) observe compliance with the design concepts, specifications, and recommendations; and 3) allow design changes in the event that subsurface conditions differ from those anticipated. The recommendations presented in this report are based on a limited amount of subsurface exploration. The nature and extent of variation across the site may not become evident until construction. If variations are exposed during construction, it will be necessary to reevaluate our recommendations.



REFERENCES

Al Atik, L., and Sitar, N., 2010, Seismic Earth Pressures on Cantilever Retaining Structures, Journal of Geotechnical and Geoenvironmental Engineering, ASCE Vol. 136, No. 10.

American Society of Civil Engineers, 2010, Minimum Design Loads for Buildings and Other Structures, ASCE Standard 7-10.

California Building Standards Commission, and International Code Council, 2016 California Building Code, California Code of Regulations, Title 24, Part 2.

County of San Mateo Health System, August 12, 2015, Case Closure, Remedial Action Oversight, , Former Al's Olympic, 160 (170) El Camino Real, San Bruno, California, SMC Co Site No. 880048.

Idriss, I.M., and Boulanger, R.W., 2008, Soil Liquefaction During Earthquakes, Earthquake Engineering Research Institute (EERI), Oakland, California.

Lew, M., Al Atik, L., Sitar, N., Pourzanjani, M., & Hudson, M., 2010, Seismic Earth Pressures on Deep Building Basements, SEAOC 2010 Convention Proceedings.

Pampeyan, Earl H., 1994, Geologic Map of the Montara Mountain and San Mateo 7-1/2' Quadrangles, San Mateo, County, California, U.S. Geological Survey Map I-2390.

Romig Engineers, Inc., August 26, 2002, Geotechnical Investigation, New Office Building, San Bruno, California, Project No. 856-2.

TEC Accutite, January 10, 2002, Case Closure Summary, Al's Olympic, 160 El Camino Real, San Bruno, California, Consultant Report, SMC Co No. 880048.


TEC Environmental, May 5, 2014, First Semi-Annual 2014 Groundwater Monitoring Report, Former Al's Olympic Service Station, 160 El Camino Real, San Bruno, California, SMC Co No. 880048.

U.S. Army Corps of Engineers, 1990, Engineering and Design, Settlement Analysis, Engineer Manual 1110-1-1904, Department of the Army, Washington, DC, September 30, 1990.

U.S.G.S., 2017, U.S. Seismic Design Maps, Earthquake Hazards Program, <http://earthquake.usgs.gov/designmaps/us/application.php>

Working Group on California Earthquake Probabilities (WGCEP), 2015, Long-Term Time-Dependent Probabilities for the Third Uniform California Earthquake Rupture Forecast, Version 3 (UCERF 3), U.S. Geological Survey Open File Report 2013-1165.






Scale: 1 inch = 2000 feet

Base is United States Geological Survey Montara Mountain 7.5 Minute Quadrangle, dated 1997.


VICINITY MAP
BOUTIQUE HOTEL
SAN BRUNO, CALIFORNIA

FIGURE 1
JUNE 2017
PROJECT NO. 4078-1



SITE PLAN
BOUTIQUE HOTEL
SAN BRUNO, CALIFORNIA

FIGURE 2
JUNE 2017
PROJECT NO. 4078-1



LEGEND

Qac	Coarse-grained alluvium
Qm	Bay mud
Qf₁	Artificial fill - Unit 1
Qc	Colma Formation
Tme	Merced Formation
fsr	Sheared rock

	Geologic Contact - dashed where approximate, dotted where inferred.
	Fault - dashed where approximate, dotted where inferred.




Scale: 1 inch = 2000 feet

Base is Geologic Map of the Montara Mountain and San Mateo 7.5 Minute Quadrangles, San Mateo County, California, (Pampeyan, 1994).

VICINITY GEOLOGIC MAP
BOUTIQUE HOTEL
SAN BRUNO, CALIFORNIA

FIGURE 3
JUNE 2017
PROJECT NO. 4078-1



REGIONAL FAULT AND SEISMICITY MAP
BOUTIQUE HOTEL
SAN BRUNO, CALIFORNIA

FIGURE 4
JUNE 2017
PROJECT NO. 4078-1

APPENDIX A

FIELD INVESTIGATION

The soils encountered during drilling were logged by our representative and samples were obtained at depths appropriate to the investigation. The samples were taken to our laboratory where they were evaluated and classified in accordance with the Unified Soil Classification System. The logs of our borings and a summary of the soil classification system used on the logs (Figure A-1), are attached.
















Several tests were performed in the field during drilling. The standard penetration test resistance was determined by dropping a 140-pound hammer through a 30-inch free fall and recording the blows required to drive the 2-inch diameter sampler 18 inches. The standard penetration test (SPT) resistance is the number of blows required to drive the sampler the last 12 inches and is recorded on the boring logs at the appropriate depths. Soil samples were also collected using 2.5-inch and 3.0-inch O.D. drive samplers. The blow counts shown on the logs for these larger diameter samplers do not represent SPT values and have not been corrected in any way.

The location of the borings were established by pacing using the site plan provided to us and should be considered accurate only to the degree implied by the method used.

The boring logs and related information depict our interpretation of subsurface conditions only at the specific location and time indicated. Subsurface conditions and ground water levels at other locations may differ from conditions at the locations where sampling was conducted. The passage of time may also result in changes in the subsurface conditions.



USCS SOIL CLASSIFICATION

PRIMARY DIVISIONS			SOIL TYPE		SECONDARY DIVISIONS	
COARSE GRAINED SOILS ($< 50\%$ Fines)	GRAVEL	CLEAN GRAVEL ($< 5\%$ Fines)	GW		Well graded gravel, gravel-sand mixtures, little or no fines.	
			GP		Poorly graded gravel or gravel-sand mixtures, little or no fines.	
		GRAVEL with FINES	GM		Silty gravels, gravel-sand-silt mixtures, non-plastic fines.	
			GC		Clayey gravels, gravel-sand-clay mixtures, plastic fines.	
	SAND	CLEAN SAND ($< 5\%$ Fines)	SW		Well graded sands, gravelly sands, little or no fines.	
			SP		Poorly graded sands or gravelly sands, little or no fines.	
		SAND WITH FINES	SM		Silty sands, sand-silt mixtures, non-plastic fines.	
			SC		Clayey sands, sand-clay mixtures, plastic fines.	
FINE GRAINED SOILS ($> 50\%$ Fines)	SILT AND CLAY Liquid limit $< 50\%$		ML		Inorganic silts and very fine sands, with slight plasticity.	
			CL		Inorganic clays of low to medium plasticity, lean clays.	
			OL		Organic silts and organic clays of low plasticity.	
	SILT AND CLAY Liquid limit $> 50\%$		MH		Inorganic silt, micaceous or diatomaceous fine sandy or silty soil.	
			CH		Inorganic clays of high plasticity, fat clays.	
			OH		Organic clays of medium to high plasticity, organic silts.	
HIGHLY ORGANIC SOILS			Pt		Peat and other highly organic soils.	
BEDROCK			BR		Weathered bedrock.	

RELATIVE DENSITY

SAND & GRAVEL	BLOWS/FOOT*
VERY LOOSE	0 to 4
LOOSE	4 to 10
MEDIUM DENSE	10 to 30
DENSE	30 to 50
VERY DENSE	OVER 50

CONSISTENCY

SILT & CLAY	STRENGTH^	BLOWS/FOOT*
VERY SOFT	0 to 0.25	0 to 2
SOFT	0.25 to 0.5	2 to 4
FIRM	0.5 to 1	4 to 8
STIFF	1 to 2	8 to 16
VERY STIFF	2 to 4	16 to 32
HARD	OVER 4	OVER 32

GRAIN SIZES




BOULDERS	COBBLES	GRAVEL		SAND			SILT & CLAY
		COARSE	FINE	COARSE	MEDIUM	FINE	
	12 "	3"	0.75"	4	10	40	200
SIEVE OPENINGS				U.S. STANDARD SERIES SIEVE			

Classification is based on the Unified Soil Classification System; fines refer to soil passing a No. 200 sieve.

* Standard Penetration Test (SPT) resistance, using a 140 pound hammer falling 30 inches on a 2 inch O.D. split spoon sampler; blow counts not corrected for larger diameter samplers.

^ Unconfined Compressive strength in tons/sq. ft. as estimated by SPT resistance, field and laboratory tests, and/or visual observation.

KEY TO SAMPLERS

	Modified California Sampler (3-inch O.D.)
	Mid-size Sampler (2.5-inch O.D.)
	Standard Penetration Test Sampler (2-inch O.D.)

KEY TO EXPLORATORY BORING LOGS

BOUTIQUE HOTEL
SAN BRUNO, CALIFORNIA

FIGURE A-1

JUNE 2017
PROJECT NO. 4078-1



LOGGED BY: RL

DATE DRILLED: 05/16/17

EXPLORATORY BORING LOG EB-1
BOUTIQUE HOTEL
SAN BRUNO, CALIFORNIA

PAGE 1 OF 3

JUNE 2017

PROJECT NO. 4078-1











DRILL TYPE: Mobile Drill B-40 with 8" Hollow Stem Auger

LOGGED BY: RL

DEPTH TO GROUND WATER: Not Encountered **SURFACE ELEVATION:** NA

DATE DRILLED: 05/16/17

CLASSIFICATION AND DESCRIPTION	SOIL CONSISTENCY/ DENSITY or ROCK HARDNESS* (Figure A-2)	SOIL TYPE	SOIL SYMBOL	DEPTH (FEET)	SAMPLE INTERVAL	PEN. RESISTANCE (Blows/ft)	WATER CONTENT (%)	SHEAR STRENGTH (TSF)*	UNCONFIN. COMP. (TSF)*
Light gray, Sandy Silt with clay, very moist, fine to medium grained sand, low plasticity fines, gaseous odor.	Very Stiff	ML		20		27	31		
Brownish gray, Sandy Silt/Sandy Lean Clay, moist, fine grained sand, low plasticity. ● 64% Passing No. 200 Sieve.	Stiff	ML/CL		25		11	22		
Light gray to brown, Silty Sand, moist, fine to medium grained sand, trace coarse sand, low plasticity fines. Color transition to grayish tan. Increased silt content. ● 50% Passing No. 200 Sieve.	Medium Dense to Very Dense	SM		30		53	15		
				35		38	16		
				40		25	20		
Continued on Next Page									

EXPLORATORY BORING LOG EB-1

BOUTIQUE HOTEL

SAN BRUNO, CALIFORNIA

BORING EB-1

PAGE 2 OF 3




JUNE 2017

PROJECT NO. 4078-1



LOGGED BY: RL

DATE DRILLED: 05/16/17

CLASSIFICATION AND DESCRIPTION	SOIL CONSISTENCY/ DENSITY or ROCK HARDNESS* (Figure A-2)	SOIL TYPE	SOIL SYMBOL	DEPTH (FEET)	SAMPLE INTERVAL	PEN. RESISTANCE (Blows/ft)	WATER CONTENT (%)	SHEAR STRENGTH (TSF)*	UNCONFIN. COMP. (TSF)*
Light gray, Silty Sand, moist, fine to medium grained sand low plasticity fines.	Dense	SM		40		50	10		
Light borwn, Poorly Graded Sand, slightly moist, fine to medium grained sand.	Dense	SP		45					
Bottom of Boring at 45 feet.				50					
				55					
				60					

Note: The stratification lines represent the approximate boundary between soil and rock types, the actual transition may be gradual.

*Measured using Torvane and Pocket Penetrometer devices.

BORING EB-1

PAGE 3 OF 3

JUNE 2017

PROJECT NO. 4078-1



LOGGED BY: RL

DATE DRILLED: 05/16/17

EXPLORATORY BORING LOG EB-2
BOUTIQUE HOTEL
SAN BRUNO, CALIFORNIA

PAGE 1 OF 2

JUNE 2017

PROJECT NO. 4078-1




DRILL TYPE: Mobile Drill B-40 with 8" Hollow Stem Auger

LOGGED BY: RL

DEPTH TO GROUND WATER: Not Encountered **SURFACE ELEVATION:** NA

DATE DRILLED: 05/16/17

CLASSIFICATION AND DESCRIPTION	SOIL CONSISTENCY/ DENSITY or ROCK HARDNESS* (Figure A-2)	SOIL TYPE	SOIL SYMBOL	DEPTH (FEET)	SAMPLE INTERVAL	PEN. RESISTANCE (Blows/ft)	WATER CONTENT (%)	SHEAR STRENGTH (TSF)*	UNCONFIN. COMP. (TSF)*
Light gray to brown, Silty Sand, moist, fine to medium grained, low plasticity fines. ● 36% Passing No. 200 Sieve. Slightly moist.	Medium Dense to Very Dense	SM		20	---	23	19		
					●				
				25	---				
				30	---				
Bottom of Boring at 30 feet. Note: The stratification lines represent the approximate boundary between soil and rock types, the actual transition may be gradual. *Measured using Torvane and Pocket Penetrometer devices.						51	10		
				35					
				40					

EXPLORATORY BORING LOG EB-2
 BOUTIQUE HOTEL
 SAN BRUNO, CALIFORNIA

BORING EB-2
 PAGE 2 OF 2
 JUNE 2017
 PROJECT NO. 4078-1



APPENDIX B

LABORATORY TESTS

Samples from subsurface exploration were selected for tests to help evaluate the physical and engineering properties of the soils encountered at the site. The tests that were performed are briefly described below.

The natural moisture content was determined in accordance with ASTM D2216 on nearly all of the soil samples recovered from the borings. This test determines the moisture content, representative of field conditions at the time the samples were collected. The results are presented on the boring logs at the appropriate sample depths.

The amount of silt and clay-sized material present was determined on five samples of soil in accordance with ASTM D422. The results are presented on the boring logs at the appropriate sample depths.

The amount of dry density was determined on two samples of soil in accordance with ASTM D7263. The results of these tests are presented on the boring logs at the appropriate sample depths.



APPENDIX C

PREVIOUS EXPLORATION LOGS

Boring Logs EB-1 through EB-4 (Romig Engineers, Inc., 2002)



DRILL TYPE: B53 Mobile drill with 8 inch Hollow Stem Auger

LOGGED BY: CB

DEPTH TO GROUND WATER: Not Encountered

SURFACE ELEVATION: NA

DATE DRILLED: 6/5/02

CLASSIFICATION AND DESCRIPTION	SOIL CONSISTENCY/ DENSITY or ROCK HARDNESS* (Figure A-2)	SOIL TYPE	DEPTH (FEET)	SAMPLE INTERVAL	SPT RESISTANCE (Blows/ft)	WATER CONTENT (%)	SHEAR STRENGTH (TSF)*	UNCONFIN. COMP. (TSF)*
Fill: Gray, Clayey Sand, slightly moist, fine grained sand, fine angular gravel, low to medium plasticity fines.	Medium Dense	SC	0					
			5		18	10		2.0
Fill: Reddish brown, Clayey Sand, slightly moist, fine to coarse grained sand, fine to coarse angular gravel, low to medium plasticity fines.	Loose to Medium Dense	SC						
◆ 19% Passing No. 200 Sieve.								
			10		7	8		0.5
Note: The stratification lines represent the approximate boundary between soil and rock types, the actual transition may be gradual.								
*Measured using Torvane and Pocket Penetrometer devices.			15		14	7		0.0
Light brown, Silty Sand, moist, fine grained sand, low plasticity fines, native soil.	Dense	SM						
			20		35	18		1.0
Continued on Sheet 2 of 2								

EXPLORATORY BORING LOG EB-1
PRUDENTIAL OFFICE BUILDING
SAN BRUNO, CALIFORNIA

BORING EB-1
AUGUST 2002
SHEET 1 OF 2

DRILL TYPE: B53 Mobile drill with 8 inch Hollow Stem Auger

LOGGED BY: CB

DEPTH TO GROUND WATER: Not Encountered

SURFACE ELEVATION: NA

DATE DRILLED: 6/5/02

CLASSIFICATION AND DESCRIPTION	SOIL CONSISTENCY/ DENSITY or ROCK HARDNESS* (Figure A-2)	SOIL TYPE	DEPTH (FEET)	SAMPLE INTERVAL	SPT RESISTANCE (Blows/ft)	WATER CONTENT (%)	SHEAR STRENGTH (TSF)*	UNCONFIN. COMP. (TSF)*
Light brown Silty Sand (Continued)	Dense	SM	20					
Gray, Silty Sand, fine grained sand, moist, low plasticity fines.	Dense to Very Dense	SM	25		35	24	0.5	
◆ 81 % Passing No. 200 Sieve.			30		52	21	1.5	
Note: The stratification lines represent the approximate boundary between soil and rock types, the actual transition may be gradual.								
*Measured using Torvane and Pocket Penetrometer devices.								
Gray, Poorly Graded Sand, primarily medium to coarse grained sand, moist to very moist, low plasticity fines.	Very Dense	SP	35		62	11	0.0	
			40		73	17	3.0	
Bottom of Boring at 40 Feet.								

EXPLORATORY BORING LOG EB-1
PRUDENTIAL OFFICE BUILDING
SAN BRUNO, CALIFORNIA

BORING EB-1
AUGUST 2002
SHEET 2 OF 2

DRILL TYPE: B53 Mobile drill with 8 inch Hollow Stem Auger

LOGGED BY: CB

DEPTH TO GROUND WATER: Not Encountered

SURFACE ELEVATION: NA

DATE DRILLED: 6/5/02

CLASSIFICATION AND DESCRIPTION	SOIL CONSISTENCY/ DENSITY or ROCK HARDNESS* (Figure A-2)	SOIL TYPE	DEPTH (FEET)	SAMPLE INTERVAL	SPT RESISTANCE (Blows/ft)	WATER CONTENT (%)	SHEAR STRENGTH (TSF)*	UNCONFIN. COMP. (TSF)*
Fill: Reddish brown, Clayey Sand, slightly moist, fine grained sand, fine to coarse angular gravel, low to medium plasticity fines. ◆ 37% Passing No. 200 Sieve. ◆ 24% Passing No. 200 Sieve.	Loose to Medium Dense	SC	0		4	15		0.5
			5	◆				
			10	◆				
Gray, Silty Sand, moist, fine grained sand, low plasticity fines, native soil. Note: The stratification lines represent the approximate boundary between soil and rock types, the actual transition may be gradual. *Measured using Torvane and Pocket Penetrometer devices.	Dense	SM			24	15		0.5
			15					
			20					
Continued on Sheet 2 of 2								

EXPLORATORY BORING LOG EB-2
PRUDENTIAL OFFICE BUILDING
SAN BRUNO, CALIFORNIA

BORING EB-2
AUGUST 2002
SHEET 1 OF 2

DRILL TYPE: B53 Mobile drill with 8 inch Hollow Stem Auger

LOGGED BY: CB

DEPTH TO GROUND WATER: Not Encountered

SURFACE ELEVATION: NA

DATE DRILLED: 6/5/02

CLASSIFICATION AND DESCRIPTION	SOIL CONSISTENCY/ DENSITY or ROCK HARDNESS* (Figure A-2)	SOIL TYPE	DEPTH (FEET)	SAMPLE INTERVAL	SPT RESISTANCE (Blows/ft)	WATER CONTENT (%)	SHEAR STRENGTH (TSF)*	UNCONFIN. COMP. (TSF)*
Gray Silty Sand (Continued)	Dense	SM	20					
Gray, Sandy Clay, moist, fine grained sand, low to medium plasticity fines.	Very Stiff	CL	25		18	29	1.0	1.0
Light brown, Silty Sand, moist, fine to coarse grained sand low to medium plasticity fines.	Dense to Very Dense	SM	30		46	10		0.0
			35		45	16		1.5
			40		56	21		
Bottom of Boring at 40 feet.								

Note: The stratification lines represent the approximate boundary between soil and rock types, the actual transition may be gradual.

*Measured using Torvane and Pocket Penetrometer devices.

EXPLORATORY BORING LOG EB-2
PRUDENTIAL OFFICE BUILDING
SAN BRUNO, CALIFORNIA

BORING EB-2
AUGUST 2002
SHEET 2 OF 2

DRILL TYPE: B53 Mobile drill with 8 inch Hollow Stem Auger

LOGGED BY: CB

DEPTH TO GROUND WATER: Not Encountered

SURFACE ELEVATION: NA

DATE DRILLED: 6/5/02

CLASSIFICATION AND DESCRIPTION	SOIL CONSISTENCY/ DENSITY or ROCK HARDNESS* (Figure A-2)	SOIL TYPE	DEPTH (FEET)	SAMPLE INTERVAL	SPT RESISTANCE (Blows/ft)	WATER CONTENT (%)	SHEAR STRENGTH (TSF)*	UNCONFIN. COMP. (TSF)*
Fill: Reddish brown, Clayey Sand, slightly moist, fine grained sand, fine to coarse angular gravel, low to medium plasticity fines.	Loose to Medium Dense	SC	0					
			5		13	9		4.5
			10		10	10		
Bottom of Boring at 10 Feet.								
			15					
			20					
Note: The stratification lines represent the approximate boundary between soil and rock types, the actual transition may be gradual. *Measured using Torvane and Pocket Penetrometer devices.								

EXPLORATORY BORING LOG EB-3
PRUDENTIAL OFFICE BUILDING
SAN BRUNO, CALIFORNIA

BORING EB-3
AUGUST 2002

DRILL TYPE: B53 Mobile drill with 8 inch Hollow Stem Auger

LOGGED BY: CB

DEPTH TO GROUND WATER: Not Encountered

SURFACE ELEVATION: NA

DATE DRILLED: 6/5/02

CLASSIFICATION AND DESCRIPTION	SOIL CONSISTENCY/ DENSITY or ROCK HARDNESS* (Figure A-2)	SOIL TYPE	DEPTH (FEET)	SAMPLE INTERVAL	SPT RESISTANCE (Blows/ft)	WATER CONTENT (%)	SHEAR STRENGTH (TSF)*	UNCONFIN. COMP. (TSF)*
Gray mottled with orange mottling, Clayey Sand, slightly moist to moist, fine to coarse grained sand, low to medium plasticity fines. ◆ 46% Passing No. 200 Sieve.	Medium Dense to Dense	SC	0 					

EXPLORATORY BORING LOG EB-4
PRUDENTIAL OFFICE BUILDING
SAN BRUNO, CALIFORNIA

BORING EB-4
AUGUST 2002
SHEET 1 OF 2

DRILL TYPE: B53 Mobile drill with 8 inch Hollow Stem Auger

LOGGED BY: CB

DEPTH TO GROUND WATER: Not Encountered

SURFACE ELEVATION: NA

DATE DRILLED: 6/5/02

CLASSIFICATION AND DESCRIPTION	SOIL CONSISTENCY/ DENSITY or ROCK HARDNESS* (Figure A-2)	SOIL TYPE	DEPTH (FEET)	SAMPLE INTERVAL	SPT RESISTANCE (Blows/ft)	WATER CONTENT (%)	SHEAR STRENGTH (TSF)*	UNCONFIN. COMP. (TSF)*
Gray brown Silty Sand (Continued) Becoming gray, medium plasticity fines.	Medium Dense to Very Dense	SM	20					
			25		57	22		
Light brown, Poorly Graded Sand, coarse grained sand, fine gravel.	Very Dense	SP						
			30		72	7		
Bottom of Boring at 30 Feet. Note: The stratification lines represent the approximate boundary between soil and rock types, the actual transition may be gradual. *Measured using Torvane and Pocket Penetrometer devices.								
			35					
			40					

EXPLORATORY BORING LOG EB-4
PRUDENTIAL OFFICE BUILDING
SAN BRUNO, CALIFORNIA

BORING EB-4
AUGUST 2002
SHEET 2 OF 2

APPENDIX D

SELECTED SITE PLANS FROM ENVIRONMENTAL REPORTS

Figure 3 - Groundwater Analytical Results (TEC Accutite, 2001)

Figure 4 - Horizontal Extent of the Existing Impacted Soil (TEC Accutite, 1999)

Figure 2 - Site Map (TEC Accutite, 2014)



SAN LUIS AVE

EL CAMINO REAL

SIDEWALK

DRIVEWAY

DRIVEWAY

DRIVEWAY

MW-1

SUBJECT PROPERTY

BUILDING

Groundwater Analysis:
TPHg = ND
B = 1.5 ppb
E = ND
MTBE = 42.9 ppb
T = ND
X = ND

MW-3

Groundwater Analysis:
TPHg = ND
B = 2.4 ppb
E = ND
MTBE = 3.7 ppb
T = ND
X = ND

MW-4

Groundwater Analysis:
TPHg = 345 ppb
B = 101 ppb
E = ND
MTBE = 30.7 ppb
T = ND
X = 3 ppb

APARTMENT COMPLEX


Groundwater Analysis:
TPHg = 67 ppb
B = 9.5 ppb
E = ND
MTBE = 1390 ppb
T = ND
X = ND

170 EL CAMINO REAL
CARPET STORE

MW-2

GROUNDWATER FLOW DIRECTION
GRADIENT = 0.005

11/27/01

SCALE: 
ONE INCH = 20 FEET

LEGEND:

#1-#10 USTs

 MONITORING WELL

**TEC
ACCUTITE**

35 SOUTH LINDEN AVENUE
SOUTH SAN FRANCISCO, CA 94080

FIGURE 3
GROUNDWATER ANALYTICAL
RESULTS

SITE: AL's OLYMPIC
160 EL CAMINO REAL
SAN BRUNO, CA

SAN LUIS AVE

EL CAMINO REAL

SIDEWALK


DRIVEWAY

BUILDING

DRIVEWAY

APARTMENT COMPLEX

DRIVEWAY



170 EL CAMINO REAL
CARPET STORE

12/17/99

SCALE:

ONE INCH = 20 FEET

LEGEND:

#1-#10 UNITS

● SOIL SAMPLE
LOCATIONS

**TEC
ACCUTITE**


35 SOUTH LINDEN AVENUE
SOUTH SAN FRANCISCO, CA 94080

1600xsample

FIGURE 4

Horizontal Extent of the
Existing Impacted Soil

160 EL CAMINO REAL
SAN BRUNO, CA



	 SCALE (ft)	 262 Michelle Court So. San Francisco, CA 94080 Main: (650) 616-1200 Fax: (650) 616-1244	FIGURE 2	Site Map	
	Revision: 2				Former Al's Olympic Station 160 El Camino Real San Bruno, California
	Date: 5/27/2008				
	Drafted By: LC				



ROMIG ENGINEERS, INC.

1390 El Camino Read, 2nd Floor

San Carlos, California 94070

Phone: (650) 591-5224

www.romigengineers.com