Print From

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: Groundwater Treatment Plants Phase B and Groundwater Supply Wells

Lead Agency: City of Anaheim

Contact Name: Jon Sanks, Environmental Services and Safety Manager

Email: environmental@anaheim.net Phone Number: (714) 765-4117

Project Location: Anaheim (*City*) Orange (*County*)

Project Description (Proposed actions, location, and/or consequences).

The Groundwater Treatment Plants Phase B and Groundwater Supply Wells Project would install ion-exchange groundwater treatment systems at five locations. The Project would involve installing resin vessels that are approximately 17 feet tall and 12 feet in diameter at each location. The Project would also involve installing features such as prefilters, pumps, pipes, valves, and electrical equipment. The Santa Cruz Site would receive a new backup generator, and a new control building would be constructed. New piping would be installed beneath roadways near the Project sites, including beneath Anaheim Way and Orangewood Avenue. Groundwater supply wells near each site would be rehabilitated with new liners installed to improve groundwater production capacity. Two new groundwater supply wells would be drilled at the Santa Cruz Site. Security features such as block walls, wrought iron fences, and chain-link fences would be installed at each site, along with new lighting and security cameras. Some trees and vegetation would be removed from within the footprint of the Willow Park Site to facilitate construction of the treatment equipment and new fences and walls. Construction is anticipated to begin in late 2021 and is expected to be completed in 2024.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

Implementation of the proposed Project, with adherence to applicable regulatory requirements, would have no impact or less than significant impacts for the following environmental issue areas: aesthetics; agriculture and forestry resources; air quality; energy; greenhouse gas emissions; hazards and hazardous materials; hydrology and water quality; land use and planning; mineral resources; population and housing; public services; recreation; transportation/traffic; utilities and service systems; and wildfire.

The proposed Project's impacts on the following issue areas would be less than significant with the implementation of project-specific mitigation measures: biological resources (MM 4-1 for migratory birds); cultural resources (MM 5-1 for archaeological resources); geology and soils (MM 6-1 for paleontological resources); noise (MMs 13-1 through 13-4 for construction activities and pump noise during operation at the Downtown Site); and tribal cultural resources (MM 18-1 through MM 18-3 for tribal cultural resources). All impacts would be less than significant after mitigation.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

None.

Provide a list of the responsible or trustee agencies for the project.

- South Coast Air Quality Management District (Responsible Agency)
- State Water Resources Control Board (Responsible Agency)