APPENDIX A

PROJECT PLANS FOR SWEETWATER SPRINGS WATER DISTRICT 2021 CAPITAL IMPROVEMENT PROJECT: OLD RIVER ROAD AND VICINITY COASTLAND CIVIL ENGINEERING, INC. OCTOBER 2020


PROJECT PLANS FOR:


SWEETWATER SPRINGS WATER DISTRICT 2021 CAPITAL IMPROVEMENT PROJECT BONITA AVE, OLD RIVER RD, PALO ALTO DR, AND WOODLAND DR

JANUARY 2021

GUERNEVILLE

SONOMA COUNTY, CALIFORNIA FOR USE IN CONJUNCTION WITH: CALTRANS STANDARD SPECIFICATIONS 2018 CALTRANS STANDARD PLANS 2018





INDEX OF SHEETS

<u>Sheet Title</u>

COVER SHEET ABBREVIATIONS, & GENERAL NOTES OLD RIVER ROAD - PLAN AND PROFILE-STA 10+00 TO STA 13+75 OLD RIVER ROAD - PLAN AND PROFILE-STA 33+75 TO STA 37+75 WOODLAND DR - PLAN AND PROFILE-STA 20+00 TO STA 23+75 WOODLAND DR - PLAN AND PROFILE-STA 23+75 TO STA 27+50 WOODLAND DR - PLAN AND PROFILE-STA 27+50 TO STA 31+25 WOODLAND DR - PLAN AND PROFILE-STA 31+25 TO STA 35+00 WOODLAND DR - PLAN AND PROFILE-STA 35+00 TO STA 38+75 PALO ALTO DR - PLAN AND PROFILE-STA 30+00 TO STA 32+75 WOODLAND DR - TEMPORARY WATER LINE PLAN MISCELLANEOUS DETAILS - 1 MISCELLANEOUS DETAILS - 2

MISCELLANEOUS DETAILS - 3 MISCELLANEOUS DETAILS - 4

> **PRELIMINARY** 90% SUBMITTAL JANUARY 2021

> > DATE

SWEETWATER SPRINGS WATER DISTRICT **APPROVED**

JOHN L. WANGER

DISTRICT ENGINEER

PROJECT NUMBER 88-4430 DRAWING DATE

JANUARY 2021 DRAWING NUMBER of **24**

Coastland Civil Engineering, Inc. 1400 Neotomas Avenue, Santa Rosa, CA 95405

STEVEN R. VAN SAUN, RCE 86180

1/8/2021

- THE CONTRACTOR SHALL POSSESS THE CLASS(ES) OF LICENSE(S) AS SPECIFIED IN THE SPECIAL PROVISIONS FOR
- THE LOCATIONS OF UTILITIES SHOWN ON THE PLANS ARE BASED ON THE BEST AVAILABLE INFORMATION. THE DISTRICT
- THE CONTRACTOR SHALL POT HOLE ALL KNOWN UTILITY CROSSINGS 5 DAYS PRIOR TO SCHEDULED CONSTRUCTION OF

ONLY ASSUMES RESPONSIBILITY FOR THE ACCURACY OF THE LOCATION OF ITS OWN UNDERGROUND UTILITIES.

- 6. THE CONTRACTOR SHALL INVESTIGATE THE SITE AND BE AWARE OF LIMITED OVERHEAD CLEARANCES.
- 7. EXISTING VEGETATION SHALL BE REMOVED ONLY AS DIRECTED BY THE ENGINEER.
- 8. ALL LANDSCAPING AND IRRIGATION SYSTEMS DISTURBED BY THE CONTRACTOR SHALL BE REPAIRED OR REPLACED IN
- THE CONTRACTOR SHALL REMOVE AND REPLACE CONCRETE SIDEWALK, DRIVEWAYS AND PLANTER STRIPS TO THE NEAREST SCORE MARK AS REQUIRED BY THE ENGINEER.
- 10. CAUTION SHALL BE EXERCISED WHEN DIGGING WITHIN THE DRIPLINE OF ANY TREE. THE ENGINEER SHALL BE NOTIFIED 48 HOURS PRIOR TO ANY UNDERGROUND WORK WITHIN THE DRIPLINE OF TREES. ROOTS OVER 2" IN DIAMETER SHALL NOT BE CUT WITHOUT PERMISSION FROM THE CONTRACTOR'S ARBORIST AND THE ENGINEER. IN THE EVENT THAT A TREE ROOT IS APPROVED FOR REMOVAL, IT SHALL BE NEATLY CUT, SQUARE, AT THE EDGE OF THE TRENCH, NOT SHREDDED OR SHATTERED, TO THE SATISFACTION OF THE CONTRACTOR'S ARBORIST.
- 11. EXCAVATIONS OVER FIVE FEET (5') DEEP REQUIRE AN EXCAVATION PERMIT FROM THE STATE DEPARTMENT OF INDUSTRIAL SAFETY.
- 12. CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY: THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND CONSTRUCTION CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY AND HOLD THE DISTRICT AND ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPTING LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE ENGINEER.
- 13. UNAUTHORIZED CHANGES & USES: THE ENGINEER PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO OR USES OF THESE PLANS. ALL CHANGES TO THE PLANS MUST BE IN WRITING AND MUST BE APPROVED BY THE PREPARER OF THESE PLANS.
- 14. NOTICE TO CONTRACTORS: THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITY LINES OR STRUCTURES SHOWN ON THESE PLANS WERE OBTAINED BY A SEARCH OF AVAILABLE RECORDS. TO THE BEST OF OUR KNOWLEDGE THERE ARE NO EXISTING UTILITIES EXCEPT AS SHOWN ON THESE PLANS. THE CONTRACTOR IS REQUIRED TO TAKE DUE PRECAUTIONARY MEASURES TO PROTECT THE UTILITY LINES SHOWN AND ANY OTHER LINES NOT OF RECORD OR NOT SHOWN ON THESE PLANS.
- 15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES TO DISTRICT OR OTHER UTILITIES CAUSED BY HIS OPERATIONS.
- 16. THE CONTRACTOR SHALL NOTIFY PROPERTY OWNERS AND THE ENGINEER, IN WRITING, 48 HOURS IN ADVANCE OF ANY DRIVEWAY ACCESS INTERRUPTIONS AS DESCRIBED IN THE PROJECT SPECIFICATIONS. MAIL SERVICE SHALL BE MAINTAINED THROUGHOUT THE COURSE OF THIS PROJECT. THE U.S. POSTAL SERVICE SHALL HAVE UNINTERRUPTED ACCESS TO MAILBOXES AT ALL TIMES.
- 17. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LAWFUL OFF-SITE DISPOSAL OF ALL BITUMINOUS PAVEMENT CONCRETE AND REINFORCEMENT, AND SPOILS NOT NEEDED FOR BACKFILL AS REQUIRED BY THE ENGINEER AND PER
- 18. PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL PROVIDE A TRAFFIC CONTROL PLAN IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.

WATER NOTES

0 -

- WATER SERVICE TAPS UP TO 1 INCH REQUIRE 24 INCHES OF SPACING BETWEEN TAPS. FOR LARGER SERVICE TAPS THE CONTRACTOR SHALL REFER TO THE PROJECT SPECIFICATIONS FOR MINIMUM SPACING REQUIREMENTS.
- 2. ONLY DISTRICT UTILITY DEPARTMENT PERSONNEL SHALL OPERATE VALVES ON THE EXISTING WATER SYSTEM. REQUIRED NOTIFICATION FOR SHUT-DOWNS IS 5 WORKING DAYS.
- 3. CUT-IN TEES AND FINAL WATER MAIN TIE-INS SHALL BE MADE UNDER THE INSPECTION OF DISTRICT PERSONNEL. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH THE DISTRICT FOR INSPECTIONS. SEE PROJECT SPECIFICATIONS FOR PRE EXCAVATION REQUIREMENTS.
- 4. WATER SERVICES OTHER THAN THOSE SHOWN ON THE PLANS SHALL NOT BE INSTALLED WITHOUT THE APPROVAL OF THE ENGINEER.
- 5. IF DAMAGE OCCURS TO ANY WATER SERVICE DURING CONSTRUCTION, THE CONTRACTOR SHALL REPLACE THE SERVICE FROM THE CORPORATION STOP AT THE MAIN TO THE WATER METER WITHOUT SPLICING.
- 6. WATER SERVICE MARKOUTS ARE APPROXIMATE. THE CONTRACTOR SHALL CAUTIOUSLY EXCAVATE UNTIL SERVICE IS EXPOSED OR AS DIRECTED BY THE ENGINEER.
- 7. WHERE CONFLICTS OCCUR WITH EXISTING UNDERGROUND FACILITIES, THE CONTRACTOR SHALL DEPRESS THE NEW WATER MAIN PER DETAILS ON THE PLANS.
- 8. NEW WATER SERVICES AND SEWER LATERALS SHALL BE SEPARATED HORIZONTALLY BY A MINIMUM OF 5 FEET.
- 9. THERE SHALL BE NO UNMETERED CONNECTIONS TO THE WATER SYSTEM, INCLUDING CONNECTIONS BYPASSING THE METER FOR OBTAINING CONSTRUCTION WATER. UNMETERED CONNECTIONS WILL BE SEVERED BY THE DISTRICT. UNMETERED CONNECTIONS WILL RESULT IN PENALTIES INCLUDING FINES AND PAYMENT OF ESTIMATED WATER USAGE FEES. REASONABLE QUANTITIES OF CONSTRUCTION WATER SHALL BE AVAILABLE TO THE CONTRACTOR, AT NO COST, AT AN EXISTING HYDRANT TO BE DETERMINED BY THE DISTRICT. CONTRACTOR SHALL BE RESPONSIBLE FOR TRANSPORT OF SUCH WATER. CONSTRUCTION WATER SHALL BE METERED. THE CONTRACTOR SHALL SUPPLY A BACKFLOW PREVENTION DEVICE TO BE INSTALLED ON THE HYDRANT TO BE USED.
- 10. ALL WATER SERVICE TIE—INS TO EXISTING HOUSE SERVICE LINES SHALL BE MADE WITH HDPE TUBING AND SHALL MATCH THE SIZE OF THE EXISTING SERVICE LINE. WHEN CONNECTING TO A LINE FOR A BACKFLOW PREVENTER, THE TIE-IN PIPE SHALL MATCH THE EXISTING SIZE AND SHALL BE MADE WITH HDPE PIPE. NO GALVANIZED FITTINGS OR PIPE WILL BE USED. ALL TIE-INS WILL BE AT BACK OF EXISTING METER.
- METER BOXES SHALL BE INSTALLED OUT OF TRAFFIC LOADING AREAS WHEREVER POSSIBLE.
- 12. THE CONTRACTOR SHALL POTHOLE ALL CROSSING UTILITIES PRIOR INSTALLATION OF NEW WATER MAIN.
- 13. LEADED JOINTS THAT ARE ENCOUNTERED IN EXISTING WATER MAINS THAT ARE TO REMAIN IN SERVICE WITHIN THE LIMITS OF EXCAVATIONS ON THIS PROJECT SHALL BE REMOVED BY THE CONTRACTOR UNDER DISTRICT INSPECTION.
- 14. ALL TEMPORARY BLOW-OFFS USED FOR REMOVING FOAM SWABS DURING WATER MAIN CLEANING SHALL BE CONSTRUCTED WITH A (SAME SIZE AS MAIN) ELBOW AND VERTICAL STAND TO PREVENT TRENCH WATER FROM FLOWING BACK INTO THE MAIN DURING SWAB REMOVAL. AFTER SWAB REMOVAL INSTALL MJ CAP ON STAND PIPE. RESTRAIN CAP AND STAND PIPE WITH MEGA-LUGS TO ALLOW TESTING.
- 15. ALL WATER SERVICE LATERAL MARKOUTS ARE APPROXIMATE, THE DISTRICT ASSUMES NO RESPONSIBILITY FOR THEIR ACCURACY OR OMISSION.
- 16. UNLESS HYDRANT STATIONING IS SPECIFICALLY CALLED OUT, LOCATIONS OF FIRE HYDRANTS ARE APPROXIMATE ONLY. CONFIRM ACTUAL LOCATIONS WITH THE DISTRICT PRIOR TO INSTALLATION.
- 17. MECHANICAL RESTRAINTS SHALL BE USED ON ALL JOINTS OF A WATER MAIN TIE-IN.
- 18. RESTRAINED MECHANICAL JOINTS SHALL BE USED ON ALL TEES, FITTINGS AND ASSOCIATED GATE VALVES UNLESS OTHERWISE APPROVED OR DIRECTED BY THE ENGINEER.

EROSION PREVENTION AND SEDIMENT CONTROL NOTES

- 1. PERFORM EROSION PREVENTION AND SEDIMENT CONTROL IN ACCORDANCE WITH CHAPTER 11 AND 11A OF THE SONOMA COUNTY CODE (SCC).
- 2. THE APPROVED PLANS SHALL CONFORM WITH THE PERMIT AND RESOURCE MANAGEMENT DEPARTMENT'S (PRMD) EROSION PREVENTION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES (BMP'S) GUIDE AS POSTED ON THE PRMD WEBSITE.
- 3. THE OWNER IS RESPONSIBLE FOR PREVENTING STORM WATER POLLUTION GENERATED FROM THE CONSTRUCTION SITE YEAR ROUND. WORK SITES WITH INADEQUATE EROSION AND SEDIMENT CONTROL MAY BE SUBJECT TO A STOP WORK ORDER.
- 4. IF DISCREPANCIES OCCUR BETWEEN THESE NOTES, MATERIAL REFERENCED HEREIN OR MANUFACTURER'S RECOMMENDATIONS, THEN THE MOST PROTECTIVE SHALL APPLY.
- 5. AT ALL TIMES THE OWNER IS RESPONSIBLE FOR OBTAINING AND COMPLYING WITH THE STATE OF CALIFORNIA NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) GENERAL PERMIT WASTE DISCHARGE REQUIREMENTS FOR DISCHARGES OF STORM WATER RUNOFF ASSOCIATED WITH CONSTRUCTION ACTIVITY. CONSTRUCTION ACTIVITIES INCLUDE BUT ARE NOT LIMITED TO CLEARING, GRADING, EXCAVATION, STOCKPILING, AND RECONSTRUCTION OF EXISTING FACILITIES INVOLVING REMOVAL AND REPLACEMENT

RAINY SEASON OPERATIONS

YEAR ROUND REQUIREMENTS

- 1. THE OWNER MUST IMPLEMENT AN EFFECTIVE COMBINATION OF EROSION PREVENTION AND SEDIMENT CONTROL ON ALL DISTURBED AREAS DURING THE RAINY SEASON (OCTOBER 15 APRIL 15). CONSTRUCTION GRADING AND DRAINAGE IMPROVEMENT SHALL BE PERMITTED DURING THE RAINY SEASON ONLY WHEN ON-SITE SOIL CONDITIONS PERMIT THE WORK TO BE PERFORMED IN COMPLIANCE WITH SCC CHAPTER 11 AND 11A. STORM WATER BMPS REFERENCED OR DETAILED IN THE PERMIT AUTHORITY'S BEST MANAGEMENT PRACTICES GUIDE SHALL BE IMPLEMENTED AND FUNCTIONAL ON THE SITE AT ALL TIMES
- 2. THE AREA OF ERODIBLE LAND EXPOSED AT ANY ONE TIME DURING THE WORK SHALL NOT EXCEED 1 ACRE OR 20% OF THE PERMITTED WORK AREA, WHICHEVER IS GREATER, AND THE TIME OF EXPOSURE SHALL BE MINIMIZED TO THE MAXIMUM EXTENT PRACTICABLE.
- 3. AGRICULTURAL GRADING AND DRAINAGE IMPROVEMENTS, AND INITIAL LAND PREPARATION WORK FOR VINEYARD AND ORCHARD PLANTING, SHALL BE PERMITTED DURING THE RAINY SEASON ONLY FROM APRIL 1 TO APRIL 15, AND ONLY WHEN ON-SITE SOIL CONDITIONS PERMIT THE WORK TO BE PERFORMED IN COMPLIANCE WITH SCC CH. 11A AND 11.
- 1. DURING THE NON-RAINY SEASON, ON ANY DAY WHEN THE NATIONAL WEATHER SERVICE FORECAST IS A CHANCE OF RAIN OF 30% OR GREATER WITHIN THE NEXT 24 HOURS, STORM WATER BMPS REFERENCED OR DETAILED IN PRMD'S BEST MANAGEMENT PRACTICES GUIDE SHALL BE IMPLEMENTED, INSTALLED, AND FUNCTIONAL ON THE SITE TO PREVENT SOIL AND OTHER POLLUTANT DISCHARGES. AT ALL OTHER TIMES, BMPS SHOULD BE STORED ON SITE IN PREPARATION FOR INSTALLATION PRIOR TO RAIN EVENTS.
- 2. EROSION PREVENTION AND SEDIMENT CONTROL MEASURES SHALL BE INSPECTED BY THE OWNER BEFORE FORECASTED STORM EVENTS AND AFTER STORM EVENTS TO ENSURE MEASURES ARE FUNCTIONING PROPERLY. EROSION PREVENTION AND SEDIMENT CONTROL MEASURES THAT HAVE FAILED OR ARE NO LONGER EFFECTIVE SHALL BE PROMPTLY REPLACED. EROSION PREVENTION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED UNTIL DISTURBED AREAS ARE STABILIZED.
- 3. THE LIMITS OF GRADING SHALL BE DEFINED AND MARKED ON SITE TO PREVENT DAMAGE TO SURROUNDING VEGETATION. PRESERVATION OF EXISTING VEGETATION SHALL OCCUR TO THE MAXIMUM EXTENT PRACTICABLE. ANY EXISTING VEGETATION WITHIN THE LIMITS OF GRADING THAT IS TO REMAIN UNDISTURBED BY THE WORK SHALL BE IDENTIFIED AND PROTECTED FROM DAMAGE BY MARKING, FENCING, OR OTHER MEASURES.
- 4. CHANGES TO THE EROSION PREVENTION AND SEDIMENT CONTROL PLAN MAY BE MADE TO RESPOND TO FIELD CONDITIONS AND SHALL BE NOTED ON THE PLAN.
- 5. DISCHARGES OF POTENTIAL POLLUTANTS FROM CONSTRUCTION SITES SHALL BE PREVENTED USING SOURCE CONTROLS TO THE MAXIMUM EXTENT PRACTICABLE. POTENTIAL POLLUTANTS INCLUDE BUT ARE NOT LIMITED TO: SEDIMENT, TRASH, NUTRIENTS, PATHOGENS, PETROLEUM HYDROCARBONS, METALS, CONCRETE, CEMENT, ASPHALT, LIME, PAINT, STAINS, GLUES, WOOD PRODUCTS, PESTICIDES, HERBICIDES, CHEMICALS, HAZARDOUS WASTE, SANITARY WASTE, VEHICLE OR EQUIPMENT WASH WATER, AND CHLORINATED WATER.
- 6. ENTRANCE(S) TO THE CONSTRUCTION SITE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF POTENTIAL POLLUTANTS OFFSITE. POTENTIAL POLLUTANTS DEPOSITED ON PAVED AREAS WITHIN THE COUNTY RIGHT-OF-WAY, SUCH AS ROADWAYS AND SIDEWALKS, SHALL BE PROPERLY DISPOSED OF AT THE END OF EACH WORKING DAY OR MORE FREQUENTLY AS NECESSARY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING CONSTRUCTION VEHICLES LEAVING THE SITE ON A DAILY BASIS TO PREVENT DUST, SILT, AND DIRT FROM BEING RELEASED OR TRACKED OFFSITE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AT THE END OF EACH WORKING DAY OR MORE OFTEN AS NECESSARY.
- 7. ALL DISTURBED AREAS SHALL BE PROTECTED BY USING EROSION PREVENTION MEASURES TO THE MAXIMUM EXTENT PRACTICABLE, SUCH AS ESTABLISHING VEGETATION COVERAGE, HYDROSEEDING, STRAW MULCH, GEOTEXTILES, PLASTIC COVERS, BLANKETS OR MATS. TEMPORARY OR PERMANENT REVEGETATION SHALL BE INSTALLED AS SOON AS PRACTICAL AFTER VEGETATION REMOVAL BUT IN ALL CASES PRIOR TO OCTOBER 15. PRIOR TO FINAL INSPECTION, ALL DISTURBED AREAS SHALL BE REVEGETATED OR LANDSCAPING SHALL BE INSTALLED.
- 8. WHENEVER IT IS NOT POSSIBLE TO USE EROSION PREVENTION MEASURES ON EXPOSED SLOPES, SEDIMENT CONTROL DEVICES SUCH AS FIBER ROLLS AND SILT FENCES SHALL BE INSTALLED TO PREVENT SEDIMENT MIGRATION. FIBER ROLLS AND SILT FENCES SHALL BE TRENCHED AND KEYED INTO THE SOIL AND INSTALLED ON CONTOUR. SILT FENCES SHALL BE INSTALLED APPROXIMATELY 2 TO 5 FEET FROM TOE OF SLOPE.
- 9. HYDROSEEDING SHALL BE CONDUCTED IN A THREE STEP PROCESS. FIRST, EVENLY APPLY SEED MIX AND FERTILIZER TO THE EXPOSED SLOPE. SECOND, EVENLY APPLY MULCH OVER THE SEED AND FERTILIZER. THIRD, STABILIZE THE MULCH IN PLACE. AN EQUIVALENT SINGLE STEP PROCESS, WITH SEED, FERTILIZER, WATER, AND BONDED FIBERS IS ACCEPTABLE
- APPLICATIONS SHALL BE BROADCASTED MECHANICALLY OR MANUALLY AT THE RATES SPECIFIED BELOW. SEED MIX AND FERTILIZER SHALL BE WORKED INTO THE SOIL BY ROLLING OR TAMPING. IF STRAW IS USED AS MULCH, STRAW SHALL BE DERIVED FROM WHEAT, RICE, OR BARLEY AND BE APPROXIMATELY 6 TO 8 INCHES IN LENGTH. STABILIZATION OF MULCH SHALL BE DONE HYDRAULICALLY BY APPLYING AN EMULSION OR MECHANICALLY BY CRIMPING OR PUNCHING THE MULCH INTO THE SOIL. EQUIVALENT METHODS AND MATERIALS MAY BE USED ONLY IF THEY ADEQUATELY PROMOTE VEGETATION GROWTH AND PROTECT EXPOSED SLOPES.

MATERIALS

SEED MIX	·
BROMUS MOLLIS (BLANDO BROME)	40
TRIFOLIUM HIRTUM (HYKON ROSE CLOVER)	20
FERTILIZER	
16-20-0 & 15% SULPHUR	500
MULCH	
STRAW	4000
HYDRAULIC STABILIZING*	
M-BINDER OR SENTINEL	75–100
EQUIVALENT MATERIAL	PER MANUFACTURER

- *NON-ASPHALTIC, DERIVED FROM PLANTS
- 10. DUST CONTROL SHALL BE PROVIDED BY CONTRACTOR DURING ALL PHASES OF CONSTRUCTION
- 11. STORM DRAIN INLETS SHALL BE PROTECTED FROM POTENTIAL POLLUTANTS UNTIL DRAINAGE CONVEYANCE SYSTEMS ARE FUNCTIONAL AND CONSTRUCTION HAS BEEN COMPLETED.
- 12.ENERGY DISSIPATERS SHALL BE INSTALLED AT STORM DRAIN OUTLETS WHICH MAY CONVEY EROSIVE STORM WATER FLOW.
- 13.SOIL, MATERIAL STOCKPILES, AND FERTILIZING MATERIAL SHALL BE PROPERLY PROTECTED TO MINIMIZE SEDIMENT AND POLLUTANT TRANSPORT FROM THE CONSTRUCTION SITE.
- 14.SOLID WASTE, SUCH AS TRASH, DISCARDED BUILDING MATERIALS AND DEBRIS, SHALL BE PLACED IN DESIGNATED COLLECTION AREAS OR CONTAINERS. THE CONSTRUCTION SITE SHALL BE CLEARED OF SOLID WASTE DAILY OR AS NECESSARY. REGULAR REMOVAL AND PROPER DISPOSAL SHALL BE COORDINATED BY THE CONTRACTOR.
- 15.A CONCRETE WASHOUT AREA, SUCH AS A TEMPORARY PIT, SHALL BE DESIGNATED TO CLEAN CONCRETE TRUCKS AND TOOLS. AT NO TIME SHALL CONCRETE PRODUCTS AND WASTE BE ALLOWED TO ENTER COUNTY WATERWAYS SUCH AS CREEKS OR STORM DRAINS. NO WASHOUT OF CONCRETE, MORTAR MIXERS, OR TRUCKS SHALL BE ALLOWED ON SOIL.
- 16.PROPER APPLICATION, CLEANING, AND STORAGE OF POTENTIALLY HAZARDOUS MATERIALS, SUCH AS PAINTS AND CHEMICALS, SHALL BE CONDUCTED TO PREVENT THE DISCHARGE OF
- 17.TEMPORARY RESTROOMS AND SANITARY FACILITIES SHALL BE LOCATED AND MAINTAINED DURING CONSTRUCTION ACTIVITIES TO PREVENT THE DISCHARGE OF POLLUTANTS.
- 18.APPROPRIATE VEHICLE STORAGE, FUELING, MAINTENANCE, AND CLEANING AREAS SHALL BE DESIGNATED AND MAINTAINED TO PREVENT DISCHARGE OF POLLUTANTS.

INSPECTIONS

APPROVAL OF ALL WORK SHALL BE NECESSARY AT THE COMPLETION OF EACH OF THE FOLLOWING STAGES OF WORK AND SUCH APPROVAL MUST BE OBTAINED BEFORE SUBSEQUENT STAGES OF WORK MAY BE COMMENCED. ADDITIONALLY, THE INSPECTOR SHALL BE NOTIFIED AT LEAST ONE WORKING DAY IN ADVANCE BEFORE ANY OF THE FOLLOWING STAGES OF WORK ARE COMMENCED. ONLY THAT WORK THAT IS DONE IN THE PRESENCE OF THE INSPECTOR, OR LACKING SUCH PRESENCE, AT THE INSPECTOR'S OPTION, DONE WITH HIS/HER KNOWLEDGE, WILL BE APPROVED. CALL THE AUTOMATED INSPECTION REQUEST SYSTEM PHONE NUMBER 707-565-3551 AND USE THE CODES PROVIDED ON THE HANDOUT YOU RECEIVED WITH YOUR PERMIT(S) TO SELECT AN INSPECTION. LARGER PROJECTS REQUIRE A PRE-CONSTRUCTION MEETING ON SITE, AND SMALLER PROJECTS BY PHONE. THE AUTOMATED INSPECTION REQUEST FOR A PRE-CONSTRUCTION MEETING IS CHOICE "200". THIS REQUEST MUST BE MADE FIVE (5) DAYS IN ADVANCE OF WORK AND AN INSPECTOR WILL CALL BACK TO MAKE ARRANGEMENTS

1. EARTHWORK:

POLLUTANTS.

CONSTRUCTION OF EMBANKMENTS, EXCAVATIONS. EXCAVATION FOR STORM DRAINS AND CULVERTS.

PREPARATION OF SUBGRADE BACK-FILLING OF STRUCTURES AND PIPES AND PUBLIC UTILITIES.

2. CONCRETE WORK:

CONSTRUCTION OF FORMS, FOR ALL CONCRETE STRUCTURES, INCLUDING CURBS, GUTTERS, AND SIDEWALKS. PLACING OF CONCRETE IN STRUCTURES, INCLUDING CURBS, GUTTERS, AND SIDEWALKS.

3.DRAINAGE FACILITIES:

PLACING OF STORM DRAINS AND CULVERT PIPES. CONSTRUCTION OF ROADSIDE DITCHES AND OTHER DRAINAGE WAYS

4. ROADWAY CONSTRUCTION:

PLACING AND COMPACTING OF BASE MATERIAL. IF MORE THAN ONE COURSE OR TYPE OF BASE OR SUB-BASE IS TO BE USED, APPROVAL SHALL BE NECESSARY FOR EACH COURSE AND/OR TYPE. PLACING OF PAVEMENT OR SURFACING.

FINAL INSPECTION MAY NOT BE REQUESTED UNTIL THE CONSTRUCTION INSPECTOR RECEIVES, REVIEWS AND APPROVES BOTH THE ENGINEER'S FINAL LETTER AND THE FINAL GEOTECHNICAL REPORT. THIS APPROVAL MUST BE OBTAINED PRIOR TO SCHEDULING A FINAL INSPECTION.

LEGEND

DESCRIPTION OF LINETYPE	PROPOSED	EXISTING
PROPERTY LINE	N/A	
FLOWLINE	N/A	
CENTERLINE/CONTROL LINE	N/A	
FENCE	N/A	<u> </u>
WATER MAIN PIPE	6" W	
SANITARY SEWER PIPE	N/A	ssss
STORM DRAIN PIPE	N/A	
GAS LINE	N/A	
TELEPHONE LINE/CONDUIT	N/A	
ELECTRICAL LINE/CONDUIT	N/A	ΕΕ
OVERHEAD UTILITY	N/A	OHOH
ABANDONED FACILITY	₩ — 8" W₩ —	
ASPHALT CONCRETE		
CONCRETE		
AGGREGATE BASE		
SUBGRADE	N/A	
WATER MAIN GATE VALVE	ŏ	©
WATER MAIN BLOW OFF	\checkmark	A
WATER METER	W	W
FIRE HYDRANT	₩	ЮН
SANITARY SEWER CLEANOUT	N/A	CO
SANITARY SEWER / STORM DRAIN MANHO	DLE N/A	<u>ss/sø</u>
STORM DRAIN CURB INLET/CATCH BASIN	N/A	0
STORM DRAIN DROP INLET (TOP OPENING)) N/A	
MAILBOX	N/A	□мв
ROADSIDE SIGN	N/A	
TREE AND DRIP LINE	N/A	
SURVEY CONTROL POINT	N/A	A
JOINT UTILITY POLE	N/A	● ^{JP}

ABBREVIATIONS

AC	ASPHALT CONCRETE	МВ	MAILBOX
ACP	ASPHALT CONCRETE PIPE	МН	MANHOLE
AB	AGGREGATE BASE	MIN.	MINIMUM
ARV	AIR RELEASE VALVE	OG	ORIGINAL GROUND
BSW	BACK OF SIDEWALK	OHU	OVERHEAD UTILITY
DIP	DUCTILE IRON PIPE	PH	UTILITY POTHOLE
Q	CENTERLINE, CONTROL LINE	PVC	POLYVINYL CHLORIDE
CB	CATCH BASIN	R	RADIUS
CLR.	CLEAR	RC	RELATIVE COMPACTION
CONC	CONCRETE	RCP	REINFORCED CONCRETE PIPE
CP	CONTROL POINT	RSP	ROCK SLOPE PROTECTION
CSP	CORRUGATED STEEL PIPE	RT	RIGHT
DI	DROP INLET	R/W	RIGHT-OF-WAY
DWY	DRIVEWAY	S	SLOPE
E	ELECTRICAL, ELECTRIC CONDUIT	SD	STORM DRAIN
EG	EXISTING GRADE	SDE	STORM DRAIN EASEMENT
EL	ELEVATION	SS	SANITARY SEWER
EP	EDGE OF PAVEMENT	SSFM	SANITARY SEWER FORCE MAIN
EXIST, EX	EXISTING	STA	STATION
Æ	FLOWLINE	STD	STANDARD
FG	FINISHED GRADE	SVC	SERVICE
FH	FIRE HYDRANT	TB	TOP OF BANK
FX	FENCE	TC	TOP OF CURB
G	GAS, GAS MAIN	TEL	TELEPHONE
GIP	GALVANIZED IRON PIPE	TG	TOP OF GRATE
HDPE	HIGH DENSITY POLYETHYLENE	TOE	TOE OF SLOPE
IE	INVERT ELEVATION	TP	TELEPHONE POLE
INV	INVERT	TYP	TYPICAL
IP	IRON PIPE	U	UNDERGROUND UTILITY
JP	JOINT POLE	UTIL	UTILITY
JT	JOINT UTILITY TRENCH	VIF	VERIFY IN FIELD
LAT	SANITARY SEWER LATERAL	W	WATER, WATER MAIN
LF	LINEAL FEET	WM	WATER METER
LT	LEFT	WV	WATER VALVE
		•	

CONSTRUCTION NOTE DESIGNATIONS

- (R1) = ROADWAY AND RELATED ITEMS CONSTRUCTION NOTES.
- (T1) = STRIPING AND RELATED ITEMS CONSTRUCTION NOTES.
- (W1) = WATER AND RELATED ITEMS CONSTRUCTION NOTES.

ering Ō ngin

O tland ິທ

0

U)

O

Ш

FF

SPRINGS WATER DISTRI


2 \mathbf{m} $\mathbf{\Omega}$ (1)

PROJECT NUMBER 88-4430

DRAWING DATE JANUARY 2021

SHEET NUMBER OF

PRELIMINARY 90% SUBMITTAL JANUARY 2021 DATE:



WOODLAND DRIVE

WOODLAND DRIVE

CPI # 27-

WOODLAND DRIVE

SUNSET AVE

 \sim -


GRAPHIC SCALE

(IN FEET)

1 inch = 60 ft.

CPI # 36-

30 60



SURVEY CONTROL DATA OLD RIVER RD					
CONTROL POINT NO.	NORTHING	EASTING	ELEV.	DESCRIPTION	
1	1948780.15	6279002.64	70.28	SET CPI CTRL MAG NAIL	
2	1948678.30	6279104.47	55.46	SET CPI CTRL MAG NAIL	
3	1948538.90	6278731.42	59.68	SET CPI CTRL MAG NAIL	
4	1948312.64	6278487.18	56.08	SET CPI CTRL MAG NAIL	
5	1948128.01	6278308.20	55.72	SET CPI CTRL MAG NAIL	
6	1948021.33	6278208.27	55.92	SET CPI CTRL MAG NAIL	
7	1947916.56	6278099.46	55.29	SET CPI CTRL MAG NAIL	
8	1947766.58	6277951.49	55.75	SET CPI CTRL MAG NAIL	
9	1947594.22	6277828.02	51.94	SET CPI CTRL MAG NAIL	
10	1947477.55	6277691.22	51.05	SET CPI CTRL MAG NAIL	
11	1947375.57	6277610.01	50.75	SET CPI CTRL MAG NAIL	
12	1947233.55	6277479.21	55.78	SET CPI CTRL MAG NAIL	
13	1947056.43	6277353.47	60.68	SET CPI CTRL MAG NAIL	
14	1946952.54	6277244.66	65.38	SET CPI CTRL MAG NAIL	
15	1946743.94	6277106.33	64.24	SET CPI CTRL MAG NAIL	
16	1946544.50	6276936.09	59.93	SET CPI CTRL MAG NAIL	
17	1946409.34	6276793.88	55.48	FND CTRL PK NAIL	
18	1946377.27	6276891.16	56.19	FND CTRL 1" IRON PIPE	




Engineering,
Santa Rosa, CA 9

PROJECT NUMBER 88-4430

DRAWING DATE JANUARY 2021

SHEET NUMBER

90% SUBMITTAL



SURVEYOR'S STATEMENT

THIS MAP REPRESENTS A FIELD SURVEY MADE BY CINQUINI & PASSARINO, INC. IN JULY OF 2020, AND NOVEMBER 11, 2020 AND REPRESENTS THE VISUAL SURFACE CONDITIONS AS OF AFORESAID DATE.

BENCHMARK

CINQUINI & PASSARINO CONTROL POINT NO. 2, BEING A SET MAG NAIL WITH WASHER STAMPED "CINQUINI & PASSARINO CONTROL" ALONG MORNINGSIDE DRIVE APPROXIMATELY 125 FEET SOUTHERLY OF THE INTERSECTION WITH OLD RIVER ROAD AS SHOWN HEREON. ELEVATION = 55.46' (NAVD 88)

THE ORTHOMETRIC ELEVATIONS SHOWN HEREON ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 1988) AND WERE DETERMINED BY STATIC GPS TIES TO CGPS STATIONS P182, P183 & P197 WITH PUBLISHED ELLIPSOIDAL HEIGHTS OF P182 = 1303.365', P183 = 35.695' AND P197 = 1.662', IN ADDITION TO APPLYING THE NGS GEOID HEIGHT MODEL "GEOID2018".

BASIS OF BEARINGS


THE BASIS OF BEARINGS FOR THIS SURVEY IS THE CALIFORNIA COORDINATE SYSTEM, ZONE II, NAD 83, EPOCH 2017.50 AS DETERMINED LOCALLY BY A LINE BETWEEN CONTINUOUS GLOBAL POSITIONING SYSTEMS (CGPS) STATION P183 AND STATION 182; BEING NORTH 25°16'52" WEST AS DERIVED FROM GEODETIC VALUES PUBLISHED BY THE CALIFORNIA SPATIAL REFERENCE CENTER (CSRC).


DATE:


PRELIMINARY


JANUARY 2021


of **24**




















CONSTRUCTION NOTES

- R2 GRIND 0.25' AND PLACE 0.25' OF TRENCH PAVING PER 16 COUNTY STD. 219B, TYPE A1 AND DETAIL 16
- W1 CONSTRUCT 6" HDPE WATER MAIN.
- (W2) INSTALL 6" GATE VALVE PER DETAIL-
- (W3) INSTALL TEMPORARY BLOW OFF PER DETAIL —
- W4 INSTALL 1" WATER SERVICE WITH 5/8" METER PER DETAIL

 TIE INTO SERVICE AT BACK OF EXISTING METER BOX.
- (W7) PLUG EXISTING WATER MAIN AND ABANDON PER DETAIL $-\left(\frac{8}{27}\right)$
- (W9) CONNECT TO EXISTING WATER MAIN WITH FITTINGS AS REQUIRED UNDER THE INSPECTION OF THE DISTRICT.
- W10 ABANDON WATER MAIN PER SPECIFICATIONS.

Line Table: Old River Rd								
Line #	Length	Direction	Start Station	Start Point	End Station	End Point		
L12	132.15	N45° 26' 42.56"E	40+48.12	N: 1948571.40 E: 6278778.55	41+80.27	N: 1948664.12 E: 6278872.71		
L13	65.63	N53° 42' 54.32"E	42+52.44	N: 1948710.87 E: 6278927.61	43+18.07	N: 1948749.71 E: 6278980.51		
L14	81.88	N55° 00' 21.08"E	43+18.07	N: 1948749.71 E: 6278980.51	43+99.95	N: 1948796.67 E: 6279047.59		

Curve Table: Old River Rd					
CURVE NO.	RADIUS	LENGTH	DELTA		
C 10)	500.00	72.17	816'12"		



SHEET INDEX MAP NOT TO SCALE

Jnc. 95405 3037 Fax

Engineering, e, Santa Rosa, CA 9

PR +000 AND ROAD 41+75 RIVER STA

PROJECT NUMBER 88-4430

DRAWING DATE JANUARY 2021

SHEET NUMBER 12 of 24

PRELIMINARY 90% SUBMITTAL JANUARY 2021

CONSTRUCTION NOTES

- R2 GRIND 0.25' AND PLACE 0.25' OF TRENCH PAVING PER 16 COUNTY STD. 219B, TYPE A1 AND DETAIL 24
- (R3) APPROXIMATE BORE PIT LOCATION.
- T2 INSTALL WHITE 12-INCH THERMOPLASTIC CROSSWALK/LIMIT LINE PER CALTRANS STD PLAN A24E.
- T3 INSTALL WHITE THERMOPLASTIC PAVEMENT MARKING "STOP" PER CALTRANS STD PLAN A24D.
- (W1) CONSTRUCT 6" HDPE WATER MAIN.
- W3 INSTALL TEMPORARY BLOW OFF PER DETAIL —
- W4 INSTALL 1" WATER SERVICE WITH 5/8" METER PER DETAIL

 TIE INTO SERVICE AT BACK OF EXISTING METER BOX.
- W7 PLUG EXISTING WATER MAIN AND ABANDON PER DETAIL-
- W9 CONNECT TO EXISTING WATER MAIN WITH FITTINGS AS REQUIRED UNDER THE INSPECTION OF THE DISTRICT.
- W10) ABANDON WATER MAIN PER SPECIFICATIONS.
- W28) WATER MAIN TO BE OPEN CUT TRENCH.
- (W29) WATER MAIN TO BE DIRECTIONAL BORED PER PROJECT SPECIFICATIONS.

	gig 2000
	Le Company of the Com
	alegar dista
	Wing.
	$\mathcal{Y}/\mathcal{Y}/\mathcal{Y}$

SHEET INDEX MAP NOT TO SCALE

Line Table: Bonita Ave							
ne #	Length	Direction	Start Station	Start Point	End Station	End Point	
L15	261.94	S45° 04' 34.60"E	30+00.00	N: 1948321.97 E: 6278474.89	32+61.94	N: 1948136.99 E: 6278660.36	

 \sim -

PLAN AND PRO 0 TO STA 20+50 AVE - P A 20+00

JDC. 95405 8037 Fax

Engineering, le, Santa Rosa, CA 9


SONITA A

PROJECT NUMBER 88-4430


DRAWING DATE JANUARY 2021


SHEET NUMBER 13 of 24


PRELIMINARY 90% SUBMITTAL JANUARY 2021



BONITA CL PROFILE







SHEET INDEX MAP NOT TO SCALE

CONSTRUCTION NOTES

- (R1) PLACE BLUE PAVEMENT MARKER PER DETAIL-
- R2 GRIND 0.25' AND PLACE 0.25' OF TRENCH PAVING PER COUNTY STD. 219B, TYPE A1 AND DETAIL
- (R4) FULL WIDTH PAVING PER COUNTY STD. 219B, TYPE A1.
- T1 INSTALL YELLOW THERMOPLASTIC DETAIL 23 PER CALTRANS STD PLAN A20A.
- T2 INSTALL WHITE 12-INCH THERMOPLASTIC CROSSWALK/LIMIT LINE PER CALTRANS STD PLAN A24E.
- T3 INSTALL WHITE THERMOPLASTIC PAVEMENT MARKING "STOP" PER CALTRANS STD PLAN A24D.
- W3 INSTALL TEMPORARY BLOW OFF PER DETAIL —
- W4 INSTALL 1" WATER SERVICE WITH 5/8" METER PER DETAIL 6
 TIE INTO SERVICE AT BACK OF EXISTING METER BOX.
- W5 INSTALL FIRE HYDRANT PER DETAIL —
- W7 PLUG EXISTING WATER MAIN AND ABANDON PER DETAIL $\frac{8}{22}$
- (W9) CONNECT TO EXISTING WATER MAIN WITH FITTINGS AS REQUIRED
- W10 ABANDON WATER MAIN PER SPECIFICATIONS.
- W12 CONSTRUCT 8" HDPE WATER MAIN.
- W13 INSTALL 8" GATE VALVE PER DETAIL —
- W14 INSTALL 1" WATER SERVICE WITH 5/8" METER PER DETAIL

 TIE INTO SERVICE IN FRONT OF EXISTING RETAINING WALL.
- W45 EXISTING 8-INCH GATE VALVE TO REMAIN.
- W46 INSTALL 2" WATER SERVICE WITH 1.5" METER PER DETAIL 18 (22) INSTALL 1.5" BACKFLOW DEVICE PER DETAIL-
- W28 WATER MAIN TO BE OPEN CUT TRENCH.
- W32 TEMPORARY WATER MAIN TO BE PLACED INTO SERVICE PRIOR TO ABANDONING OF EXISTING WATER MAIN. SEE SHEET 20 FOR LOCATION AND DETAILS.
- W37) INSTALL TRENCH CONTAINMENT CUTOFF PER DETAIL 14 23

Line Table: Woodland Dr							
Line#	Length	Direction	Start Station	Start Point	End Station	End Point	
L16	21.87	N90° 00' 00.00"E	20+00.00	N: 1946635.15 E: 6276094.89	20+21.87	N: 1946635.15 E: 6276116.76	
L17	97.60	N49* 03' 38.43"E	20+21.87	N: 1946635.15 E: 6276116.76	21+19.48	N: 1946699.11 E: 6276190.49	
L18	90.70	N67° 38' 58.33"E	21+19.48	N: 1946699.11 E: 6276190.49	22+10.18	N: 1946733.60 E: 6276274.38	
L19	53.67	N53* 37' 56.50"E	22+71.34	N: 1946763.51 E: 6276327.55	23+25.01	N: 1946795.33 E: 6276370.77	

Curve Table: Woodland Dr						
CURVE NO. RADIUS LENGTH DELTA						
C11)	250.00	61.16	14°01'02"			
C12	90.00	53.37	33°58'37"			

PRELIMINARY 90% SUBMITTAL JANUARY 2021

PROJECT NUMBER 88-4430

Jnc. 95405 8037 Fax

Engineering, |

Coastland
1400 Neotomas
707.571.8005

PR-75

ND 23-

4

 \triangleleft

<u>ال</u>


DR-+00

0

TWATER SPRINGS WATER DISTRIC CAPITAL IMPROVEMENT PROJECT

DRAWING DATE JANUARY 2021

SHEET NUMBER 14 of 24



26+50

27+00

27+50

26+00

25+50

25+00

24+00

23+75

24+50

 \sim -

 \circ –

Jnc. 95405 8037 Fax

Engineering, |

Coastland
1400 Neotomas
707.571.8005

PR -50

ND 27-

44

P

DLAN

0

T


S


DATE:


PROJECT NUMBER 88-4430

DRAWING DATE JANUARY 2021

SHEET NUMBER 15 of 24







SHEET INDEX MAP NOT TO SCALE

CONSTRUCTION NOTES

- R1 PLACE BLUE PAVEMENT MARKER PER DETAIL-
- R2 GRIND 0.25' AND PLACE 0.25' OF TRENCH PAVING PER COUNTY STD. 219B, TYPE A1 AND DETAIL
- R3 APPROXIMATE BORE PIT LOCATION.
- (W1) CONSTRUCT 6" HDPE WATER MAIN.
- W2 INSTALL 6" GATE VALVE PER DETAIL
- W3 INSTALL TEMPORARY BLOW OFF PER DETAIL —
- W4 INSTALL 1" WATER SERVICE WITH 5/8" METER PER DETAIL

 TIE INTO SERVICE AT BACK OF EXISTING METER BOX.
- W5 INSTALL FIRE HYDRANT PER DETAIL —
- W7 PLUG EXISTING WATER MAIN AND ABANDON PER DETAIL $\frac{8}{22}$
- W9 CONNECT TO EXISTING WATER MAIN WITH FITTINGS AS REQUIRED UNDER THE INSPECTION OF THE DISTRICT.
- W10 ABANDON WATER MAIN PER SPECIFICATIONS.
- (W11) INSTALL BLIND FLANGE ON EXISTING TEE.
- W27 INSTALL 6" X 6" X 6" TEE WITH 6" TO 2" REDUCER AND 2" GATE VALVE.
- W26 INSTALL AIR RELEASE VALVE PER DETAIL PER-
- W28 WATER MAIN TO BE OPEN CUT TRENCH.
- W29 WATER MAIN TO BE DIRECTIONAL BORED PER PROJECT SPECIFICATIONS.

Line Table: Woodland Dr							
Line#	Length	Direction	Start Station	Start Point	End Station	End Point	
L23	381.36	N0° 55' 02.73"W	28+70.05	N: 1947089.60 E: 6276780.69	32+51.41	N: 1947470.92 E: 6276774.59	
L24	387.39	NO* 46' 59.28"E	32+51.41	N: 1947470.92 E: 6276774.59	36+38.80	N: 1947858.27 E: 6276779.88	

DRAWING DATE PRELIMINARY JANUARY 2021

90% SUBMITTAL

JANUARY 2021

SHEET NUMBER

PROJECT NUMBER 88-4430

SWEETWATER SPRINGS WATER DISTRIC 2021 CAPITAL IMPROVEMENT PROJECT

Jnc. 95405 8037 Fax

Engineering, e. Santa Rosa, CA 9

Coastland
1400 Neotomas
707.571.8005

) PR(+00


AND 'A 35+


PLAN, TO ST,

DR-1+25

ODLAND

17 of 24






CONSTRUCTION NOTES

- R2 GRIND 0.25' AND PLACE 0.25' OF TRENCH PAVING PER COUNTY STD. 219B, TYPE A1 AND DETAIL
- (R3) APPROXIMATE BORE PIT LOCATION.
- T2 INSTALL WHITE 12-INCH THERMOPLASTIC CROSSWALK/LIMIT LINE PER CALTRANS STD PLAN A24E.
- T3 INSTALL WHITE THERMOPLASTIC PAVEMENT MARKING "STOP" PER CALTRANS STD PLAN A24D.
- W3 INSTALL TEMPORARY BLOW OFF PER DETAIL —
- W13) INSTALL 8" GATE VALVE PER DETAIL —
- W24 INSTALL CUT-IN 12" X 12" X 8" TEE, (1) 8" GATE VALVE, AND FITTINGS AS REQUIRED UNDER THE INSPECTION OF THE DISTRICT.
- W26 INSTALL AIR RELEASE VALVE PER DETAIL PER-
- W28) WATER MAIN TO BE OPEN CUT TRENCH.
- W29 WATER MAIN TO BE DIRECTIONAL BORED PER PROJECT SPECIFICATIONS.

Line Table: Palo Alto Dr								
Line#	Length	Direction	Start Station	Start Point	End Station	End Point		
L26	144.77	S47° 50′ 23.41″E	30+00.00	N: 1947066.70 E: 6276757.46	31+44.77	N: 1946969.52 E: 6276864.78		
L27	86.74	S39° 40′ 37.94″E	31+73.26	N: 1946948.96 E: 6276884.47	32+60.00	N: 1946882.21 E: 6276939.85		

Curve Table: Palo Alto Dr							
CURVE NO.	RADIUS	LENGTH	DELTA				
C17	200.00	28.49	8*09'45"				



SHEET INDEX MAP NOT TO SCALE

PRELIMINARY

90% SUBMITTAL JANUARY 2021

Jnc 95405 8037 Fax

Engineering, I

PRC +75 PLAN AND TO STA 32+ ALTO DR -STA 30+00


SWEETWATER SPRINGS WATER DISTRIC 2021 CAPITAL IMPROVEMENT PROJECT


Ω

PROJECT NUMBER 88-4430

DRAWING DATE JANUARY 2021

SHEET NUMBER 19 of 24






W35 CONSTRUCT 2" HDPE TEMPORARY WATER LINE PER DETAIL $\frac{1}{20}$

W36 INSTALL TEMPORARY WATER SERVICE TO EXISTING WATER METER.

W39 NEW 8-INCH HDPE WATER MAIN, SEE SHEETS 14 AND 15.



TEMPORARY WATER LINE INSTALLATION DETAIL 1

Civil Engineering, I

SWEETWATER SPRINGS WATER DISTRIC 2021 CAPITAL IMPROVEMENT PROJECT


WOODLAND DR TEMPORARY WATER LINE

PROJECT NUMBER 88-4430


DRAWING DATE JANUARY 2021

SHEET NUMBER 20 of 24

PRELIMINARY
90% SUBMITTAL
DATE: JANUARY 2021



8037 Fax



TEMPORARY METER & DOUBLE CHECK VALVE INSTALLED


Engineering,
Santa Rosa, CA 8

PROJECT NUMBER

DRAWING DATE


JANUARY 2021

22 of 24



TRENCH DIMENSION CHART MIN MAX MIN. 20" 4",6" 18" 24" 20" 26"

DETAIL 'A'



- 1. AC THICKNESS TO MATCH EXISTING OR 0.25' MINIMUM WHICHEVER IS GREATER.

- 4. FULL TACK COAT COVERAGE ON ALL VERTICAL SERVICES.
- 5. MINIMUM COVER SHALL BE 36-INCHES UNLESS OTHERWISE SHOWN ON THE PLANS.
- LESS THAN 3-FEET WIDE.


STANDARD TRENCH AND BORE PIT PAVING AND BACKFILL NOT TO SCALE



NOT TO SCALE

CONSTRUCTION NOTES

- (R2) TRENCH PAVING PER COUNTY STD. 219B, TYPE A1.
- (W3) INSTALL TEMPORARY BLOW OFF PER DETAIL —
- W7 PLUG EXISTING WATER MAIN AND ABANDON PER DETAIL $\frac{8}{21}$
- (W16) INSTALL 12" X 12" X 12" TEE, 12" X 6" REDUCER AND 6" GATE VALVE.
- (W17) INSTALL 12" X 12" X 6" CUT-IN TEE AND 6" GATE VALVE.



Engineering, |

Jnc 95405 3037 Fax

Ш Z

PROJECT NUMBER 88-4430


DRAWING DATE JANUARY 2021

PRELIMINARY

90% SUBMITTAL

JANUARY 2021

SHEET NUMBER 24 of 24



- 1. REDUCED PRESSURE TYPE BACKFLOW DEVICES SHALL BE REQUIRED FOR ANY USE WHERE TOXIC MATERIALS ARE USED OR STORED ON SITE OR WHERE POSITIVE PROTECTION FOR THE PUBLIC WATER SUPPLY IS REQUIRED. TYPICAL APPLICATIONS INCLUDE: ALL IRRIGATION SERVICES & PARKS, HOSPITALS, MEDICAL & DENTAL LABORATORIES, MORTUARIES,
- 2. APPROVED REDUCED PRESSURE BACKFLOW DEVICE SHALL BE AS SHOWN ON "LIST OF APPROVED BACKFLOW PROTECTION DEVICES" (LATEST REVISION) BY THE UNIVERSITY OF SOUTHERN CALIFORNIA FOUNDATION FOR CROSS-CONNECTION CONTROL & HYDRAULIC RESEARCH.
- 3. BACKFLOW PREVENTION DEVICES SHALL BE INSTALLED ADJACENT TO AND ON PROPERTY SIDE OF SIDEWALK WHERE APPLICABLE. WHERE NO SIDEWALK EXISTS THE ASSEMBLY SHALL BE INSTALLED AS CLOSE AS POSSIBLE TO THE WATER METER LOCATION..
- 4. A VALVE OF THE SAME SIZE AS THE BACKFLOW PREVENTER SHALL BE INSTALLED ON EACH SIDE OF THE BACKFLOW PREVENTION
- ASSEMBLY. VALVES 2" & LESS SHALL BE THREADED FORD BALL VALVES. VALVES 3" SHALL BE WATTS BALL VALVES, AND
- 6. IN LIMITED SPACE APPLICATIONS VALVES MAY BE INSTALLED ON RISERS, MIN. 4" ABOVE GRADE.
- 7. THE ADDITION OF SPOOLS MUST BE APPROVED BY THE CITY INSPECTOR PRIOR TO INSTALLATION.

- DETAIL OF ANCHOR

PROFILE

- STEEL CLAMP

- VERT MJ BEND

ELEVATION

22 1/2° BEND

0.8

1.2

TWO SHUT OFF VALVES

15

VAR/

MIN VOLUME CUBIC YARDS

45° BEND

1.4

2.4

BLOCK BELOW

5/8"

3" X 1/4"

3/4" 3-1/4" X 1/4"

8. THE PIPING FROM THE REDUCED PRESSURE BACKFLOW PREVENTER & THE REDUCED PRESSURE BACKFLOW PREVENTER VALVE ASSEMBLY

ITSELF MUST BE THE SAME SIZE AS THE SERVICE LINE UNLESS OTHERWISE APPROVED BY THE DISTRICT.

REDUCED PRESSURE BACKFLOW PREVENTER 18 NOT TO SCALE

4" & LARGER SHALL BE RESILIENT SEATED GATE VALVES. 5. ANY COVER OR SCREENING FOR THE BACKFLOW PREVENTION ASSEMBLY MUST BE APPROVED BY THE CITY ENGINEER PRIOR TO

SHOULDER OR DRIVEWAY AREAS

NOTES:

2. IF WIDTH IS LESS THAN 12" AND DEPTH IS LESS THAN 3', CDF BACKFILL SHALL BE USED.

3. USE 6" MIN. OF DRAIN ROCK ADDED TO BOTTOM OF UNSTABLE TRENCH AS REQUIRED.

6. TRENCH PAVING IN COUNTY RIGHT-OF-WAY SHALL HAVE A WIDTH AS SHOWN ON THE PLANS. NO