

Drainage Report

1615 Ocean Front San Diego, CA 92104

APN 539-143-01, 539-143-02

(PTS No. 612237)

Prepared for:

The City of San Diego



September 3, 2021

Table of Contents

1.	Existing Conditions	. 3
2.	Proposed Project	. 3
	Purpose and Scope of Report	
4.	Method of Calculations	. 3
5.	Results and Conclusions:	. 4
6.	Clean Water Act (CWA) Compliance	. 4
7.	Declaration of Responsible Charge	. 5

Appendix A – Drainage Maps

- Drainage Map 'A' Existing Drainage Conditions
- Drainage Map 'B' Proposed Drainage Conditions

Appendix B - Calculations/Evaluations

- 100 year storm
- Weight Runoff Coefficients

Appendix C – Reference Tables & Figures (City of San Diego Drainage Design Manual 2017)

- Figure A-1– Intensity-Duration Design Chart
- Figure A-4– Rational Formula-Overland Time of Flow
- Table A-1– Runoff coefficients for Rational Method
- Soil Hydrology Groups

1. Existing Conditions

In existing conditions, this project site is a residential lot with existing house. The majority of storm water runoff generated from this site (house, carport, front yard hardscape and landscape areas) currently discharges to the alley at the front of the property, where it flows northeasterly to an existing public storm drain system at the intersection of Cable Street and Niagara Avenue, before ultimately discharging to the Pacific Ocean.

See Appendix A- Drainage Map A.

2. Proposed Project

In proposed conditions, this project site will remain a residential lot and include a large addition to the house. A new carport will be constructed, along with a covered deck and surrounding hardscape. A below grade car lift will also be installed. The flow patterns will remain relatively the same as pre-construction conditions. Storm water runoff coming into contact with the rooftop and deck cover will reach landscape drains in the front yard and rear courtyard and be routed to a below-ground sump pump system. Sump flows will be pumped to a city-standard D-27 sidewalk underdrain at the northeast corner of the site, which will discharge the flows to the street through 2-3" diameter PVC outlet pipes. The walkway and parking area/lift will sheet flow into Ocean Front Street.

The rear yard bluff will remain untouched, and replicate the pre-construction drainage pattern.

See Appendix A- Drainage Map B.

3. Purpose and Scope of Report

This report will evaluate the proposed drainage pipe system and flow rate discharge to the street.

4. Method of Calculations

The Rational Method, as defined by *City of San Diego Drainage Design Manual 2017*, will be used to calculate storm water flow rates. Where noted, the following calculations were used to determine flow properties:

Rainfall Characteristics

$$Q = C * I * A$$
, where

 $Q = Flow rate (ft^3/sec)$

C = Runoff coefficient

(Runoff coefficient per *City of San Diego Drainage Design Manual 2017* reproduced in Appendix C. Soil type D determined from the *Soil Hydrologic Groups* map from the County of San Diego Hydrology Manual reproduced in Appendix C also.)

I = Rainfall intensity (in/hr.)

A = Area (acres)

5. Results and Conclusions:

Based on the calculations, the site will feature a slightly larger discharge to Ocean Front Street in proposed conditions, from 0.17 cfs to 0.24 cfs. Consequently, there is less runoff directed to the bluffs, from 0.25 cfs to 0.18 cfs. There are no anticipated impacts to adjacent properties as all storm water runoff from the habitable area discharges directly to the frontage street.

In pre-construction conditions, there is a 3" outlet located at the northeast corner of the property. Since it is unknown exactly how much runoff directly reaches this outlet pipe, at max velocity the pipe is expected to discharge to the street at 2.43 FPS.

The proposed D-27 sidewalk underdrain contains 2-3" diameter outlet pipes discharging to Ocean Front Street at a velocity of 2.43 FPS. Therefore, there is no increase or decrease of velocity expected to Ocean Front Street.

The final flow calculations will be submitted during the ministerial review.

6. Clean Water Act (CWA) Compliance

The proposed project is exempt from permitting under Federal Clean Water Act section 401 or 404 because it does not directly discharge into navigable waters of the United States.

7. Declaration of Responsible Charge

I hereby declare that I am the Civil Engineer of work for this project, that I have exercised responsible charge over the design of the project as defined in section 6703 of the business and professions code, and that the design is consistent with current design.

I understand that the check of project drawings and specifications by the City of San Diego is confined to a review only and does not relieve me, as Engineer of Work, of my responsibilities for project design.

Michael C. Kinnear RCE 76785 Exp. 12-31-22

Date



Appendix A – Drainage Map

STD DWG DESCRIPTION <u>SYMBOL</u> <u>N45°45'45"W</u> PROPERTY LINE STREET CENTERLINE (E) CONTOUR ₊100.00 (E) SPOT ELEVATION (E) FENCE TO REMAIN (E) WATER LINE _____s____ (E) SEWER LINE (E) WATER SERVICE (E) SEWER SERVICE (E) FIRE HYDRANT EXISTING TREE PVT SPOT ELEVATION PVT PVC DRAIN LINE (PER PLAN) SDR-35 SCH 40 ROOF DRAIN PVT FREESTANDING WALL PVT BUILDING FOOTPRINT PVT FENCE (MAT'L PER ARCHITECT) PVT PAVERS PVT DECK BUILDING FOOTPRINT BUILDING STEP (ELEVATION CHANGE) -----BUILDING OVERHANG _ _ _ _ _ _ _

LEGAL DESCRIPTION

LOT 9 & 10 IN BLOCK 66 OF OCEAN BEACH, IN THE CITY OF SAN DIEGO, COUNTY OF SAN DIEGO, STATE OF CALIFORNIA. ACCORDING TO MAP THEREOF NO. 279 FILED IN THE OFFICE OF THE COUNTY RECORDER OF SAN DIEGO, MAY 28, 1987.

APN: 448-161-02

BENCHMARK

CABLE STREET AND DEL MAR AVENUE N 2103, E 16916, EL=39.021, MSL, SBP AS PUBLISHED IN THE CITY OF SAN DIEGO VERTICAL CONTROL BENCHBOOK, OCTOBER 2011.


SOURCE OF TOPOGRAPHY

<u>FIELD TOPO BY:</u> BERGGREN & ASSOCIATES 6046 CORNERSTONE COURT, #116 SAN DIEGO, 92121 DATED: FEBRUARY 2019

EASEMENTS

THIS PLAN WAS PREPARED WITHOUT THE BENEFIT OF A TITLE REPORT. EASEMENTS MAY BE PRESENT ON THE SUBJECT PROPERTY.

ABBREVIATIONS



UTILITY NOTE

1. THE LOCATIONS OF UTILITIES, IF ANY, SHOWN ON THIS PLAN ARE GENERATED FROM RECORDS PROVIDED BY UTILITY/GOVERNING AGENCIES AND/OR FIELD DATA COLLECTED DURING THE SURVEY. THE PLOTTING OF UTILITIES ON THIS PLAN DOES NOT CONSTITUTE A GUARANTEE OF THEIR LOCATION, DEPTH, SIZE, OR TYPE.



No. C062716 9/3/21

ERING,

Ш

 $\frac{Z}{0}$

Ž W

mo

DRAWN BY: DK/MR CHECKED BY: JC

ORIGINAL 9/3/21 REVISION 1


REVISION 2 REVISION 3


REVISION 4 REVISION 5

GRADING and DRAINAGE PLAN

SCALE: 1" = 10'

SHT ___1 OF ___1 SHTS





Appendix B – Calculation / Evaluations

100 Year Storm							
Table A - Pre Construction Flow Conditions				Hydraulics of Existing Structures			
	Summary						
Flow ID (Basin)	Runoff Coefficient, C	Total time-of- concentration. T .	Rainfall Intensity, I (in/hr)	Basin Area, A (acres)	Q (cfs)	Flow ID (Basin)	Flow Description
X.1	0.55	5.00	4.40	0.07	0.17	X.1	Discharge to Ocean Front Street
Y.1	0.55	5.00	4.40	0.10	0.25	Y.1	Bluff to Pacific Ocean
				Sum =	0.42		

Table B - Post Construction Flow Conditions						Hydraulics of Proposed Structures	
		Summary					
Flow ID (Basin)	Runoff Coefficient, C	Total time-of- concentration, T .	Intensity, I	Basin Area, A (acres)	Q (cfs)	Flow ID (Basin)	Flow Description
A.1	0.55	5.00	4.40	0.08	0.20	A.1	Sump pump to Ocean Front Street
A.2	0.55	5.00	4.40	0.01	0.04	A.2	Sheet flow to Ocean Front Street
B.1	0.55	5.00	4.40	0.08	0.18	B.1	Bluff to Pacific Ocean
				Sum =	0.42		

Weighted Runoff Coefficients							
Pre-Construction Conditions	Pre-Construction Conditions						
Drainage Basin ID (Type)	Impervious Area (SF)	Pervious Area (SF)	Basin Area (SF)	Total (AC)	C-Value		
X.1	2,712	306	3,018	0.07	0.55		
Y.1	857	3,603	4,460	0.10	0.55		
Total	3,569	3,909	7,478	0.17			

Post-Construction Conditions							
Drainage Basin ID (Type)	Impervious Area (SF)	Pervious Area (SF)	Basin Area (SF)	Total (AC)	C-Value		
A.1	1,972	1,562	3,534	0.08	0.55		
A.2	336	294	630	0.01	0.55		
B.1	0	3,305	3,314	0.08	0.55		
Total	2,308	5,161	7,478	0.17			

Table A-1. Runoff Coefficients for Rational Method

Land Use	Runoff Coefficient (C) Soil Type (1)
Residential:	
Single Family	0.55
Multi-Units	0.70
Mobile Homes	0.65
Rural (lots greater than ½ acre)	0.45
Commercial (2)	
80% Impervious	0.85
Industrial (2)	
90% Impervious	0.95

Note:

(1) Type D soil to be used for all areas.

(2) Where actual conditions deviate significantly from the tabulated imperviousness values of 80% or 90%, the values given for coefficient C, may be revised by multiplying 80% or 90% by the ratio of actual imperviousness to the tabulated imperviousness. However, in case shall the final coefficient be less than 0.50. For example: Consider commercial property on D soil.

Actual imperviousness = 50%

Tabulated imperviousness = 80%

Pipe Flow						
Radius	Arc Length					
0.125	0.545415391					
Theta (Deg)	Theta (Rad)	Perimeter				
250	4.36332313	0.075960105				
2-3" PVC Discharging to Od	cean Front St. (A.1) - 3" Clo	osed Conduit - PVC @ 1%				
	1	Manning N				
Diameter (inches)		1.Closed Conduit - PVC				
3		0.011				
Slope (FT/FT) 0.0100		Q (CFS) 0.100653814030				
0.0100		0.100055814050				
Depth (feet)		Depth/Diameter				
0.19670		78.6788%				
Velocity (ft/sec)		Velocity Head (feet)				
2.429502155		0.091653427				
Area						
0.041429811						

Appendix C –Reference Tables & Figures (City of San Diego Drainage Manual 2017)




Figure A-4. Rational Formula - Overland Time of Flow Nomograph

Note: Use formula for watercourse distances in excess of 100 feet.






Figure A-1. Intensity-Duration-Frequency Design Chart



Table A-1. Runoff Coefficients for Rational Method

Land Use	Runoff Coefficient (C)		
Land Use	Soil Type (1)		
Residential:			
Single Family	0.55		
Multi-Units	0.70		
Mobile Homes	0.65		
Rural (lots greater than ½ acre)	0.45		
Commercial (2)			
80% Impervious	0.85		
Industrial (2)			
90% Impervious	0.95		

Note:

Actual imperviousness = 50% Tabulated imperviousness = 80% Revised C = (50/80) x 0.85 = 0.53

The values in Table A–1 are typical for urban areas. However, if the basin contains rural or agricultural land use, parks, golf courses, or other types of nonurban land use that are expected to be permanent, the appropriate value should be selected based upon the soil and cover and approved by the City.


A.1.3. Rainfall Intensity

The rainfall intensity (I) is the rainfall in inches per hour (in/hr.) for a duration equal to the T_{C} for a selected storm frequency. Once a particular storm frequency has been selected for design and a T_{C} calculated for the drainage area, the rainfall intensity can be determined from the Intensity-Duration-Frequency Design Chart (Figure A-1).



⁽¹⁾ Type D soil to be used for all areas.

⁽²⁾ Where actual conditions deviate significantly from the tabulated imperviousness values of 80% or 90%, the values given for coefficient C, may be revised by multiplying 80% or 90% by the ratio of actual imperviousness to the tabulated imperviousness. However, in case shall the final coefficient be less than 0.50. For example: Consider commercial property on D soil.



Appendix C –Reference Tables & Figures (City of San Diego Drainage Manual 2017)