
Appendix E Energy Calculations





Culver Crossings Construction Energy Analysis

Annual Fuel Summary

O	<u>ı ruei Sullillal y</u>	
		Heavy-Duty Construction Equipment
	406,700	Total Project Consumption
	140,707	Annual Consumption
		Haul Trucks
	199,723	Total Project Consumption
	69,098	Annual Consumption
		Vendor Trucks
	155,206	Total Project Consumption
	53,697	Annual Consumption
		Workers
	98,493	Total Project Consumption
	34,076	Annual Consumption
	354,929	Project Consumption of diesel for Haul Trucks and Vendors
	122,795	Annual Consumption
	761,629	Total Gallons Diesel
	98,493	Total Gallons Gasoline

2.9 Estimated Project Construction Duration (years)

263,502 Annual Average Gallons Diesel 34,076 Annual Average Gallons Gasoline

Los Ange	eles County		Percent of Annual Project Compared to Los Angeles County
Source	Fuel Type	Gallons	
Workers	Gasoline	2,770,000,000	0.0012%
Off-Road/Vendor/Haul Trucks	Diesel	610,204,082	0.043%
Notes:			

12,990 kWh/year

13,562 kWh/year

572 kWh/year

Annual Electricity Summary

Temporary Construction Trailer - Electricity
Construction Water Energy Estimates
Total

¹ Gasoline and diesel amounts from CEC, 2019. Available: https://www.energy.ca.gov/data-reports/energy-almanac/transportation-energy/california-retail-fuel-outlet-annual-reporting

Off-Road Equipment

Equipment ≤ 100 hp

pounds diesel fuel/hp-hr (lb/hp-hr): 1 0.408 lb/hp-hr diesel density (lb/gal): 1 7.11 lb/gal diesel gallons/hp-hr: 0.0574 gal/hp-hr Total <100 5,074,177 hp-hr Total diesel gallons: 291,221 gal

Equipment > 100 hp

pounds diesel fuel/hp-hr (lb/hp-hr):¹ 0.367 lb/hp-hr diesel density (lb/gal):¹ 7.11 lb/gal

diesel gallons/hp-hr: 0.0516 gal/hp-hr
Total >100 2,236,855 hp-hr
Total diesel gallons: 115,479 gal

diesel density (lb/gal):1 406,700 gal

1. OFFROAD2017 Emission Factor Documentation

Phase	Construction Phase	Equipment	Number	Hours/Day	HP	Load	Days	Total hp-hr
P1	Demolition	Air Compressors	1	8	78	0.5	25	7,488
P1	Demolition	Backhoes	1	8	97	0.4	25	7,178
P1	Demolition	Crawler Tractors	1	8	212	0.4	25	18,232
P1	Demolition	Dumpers/Tenders	1	8	16	0.4	25	1,216
P1	Demolition	Excavators	1	8	158	0.4	25	12,008
P1	Demolition	Forklifts	1	8	89	0.2	25	3,560
P1	Demolition	Generator Sets	1	8	84	0.7	25	12,432
P1	Demolition	Jackhammers (Backhoes)	2	8	97	0.4	25	14,356
P1	Demolition	Skid Steer Loaders	2	8	65	0.4	25	9,620
P1	Demolition	Sweepers/Scrubbers	1	8	64	0.5	25	5,888
P1	Site Preparation	Excavators	1	8	158	0.4	28	13,449
P1	Site Preparation	Forklifts	1	8	89	0.2	28	3,987
P1	Site Preparation	Loaders	1	8	97	0.4	28	8,039
P1	Site Preparation	Scrapers	1	8	367	0.5	28	39,460
P1	Site Preparation	Sweepers/Scrubbers	1	8	64	0.5	28	6,595
P1	Grading/Excavation	Bore/Drill Rigs	1	8	221	0.5	85	75,140
P1	Grading/Excavation	Crawler Tractors	1	8	212	0.4	85	61,989
P1	Grading/Excavation	Excavators	2	8	158	0.4	85	81,654
P1	Grading/Excavation	Pile Drivers (Excavators)	2	8	158	0.4	85	81,654
P1	Grading/Excavation	Sweepers/Scrubbers	1	8	64	0.5	85	20,019
P1	Drainage/Utility/Trenching	Backhoes	1	8	97	0.4	27	7,752
P1	Drainage/Utility/Trenching	Forklifts	1	8	89	0.2	27	3,845
P1	Drainage/Utility/Trenching	Skid Steer Loaders	1	8	65	0.4	27	5,195
P1	Foundations/Concrete Pours	Cement and Mortar Mixers	102	8	9	0.6	168	690,924
P1	Foundations/Concrete Pours	Pumps	2	8	84	0.7	168	167,086
P1	Building Construction	Air Compressors	1	8	78	0.5	310	92,851
P1	Building Construction	Cement and Mortar Mixers	1	8	9	0.6	310	12,499
P1	Building Construction	Cranes	1	8	231	0.3	310	166,135
P1	Building Construction	Forklifts	1	8	89	0.2	310	44,144
P1	Building Construction	Generator Sets	1	8	84	0.7	310	154,157
P1	Building Construction	Pumps	1	8	84	0.7	310	154,157
P1	Building Construction	Sweepers/Scrubbers	1	8	64	0.5	310	73,011
P1	Architectural Coating	Air Compressors	1	8	78	0.5	127	38,039
P1	Architectural Coating	Generator Sets	1	8	84	0.7	127	63,155
P1	Paving	Crushing/Proc. Equipment	1	8	85	0.8	110	58,344
P1	Paving	Dumpers/Tenders	1	8	16	0.4	110	5,350
P1	Paving	Pavers	1	8	130	0.4	110	48,048
P1	Paving	Paving Equipment	1	8	132	0.4	110	41,818
P1	Paving	Rollers	1	8	80	0.4	110	26,752
P1	Paving	Signal Boards	1	8	6	0.8	110	4,330
P1	Paving	Sweepers/Scrubbers	1	8	64	0.5	110	25,907
P2	Demolition	Air Compressors	3	8	78	0.5	25	22,464
P2	Demolition	Backhoes	1	8	97	0.4	25	7,178
P2	Demolition	Crawler Tractors	1	8	212	0.4	25	18,232
P2	Demolition	Dumpers/Tenders	1	8	16	0.4	25	1,216
P2	Demolition	Excavators	1	8	158	0.4	49	23,536
P2	Demolition	Forklifts	1	8	89	0.4	49	6,978
P2	Demolition	Generator Sets	1	8	84	0.2	49	24,367

Phase	Construction Phase	Equipment	Number	Hours/Day	HP	Load	Days	Total hp-hr
P2	Demolition	Jackhammers (Backhoes)	3	8	97	0.4	49	42,207
P2	Demolition	Skid Steer Loaders	1	8	65	0.4	49	9,428
P2	Demolition	Sweepers/Scrubbers	1	8	64	0.5	49	11,540
P2	Site Preparation	Excavators	2	8	158	0.4	61	58,599
P2	Site Preparation	Forklifts	1	8	89	0.2	61	8,686
P2	Site Preparation	Loaders	2	8	97	0.4	61	35,029
P2	Site Preparation	Scrapers	1	8	367	0.5	61	85,966
P2	Site Preparation	Sweepers/Scrubbers	1	8	64	0.5	61	14,367
P2	Grading/Excavation	Bore/Drill Rigs	2	8	221	0.5	147	259,896
P2	Grading/Excavation	Crawler Tractors	1	8	212	0.4	147	107,204
P2	Grading/Excavation	Excavators	3	8	158	0.4	147	211,821
P2	Grading/Excavation	Pile Drivers (Excavators)	2	8	158	0.4	147	141,214
P2	Grading/Excavation	Sweepers/Scrubbers	2	8	64	0.5	147	69,243
P2	Drainage/Utility/Trenching	Backhoes	1	8	97	0.4	48	13,782
P2	Drainage/Utility/Trenching	Forklifts	2	8	89	0.2	48	13,670
P2	Drainage/Utility/Trenching	Skid Steer Loaders	1	8	65	0.4	48	9,235
P2	Foundations/Concrete Pours	Cement and Mortar Mixers	133	8	9	0.6	280	1,501,517
P2	Foundations/Concrete Pours	Pumps	3	8	84	0.7	280	417,715
P2	Building Construction	Air Compressors	1	8	78	0.5	273	81,769
P2	Building Construction	Cement and Mortar Mixers	2	8	9	0.6	273	22,015
P2	Building Construction	Cranes	1	8	231	0.3	273	146,306
P2	Building Construction	Crawler Tractors	1	8	212	0.4	273	199,093
P2	Building Construction	Forklifts	2	8	89	0.2	273	77,750
P2	Building Construction	Generator Sets	2	8	84	0.7	273	271,515
P2	Building Construction	Sweepers/Scrubbers	1	8	64	0.5	273	64,297
P2	Architectural Coating	Air Compressors	1	8	78	0.5	97	29,053
P2	Paving	Crushing/Proc. Equipment	2	8	85	0.8	67	71,074
P2	Paving	Dumpers/Tenders	1	8	16	0.4	67	3,259
P2	Building Construction	Cranes	1	8	231	0.3	273	146,306
P2	Building Construction	Crawler Tractors	1	8	212	0.4	273	199,093
P2	Building Construction	Forklifts	2	8	89	0.2	273	77,750
P2	Building Construction	Generator Sets	2	8	84	0.7	273	271,515
P2	Building Construction	Sweepers/Scrubbers	1	8	64	0.5	273	64,297
P2	Architectural Coating	Air Compressors	1	8	78	0.5	97	29,053
P2	Paving	Crushing/Proc. Equipment	2	8	85	0.8	67	71,074
P2	Paving	Dumpers/Tenders	1	8	16	0.4	67	3,259
	1						Total >100	2,236,855
							Total <100	5,074,177

Year	Туре	Fuel Type	CC1 VMT	CC2 VMT	Total VMT	Fuel Consumption (gal)
2023	Worker	Gasoline	168,227	64,239	232,466	9,104
2023	Vendor	Diesel	197,920	5,796	203,716	28,522
2023	Haul	Diesel	386,520	560,012	946,532	158,488
2024	Worker	Gasoline	763,959	411,100	1,175,059	45,166
2024	Vendor	Diesel	169,436	399,731	569,167	78,982
2024	Haul	Diesel	0	249,388	249,388	41,235
2025	Worker	Gasoline	0	1,170,502	1,170,502	44,223
2025	Vendor	Diesel	0	347,277	347,277	47,703
2025	Haul	Diesel	0	0	0	0

Vehicle Type		gal	lons/mile	
,,	2023	2024	2025	2026
Haul	0.16744	0.165345	0.163052	0.160756677
Vendor	0.140008	0.138767	0.137363	0.135957296
Worker	0.039164	0.038437	0.037781	0.037118687

Source: EMFAC2021

Fuel Type	Fuel Consumption (gal)								
i dei Type	2023	2024	2025	Total					
Worker	9,104	45,166	44,223	98,493					
Vendor	28,522	78,982	47,703	155,206					
Haul	158,488	41,235	0	199,723					

Construction VMT - PA1

						Worker Trip	Vendor Trip	Haul Trip						
Phase	Subphase	Phase Start Date	Phase End Date	Year	Working Days	Number	Number	Number	Worker Trips	Vendor Trips	Haul Trips	Worker VMT	Vendor VMT	Haul VMT
PA1	Demolition	2/16/2023	3/16/2023	2023	25	30	4	178	750	100	178	11025	690	5340
PA1	Site Preparation	3/1/2023	4/1/2023	2023	28	8	4	40	224	112	40	3293	773	1200
PA1	Grading/Excavation	3/17/2023	6/23/2023	2023	85	12	4	12666	1020	340	12666	14994	2346	379980
PA1	Drainage/Utilities/Trenching	6/24/2023	7/25/2023	2023	27	20	4	0	540	108	0	7938	745	0
PA1	Foundations/Concrete Pours	7/26/2023	12/31/2023	2023	136	60	204	0	8160	27744	0	119952	191434	0
PA1	Foundations/Concrete Pours	1/1/2024	2/6/2024	2024	32	60	204	0	1920	6528	0	28224	45043	0
PA1	Building Construction	12/26/2023	12/31/2023	2023	5	150	56	0	750	280	0	11025	1932	0
PA1	Building Construction	1/1/2024	12/20/2024	2024	305	150	56	0	45750	17080	0	672525	117852	0
PA1	Architectural Coating	6/15/2024	11/9/2024	2024	127	20	4	0	2540	508	0	37338	3505	0
PA1	Paving	7/5/2024	11/9/2024	2024	110	16	4	0	1760	440	0	25872	3036	0

Worker, Vendor, Haul Trip Lengths

	Default Trip Length (mi)
Worker	14.7
Vendor	6.9
Haul	30.0

	Trip Type	2023	2024	Total
ſ	Worker	168,227	763,959	932,186
١	Vendor	197,920	169,436	367,356
١	Haul	386,520	0	386,520

Source: Haul trip length = distance to landfill

Construction VMT - PA2

	Construction VIVIT - PAZ					Worker Trip	Vendor Trip	Haul Trip						
Phase	Subphase	Phase Start Date	Phase End Date	Year	Working Days	Number	Number	Number	Worker Trips	Vendor Trips	Haul Trips	Worker VMT	Vendor VMT	Haul VMT
PA2	Demolition	7/11/2023	9/5/2023	2023	49	40	4	820	1960	196	820	28812	1352	24600
PA2	Site Preparation	8/15/2023	10/24/2023	2023	61	10	4	160	610	244	160	8967	1684	4800
PA2	Grading/Excavation	9/6/2023	12/31/2023	2023	100	18	4	17687	1800	400	17687	26460	2760	530612
PA2	Grading/Excavation	1/1/2024	2/23/2024	2024	47	18	4	8313	846	188	8313	12436	1297	249388
PA2	Drainage/Utilities/Trenching	2/24/2024	4/19/2024	2024	48	20	4	0	960	192	0	14112	1325	0
PA2	Foundations/Concrete Pours	4/22/2024	12/31/2024	2024	218	120	264	0	26160	57552	0	384552	397109	0
PA2	Foundations/Concrete Pours	1/1/2025	3/13/2025	2025	62	120	264	0	7440	16368	0	109368	112939	0
PA2	Building Construction	2/6/2025	12/20/2025	2025	273	250	122	0	68250	33306	0	1003275	229811	0
PA2	Architectural Coating	8/10/2025	12/1/2025	2025	97	24	4	0	2328	388	0	34222	2677	0
PA2	Paving	9/15/2025	12/1/2025	2025	67	24	4	0	1608	268	0	23638	1849	0

Worker, Vendor, Haul Trip Lengths

		_	Trip Type	2023	2024	2025	Total
	Default Trip Length (mi)		Worker	64,239	411,100	1,170,502	1,645,841
Worker	14.7		Vendor	5,796	399,731	347,277	752,804
Vendor	6.9		Haul	560,012	249,388	0	809,400
Haul	30.0				•	•	•

Source: Haul trip length = distance to landfill

Culver Crossings Construction Energy Analysis

Temporary Construction Trailer - Electricity					
Land Use	Square Feet	Energy Use per year (kWh)	Total Energy Use (kWh)		
General Office	1,000	12,990	37,546		
Note: CalEEMod 2016.3	Note: CalEEMod 2016.3.2 used to estimate energy use for temporary construction office				

Construction Water GHG Emissions Total	Electricity Emission Factor	Electricity Emission Factor
8.72	(MT CO2e/MWh)	(lbs CO2e/MWh)
	0.23	512.23

Culver Crossings Construction Energy

Construction Water Energy Estimates

Source	Gallons per Day	Number of Days	Total Construction Water Use (Mgal)	Electricity Demand from Water Conveyance (kWh)	Annual Electricity Demand from Water Conveyance (kWh)
Project Construction	2,000	1,055	2.11	1,652.1	571.6
Total			2.110	1,652.1	571.6


CalEEMod Water Electricity Factors	Electricity Intensity Factor for Recycled Non-Potable Water	Electricity Intensity Factor for Recycled Water Conveyance	
	419	364	

Construction Water GHG	Electricity Emission Electricity Emiss	
0.38	(MT CO2e/MWh) (lbs CO2e/MW	
	0.23	512.23

Sources and Assumptions:

Next 10 and Pacific Institute, The Future of California's Water-Energy-Climate Nexus, Table 4, https://pacinst.org/wp-content/uploads/2021/09/Water-Energy-Report_Sept-2021.pdf

- -Assumes use of non-potable recycled water and conveyance of recycled water to the South Coast Region
- -Conservatively assumes a water consumption rate of 2,000 gpd during construction per Section 4.14.1 Utilities and Service Systems Water of the Draft EIR



Culver Crossings Operational Energy Demand

Electricity	kWh/yr	MWh/yr
Existing		
Building Energy - Los Angeles	1,151,231	1,151
Building Energy - Culver City	52,980	53
Water Use - Los Angeles	13,284	13
Water Use - Culver City	136	0
Subtotal Exsiting - Los Angeles	1,164,515	1,165
Subtotal Exsiting - Culver City	53,117	53
Existing Total	1,217,631	1,218
Project		
Los Angeles - Office	4,996,260	4,996
Los Angeles - Parking	2,015,661	2,016
Los Angeles - Restaurant	1,387,929	1,388
Culver City - Office	2,261,180	2,261
Culver City - Parking	904,346	904
Los Angeles - Building Total	8,399,850	8,400
Culver City - Building Total	3,165,526	3,166
		-
EV Charging - Los Angeles Site	118,844	119
EV Charging - Culver City Site	77,088	77
Total Building Energy	11,565,376	11,565
Total	11,761,308	11,761.31
Total (including water, see below)	12,139,321	12,139
Total Net Electricity	10,921,690	10,922
Total - Los Angeles Site	8,794,737	8,795
Total - Culver City Site	3,344,584	3,345

Source: California Air Resources Board, CalEEMod, Version 2020.4.0.

Water	Mgal/yr	MWh/yr
Existing		
Los Angeles Site	1.0	13.3
Culver City Site	0.0	0.1
Existing Total	1.0	13.4
Project		
Los Angeles Site	21.2	276.0
Culver City Site	7.8	102.0
Total	29.0	378.0
Electricity Intensity Factors	kWh/Mgal	
Electricity Factor - Supply	9,727	
Electricity Factor - Treat	111	
Electricity Factor - Distribute	1,272	
Electricity Factor - Wastewater Treatment	1,911	
Electricity from Water Demand	kWh/yr	MWh/yr
Existing Total	13,420.08	13.4
Project Total	378,012.91	378.0

Source: California Air Resources Board, CalEEMod, Version 2016.3.2.

Water Demand based on Project Water supply Assessment

Sewage Facilities Charge, Sewage Generation Factor for Residential and Commercial Categories, 2012.

Natural Gas Existing Site		kBtu/yr	cubic foot (cf)	
Building Energy		697,538	673,949	
Mobile Sources		397,804	384,351	
	Existing Site Total	1,095,341	1,058,301	
Project				
Los Angeles - Restaurant		7,388,065	7,138,227	
Mobile Sources		1,294,728	1,250,945	
	Total	8,682,793	8,389,172	
	Total Net	7,587,452	7,330,872	

Source: California Air Resources Board, CalEEMod, Version 2020.4.0.

 $Conversion\ factor\ of\ 1,035\ Btu\ per\ cubic\ foot\ based\ on\ United\ States\ Energy\ Information\ Administration\ data$

(see: USEIA, Natural Gas, Heat Content of Natural Gas Consumed, February 28, 2018,

https://www.eia.gov/dnav/ng/ng_cons_heat_a_EPG0_VGTH_btucf_a.htm. Accessed March 2020.)

MWh/yr
120,000,000
27,428,711
7,630.22
3,291.47
0.028% 0.003%

Source: Los Angeles Department of Water and Power,
2017 Long-Term Resource Plan, Appendix A, 2017.
https://efiling.energy.ca.gov/getdocument.aspx?tn=227897

CEC. 2018. The California Energy Demand 2018–2030 Revised Forecast. Available at:
http://docketpublic.energy.ca.gov/PublicDocuments/17-IEPR03/TN222287_20180120T141708_The_California_Energy_Demand_20182030_Revised_Forecast.pdf

Natural Gas	million cubic foot (cf)
SoCalGas 2026	896,805
Net Annual	7.331
Percent Net Project of SoCalGas	0.0008%

Source: California Gas and Electric Utilities, 2020 California Gas

Report, p. 145,2020.

Culver Crossings Operational Energy Analysis

Estimated Electricity demand from Electric Vehicle Supply Equipment (EVSE)

		Number of EVSE	Average Charge			Electricity Demand
Lar	d Use Type	Charging Spaces	(kWh/day) ^a	Days/Year	Electricity Demand (kWh/yr)	(MWh/yr)
	Culver City	48	4.4	365	77,088	77
	Los Angeles	74	4.4	365	118,844	119
	Total	122	4.4	365	195,932	196

Notes:

- a. Estimated based on reference sources listed below.
- b. Project would install EV charing spaces for 10 percent of its parking capacity for immediate use
- c. Project would install pre-wiring for EV charging spaces for 30 percent of its parking capacity for future use (so 20% in addition to the immediate use).

Sources:

US Department of Energy. Alternative Fuels Data Center, 2016. Hybrid and Plug-In Electric Vehicle Emissions Data Sources and Assumptions.

Available at: https://www.afdc.energy.gov/vehicles/electric emissions sources.html.

US Department of Energy. Smith, Margaret, 2016. Level 1 Electric Vehicle Charging Stations at the Workplace.

Available at: https://www.afdc.energy.gov/uploads/publication/WPCC_L1ChargingAtTheWorkplace_0716.pdf.

UCLA Luskin Center for Innovation. Williams, Brett and JR deShazo, 2013. Pricing Workplace Charging: Financial Viability and Fueling Costs.

Available at: http://luskin.ucla.edu/sites/default/files/Luskin-WPC-TRB-13-11-15d.pdf.

Culver Crossings Operational Energy Analysis Fuel Usage from VMT

Daily VMT: 37,134 miles/day
Annual VMT⁴: 13,553,910 miles/year

Fuel Type: ¹	Gasoline	Diesel	Electricity	Natural Gas	Plug-in Hybrid
Percent:	88.2%	5.2%	4.1%	0.3%	2.2%
Miles per Gallon Fuel:	25.0	8.8	-	4.2	58.8
Annual VMT by Fuel Type (miles):	11,956,216	701,134	560,310	42,596	293,654
Annual Fuel Usage (gallons): Annual Natural Gas Use (kbtu):	477,331	80,033	-	10,123 1,294,728	4,995
Annual Fuel Savings from Electric Vehicles: ²	-	-	22,369		

	Los Angeles County Fuel Consumption ³		
	Gasoline	Diesel	
Los Angeles County:	2,770,000,000	610,204,082	
Existing Total:	159,408	23,179	
Project Annual Total:	482,326	80,538	
Project Mobile Sources:	482,326	80,033	
Project Emergency Generator:	-	504	
Net Annual Total:	322,918	57,359	
Percent Net Project of Los Angeles County:	0.0117%	0.0094%	

Notes

- 1. California Air Resources Board, EMFAC2021 (South Coast Air Basin; Annual; 2026', Aggregate Fleet).
- 2. Assumes electric vehicles would replace traditional gasoline-fueled vehicles.
- 3. California Energy Commission, California Retail Fuel Outlet Annual Reporting (CEC-A15) Results, 2020. Available at: https://ww2.energy.ca.gov/almanac/transportation_data/gasoline/piira_retail_survey.html. Accessed March 2022. Diesel is adjusted to account for retail (49%) and non-retail (51%) diesel sales.
- 4. City of LA VMT Calculator Tool

Annual VMT (Traffic Study)⁴:

3,977,333 miles/year

Fuel Type: ¹	Gasoline	Diesel	Electricity	Natural Gas	Plug-in Hybrid
Percent:	91.9%	4.7%	1.7%	0.3%	1.4%
Miles per Gallon Fuel:	23.1	8.0	-	4.0	51.7
Annual VMT by Fuel Type (miles):	3,655,698	186,585	68,428	12,314	54,308
Annual Fuel Usage (gallons): Annual Natural Gas Use (kbtu):	158,357	23,179	-	3,110 397,804	1,051
Annual Fuel Savings from Electric Vehicles: ²	-	-	2,964		

	Los Angeles County Fuel Consumption ³		
	Gasoline Diesel		
Los Angeles County:	2,770,000,000	610,204,082	
Existing Annual Total:	159,408	23,179	
Percent Net Project of Los Angeles County:	0.0058%	0.0038%	

Notes:

- 1. California Air Resources Board, EMFAC2021 (South Coast Air Basin; Annual; 2026', Aggregate Fleet).
- 2. Assumes electric vehicles would replace traditional gasoline-fueled vehicles.
- 3. California Energy Commission, California Retail Fuel Outlet Annual Reporting (CEC-A15) Results, 2020. Available at: https://ww2.energy.ca.gov/almanac/transportation_data/gasoline/piira_retail_survey.html. Accessed March 2022. Diesel is adjusted to account for retail (49%) and non-retail (51%) diesel sales.
- 4. CalEEMod v 2020.4.0 Default VMT

Culver Crossings Emergency Generator Fuel Use

Emergency Generator rue: Osc				
	Total CO ₂	Fuel	Factor	
	MT/yr	Туре	KGCO ₂ /gal	Gallons

Emergency Generator

Assumptions

10.15 KGCO₂/gal diesel 8.91 KGCO₂/gal gasoline 1 MT = 1,000 kilograms

5.1206


10.15

504

diesel

CITY OF LOS ANGELES VMT CALCULATOR Version 1.3





Analysis Results

Proposed Project	With Mitigation
3,786 Daily Vehicle Trips	3,786 Daily Vehicle Trips
37,134 Daily VMT	37,134 Daily VMT
0.0 Houseshold VMT per Capita	0.0 Houseshold VMT per Capita
11.2 Work VMT per Employee	11.2 Work VMT per Employee
Significant \	/MT Impact?
Household: No	Household: No
Threshold = 6.0 15% Below APC	Threshold = 6.0 15% Below APC
Work: No Threshold = 11.6 15% Below APC	Work: No Threshold = 11.6 15% Below APC



Report 1: Project & Analysis Overview

Date: December 17, 2021

Project Name: Project Crossings

Project Scenario:



	Project Informa	ntion			
Land Use Type Value U					
	Single Family	0	DU		
	Multi Family	0	DU		
Housing	Townhouse	0	DU		
	Hotel	0	Rooms		
	Motel	0	Rooms		
	Family	0	DU		
Affandabla Harraina	Senior	0	DU		
Affordable Housing	Special Needs	0	DU		
	Permanent Supportive	Value 0	DU		
	General Retail	0.000	ksf		
	Furniture Store	0.000	ksf		
	Pharmacy/Drugstore	0.000	ksf		
	Supermarket	0.000	ksf		
	Bank	0.000	ksf		
	Health Club	0.000	ksf		
D-1-1	High-Turnover Sit-Down				
Retail	Restaurant	0.000	ksf		
	Fast-Food Restaurant	0.000	ksf		
	Quality Restaurant	0.000	ksf		
	Auto Repair	0.000	ksf		
	Home Improvement	0.000	ksf		
	Free-Standing Discount	0.000	ksf		
	Movie Theater	0	Seats		
Off.	General Office	536.000	ksf		
Office	Medical Office	0.000	ksf		
	Light Industrial	0.000	ksf		
Industrial	Manufacturing	0.000	ksf		
	Warehousing/Self-Storage	0.000	ksf		
	University	0	Students		
	High School	0	Students		
School	Middle School	0	Students		
	Elementary	0	Students		
	Private School (K-12)	0	Students		

Date: December 17, 2021
Project Name: Project Crossings

Project Scenario:

Report 1: Project & Analysis Overview

Project Address: 8876 W VENICE BLVD, 90034

ther 0 Trips

Report 1: Project & Analysis Overview

Date: December 17, 2021

Project Name: Project Crossings





	Analysis Res	culte				
	Analysis Results					
	Total Employees:					
	Total Population:	0				
Propos	ed Project	With M	itigation			
3,786	Daily Vehicle Trips	3,786	Daily Vehicle Trips			
37,134	Daily VMT	37,134	Daily VMT			
0	Household VMT per Capita	0	Household VMT per Capita			
11.2	Work VMT per Employee	11.2	Work VMT per Employee			
	Significant VMT	Impact?				
	APC: South Los	Angeles				
	Impact Threshold: 15% Beld	ow APC Average				
	Household = 6	5.0				
	Work = 11.6	5				
Propos	ed Project	With M	itigation			
VMT Threshold	Impact	VMT Threshold	Impact			
Household > 6.0	No	Household > 6.0	No			
Work > 11.6	No	Work > 11.6	No			

Report 2: TDM Inputs

Date: December 17, 2021
Project Name: Project Crossings

Project Scenario:

Project Address: 8876 W VENICE BLVD, 90034



	TDM Strategy Inputs				
Stra	tegy Type	Description	Proposed Project	Mitigations	
	Doduce narking cumble	City code parking provision (spaces)	0	0	
	Reduce parking supply	Actual parking provision (spaces)	0	0	
_	Unbundle parking	Monthly cost for parking (\$)	\$0	\$0	
	Parking cash-out	Employees eligible (%)	0%	0%	
	Price workplace	Daily parking charge (\$)	\$0.00	\$0.00	
	parking	Employees subject to priced parking (%)	0%	0%	
	Residential area parking permits	Cost of annual permit (\$)	\$0	<i>\$0</i>	

(cont. on following page)

Report 2: TDM Inputs

Date: December 17, 2021
Project Name: Project Crossings

Project Scenario:



Strate	egy Type	Description	Proposed Project	Mitigations
	Reduce transit headways	Reduction in headways (increase in frequency) (%)	0%	0%
		Existing transit mode share (as a percent of total daily trips) (%)	0%	0%
		Lines within project site improved (<50%, >=50%)	0	0
Transit	Implement	Degree of implementation (low, medium, high)	0	0
	neighborhood shuttle	Employees and residents eligible (%)	0%	0%
		Employees and residents eligible (%)	0%	0%
	Transit subsidies	Amount of transit subsidy per passenger (daily equivalent) (\$)	\$0.00	\$0.00
Education &	Voluntary travel behavior change program	Employees and residents participating (%)	0%	0%
Encouragement	Promotions and marketing	Employees and residents participating (%)	0%	0%

Report 2: TDM Inputs

Date: December 17, 2021
Project Name: Project Crossings

Project Scenario:



Strate	gy Type	Description	Proposed Project	Mitigations
	Required commute trip reduction program	Employees participating (%)	0%	0%
	Alternative Work Schedules and	Employees participating (%)	0%	0%
	Telecommute	Type of program	0	0
Commute Trip Reductions		Degree of implementation (low, medium, high)	0	0
	Employer sponsored vanpool or shuttle	Employees eligible (%)	0%	0%
		Employer size (small, medium, large)	0	0
	Ride-share program	Employees eligible (%)	0%	0%
	Car share	Car share project setting (Urban, Suburban, All Other)	0	0
Shared Mobility	Bike share	Within 600 feet of existing bike share station - OR- implementing new bike share station (Yes/No)	0	0
	School carpool program	Level of implementation (Low, Medium, High)	0	0

Report 2: TDM Inputs

Date: December 17, 2021
Project Name: Project Crossings

Project Scenario:



TDM Strategy Inputs, Cont.					
Strate	Strategy Type Description Proposed Project Mitigations				
	Implement/Improve on-street bicycle facility	Provide bicycle facility along site (Yes/No)	0	0	
Bicycle Infrastructure	Include Bike parking per LAMC	nclude Bike parking Meets City Bike Parking Code Ye	Yes	Yes	
Include s	Include secure bike parking and showers	Includes indoor bike parking/lockers, showers, & repair station (Yes/No)	Yes	Yes	
	Traffic calming	Streets with traffic calming improvements (%)	0%	0%	
Neighborhood	improvements	Intersections with traffic calming improvements (%)	0%	0%	
Enhancement	Pedestrian network improvements	Included (within project and connecting offsite/within project only)	0	0	

Report 3: TDM Outputs

Date: December 17, 2021 Project Name: Project Crossings

Project Scenario:

Project Address: 8876 W VENICE BLVD, 90034



TDM Adjustments by Trip Purpose & Strategy

						Place type	: Compact	Infill						
			ased Work luction		ased Work action		ased Other duction		ased Other action		Based Other		Based Other	Source
		Proposed	Mitigated	Proposed	Mitigated	Proposed	Mitigated	Proposed	Mitigated	Proposed	Mitigated	Proposed	Mitigated	_
	Reduce parking supply	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	
	Unbundle parking	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	
Parking	Parking cash-out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	TDM Strategy Appendix, Parking
Tarking	Price workplace parking	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	sections 1 - 5
	Residential area parking permits	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	
	Reduce transit headways	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	TDM Strategy
Transit	Implement neighborhood shuttle	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	Appendix, Transit sections 1 - 3
	Transit subsidies	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	
Education &	Voluntary travel behavior change program	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	TDM Strategy Appendix, Education & Encouragement sections 1 - 2
Encouragement	Promotions and marketing	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	
	Required commute trip reduction program	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	TDM Stratom
Commute Trip Reductions	Alternative Work Schedules and Telecommute Program	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	TDM Strategy Appendix, Commute Trip Reductions sections 1 - 4
	Employer sponsored vanpool or shuttle	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	
	Ride-share program	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	
	Car-share	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	TDM Strategy
Shared Mobility	Bike share	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	Appendix, Shared
Shared Woodinty	School carpool program	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	Mobility sections 1 - 3

Report 3: TDM Outputs

Date: December 17, 2021

Project Name: Project Crossings

Project Scenario:

Project Address: 8876 W VENICE BLVD, 90034



				TDM Ac	ljustment	s by Trip	Purpose	& Strateg	y, Cont.					
						Place type	: Compact	Infill						
			ased Work		ased Work		ased Other		ased Other		Based Other		Based Other	
		Proc	luction	Attr	action	Prod	luction	Attr	raction	Prod	luction	Atti	raction	Source
		Proposed	Mitigated	Proposed	Mitigated	Proposed	Mitigated	Proposed	Mitigated	Proposed	Mitigated	Proposed	Mitigated	
Bicycle Infrastructure	Implement/ Improve on-street bicycle facility	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	TDM Strategy
	Include Bike parking per LAMC	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	Appendix, Bicyc
	Include secure bike parking and showers	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	0.6%	sections 1 - 3
Neighborhood	Traffic calming improvements	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	TDM Strategy Appendix,
Enhancement	Pedestrian network improvements	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	Neighborhood Enhancement

Final Combined & Maximum TDM Effect												
	Home Based Work Production		Home Based Work Attraction		Home Based Other Production		Home Based Other Attraction		Non-Home Based Other Production		Non-Home Based Other Attraction	
	Proposed	Mitigated	Proposed	Mitigated	Proposed	Mitigated	Proposed	Mitigated	Proposed	Mitigated	Proposed	Mitigated
COMBINED TOTAL	1%	1%	1%	1%	1%	1%	1%	1%	1%	1%	1%	1%
MAX. TDM EFFECT	1%	1%	1%	1%	1%	1%	1%	1%	1%	1%	1%	1%

= Minimum (X%, 1-[(1-A)*(1-B)]) where X%=							
PLACE	urban	75%					
TYPE	compact infill	40%					
MAX:	suburban center	20%					
	suburban	15%					

Note: (1-[(1-A)*(1-B)...]) reflects the dampened combined effectiveness of TDM Strategies (e.g., A, B,...). See the TDM Strategy Appendix (*Transportation Assessment Guidelines Attachment G*) for further discussion of dampening.

Project Scenario:

Project Name: Project Crossings



Report 4: MXD Methodology

Project Address: 8876 W VENICE BLVD, 90034

Date: December 17, 2021

v	פו	31	ΟI	د ا	1.5	

MXD Methodology - Project Without TDM									
	Unadjusted Trips	MXD Adjustment	MXD Trips	Average Trip Length	Unadjusted VMT	MXD VMT			
Home Based Work Production	0	0.0%	0	6.5	0	0			
Home Based Other Production	0	0.0%	0	5.1	0	0			
Non-Home Based Other Production	557	-4.5%	532	6.3	3,509	3,352			
Home-Based Work Attraction	2,473	-21.6%	1,940	12.5	30,913	24,250			
Home-Based Other Attraction	1,115	-25.6%	830	6.6	7,359	5,478			
Non-Home Based Other Attraction	557	-4.5%	532	8.5	4,735	4,522			

MXD Methodology with TDM Measures									
		Proposed Project		Project with Mitigation Measures					
	TDM Adjustment	Project Trips	Project VMT	TDM Adjustment	Mitigated Trips	Mitigated VMT			
Home Based Work Production	-1.2%		0	-1.2%					
Home Based Other Production	-1.2%			-1.2%					
Non-Home Based Other Production	-1.2%	525	3,310	-1.2%	525	3,310			
Home-Based Work Attraction	-1.2%	1,916	23,948	-1.2%	1,916	23,948			
Home-Based Other Attraction	-1.2%	820	5,410	-1.2%	820	5,410			
Non-Home Based Other Attraction	-1.2%	525	4,466	-1.2%	525	4,466			

MXD VMT Methodology Per Capita & Per Employee										
Total Population: 0 Total Employees: 2,144										
APC: South Los Angeles										
	Proposed Project	Project with Mitigation Measures								
Total Home Based Production VMT	0	0								
Total Home Based Work Attraction VMT	23,948	23,948								
Total Home Based VMT Per Capita	0.0	0.0								
Total Work Based VMT Per Employee	11.2	11.2								