

# LOW IMPACT DEVELOPMENT STANDARD URBAN STORM WATER MITIGATION PLAN

## FOR

12300 Lakeland Drive Santa Fe Springs, CA, 90670

PREPARED FOR: DUKE REALTY 200 Spectrum Center Drive, Suite 1600 Irvine, CA 92618 DJ Arellano DJ.Arellano@DUKEREALTY.com

PREPARED BY: Walden & Associates 2552 White Road, Suite B Irvine, CA 92614 Marcos Padilla 949-660-0110 mpadilla@waldenassciates.net JN: 2088-962-001

### TABLE OF CONTENTS

| Section I    | Introduction   |  |
|--------------|--|--|
| Section II   | Project Description  | 4  |
| Section III  | Site Description   | 6  |
| Section IV   | SUSMP Requirem   | ents and Provisions7   |
| Section V    | Volume and Flow I  | Rate Calculations10  |
| Section VI   | Best Management  | Practices (BMPs)11   |
| Section VII  | Operation and Ma   | intenance Guidelines12   |
| Section VIII | Figures  |  |
| 1.<br>2.     | Vicinity Map<br>Site Plan                                  |  |
| Section IX   | Attachments  |  |
|              | Attachment A<br>Attachment B<br>Attachment C               | EPA: When it rains it drains<br>EPA: Preventing Pollution Through Efficient Water Use<br>Solution to Pollution - Twenty Ways to Protect Your Water |
| Section X    | Appendix   |  |
|              | BMP Sizing Calcula<br>Contech Details<br>Hydromodification |  |
| Section XI   | Geotechnical Repo  | rt (Infiltration Study)  |

### I. INTRODUCTION

The municipal storm water National Pollutant Discharge Elimination System (NPDES) permit (Los Angeles County Permit) issued to the City of Santa Fe Springs (Permittee) by the Los Angeles Regional Water Quality Control Board (Regional Board) in 2012, requires the development and implementation of a program addressing storm water pollution issues in development planning for private projects.

The requirement to implement a program for development planning is based on, federal and state statutes including Section 402 (p) of the Clean Water Act, Section 6217 of Coastal Zone Act Reauthorization Amendments of 1990 ("CZARA") and the California Water Code. The Clean Water Act Amendments of 1987 established a framework of regulating storm water discharges from municipal, industrial, and construction activities under the NPDES program.

The permittee will approve the project plan as part of the development plan approval process and prior to issuing building and grading permits for the projects covered by the SUSMP requirements.

In accordance with NPDES requirements, a "Water Quality Management Plan" or "Standard Urban Storm Water Mitigation Plan" shall be prepared by a Civil or Environmental Engineer. "Best Management Practices" shall be identified and incorporated into the design.

### II. PROJECT DESCRIPTION

The project site is an 8.73-acre industrial development located on Lakeland Road in the City of Santa Fe Springs, California. The site is currently developed with four commercial/industrial buildings with footprints ranging from 4,000 to 50,000 ft <sup>2</sup>. The buildings are single-story structures of concrete tilt-up and metal frame construction, which are assumed to be supported on conventional shallow foundations with concrete slab-on-grade floors. Several parallel steel beams transect the site east-to-west which are utilized to transport manufactured metal beams. The buildings are surrounded by asphaltic concrete pavements, with sparse regions of Portland Cement concrete (PCC). The pavements throughout the site are in poor condition, with extensive cracking throughout. The ground surface cover of the northwestern parking lot consists of open graded gravel.

The proposed improvements include the construction of one warehouse building. The building will be 184,680 ft<sup>2</sup> in size and will be in the east-central area of the subject site, Dock-high doors will be constructed along a portion of the west building wall, The building will be surrounded by asphaltic concrete pavements in the parking and drive areas, Portland cement concrete pavements in the truck court areas, and limited areas of concrete flatwork and landscape planters throughout.

Currently, the site surface drains in a southwesterly direction. The westerly portion of the site flows westerly into an existing parkway drain thru the curb along Norwalk Boulevard. Similar, the westerly portion drains westerly and southerly and into an existing parkway drain thru the curb along Norwalk Boulevard.

The proposed improvements to the site will generally maintain similar drainage patterns to the existing ones. At project completion, the site will include an on-site storm drain system with multiple inlets located on the easterly and southerly side of the site, ultimately discharging into the parkway drain by the sump pump. Drainage area A-1 will be conveyed to one modular wetland system in the southwesterly corner of the site. Drainage area A-2 will be conveyed to one modular wetland system along the westerly side of the site. Drainage area A-4 will be conveyed to one modular wetland system along the westerly side of the site. Drainage area A-3 will be conveyed to three biofiltration trenches along the easterly side of the site.

Potential pollutants generated from this project include metals, oil and grease (gasoline), suspended solids (sediments), pathogens, nutrients, trash and debris. Sources of metals (total cadmium, total chromium, total copper, total lead and total zinc) in the stormwater may include vehicle paints, metal rooftops, preservatives and motor oil. Oil and grease are usually associated with leaking vehicles in driveways. There will be no fueling areas located on site. The major source of sediments is bare or poorly vegetated ground. In addition, wind and water have the potential to introduce sediments in stormwater runoff. Sources of pathogens include wild bird and animal waste, garbage, and leaky sanitary systems. Nutrients (total phosphorus) are generally associated with poor landscaping practices, leaks from sanitary systems, and animal wastes. The major source for trash and debris in stormwater is poorly managed trash containers.

To reduce pollutants from the urban runoff, various BMPs are proposed for the project. As a first line of defense, Source Control BMPs will be employed, which include: street sweeping, litter control, and catch basin inspection. To remove pollutants from the stormwater runoff, Treatment Control BMPs are implemented, which are the proposed Contech inserts and pretreatment units that filter the runoff prior to discharging into biorention systems.

### III. SITE DESCRIPTION

The street is bounded to the north by Lakeland Road, to the west by Norwalk Boulevard and an existing aerospace manufacturing facility, to the south by a parking lot and a commercial/industrial building, and to the east by Getty Drive. The general location of the site is illustrated on the Vicinity Map included in Section VI.

The site is not within or adjacent to a Significant Ecological Area (SEA). The bioretention systems have been places away from Building and existing or proposed Utility lines.

See the table provided on the site plan for a breakdown or area that shows pervious and impervious features (roof, sidewalk, pavement, and landscape).

The site drains to a concrete lined channel and is not within a channel susceptible to hydro modification.

The project site is within Region 4 of the Regional Water Quality Control Board (RWQCB) jurisdiction and within the San Gabriel River Watershed. Street runoff from the project flows easterly from the site and ultimately discharges into the San Gabriel River Reach 2, which flows south and empties into the San Pedro Bay in Seal Beach.

The 2010 Integrated Report 303(d) list identifies the following pollutants of concern in the receiving waters:

San Gabriel River Reach 2:

303(d) List Pollutants of Concern: Cyanide, Lead TMDL List: Aluminum, Chloride, Coliform Bacteria, Copper, Cyanide, Iron, Lead, Nitrogen Nitrite, Total Dissolved Solids, Zinc

To the best of our knowledge, there are no pre-existing water quality problems.

### IV. SUSMP REQUIREMENTS AND PROVISIONS

### 1. <u>Peak Storm Water Runoff Discharge Rates</u>

The project is required to attenuate peak flows to the levels allowable by the public storm drain plan.

### 2. Conserve Natural Areas

There is no significant vegetation to save.

### 3. Minimize Stormwater Pollutants of Concern

The project is designed to minimize, to the maximum extent practicable, the introduction of pollutants of concern (POCs) that may result in significant impacts, generated from site runoff. The BMPs described in Section IV are selected to minimize POCs. Particularly, Treatment Control BMPs are employed to effectively remove POCs from the project's stormwater runoff. Site runoff will drain through Contech units and into underground subsurface infiltration systems. This stormwater "treatment train" approach is an effective way to target a wider variety of pollutants while utilizing existing facilities.

4. Protect Slopes and Channels

There are no significant slopes within the project.

### 5. Provide Storm Drain System Stenciling and Signage

All catch basins within the project site will be stenciled as per City Standards to prohibit dumping of improper materials. Legibility of stencils will be maintained. A stencil detail is included in Section VI for reference. Refer to Site Plan in Section VIII for locations of catch basins with stenciling.

#### 6. Properly Design Outdoor Material Storage Areas

There will be no outdoor material storage areas.

### 7. Properly Design Trash Storage Areas

There are no trash enclosures on the project site.

#### 8. Provide Proof of Ongoing BMP Maintenance

The owner is responsible for maintenance of on-site BMPs in accordance with Section VII. A blank BMP Maintenance Form is provided on page 11. This form will be used to record implementation, maintenance, and inspection of BMPs. Records will be kept for at least five (5) years and must be made available for inspection upon request at any time.

### 9. Design Standards For Structural or Treatment Control BMPs

On-site BMPs are designed and sized to treat the BMP design flow. See Section V for BMP Flow-Based Calculations. See Attachment D for BMP Details and Specifications.

# 10. <u>Non-residential Developments (Commercial or Industrial) must comply with NPDES and/or LID as follows:</u>

Redevelopment projects, which are developments that result in creation or addition or replacement of either: (1) 5,000 square feet or more of impervious surface on a site that was previously developed; or (2) 10,000 square feet or more of impervious surface area on a site that was previously developed as a single family home.

- Where 50 percent or more of the impervious surface of a previously developed site is proposed to be altered and the previous development project was not subject to post-construction stormwater quality control measures, the entire development site (e.g. both the existing development and the proposed alteration) must meet the requirements of the LID Standards Manual.
- Where less than 50 percent of the impervious surface of a previously developed site is proposed to be altered and the previous development project was not subject to post-construction stormwater quality control measures, only the proposed alteration must meet the requirements of the LID Standards Manual.
- Redevelopment does not include routine maintenance activities that are conducted to maintain original line and grade, hydraulic capacity, original purpose of facility or emergency redevelopment activity required to protect public health and safety. Impervious surface replacement, such as the reconstruction of parking lots and roadways, which does not disturb additional area and maintains the original grade and alignment, is considered routine maintenance activity. Redevelopment does not include repaving of existing roads to maintain original line and grade.

Requirements:

- A. The 85<sup>th</sup> percentile, 24-hour rain event is equal to 0.85, which is greater than 0.75
- B. Treatment Control systems will be used.
- C. The site's demand for green roofs and harvest and reuse is not potentially feasible due to the arid climate and high demand.

DUKE REALTY will be responsible for having all inlets inspected, at a minimum of once per year and cleaned if necessary.

### 12. Street Sweeping

DUKE REALTY will be responsible for having the driveways and parking areas swept immediately prior to October 1st of each year.

#### 13. Water Conservation

Irrigation of landscaped areas is only allowed on Monday, Thursday, and Saturday and between the hours of 4:00 pm and 9:00 am. Over-watering of landscaped areas will be minimized. Hosing down of driveways, sidewalks, parking areas, patios and other paved areas are prohibited.

#### **Source Control BMPs**

### Education for Property Owners, Tenants and Occupants

Owner will provide information contained within this report to educate its employees of general good housekeeping practices that contribute to the protection of storm water quality. See all attachments.

#### Common Area Landscape Management

Owner will be responsible for ongoing landscape maintenance of the Project consistent with the County Management Guidelines for Use of Fertilizers and Pesticides (see Attachment B) and County Ordinance No. 0-97-3987, Water Management and Urban Runoff.

#### **BMP** Maintenance

Owner will be responsible for implementation of each non-structural BMP and scheduled cleaning of all structural BMP facilities. See Table 1.

#### Common Area Litter Control

Owner will implement trash management and litter control procedures aimed at reducing off-site migration of trash and pollution of drainage water. Owner may contract with landscape maintenance firms to provide this service during regularly scheduled maintenance, which should consist of litter patrol and emptying of trash receptacles.

#### Employee Training

Owner will train its employees in the methods of storm water protection and public information. This will include the use of the materials contained within this WQMP.

#### Common Area Catch Basin Inspection

Owner will be responsible for having the catch basins inspected and cleaned after major rain events and immediately prior to October 1st of each year.

#### Private Street Sweeping

Owner will be responsible for having the driveways and parking areas swept immediately prior to October 1st of each year and on a regular basis (monthly at minimum).

### Provide Storm Drain System Stenciling and Signage

Storm drain stencils are highly visible source control messages, typically placed directly adjacent to storm drain inlets. The stencils contain a brief statement that prohibits the dumping of improper materials into the storm drain system. Graphical icons, either illustrating anti-dumping symbols or images of receiving water fauna, are effective supplements to the anti-dumping message. Stencils and signs alert the public to the destination of pollutants discharged into storm water. The following requirements shall be included in the project design and shown on the project plans:

Provide stenciling or labeling of all storm drain inlets and catch basins, constructed or modified, within the project area with prohibitive language (such as: "NO DUMPING-DRAINS TO OCEAN") and /or graphical icons to discourage illegal dumping.

Post signs and prohibitive language and/or graphical icons which prohibit illegal dumping at public access points along channels and creeks within the project area.

Maintain legibility of stencils and signs.

<u>Design and Construct Trash and Waste Storage Areas to Reduce Pollution Introduction</u> The trash enclosure is designed to have drainage diverted around the area, not through the area. The trash bins will have rain tight lids installed.

#### Use Efficient Irrigation Systems and Landscape Design

The irrigation system will comply with the City and County requirements with respect to water conservation and programmable timers. The landscape areas will comply with the City approved landscape plans and maintenance will comply with the County Management Guidelines on Fertilizers and Pesticides.

### V. VOLUME AND FLOW RATE CALCULATIONS

BMP flow quantities are shown below. Calculations were performed using the LADPW HydroCalc (0.2.0-beta) program. The 85<sup>th</sup> percentile, 24-hour event produces a 0.85-inch storm event, which is greater than the 0.75-inch storm and will be used as required by the LA County LID Manual.

### **RESULTS:**

.

| SUBAREA | AREA (AC) | Q <sub>РМ85TH</sub><br>(cfs) | Q <sub>РМ85TH</sub><br>Provided | BMP<br>Provided |
|---------|-----------|------------------------------|---------------------------------|-----------------|
| A-1     | 1.736     | 0.36                         | 0.462                           | MWS-L-8-16-C    |
| A-2     | 2.766     | 0.6032                       | 0.693                           | MWS-L-8-24-V    |
| A-4     | 0.877     | 0.1983                       | 0.231                           | MWS-L-8-8-V     |

| SUBAREA | AREA (AC) | V <sub>РМ85ТН</sub><br>(cf) | V <sub>РМ85TH x 1.5</sub><br>(cf) | Surface<br>Area<br>Required | Surface<br>Area<br>Provided |
|---------|-----------|-----------------------------|-----------------------------------|-----------------------------|-----------------------------|
| A-3     | 2.833     | 6,328                       | 9,492                             | 9,492                       | 9,600                       |

NOTE: Refer to Site Plan in Section VIII for BMP locations and catchment areas.

### VI. BEST MANAGEMENT PRACTICES (BMPs)

Best Management Practices (BMPs) are intended to provide measures which minimize or eliminate the introduction of pollutants into the storm water system. Structural BMPs which are economical, practicable small scale measures to minimize pollutant runoff are to be constructed on new developments as appropriate. Non-structural BMPs include education, cleanup and facility maintenance to prevent pollutants from entering the storm water system.

### SELECTED BMPs

The following BMPs have been selected and included as applicable to this site. They shall be implemented in an on going basis throughout the life of the project.

- Contech MWS Units Proprietary Treatment Controls
- Biofiltration Trench
- Standard Catch Basin Stencil
- Storm Drain Signage (SD-13)
- Building & Grounds Maintenance (SC-41)

Details, Specifications and Fact Sheets are included in the following pages to offer guidelines and recommendations for installing, implementing and maintaining the BMPs listed above.

# Storm Drain Signage



**Design Objectives** 

Maximize Infiltration

**Provide Retention** 

Slow Runoff

Minimize Impervious Land Coverage

 Prohibit Dumping of Improper Materials

Contain Pollutants

**Collect and Convey** 

### Description

Waste materials dumped into storm drain inlets can have severe impacts on receiving and ground waters. Posting notices regarding discharge prohibitions at storm drain inlets can prevent waste dumping. Storm drain signs and stencils are highly visible source controls that are typically placed directly adjacent to storm drain inlets.

### Approach

The stencil or affixed sign contains a brief statement that prohibits dumping of improper materials into the urban runoff conveyance system. Storm drain messages have become a popular method of alerting the public about the effects of and the prohibitions against waste disposal.

### **Suitable Applications**

Stencils and signs alert the public to the destination of pollutants discharged to the storm drain. Signs are appropriate in residential, commercial, and industrial areas, as well as any other area where contributions or dumping to storm drains is likely.

### **Design Considerations**

Storm drain message markers or placards are recommended at all storm drain inlets within the boundary of a development project. The marker should be placed in clear sight facing toward anyone approaching the inlet from either side. All storm drain inlet locations should be identified on the development site map.

### **Designing New Installations**

The following methods should be considered for inclusion in the project design and show on project plans:

 Provide stenciling or labeling of all storm drain inlets and catch basins, constructed or modified, within the project area with prohibitive language. Examples include "NO DUMPING –



DRAINS TO OCEAN" and/or other graphical icons to discourage illegal dumping.

• Post signs with prohibitive language and/or graphical icons, which prohibit illegal dumping at public access points along channels and creeks within the project area.

Note - Some local agencies have approved specific signage and/or storm drain message placards for use. Consult local agency stormwater staff to determine specific requirements for placard types and methods of application.

### **Redeveloping Existing Installations**

Various jurisdictional stormwater management and mitigation plans (SUSMP, WQMP, etc.) define "redevelopment" in terms of amounts of additional impervious area, increases in gross floor area and/or exterior construction, and land disturbing activities with structural or impervious surfaces. If the project meets the definition of "redevelopment", then the requirements stated under " designing new installations" above should be included in all project design plans.

### Additional Information

### **Maintenance Considerations**

 Legibility of markers and signs should be maintained. If required by the agency with jurisdiction over the project, the owner/operator or homeowner's association should enter into a maintenance agreement with the agency or record a deed restriction upon the property title to maintain the legibility of placards or signs.

### Placement

- Signage on top of curbs tends to weather and fade.
- Signage on face of curbs tends to be worn by contact with vehicle tires and sweeper brooms.

### **Supplemental Information**

#### Examples

• Most MS4 programs have storm drain signage programs. Some MS4 programs will provide stencils, or arrange for volunteers to stencil storm drains as part of their outreach program.

#### **Other Resources**

A Manual for the Standard Urban Stormwater Mitigation Plan (SUSMP), Los Angeles County Department of Public Works, May 2002.

Model Standard Urban Storm Water Mitigation Plan (SUSMP) for San Diego County, Port of San Diego, and Cities in San Diego County, February 14, 2002.

Model Water Quality Management Plan (WQMP) for County of Orange, Orange County Flood Control District, and the Incorporated Cities of Orange County, Draft February 2003.

Ventura Countywide Technical Guidance Manual for Stormwater Quality Control Measures, July 2002.

# Building & Grounds Maintenance

SC-41



### Description

Stormwater runoff from building and grounds maintenance activities can be contaminated with toxic hydrocarbons in solvents, fertilizers and pesticides, suspended solids, heavy metals, abnormal pH, and oils and greases. Utilizing the protocols in this fact sheet will prevent or reduce the discharge of pollutants to stormwater from building and grounds maintenance activities by washing and cleaning up with as little water as possible, following good landscape management practices, preventing and cleaning up spills immediately, keeping debris from entering the storm drains, and maintaining the stormwater collection system.

### Approach

Reduce potential for pollutant discharge through source control pollution prevention and BMP implementation. Successful implementation depends on effective training of employees on applicable BMPs and general pollution prevention strategies and objectives.

### **Pollution Prevention**

- Switch to non-toxic chemicals for maintenance when possible.
- Choose cleaning agents that can be recycled.
- Encourage proper lawn management and landscaping, including use of native vegetation.

### California Stormwater Cualify Association

#### Objectives

- Cover
- Contain
- Educate
- Reduce/Minimize
- Product Substitution

### Targeted Constituents

| Sediment       | 1 |
|----------------|---|
| Nutrients      | 1 |
| Trash          |   |
| Metals         | 1 |
| Bacteria       | 1 |
| Oil and Grease |   |
| Organics       |   |
|                |   |

- Encourage use of Integrated Pest Management techniques for pest control.
- Encourage proper onsite recycling of yard trimmings.
- Recycle residual paints, solvents, lumber, and other material as much as possible.

### Suggested Protocols

### Pressure Washing of Buildings, Rooftops, and Other Large Objects

- In situations where soaps or detergents are used and the surrounding area is paved, pressure
  washers must use a water collection device that enables collection of wash water and
  associated solids. A sump pump, wet vacuum or similarly effective device must be used to
  collect the runoff and loose materials. The collected runoff and solids must be disposed of
  properly.
- If soaps or detergents are not used, and the surrounding area is paved, wash runoff does not have to be collected but must be screened. Pressure washers must use filter fabric or some other type of screen on the ground and/or in the catch basin to trap the particles in wash water runoff.
- If you are pressure washing on a grassed area (with or without soap), runoff must be dispersed as sheet flow as much as possible, rather than as a concentrated stream. The wash runoff must remain on the grass and not drain to pavement.

### Landscaping Activities

- Dispose of grass clippings, leaves, sticks, or other collected vegetation as garbage, or by composting. Do not dispose of collected vegetation into waterways or storm drainage systems.
- Use mulch or other erosion control measures on exposed soils.

### Building Repair, Remodeling, and Construction

- Do not dump any toxic substance or liquid waste on the pavement, the ground, or toward a storm drain.
- Use ground or drop cloths underneath outdoor painting, scraping, and sandblasting work, and properly dispose of collected material daily.
- Use a ground cloth or oversized tub for activities such as paint mixing and tool cleaning.
- Clean paintbrushes and tools covered with water-based paints in sinks connected to sanitary sewers or in portable containers that can be dumped into a sanitary sewer drain. Brushes and tools covered with non-water-based paints, finishes, or other materials must be cleaned in a manner that enables collection of used solvents (e.g., paint thinner, turpentine, etc.) for recycling or proper disposal.
- Use a storm drain cover, filter fabric, or similarly effective runoff control mechanism if dust, grit, wash water, or other pollutants may escape the work area and enter a catch basin. This is particularly necessary on rainy days. The containment device(s) must be in place at the beginning of the work day, and accumulated dirty runoff and solids must be collected and disposed of before removing the containment device(s) at the end of the work day.

- If you need to de-water an excavation site, you may need to filter the water before discharging to a catch basin or off-site. If directed off-site, you should direct the water through hay bales and filter fabric or use other sediment filters or traps.
- Store toxic material under cover during precipitation events and when not in use. A cover would include tarps or other temporary cover material.

### Mowing, Trimming, and Planting

- Dispose of leaves, sticks, or other collected vegetation as garbage, by composting or at a
  permitted landfill. Do not dispose of collected vegetation into waterways or storm drainage
  systems.
- Use mulch or other erosion control measures when soils are exposed.
- Place temporarily stockpiled material away from watercourses and drain inlets, and berm or cover stockpiles to prevent material releases to the storm drain system.
- Consider an alternative approach when bailing out muddy water: do not put it in the storm drain; pour over landscaped areas.
- Use hand weeding where practical.

### Fertilizer and Pesticide Management

- Follow all federal, state, and local laws and regulations governing the use, storage, and disposal of fertilizers and pesticides and training of applicators and pest control advisors.
- Use less toxic pesticides that will do the job when applicable. Avoid use of copper-based pesticides if possible.
- Do not use pesticides if rain is expected.
- Do not mix or prepare pesticides for application near storm drains.
- Use the minimum amount needed for the job.
- Calibrate fertilizer distributors to avoid excessive application.
- Employ techniques to minimize off-target application (e.g., spray drift) of pesticides, including consideration of alternative application techniques.
- Apply pesticides only when wind speeds are low.
- Fertilizers should be worked into the soil rather than dumped or broadcast onto the surface.
- Irrigate slowly to prevent runoff and then only as much as is needed.
- Clean pavement and sidewalk if fertilizer is spilled on these surfaces before applying irrigation water.
- Dispose of empty pesticide containers according to the instructions on the container label.

- Use up the pesticides. Rinse containers, and use rinse water as product. Dispose of unused pesticide as hazardous waste.
- Implement storage requirements for pesticide products with guidance from the local fire department and County Agricultural Commissioner. Provide secondary containment for pesticides.

### Inspection

Inspect irrigation system periodically to ensure that the right amount of water is being
applied and that excessive runoff is not occurring. Minimize excess watering and repair
leaks in the irrigation system as soon as they are observed.

### Training

- Educate and train employees on pesticide use and in pesticide application techniques to prevent pollution.
- Train employees and contractors in proper techniques for spill containment and cleanup.
- Be sure the frequency of training takes into account the complexity of the operations and the nature of the staff.

### Spill Response and Prevention

- Keep your Spill Prevention Control and Countermeasure (SPCC) Plan up-to-date.
- Place a stockpile of spill cleanup materials, such as brooms, dustpans, and vacuum sweepers (if desired) near the storage area where it will be readily accessible.
- Have employees trained in spill containment and cleanup present during the loading/unloading of dangerous wastes, liquid chemicals, or other materials.
- Familiarize employees with the Spill Prevention Control and Countermeasure Plan.
- Clean up spills immediately.

### Other Considerations

Alternative pest/weed controls may not be available, suitable, or effective in many cases.

### Requirements

### Costs

- Cost will vary depending on the type and size of facility.
- Overall costs should be low in comparison to other BMPs.

### Maintenance

Sweep paved areas regularly to collect loose particles. Wipe up spills with rags and other absorbent material immediately, do not hose down the area to a storm drain.

### Supplemental Information

### Further Detail of the BMP

### Fire Sprinkler Line Flushing

Building fire sprinkler line flushing may be a source of non-stormwater runoff pollution. The water entering the system is usually potable water, though in some areas it may be non-potable reclaimed wastewater. There are subsequent factors that may drastically reduce the quality of the water in such systems. Black iron pipe is usually used since it is cheaper than potable piping, but it is subject to rusting and results in lower quality water. Initially, the black iron pipe has an oil coating to protect it from rusting between manufacture and installation; this will contaminate the water from the first flush but not from subsequent flushes. Nitrates, polyphosphates and other corrosion inhibitors, as well as fire suppressants and antifreeze may be added to the sprinkler water system. Water generally remains in the sprinkler system a long time (typically a year) and between flushes may accumulate iron, manganese, lead, copper, nickel, and zinc. The water generally becomes anoxic and contains living and dead bacteria and breakdown products from chlorination. This may result in a significant BOD problem and the water often smells. Consequently dispose fire sprinkler line flush water into the sanitary sewer. Do not allow discharge to storm drain or infiltration due to potential high levels of pollutants in fire sprinkler line water.

### **References and Resources**

California's Nonpoint Source Program Plan <u>http://www.swrcb.ca.gov/nps/index.html</u>

Clark County Storm Water Pollution Control Manual <u>http://www.co.clark.wa.us/pubworks/bmpman.pdf</u>

King County Storm Water Pollution Control Manual http://dnr.metrokc.gov/wlr/dss/spcm.htm

Mobile Cleaners Pilot Program: Final Report. 1997. Bay Area Stormwater Management Agencies Association (BASMAA). <u>http://www.basmaa.org/</u>

Pollution from Surface Cleaning Folder. 1996. Bay Area Stormwater Management Agencies Association (BASMAA). <u>http://www.basmaa.org/</u>

Santa Clara Valley Urban Runoff Pollution Prevention Program http://www.scvurppp.org

The Storm Water Managers Resource Center <u>http://www.stormwatercenter.net/</u>

### VII. OPERATION AND MAINTENANCE GUIDELINES

### **Designated Responsible Party:**

DUKE REALTY or its successors will be responsible for ongoing maintenance of the BMPs listed below.

### **Biofiltration Facility:**

Periodic and inspection, repair damaged areas as needed, mowing, and plants to be tolerant of summer drought. See Planting/Storage Media above for clogging replacement and recommendations. Inspect/replace overflow device and underdrain when potential failure signs surface.

### **Contech Catch Basin Filter Insert:**

Catch basin inserts should be inspected at regular intervals and maintained when necessary to ensure optimum performance. Remove and clean grates, remove litter and debris, and repair as needed.

### **Employees Training Program:**

Maintenance Guidelines are included in the Attachments (Section IX) and will be provided to BMP maintenance personnel at the time of hiring.

### Recordkeeping

Inspection and Maintenance logs are provided in the following pages. A blank BMP Maintenance Form is provided following the Inspection and Maintenance logs for recording implementation, maintenance, and inspection of additional BMPs. Records will be kept for at least five (5) years and must be made available for inspection upon request at any time.

#### **Transfer of Responsibility**

By signing the Maintenance Covenant for SUSMP Requirements (hereinafter referred to as "covenant"), DUKE REALTY, agrees that the maintenance responsibilities outlined in the Operation and Maintenance Guidelines will be transferred to future property owners. At the time of transfer, the new property owner will sign the covenant and provide a copy of the recorded covenant to DUKE REALTY Department of Public Works.

Water Quality Management Plan for Lakeland Industrial 12300 Lakeland Drive

Santa Fe Springs, CA 90670

| BMP<br>Applicable?<br>Yes/No | BMP Name and BMP Implementation,<br>Maintenance and Inspection Procedures  | Implementation, Maintenance, and Inspection<br>Frequency and Schedule  | Person or Entity with Operation &<br>Maintenance Responsibility                        |
|------------------------------|--|--|--|
|                              | Non-Structur   | al Source Control BMPs   |  |
| Y                            | Education for Property Owners, Tenants and Occupants<br>Practical information materials will be provided to the first<br>residents/occupants/tenants on general housekeeping<br>practices that contribute to the protection of stormwater<br>quality. These materials will be initially developed and<br>provided to first residents/occupants/tenants by the<br>developer. Thereafter such materials will be available<br><b>through the Permittees' education program. Different</b><br>materials for residential, office commercial, retail commercial,<br>vehicle-related commercial and industrial uses will be<br>developed. | Provide education information to new owners,<br>Tenants and occupants as needed  | DUKE REALTY  |
| Ν                            | Activity Restrictions  |  |  |
| Y                            | Common Area Landscape Management<br>Identify on-going landscape maintenance requirements that<br>are consistent with those in the County Water Conservation<br>Resolution (or city equivalent) that include fertilizer and/or<br>pesticide usage consistent with Management Guidelines for<br>Use of Fertilizers. Statements regarding the specific<br>applicable guidelines must be included.   | Manage landscaping in accordance with County of<br>Orange Water Conservation Ordinance No. 3802<br>and with Management Guidelines for Use of<br>Fertilizers and Pesticides | Construction Superintendent during construction; DUKE REALTY during post-construction. |
| Y                            | BMP Maintenance<br>The Project WQMP shall identify responsibility for<br>implementation of each non-structural BMP and scheduled<br>cleaning and/or maintenance of all structural BMP facilities.  | See. BMP table.  | DUKE REALTY  |
| Ν                            | Title 22 CCR Compliance  |  |  |
| N                            | Local Water Quality Permit Compliance  |  |  |

| BMP<br>Applicable?<br>Yes/No | BMP Name and BMP Implementation,<br>Maintenance and Inspection Procedures  | Implementation, Maintenance, and Inspection<br>Frequency and Schedule   | Person or Entity with Operation &<br>Maintenance Responsibility                              |
|------------------------------|--|---|--|
| Ν                            | Spill Contingency Plan   |   |  |
| Ν                            | Underground Storage Tank Compliance  |   |  |
| Ν                            | Hazardous Materials Disclosure Compliance  |   |  |
| Ν                            | Uniform Fire Code Implementation   |   |  |
| Y                            | Common Area Litter Control<br>For industrial/commercial developments, the owner should be<br>required to implement trash management and litter control<br>procedures in the common areas aimed at reducing pollution<br>of drainage water. The owner may contract with their<br>landscape maintenance firms to provide this service during<br>regularly scheduled maintenance, which should consist of<br>litter patrol, emptying of trash receptacles in common areas,<br>and noting trash disposal violations by tenants or businesses<br>and reporting the violations to the owner for investigation. | Litter Maintenance. Daily.  | Construction Superintendent during<br>construction; DUKE REALTY during<br>post-construction. |
| Y                            | Employee Training<br>Education program (see N1) as it would apply to future<br>employees of individual businesses. Developer either<br>prepares manuals for initial purchasers of business site or for<br>development that is constructed for an unspecified use<br>makes commitment of future business owner to prepare. An<br>example would be training on the proper storage and use of<br>fertilizers and pesticides, or training on the implementation of<br>hazardous spill contingency plans.   | Include the education materials contained in the<br>approved Water Quality Management Plan.<br>Monthly for construction maintenance personnel<br>and employees. | DUKE REALTY  |
| Ν                            | Housekeeping of Loading Docks  |   |  |

| BMP<br>Applicable?<br>Yes/No | BMP Name and BMP Implementation,<br>Maintenance and Inspection Procedures  | Implementation, Maintenance, and Inspection<br>Frequency and Schedule   | Person or Entity with Operation &<br>Maintenance Responsibility |
|------------------------------|--|---|---|
| Y                            | Common Area Catch Basin Inspection<br>For industrial/commercial developments and for<br>developments with privately maintained drainage systems,<br>the owner is required to have at least 80 percent of drainage<br>facilities inspected, cleaned and maintained on an annual<br>basis with 100 percent of the facilities included in a two-year<br>period. Cleaning should take place in the late summer/early<br>fall prior to the start of the rainy season. Drainage facilities<br>include catch basins, open drainage channels and lift<br>stations. Records should be kept to document the annual<br>maintenance. | Catch Basins will be inspected and cleaned after<br>major rain events and immediately prior to the start<br>of the rainy season on October 1st. | DUKE REALTY   |
| Y                            | Street Sweeping Private Streets and Parking Lots<br>Streets and parking lots are required to be swept prior to the<br>storm season, in late summer or early fall, prior to the start of<br>the rainy season or equivalent as required by the governing<br>jurisdiction.  | Parking lot will be swept monthly at a minimum and<br>immediately prior to the start of the rainy season on<br>October 1st.                     | DUKE REALTY   |
|                              |  |   |   |

| BMP<br>Applicable?<br>Yes/No | BMP Name and BMP Implementation,<br>Maintenance and Inspection Procedures  | Implementation, Maintenance, and Inspection<br>Frequency and Schedule | Person or Entity with Operation &<br>Maintenance Responsibility |
|------------------------------|--|---|---|
|                              | Structural   | Source Control BMPs   |   |
| Y                            | <ul> <li>Provide Storm Drain System Stenciling and Signage</li> <li>Storm drain stencils are highly visible source control messages, typically placed directly adjacent to storm drain inlets. The stencils contain a brief statement that prohibits the dumping of improper materials into the municipal storm drain system. Graphical icons, either illustrating anti-dumping symbols or images of receiving water fauna, are effective supplements to the anti-dumping message. Stencils and signs alert the public to the destination of pollutants discharged into stormwater. The following requirements should be included in the project design and shown on the project plans:</li> <li>Provide stenciling or labeling of all storm drain inlets and catch basins, constructed or modified, within the project area with prohibitive language (such as: "NO DUMPING – DRAINS TO OCEAN") and/or graphical icons to discourage illegal dumping.</li> <li>Post signs and prohibitive language and/or graphical icons, which prohibit illegal dumping at public access points along channels and creeks within the project area.</li> <li>Maintain legibility of stencils and signs.</li> </ul> | Repaint as necessary but at minimum once every five years. Annually   | DUKE REALTY   |
| Ν                            | Design Outdoor Hazardous Material Storage Areas to Reduce Pollutant Introduction   |   |   |

| BMP<br>Applicable?<br>Yes/No | BMP Name and BMP Implementation,<br>Maintenance and Inspection Procedures  | Implementation, Maintenance, and Inspection<br>Frequency and Schedule   | Person or Entity with Operation &<br>Maintenance Responsibility                              |
|------------------------------|--|---|--|
| Y                            | <ul> <li>Design Trash Enclosures to Reduce Pollutant<br/>Introduction</li> <li>Design trash storage areas to reduce pollutant introduction.</li> <li>All trash container areas shall meet the following<br/>requirements: <ol> <li>Paved with an impervious surface, designed not to<br/>allow run-on from adjoining areas, designed to divert<br/>drainage from adjoining roofs and pavements<br/>diverted around the area, screened or walled to<br/>prevent off-site transport of trash; and</li> <li>Provide solid roof or awning to prevent direct<br/>precipitation.</li> </ol> </li> <li>Connection of trash area drains to the municipal storm drain<br/>system is prohibited.</li> <li>Potential conflicts with fire code and garbage hauling<br/>activities should be considered in implementing this source<br/>control.</li> </ul> | Clean trash container area to prevent buildup of<br>excess trash in area. Daily   | Construction Superintendent during<br>construction; DUKE REALTY during<br>post-construction. |
| Υ                            | <ul> <li>Use Efficient Irrigation Systems and Landscape Design</li> <li>Projects shall design the timing and application methods of irrigation water to minimize the runoff of excess irrigation water into the municipal storm drain system. The following methods to reduce excessive irrigation runoff shall be considered, and incorporated on common areas of development and other areas where determined applicable and feasible by the Permittee:</li> <li>1. Employing rain shutoff devices to prevent irrigation after precipitation.</li> <li>2. Designing irrigation systems to each landscape area's specific water requirements.</li> </ul>  | Verify that runoff minimizing landscape design<br>continues to function by checking that water<br>sensors are functioning properly, that irrigation<br>heads are adjusted properly to eliminate overspray<br>to hardscape areas, and to verify that irrigation<br>timing and cycle lengths are adjusted in<br>accordance with water demands, given time of<br>year, weather and day or night time temperatures.<br>Verify that plants continue to be grouped according<br>to similar water requirements in order to reduce<br>excess irrigation runoff. Once a week, in<br>conjunction with maintenance activities. | DUKE REALTY  |

| BMP<br>Applicable?<br>Yes/No | BMP Name and BMP Implementation,<br>Maintenance and Inspection Procedures   | Implementation, Maintenance, and Inspection<br>Frequency and Schedule | Person or Entity with Operation &<br>Maintenance Responsibility |
|------------------------------|---|---|---|
|                              | Use Efficient Irrigation Systems and Landscape Design   |   |   |
|                              | <ol> <li>Using flow reducers or shutoff valves triggered by a pressure drop to control water loss in the event of broken sprinkler heads or lines.</li> <li>Implementing landscape plan consistent with County Water Conservation Resolution or city equivalent, which may include provision of water sensors, programmable irrigation times (for short</li> </ol>    |   |   |
|                              | <ol> <li>5. The timing and application methods of irrigation water shall be designed to minimize the runoff of excess irrigation water into the municipal storm drain system.</li> </ol>  |   |   |
|                              | <ol> <li>Employing other comparable, equally effective,<br/>methods to reduce irrigation water runoff.</li> <li>Group plants with similar water requirements in<br/>order to reduce excess irrigation runoff and promote<br/>surface filtration. Choose plants with low irrigation<br/>requirements. Consider other design features, such<br/>as:</li> </ol>          |   |   |
|                              | <ul> <li>Use mulches (such as wood chips or shredded wood products) in planter areas without ground cover to minimize sediment in runoff.</li> <li>Install appropriate plant materials for the location, in accordance with amount of sunlight and climate, and use native plant material where possible and/or as recommended by the landscape architect.</li> </ul> |   |   |

| BMP<br>Applicable?<br>Yes/No | BMP Name and BMP Implementation,<br>Maintenance and Inspection Procedures  | Implementation, Maintenance, and Inspection<br>Frequency and Schedule | Person or Entity with Operation &<br>Maintenance Responsibility |
|------------------------------|--|---|---|
|                              | <ul> <li>Leave a vegetative barrier along the property<br/>boundary and interior watercourses, to act as a<br/>pollutant filter, where appropriate and feasible.</li> <li>Choose plants that minimize or eliminate the<br/>use of fertilizer or pesticides to sustain growth.</li> </ul> |   |   |
| Ν                            | Protect Slopes and Channels  |   |   |
| Ν                            | Loading Dock Areas   |   |   |
| Ν                            | Maintenance Bays and Docks   |   |   |
| Ν                            | Vehicle Wash Areas   |   |   |
| Ν                            | Outdoor Processing Areas   |   |   |
| Ν                            | Equipment Wash Areas   |   |   |
| Ν                            | Fueling Areas  |   |   |
| N                            | Site Design and Landscape Planning   |   |   |
| N                            | Wash Water Controls for Food Preparation Areas   |   |   |
| N                            | Community Car Wash Racks   |   |   |

| BMP Name and BMP Implementation,<br>Maintenance and Inspection Procedures                         | Implementation, Maintenance, and Inspection<br>Frequency and Schedule  | Person or Entity with Operation &<br>Maintenance Responsibility |  |  |  |
|---|--|---|--|--|--|
| Low Impact Development BMPs   |  |   |  |  |  |
| Hydrologic Source Control BMP # 1   |  |   |  |  |  |
| Hydrologic Source Control BMP # 2   |  |   |  |  |  |
| Miscellaneous BMP # 1<br>Sump Pump<br>Zoeler Model #M295 230V-2H.P17.1 Amp Single- Automatic Pump | Record flow rate, amperage, smoothness of<br>operation, check for leaks monthly. Check seal fail<br>circuit and motor bearings, megger the motor<br>windings and record megohm values every 6<br>months.<br>Record flow rate, amperage, smoothness of<br>operation, check for leaks monthly. Check seal fail<br>circuit and motor bearings, megger the motor<br>windings and record megohm values every 6<br>months. | DUKE REALTY   |  |  |  |
| Infiltration BMP # 1  |  |   |  |  |  |
| Infiltration BMP # 2  |  |   |  |  |  |
|   |  |   |  |  |  |
| Harvest and use BMP # 1   |  |   |  |  |  |
| Harvest and use BMP # 2   |  |   |  |  |  |

| BMP Name and BMP Implementation,<br>Maintenance and Inspection Procedures | Implementation, Maintenance, and Inspection<br>Frequency and Schedule  | Person or Entity with Operation &<br>Maintenance Responsibility |  |  |
|---|--|---|--|--|
| Biotreatment BMP # 1<br>Biofiltration Trench                              | Periodic and inspection, repair damaged<br>areas as needed, mowing, and plants to be<br>tolerant of summer drought. See<br>Planting/Storage Media above for<br>clogging replacement and<br>recommendations. Inspect/replace<br>overflow device and underdrain when<br>potential failure signs surface. | Maintenance Responsibility<br>DUKE REALTY                       |  |  |
| Biotreatment BMP # 2<br>MWS-L-8-16-C, MWS-L-8-24-V & MWS-L-8-8-V          | Periodic and inspection, repair damaged<br>areas as needed, mowing, and plants to be<br>tolerant of summer drought. See<br>Planting/Storage Media above for<br>clogging replacement and<br>recommendations. Inspect/replace<br>overflow device and underdrain when<br>potential failure signs surface. | DUKE REALTY   |  |  |
| Treatment Control BMPs  |  |   |  |  |
| Treatment Control BMP #1  |  |   |  |  |
| Pre-Treatment/Gross Solids Removal BMPs                                   |  |   |  |  |
| Pre-Treatment BMP # 1   |  |   |  |  |
|   |  |   |  |  |

### **Required Permits**

No permits are required for the implementation, operation, and maintenance of the BMPs. If no permits are required, a statement to that effect should be made.

### **Responsible Party**

The owner is aware of the maintenance responsibilities of the proposed BMPs. A funding mechanism is in place to maintain the BMPs at the frequency stated in the LID Plan. The contact information for the entity responsible is below:

| Name:         | DJ Arellano<br>DUKE REALTY            |  |  |
|---------------|---------------------------------------|--|--|
| Company:      |                                       |  |  |
| Title:        |                                       |  |  |
| Address 1:    | 200 Spectrum Center Drive, Suite 1600 |  |  |
| Address 2:    | Irvine, CA 92618                      |  |  |
| Phone Number: |                                       |  |  |
| Email:        | DJ.Arellano@DUKEREALTY.com            |  |  |

### Forms to Record BMP Implementation, Maintenance, and Inspection

The form that will be used to record implementation, maintenance, and inspection of BMPs is attached.

### **Recordkeeping**

All records must be maintained for at least five (5) years and must be made available for review upon request.

### **RECORD OF BMP IMPLEMENTATION, MAINTENANCE, AND INSPECTION**

Today's Date:

Name of Person Performing Activity (Printed):

Signature:

| BMP Name<br>(As Shown in O&M Plan) | Brief Description of Implementation, Maintenance, and<br>Inspection Activity Performed |
|------------------------------------|--|
|                                    |  |
|                                    |  |
|                                    |  |
|                                    |  |
|                                    |  |
|                                    |  |
|                                    |  |
|                                    |  |
|                                    |  |

### **BMP IMPLEMENTATION MAINTENANCE FORM**

Today's Date:


Name of Person Performing Activity (Printed):


Signature: \_\_\_\_\_

| BMP Name | Brief Description of Implementation, Maintenance, and<br>Inspection Activity Performed |
|----------|--|
|          |  |
|          |  |
|          |  |
|          |  |
|          |  |
|          |  |
|          |  |
|          |  |
|          |  |
|          |  |

## **SECTION VIII**

VICINITY MAP SITE PLAN





| DMA | AREA<br>AC | IMP.<br>AC | PERV.<br>AC |
|-----|------------|------------|-------------|
| A-1 | 1.736      | 1.656      | 0.08        |
| A-2 | 2.766      | 2.74       | 0.026       |
| A-3 | 2.833      | 2.033      | 0.80        |
| A-4 | 0.877      | 0.757      | 0.12        |

| LEGEND:                                  |  |  |  |  |
|--|--|--|--|--|
| SURFACE DRAINAGE F                       |  |  |  |  |
| DENOTES DRAINAGE 1<br>DRAINAGE AREA BOUN |  |  |  |  |
| PERVIOUS AREA                            |  |  |  |  |
| DENOTES DRAINAGE /<br>DENOTES DRAINAGE / |  |  |  |  |
| BIORETENTION FACILIT                     |  |  |  |  |
| MODULAR WETLAND E                        |  |  |  |  |
| SUMP PUMP                                |  |  |  |  |
|  |  |  |  |  |

| BMP | Qreq<br>CFS | Qbmp<br>CFS | MODEL<br>MWS | GPS<br>LAT, LONG       |
|-----|-------------|-------------|--------------|------------------------|
| A-1 | 0.36        | 0.462       | MWS-L-8-16-C | 33.930427, -118.071663 |
| A-2 | 0.6032      | 0.693       | MWS-L-8-24-V | 33.931226, -118.071722 |
| A-4 | 0.1983      | 0.231       | MWS-L-8-8-V  | 33.931223, -118.072517 |

| BMP | Vreq<br>CF | Areq<br>SF | Aprovided<br>SF | GPS<br>LAT, LON   |
|-----|------------|------------|-----------------|-------------------|
| A-3 | 6,328      | 9,492      | 9,600           | 33.931528, -118.0 |

CIVIL ENGINEERS LAND SURVEYORS PLANNERS 2552 WHITE ROAD, SUITE B, IRVINE, CA 92614 (949) 660-0110 FAX: 660-0418

LOW IMPACT DEVELOPMENT PLAN FOR 12300 Lakeland Drive


AINAGE PATTERN RAINAGE TRIBUTARY AREA BOUNDARY REA BOUNDARY


RAINAGE AREA DESIGNATION RAINAGE AREA IN ACRES


ON FACILITY (1.0' PONDING DEPTH) ETLAND BIOFILTRATION (SIZE HEREON)

8.072517

١G .070596







## **SECTION IX**

### **ATTACHMENTS**

## ATTACHMENT A

## **EPA: WHEN IT RAINS IT DRAINS**

United States Environmental Protection Agency August 1993 832-F-93-002 WH-547


#### Office of Water

EPA When It Rains, It Drains What Everyone Should Know About Storm Water

EEE 100 000

## WHAT IS STORM WATER?

Storm water is water from precipitation that flows across the ground and pavement when it rains or when snow and ice melt. The water seeps into the ground or drains into what we call storm sewers. These are the drains you see at street corners or at low points on the sides of your streets. Collectively, the draining water is called storm water runoff and is a concern to us in commercial and industrial sites as well as your neighborhood because of the pollutants it carries.



Debris along street picked up by storm water.


#### WHY IS STORM WATER A PROBLEM?

Storm water is a problem when it picks up debris, chemicals, and other pollutants as it flows or when it causes flooding and erosion of stream banks. The pollutants are deposited untreated into our waterways. The result can be the closing of our beaches; no swimming, fishing or boating; and injury to the plants and animals that live in or use the water.


#### WHAT ARE THESE POLLUTANTS? WHERE DO THEY COME FROM ? WHAT ARE SOME OF THEIR EFFECTS ON PLANTS, ANIMALS, AND HUMANS ?

The following information will answer these questions and let you know what you and your community can do to help recognize where there could be a problem and what to do to help solve it !


EPA has a storm water program that, with your help, can keep our rivers, lakes, streams, and oceans open to use and enjoyment, and healthy for plants and animals to live in.



Storm water that does not seep into the ground, drains into systems of underground pipes or roadside ditches and may travel for many miles before being released into a lake, river, stream, wetland area, or coastal waters.




Debris washed up on the beach by storm water.




# COMMON CONTRIBUTORS TO




**INDUSTRY** – At industrial sites, chemical spills that contain tox ic substances, smoke stacks that spew emissions, and uncovered or unprotected outdoor storage or waste areas can contribute pollutants to storm water runoff.



AGRICULTURE – Pesticides, fertilizers, and herbicides used in crop production can be toxic to aquatic life and can contribute to over-enrichment of the water, causing excess algae growth and oxygen depletion. Although storm water runoff from agricultural areas is not regulated under the EPA storm water permitting program, it is a nonpoint source of storm water pollution covered under other EPA programs.



**CONSTRUCTION** – Waste from chemicals and materials used in construction can wash into our waterways during wet weather. Soil that erodes from construction sites can contribute to environmental degradation as well.




WHAT ARE SOME OF THEIR EFFECTS ON PLANTS, ANIMALS, AND HUMANS?


When polluted storm water runoff reaches our waterways, it can have many adverse effects on aquatic plant and animal life, other wildlife that use the water, humans who drink the water, use it for plants to survive.

fishing, boating, swimming and other recreational activities, and on humans and animals who cat the contaminated fish and other seafood.

# STORM WATER POLLUTION



HOUSEHOLD – Vehicles drip fluids (oil, grease, gasoline, antifreeze, brake fluids, etc.) onto paved areas where storm water runoff carries them through our storm drains and into our waterways.




**HOUSEHOLD** – Pet wastes left on the ground get carried away by storm water, contributing harmful bacteria, parasites and viruses to our waterways.



HOUSEHOLD – Chemicals used to grow and maintain beautiful lawns and gardens, if not used properly, can run off into the storm drains when it rains or when we water our lawns and gardens.

OTHER COMMON HOUSEHOLD PRODUCTS THAT COULD CAUSE POLLUTION IF CARRIED OFF BY STORM WATER RUNOFF OR DUMPED DOWN STORM SEWERS:

- · Ammonia-based cleaners, drain cleaners
- Car care products such as detergents with phosphate and car waxes
- Paint, paint thinners, varnish, furniture refinishing products, paint brush cleaners
- Concrete or wood sealants
- Degreasers
- Chlorine bleaches and disinfectants (for swimming pools, etc.)




## MUNICIPAL PROGRAM

Here are some of the most important steps your community can take to control storm water pollution:



Prevent the release into the storm sewer system of hazardous substances such as used oil or household or yard chemicals



Make sure new commercial and residential developments include storm water management controls, such as reducing areas of paved surfaces to allow storm water to seep into the ground.



Promote practices such as street sweeping, limiting use of road salt, picking up litter, and disposing of leaves and yard wastes quickly.



Collect samples of storm water from industrial sites to see whether pollutants are being released. If so, identify the type and quantity of pollutants being released.



Design and institute flood control projects in a way that does not impair water quality.



Prevent runoff of excess pesticides, fertilizers, and herbicides by using them properly and efficiently. (Commercial, institutional, and residential landscapes can be designed to prevent pollution, conserve water, and look beautiful at the same time.)




Make sure that construction sites control the amount of soil that is washed off by rain into waterways.



Promote citizen participation and public group activity to increase awareness and education at all levels. Encourage local collection pick-up days and recycling of household hazardous waste materials to prevent their disposal into storm drains.

## MUNICIPAL SUCCESS STORY

A northwest city, recognizing the need for storm water management, set up a special water utility to oversee all local government storm water control activities and to raise the money for storm water projects. The city collects fees from citizens using the storm water sewer system and uses the funds to implement storm water programs. The program is still successfully providing funds for such varied purposes as flood control, maintenance of existing storm water controls, and public education. We can agree that the best way to protect water quality is to avoid polluting it in the first place. EPA has a National Storm Water Permit Program that focuses on municipal and industrial pollution prevention to help control storm water pollution. This program involves issuing permits to certain municipalities and industries to control storm water pollution. Development' of State and local storm water management programs can help to achieve the Clean Water Act goals of fishable and swimmable waters.



Permits issued for municipal storm water systems allow communities to design storm water

NICIPAL PROGRAM

community interest and participation in solving storm water runoff problems.

#### INDUSTRIAL PROGRAM

Most permits issued under the storm water program require development and use of a storm water pollution prevention plan. Such plans describe how the facility will prevent storm water from becoming polluted by making sure that:

- Potential pollutants are not left outside uncovered
- Spills are prevented
- If spills occur, they are cleaned up right away
- There is no dumping of polluting substances into storm drains
- Grass and other vegetation is planted as quickly as possible after soils are disturbed

Some permits may require more extensive pollution control.

## INDUSTRIAL PROGRAM

Storm water permits require many industrial facilities to prepare and implement storm water pollution prevention plans. Listed below are examples of industries and their pollution prevention activities.

Owners of construction sites that disturb 5 or more acres must develop a plan before beginning construction. The plan must limit the area of disturbed soil and provide controls — like sediment basins — to keep sediment from running off.




Operators of saw mills can reduce pollution by storing their materials and processing their products indoors; and removing any by-products from outdoor areas before these products come in contact with storm water runoff.

Operators of landfills should keep the storm water runoff from flowing over the pollutants and carrying them off the landfill site.

Airport employees can reduce storm water runoff pollution by using de-icing chemicals only in designated collection areas and by cleaning oil and grease spills from pavement immediately.

Chemical plant operators should develop spill prevention plans and use types of containers that do not rust or leak, eliminating exposure of materials to storm water runoff.












Operators of trucking terminals should develop good housekeeping practices that clean up leaks and spills of oil and grease from the path of storm water runoff.

Power plant operators often store piles of coal and other fuels that have toxic components. Runoff from coal piles must be treated; other substances should be stored away from any possible contact with storm water runoff.



#### INDUSTRIAL SUCCESS STORY

A manufacturing facility located in a large midwestern city took an innovative approach to storm water management. Employees at a plant with a large fueling station noticed that during a rain storm, the runoff flowing into the city's storm sewer system had an oily sheen, caused by spilled fuel. To prevent future spills, the plant trained its drivers to avoid overfilling fuel tanks, laid down sawdust around the fueling station to absorb any accidental spills (the plant is careful not to wash the sawdust down the drain), and installed an oil/water separator to remove oil from the runoff before the runoff enters the storm drain.



## WHAT CAN I DO TO HELP ?

First, become more aware of what may be causing storm water pollution in your area.

Second, help your municipality by:

- 1. Reporting to your local municipal officials -
  - Any dumping of inappropriate materials into storm water drains (such as oil, antifreeze).
  - Construction sites over 5 acres that do not have erosion or sediment controls.
- 2. Using good housekeeping practices with lawn care chemicals, oil, gasoline, pet wastes, etc.
- 3. Helping to start or participating in programs to recycle and safely dispose of used oil and household hazardous wastes and containers.
- 4. Telling others about pollution from storm water runoff and what they can do to help.

## WHERE CAN I FIND OUT MORE INFORMATION?

#### Your EPA Regional Office (Water Management Division)

- 1. EPA Region I (CT, ME, MA, NH, RI, VT) JFK Federal Bldg.; Boston, MA 02203 617-565-3478
- EPA Region II (NJ, NY, PR, VI)
   26 Federal Plaza; New York, NY 10278
   212-264-2513
- EPA Region III (DE, MD, PA, VA, WV, DC) 841 Chestnut Street; Philadelphia, PA 19107 215-597-9410
- 4. EPA Region IV (AL, GA, FL, MS, NC, SC, TN, KY) 345 Courtland St., NE; Atlanta, GA 30365 404-347-4450
- EPA Region V (IL, IN, OH, MI, MN, WI) 77 W. Jackson Blvd.; Chicago, IL 60604 312-353-2145
- 6. EPA Region VI (AR, LA, OK, TX, NM) 1445 Ross Ave., Suite 1200 Dallas, TX 75202-2733 214-655-7100
- EPA Region VII (IA, KS, MO, NE) 726 Minnesota Ave.; Kansas City, KS 66101 913-551-7030
- EPA Region VIII (CO, UT, WY, MT, ND, SD) 999 18th St., Suite 500; Denver, CO 80202 303-293-1542
- EPA Region IX (AZ, CA, GM, HI, NV) 75 Hawthorne Street; San Francisco, CA 94105 415-744-2125
- 10. EPA Region X (AK, ID, OR, WA) 1200 Sixth Ave.; Seattle, WA 98101 206-553-1793

#### Other sources include:

- Storm Water Hotline (703) 821-4823
- State and Local Agencies



Recycled/Recyclable Printed with Soy/Canola Ink on paper that contains at least 50% recycled fiber

## ATTACHMENT B

## EPA: PREVENTING POLLUTION THROUGH EFFICIENT WATER USE

United States 20W-0002 Environmental Protection Reprinted Agency

OW (4204)

April 1997

OPPE (2164)


## Preventing €EPA Pollution Through Efficient Water Use



For more information on what you and your community can do to use water more efficiently, contact:

**U.S. Environmental Protection Agency Office of Water** 401 M Street, S.W. Washington, D.C. 20460





**U.S. Environmental Protection Agency Office of Pollution Prevention** 401 M Street, S.W. Washington, D.C. 20460



**How Efficient Water Use Helps Prevent Pollution** 



Other Reasons to Use Water Wisely



What Individuals Can Do



What Communities Can Do



## **How Efficient Water Use Helps Prevent Pollution**

Using water more efficiently can help prevent pollution as well as protect and conserve our finite water resources. More efficient water use by you and your community has many other benefits.

#### **Fewer Pollutants**

- Using less water reduces the amount of wastewater discharged into our lakes, streams, rivers, and marine waters.
- The amount of pollutants wastewater carries can also be reduced, as treatment efficiency improves.
- Recycled process water can reduce pollutants from industry.
- More efficient irrigation can minimize runoff of agricultural pollutants and reduce the use of fertilizers and pesticides.

#### **Protection of Aquatic Habitats**

- Building fewer and smaller new water projects can help preserve wetlands, which naturally treat pollutants.
- Diverting less water preserves more streamflow to maintain a healthy aquatic environment.

#### **Protection of Drinking Water Sources**

- Less pumping of groundwater lowers the chance that pollutants will be drawn into a water supply well.
- With less water use, septic system performance can improve, reducing the risk of groundwater contamination.
- Highest quality water sources are preserved for drinking water by using treated wastewater for other uses.

#### **Energy Conservation**

- Efficient water use means less power needed to pump and treat water and wastewater.
- Less water use reduces the amount of energy required for heating hot water.
- Less energy demand results in fewer harmful byproducts from power plants.



## Other Reasons to Use Water Wisely

Preventing pollution is only one reason why using water efficiently makes sense. Here are a few more:

#### **Money Saved**

- Less water use results in fewer pumping and treatment costs.
- Saving money on water and wastewater operations frees money for meeting water quality, public health and water treatment goals.
- Water saved is also energy, and money, saved for you and your community.

#### **Improved Reliability**

- Water conservation provides a hedge against drought impacts.
- Improving water efficiency may be quicker and cheaper than developing a new supply.
- Reduced water use may extend the life of your water or wastewater facility.
- Reduced water use may increase the efficiency of wastewater treatment, and reduce overflows during storms.
- Communities which use water efficiently are better prepared to cope with effects of possible future climate change.



## What Individuals Can Do

More efficient water use begins with individuals, in the home and place of work. Taking these and other steps, and encouraging others to do so, makes good" economic as well as environmental sense.

#### In The Home

- Install a toilet dam or plastic bottle in your toilet tank.
- Install a water-efficient showerhead (2.5 gallons or less per minute).
- When you buy a new toilet, purchase a low flow model (1.6 gallons or less per flush).

#### Outdoors

- Water in the morning or evening, to minimize evaporation.
- Install a drip-irrigation watering system for valuable plants.
- Use drought-tolerant plants and grasses for landscaping, and reduce grass-covered areas.

#### At Work or School

- Adopt the same water-saving habits that are effective at home.
- Ask about installing water-efficient equipment and reducing outdoor water use.
- Encourage employers to explore the use of recycled "gray-water" or reclaimed wastewater.



#### What Communities Can Do

A water supplier or wastewater system operator (public or private) has cost-effective options to process and deliver water more efficiently. A community can do the same, and can foster ways to use water wisely.

Not all of these steps are expensive. The best choices vary by region and by community; start by asking if these are appropriate where you live and work.

#### A Water Supplier or Wastewater Processor Can:

- Identify who uses water, and reduce unaccounted-for water use.
- Find and repair leaking pipes.
- Consider a new pricing scheme which encourages conservation.
- Reduce excess pressure in water lines.
- Explore the reuse of treated wastewater for uses other than drinking water.
- Charge hookup fees which encourage more efficient water use in new buildings.
- Build water efficiency into future demand projections, facility planning, and drought planning.

#### A Community Can:

- Adopt plumbing and building codes that require water-efficient equipment and practices.
- Adopt a water-efficient landscaping ordinance to reduce the water used for golf courses and commercial landscapes.
- Retrofit older buildings with water-efficient equipment, starting with public buildings.
- Reduce municipal water use for landscaping and other uses.
- Conduct a public education campaign.
- Require developers to build in water efficiency measures.

## ATTACHMENT C

### SOLUTION TO POLLUTION TWENTY WAYS TO PROTECT YOUR WATER

## The Solution to Pollution - Begins with YOU! Here are 20 WAYS that YOU can make a difference.

#### YOUR YARD

1. Apply pesticides and fertilizers carefully and sparingly. Do not apply chemicals if heavy rain is forecast.

2. Use a broom, rather than a hose, to clean up garden clippings. Deposit leaves and clippings in a trash can or a compost pile.

3. Divert rainwater runoff from hard surfaces onto grass and permeable soil to help filter harmful substances.

4. Don't overwater your lawn and garden . . . water will only run into the street and storm drain.

5. Pick up animal waste and dispose of it in trash cans. Animal waste contains coliform bacteria and can spread serious diseases.

6. Control soil erosion. Prevent dirt and debris from washing into storm drains.

#### YOUR HOME

7. Use and dispose of household products carefully. Cleaning solutions and solvents often contain toxic elements.

8. Use non-hazardous cleaning substances such as baking soda, white vinegar or borax.

9. Take unwanted household hazardous materials to a Countywide Household Hazardous Waste collection event or other local collection programs.

10. When using water-based paints, clean brushes in a sink. Don'l pour cleanup water down the storm drain. Dispose of oil-based products and solvents at a hazardous waste collection event.

**11.** Buy recycled products and recycle reusable materials. Many waste haulers provide curb-side service. Call yours for more information.

12. Use cat litter or other absorbent material to clean spills from paved surfaces. Dispose of absorbent material in the garbage or at a household hazardous waste collection event, as appropriate.

## YOUR AUTO

**13.** Take used motor oil, antifreeze and other toxic solvents to collection centers.

14. Fix oil, radiator, and transmission leaks. Don't leave oil slicks to wash off in the rain.

15. Take your car to a car wash or wash your car on the grass. Don't just wash grimy road dirt down the driveway and into the storm drain.

**16.** Reduce polluting automotive emissions. Keep your car tuned, carpool, and use public transportation.

#### YOUR NEIGHBORHOOD

17. Never pour anything into a storm drain.

18. Tell others how to prevent stormwater pollution. Don't let others pollute your water.


**19.** Report illegal dumping to local authorities.

20. Organize a stenciling campaign in your neighborhood. (Storm drain stencils remind us that there should be "only rain in the drain.") Call us for information on how to stencil.

## Stormwater pollution . . . is fouling our water!

Every day, water from garden hoses, sprinklers and rainfall washes pollutants off roads and yards . . . right into neighborhood storm drains. Storm drains carry untreated water and pollutants **directly** to our water resources.

> Some pollutants, such as grease and dirt from streets, reach the storm drains unintentionally. But, many pollutants like used motor oil, detergents, paints, and solvents, are carelessly dumped into the storm drains.



Polluted stormwater harms wildlife, jeopardizes the use of our rivers and lakes for recreation . . . and may eventually contaminate the water we drink!

Twenty Ways to Protect Your Water



You Can Make A Difference!

## SECTION X

## APPENDIX

### BIORETENTION SIZING CALCULATIONS STORMWATER BMP DESIGN AND MAINTENANCE MANUAL

#### EXAMPLE: BIORETENTION "AREA A-1":

#### **SOLUTION**

TREAT DETAINTED VOLUME USING QPM.

#### **FLOW**

| SUBAREA | AREA (AC) | Q <sub>РМ85TH</sub><br>(cfs) | Q <sub>PM85TH</sub><br>Provided | BMP<br>Provided |
|---------|-----------|------------------------------|---------------------------------|-----------------|
| A-1     | 1.736     | 0.36                         | 0.462                           | MWS-L-8-16-C    |
| A-2     | 2.766     | 0.6032                       | 0.693                           | MWS-L-8-24-V    |
| A-4     | 0.877     | 0.1983                       | 0.231                           | MWS-L-8-8-V     |

#### **EXAMPLE: BIORETENTION "AREA A-3":**

 $\label{eq:generalized_states} \begin{array}{l} \underline{\textit{GIVEN:}} \\ \text{REQUIRED WATER QUALITY WQ VOLUME = V = 6,328 C.F.} \\ \text{Bioretention= Volume x 1.5= 9,492 C.F.} \\ t_p = 96 \text{ HR.} \\ \text{fdesign = 5.0 IN./HR.} \\ \text{d= ponding depth; use 1'} \\ \underline{\textit{SOLUTION:}} \end{array}$ 

Where: A = Volume x 1.5 / dA = 9,492 / 1 = 9,492 S.F.


Bioretention SURFACE = 9,600 S.F.

#### 9,600 S.F. > 9,492 S.F. ← **THEREFORE OK**

#### VOLUME

| SUBAREA | AREA (AC) | V <sub>РМ85ТН</sub><br>(cf) | V <sub>РМ85TH x 1.5</sub><br>(cf) | Surface<br>Area<br>Required | Surface<br>Area<br>Provided |
|---------|-----------|-----------------------------|-----------------------------------|-----------------------------|-----------------------------|
| A-3     | 2.833     | 6,328                       | 9,492                             | 9,492                       | 9,600                       |

|                | SITE SPEC       | IFIC DATA        |           |  |
|----------------|-----------------|------------------|-----------|--|
| PROJECT NUMBE  | R               |                  |           |  |
| PROJECT NAME   |                 |                  |           |  |
| PROJECT LOCATI | ON              |                  |           |  |
| STRUCTURE ID   |                 |                  |           |  |
|                | TREATMENT       | REQUIRED         |           |  |
| VOLUME B       | ASED (CF)       | FLOW BASED (CFS) |           |  |
| N,             | /A              | 0.693            |           |  |
| PEAK BYPASS R  | EQUIRED (CFS) - | IF APPLICABLE    | OFFLINE   |  |
| PIPE DATA      | <i>I.E.</i>     | MATERIAL         | DIAMETER  |  |
| INLET PIPE 1   |                 |                  |           |  |
| INLET PIPE 2   | N/A             | N/A              | N/A       |  |
| OUTLET PIPE    |                 |                  |           |  |
|                | PRETREATMENT    | BIOFILTRATION    | DISCHARGE |  |
| RIM ELEVATION  |                 | · · ·            |           |  |
| SURFACE LOAD   | PEDESTRIAN      |                  |           |  |
| FRAME & COVER  | 3EA Ø30"        | OPEN PLANTER     | 2EA Ø24"  |  |




\* PRELIMINARY NOT FOR CONSTRUCTION

#### **INSTALLATION NOTES**


- CONTRACTOR TO PROVIDE ALL LABOR, EQUIPMENT, MATERIALS AND 1. INCIDENTALS REQUIRED TO OFFLOAD AND INSTALL THE SYSTEM AND APPURTENANCES IN ACCORDANCE WITH THIS DRAWING AND THE MANUFACTURERS SPECIFICATIONS, UNLESS OTHERWISE STATED IN MANUFACTURERS CONTRACT.
- 2. UNIT MUST BE INSTALLED ON LEVEL BASE. MANUFACTURER RECOMMENDS A MINIMUM 6" LEVEL ROCK BASE UNLESS SPECIFIED BY THE PROJECT ENGINEER. CONTRACTOR IS RESPONSIBLE TO VERIFY PROJECT ENGINEERS RECOMMENDED BASE SPECIFICATIONS.
- 4. CONTRACTOR TO SUPPLY AND INSTALL ALL EXTERNAL CONNECTING IF IN PIPES. ALL PIPES MUST BE FLUSH WITH INSIDE SURFACE OF CONCRETE. (PIPES CANNOT INTRUDE BEYOND FLUSH). INVERT OF OUTFLOW PIPE MUST BE FLUSH WITH DISCHARGE CHAMBER FLOOR. ALL PIPES SHALL BE SEALED WATER TIGHT PER MANUFACTURERS STANDARD CONNECTION DETAIL.
- 5. CONTRACTOR RESPONSIBLE FOR INSTALLATION OF ALL RISERS, MANHOLES, AND HATCHES. CONTRACTOR TO GROUT ALL MANHOLES AND HATCHES TO MATCH FINISHED SURFACE UNLESS SPECIFIED OTHERWISE.
- VEGETATION SUPPLIED AND INSTALLED BY OTHERS. ALL UNITS WITH 6. VEGETATION MUST HAVE DRIP OR SPRAY IRRIGATION SUPPLIED AND INSTALLED BY OTHERS.
- CONTRACTOR RESPONSIBLE FOR CONTACTING BIO CLEAN FOR ACTIVATION OF UNIT. MANUFACTURERS WARRANTY IS VOID WITH OUT PROPER ACTIVATION BY A BIO CLEAN REPRESENTATIVE.

#### **GENERAL NOTES**


- MANUFACTURER TO PROVIDE ALL MATERIALS UNLESS OTHERWISE NOTED.
- ALL DIMENSIONS, ELEVATIONS, SPECIFICATIONS AND CAPACITIES ARE SUBJECT TO 2. CHANGE. FOR PROJECT SPECIFIC DRAWINGS DETAILING EXACT DIMENSIONS, WEIGHTS AND ACCESSORIES PLEASE CONTACT BIO CLEAN.







|                 | SITE SPEC      | IFIC DATA     |            |                     |
|-----------------|----------------|---------------|------------|---------------------|
| PROJECT NUMBER  | ኖ              |               |            |                     |
| ORDER NUMBER    |                |               |            | WETLANDMEDIA        |
| PROJECT NAME    |                |               |            | BED<br>PATENTED~    |
| PROJECT LOCATIO | 2N             |               |            | PERIMETER           |
| STRUCTURE ID    |                |               |            | VOID AREA           |
|                 | TREATMENT      | REQUIRED      |            |                     |
| VOLUME BA       | ISED (CF)      | FLOW BAS      | ED (CFS)   | ~                   |
|                 |                |               |            |                     |
| TREATMENT HGL . | AVAILABLE (FT) |               |            |                     |
| PEAK BYPASS RE  | QUIRED (CFS) – | IF APPLICABLE |            |                     |
| PIPE DATA       | <i>I.E</i> .   | MATERIAL      | DIAMETER   |                     |
| INLET PIPE 1    |                |               |            |                     |
| INLET PIPE 2    |                |               |            |                     |
| OUTLET PIPE     |                |               |            |                     |
|                 | PRETREATMENT   | BIOFILTRATION | DISCHARGE  | PRE-FILT<br>CARTRID |
| RIM ELEVATION   |                |               |            |                     |
| SURFACE LOAD    | PEDESTRIAN     | OPEN PLANTER  | PEDESTRIAN |                     |
| FRAME & COVER   | 2EA ø30"       | N/A           | ø24"       |                     |
| WETLANDMEDIA VO | OLUME (CY)     |               | TBD        |                     |
|                 | A. INCHES)     |               | TBD        | 1                   |




#### INSTALLATION NOTES

- CONTRACTOR TO PROVIDE ALL LABOR, EQUIPMENT, MATERIALS AND 1. INCIDENTALS REQUIRED TO OFFLOAD AND INSTALL THE SYSTEM AND APPURTENANCES IN ACCORDANCE WITH THIS DRAWING AND THE MANUFACTURERS SPECIFICATIONS, UNLESS OTHERWISE STATED IN MANUFACTURERS CONTRACT.
- 2. UNIT MUST BE INSTALLED ON LEVEL BASE. MANUFACTURER RECOMMENDS A MINIMUM 6" LEVEL ROCK BASE UNLESS SPECIFIED BY THE PROJECT ENGINEER. CONTRACTOR IS RESPONSIBLE TO VERIFY PROJECT ENGINEERS RECOMMENDED BASE SPECIFICATIONS.
- CONTRACTOR TO SUPPLY AND INSTALL ALL EXTERNAL CONNECTING 4. PIPES. ALL PIPES MUST BE FLUSH WITH INSIDE SURFACE OF CONCRETE. (PIPES CANNOT INTRUDE BEYOND FLUSH). INVERT OF OUTFLOW PIPE MUST BE FLUSH WITH DISCHARGE CHAMBER FLOOR. ALL PIPES SHALL BE SEALED WATER TIGHT PER MANUFACTURERS STANDARD CONNECTION DETAIL.
- CONTRACTOR RESPONSIBLE FOR INSTALLATION OF ALL RISERS. 5. MANHOLES. AND HATCHES. CONTRACTOR TO GROUT ALL MANHOLES AND HATCHES TO MATCH FINISHED SURFACE UNLESS SPECIFIED OTHERWISE.
- 6. VEGETATION SUPPLIED AND INSTALLED BY OTHERS. ALL UNITS WITH VEGETATION MUST HAVE DRIP OR SPRAY IRRIGATION SUPPLIED AND INSTALLED BY OTHERS.
- CONTRACTOR RESPONSIBLE FOR CONTACTING BIO CLEAN FOR 7. ACTIVATION OF UNIT. MANUFACTURERS WARRANTY IS VOID WITH OUT PROPER ACTIVATION BY A BIO CLEAN REPRESENTATIVE.

#### **GENERAL NOTES**

- MANUFACTURER TO PROVIDE ALL MATERIALS UNLESS OTHERWISE NOTED. 1
- ALL DIMENSIONS, ELEVATIONS, SPECIFICATIONS AND CAPACITIES ARE SUBJECT TO 2. CHANGE. FOR PROJECT SPECIFIC DRAWINGS DETAILING EXACT DIMENSIONS, WEIGHTS AND ACCESSORIES PLEASE CONTACT BIO CLEAN.



**ELEVATION VIEW** 


PROPRIETARY AND CONFIDENTIAL:

THE INFORMATION CONTAINED IN THIS DOCUMENT IS THE SOLE

ETLANDS

THIS PRODUCT MAY BE PROTECTED BY ONE OR MORE O THE FOLLOWING US FATENTS: 7,425,262; 7,470,362; 7,674,378; 8,303,816; RELATED FOREIGN PATENTS OR OTHER PATENTS PENDING






**RIGHT END VIEW** 

| an<br>Company | <i>MWS-L-8-16-C</i><br>STORMWATER BIOFILTRATION<br>STANDARD DETAIL | ' SYSTEM |
|---------------|--|----------|
|               | WETLAND MEDIA LOADING RATE (GPM/SF)                                | 1.0      |
|               | PRETREATMENT LOADING RATE (GPM/SF)                                 | 2.0      |
|               | OPERATING HEAD (FT)  | 3.4      |
|               | TREATMENT FLOW (CFS)   | 0.462    |
|               |  |          |

|               | SITE SPEC        | IFIC DATA     |                  |  |  |
|---------------|------------------|---------------|------------------|--|--|
| PROJECT NUMBE | ĒR               |               |                  |  |  |
| PROJECT NAME  |                  |               |                  |  |  |
| PROJECT LOCAT | ION              |               |                  |  |  |
| STRUCTURE ID  |                  |               |                  |  |  |
|               | TREATMENT        | REQUIRED      |                  |  |  |
| VOLUME B      | ASED (CF)        | FLOW BAS      | FLOW BASED (CFS) |  |  |
| N/A           |                  | 0.693         |                  |  |  |
| PEAK BYPASS R | PEQUIRED (CFS) – | IF APPLICABLE | OFFLINE          |  |  |
| PIPE DATA     | <i>I.E.</i>      | MATERIAL      | DIAMETER         |  |  |
| INLET PIPE 1  |                  |               |                  |  |  |
| INLET PIPE 2  | N/A              | N/A           | N/A              |  |  |
| OUTLET PIPE   |                  |               |                  |  |  |
|               | PRETREATMENT     | BIOFILTRATION | DISCHARGE        |  |  |
| RIM ELEVATION |                  | •             |                  |  |  |
| SURFACE LOAD  | PEDESTRIAN       |               |                  |  |  |
| FRAME & COVER | ø30"             | OPEN PLANTER  | ø24"             |  |  |




\* PRELIMINARY NOT FOR CONSTRUCTION

#### **INSTALLATION NOTES**

- CONTRACTOR TO PROVIDE ALL LABOR, EQUIPMENT, MATERIALS AND 1. INCIDENTALS REQUIRED TO OFFLOAD AND INSTALL THE SYSTEM AND APPURTENANCES IN ACCORDANCE WITH THIS DRAWING AND THE MANUFACTURERS SPECIFICATIONS, UNLESS OTHERWISE STATED IN MANUFACTURERS CONTRACT.
- UNIT MUST BE INSTALLED ON LEVEL BASE. MANUFACTURER 2. RECOMMENDS A MINIMUM 6" LEVEL ROCK BASE UNLESS SPECIFIED BY THE PROJECT ENGINEER. CONTRACTOR IS RESPONSIBLE TO VERIFY PROJECT ENGINEERS RECOMMENDED BASE SPECIFICATIONS.
- CONTRACTOR TO SUPPLY AND INSTALL ALL EXTERNAL CONNECTING PIPES. ALL PIPES MUST BE FLUSH WITH INSIDE SURFACE OF CONCRETE. (PIPES CANNOT INTRUDE BEYOND FLUSH). INVERT OF OUTFLOW PIPE MUST BE FLUSH WITH DISCHARGE CHAMBER FLOOR. ALL PIPES SHALL BE SEALED WATER TIGHT PER MANUFACTURERS STANDARD CONNECTION DETAIL.
- 5. CONTRACTOR RESPONSIBLE FOR INSTALLATION OF ALL RISERS, MANHOLES, AND HATCHES. CONTRACTOR TO GROUT ALL MANHOLES AND HATCHES TO MATCH FINISHED SURFACE UNLESS SPECIFIED OTHERWISE.
- VEGETATION SUPPLIED AND INSTALLED BY OTHERS. ALL UNITS WITH 6. VEGETATION MUST HAVE DRIP OR SPRAY IRRIGATION SUPPLIED AND INSTALLED BY OTHERS.
- CONTRACTOR RESPONSIBLE FOR CONTACTING BIO CLEAN FOR 7. ACTIVATION OF UNIT. MANUFACTURERS WARRANTY IS VOID WITH OUT PROPER ACTIVATION BY A BIO CLEAN REPRESENTATIVE.

#### **GENERAL NOTES**

- MANUFACTURER TO PROVIDE ALL MATERIALS UNLESS OTHERWISE NOTED.
- ALL DIMENSIONS, ELEVATIONS, SPECIFICATIONS AND CAPACITIES ARE SUBJECT TO 2. CHANGE. FOR PROJECT SPECIFIC DRAWINGS DETAILING EXACT DIMENSIONS, WEIGHTS AND ACCESSORIES PLEASE CONTACT BIO CLEAN.






#### PROPRIETARY AND CONFIDENTIAL:

THE INFORMATION CONTAINED IN THIS DOCUMENT IS THE SOLE PROPERTY OF FORTERRA AND ITS COMPANIES. THIS DOCUMENT, NOR ANY PART THEREOF, MAY BE USED, REPRODUCED OR MODIFIED IN ANY MANNER WITH OUT THE WRITTEN CONSENT OF FORTERRA.





10

VARIES VARIES

> STORMWATER BIOFILTRATION SYSTEM STANDARD DETAIL



## California Full Capture Product Line Card

#### **FULL CAPTURE INSERTS**

#### Catch Basin Inlet Filter | Full Capture Type

The Catch Basin Inlet Filters are insertable systems designed to capture fine to coarse sediments, floatable trash, debris, total suspended solids (TSS), nutrients, metals, and hydrocarbons conveyed in stormwater runoff. The filter system is available in four different model types: Full Capture Type, Multi-Level Screen Type, Kraken Filter Type, and the Media Filter Type.

#### Notable Approvals

California Water Board, Full Capture Certification

#### **Bio Clean CPS**

The Bio Clean CPS (Connector Pipe Screen) can be retrofitted into any curb or drop inlet to help municipalities meet stormwater regulations and comply with their National Pollutant Discharge Elimination System (NPDES) or municipal separate storm sewer system (MS4) permit. Bio Clean CPS devices can be used as the first line of defense to prevent trash from reaching downstream stormwater systems, where debris can cause clogging and unnecessary maintenance burdens.

#### **Notable Approvals**

California Water Board, Full Capture Certification

#### **FULL CAPTURE HIGH FLOW SYSTEMS**

#### **Debris Separating Baffle Box (DSBB)**

The Debris Separating Baffle Box (DSBB) is an advanced stormwater treatment system utilizing a nonclogging screen technology and hydrodynamic separation to capture pollutants. The non-clogging screening system stores trash and debris in a dry state, suspended above the sedimentation chambers, minimizing nutrient leaching, bacterial growth, bad odors, and allows for easier maintenance.

#### Notable Approvals

- California Water Board, Full Capture Certification
- NJCAT Verified

#### **Modular Wetlands® Linear**

The Modular Wetlands<sup>®</sup> Linear (MWS Linear) represents a pioneering breakthrough in stormwater technology as the only biofiltration system to utilize patented horizontal flow, allowing for a smaller footprint and higher treatment capacity. Unlike most biofiltration products, the Modular Wetlands Linear offers an advanced pretreatment chamber that includes separation and pre-filter boxes.

#### **Notable Approvals**

- Washington State TAPE/GULD, Approval
- California Water Board, Full Capture Certification
- California Water Board Approved MS4 System





**STORAGE** 



BIOFILTRATION



SEPARATION



COMPREHENSIVE STORMWATER SOLUTIONS

FILTRATION















## **Modular Wetlands<sup>®</sup> Linear** A Stormwater Biofiltration Solution

## OPERATION & MAINTENANCE MANUAL






## Inspection Guidelines for Modular Wetland System - Linear

#### **Inspection Summary**

- Inspect Pre-Treatment, Biofiltration and Discharge Chambers average inspection interval is 6 to 12 months.
  - (15 minute average inspection time).
- <u>NOTE</u>: Pollutant loading varies greatly from site to site and no two sites are the same. Therefore, the first year requires inspection monthly during the wet season and every other month during the dry season in order to observe and record the amount of pollutant loading the system is receiving.



#### www.modularwetlands.com



## **Inspection Overview**

As with all stormwater BMPs inspection and maintenance on the MWS Linear is necessary. Stormwater regulations require that all BMPs be inspected and maintained to ensure they are operating as designed to allow for effective pollutant removal and provide protection to receiving water bodies. It is recommended that inspections be performed multiple times during the first year to assess the site specific loading conditions. This is recommended because pollutant loading and pollutant characteristics can vary greatly from site to site. Variables such as nearby soil erosion or construction sites, winter sanding on roads, amount of daily traffic and land use can increase pollutant loading on the system. The first year of inspections can be used to set inspection and maintenance intervals for subsequent years to ensure appropriate maintenance is provided. Without appropriate maintenance a BMP will exceed its storage capacity which can negatively affect its continued performance in removing and retaining captured pollutants.

#### **Inspection Equipment**

Following is a list of equipment to allow for simple and effective inspection of the MWS Linear:

- Modular Wetland Inspection Form
- Flashlight
- Manhole hook or appropriate tools to remove access hatches and covers
- Appropriate traffic control signage and procedures
- Measuring pole and/or tape measure.
- Protective clothing and eye protection.
- 7/16" open or closed ended wrench.
- Large permanent black marker (initial inspections only first year)
- Note: entering a confined space requires appropriate safety and certification. It is generally not required for routine inspections of the system.



www.modularwetlands.com



#### Inspection Steps


The core to any successful stormwater BMP maintenance program is routine inspections. The inspection steps required on the MWS Linear are quick and easy. As mentioned above the first year should be seen as the maintenance interval establishment phase. During the first year more frequent inspections should occur in order to gather loading data and maintenance requirements for that specific site. This information can be used to establish a base for long term inspection and maintenance interval requirements.

The MWS Linear can be inspected though visual observation without entry into the system. All necessary pre-inspection steps must be carried out before inspection occurs, especially traffic control and other safety measures to protect the inspector and near-by pedestrians from any dangers associated with an open access hatch or manhole. Once these access covers have been safely opened the inspection process can proceed:

- Prepare the inspection form by writing in the necessary information including project name, location, date & time, unit number and other info (see inspection form).
- Observe the inside of the system through the access hatches. If minimal light is available and vision into the unit is impaired utilize a flashlight to see inside the system and all of its chambers.
- Look for any out of the ordinary obstructions in the inflow pipe, pre-treatment chamber, biofiltration chamber, discharge chamber or outflow pipe. Write down any observations on the inspection form.
- Through observation and/or digital photographs estimate the amount of trash, debris and sediment accumulated in the pre-treatment chamber. Utilizing a tape measure or measuring stick estimate the amount of trash, debris and sediment in this chamber. Record this depth on the inspection form.



Through visual observation inspect the condition of the pre-filter cartridges. Look for excessive build-up of sediments on the cartridges, any build-up on the top of the cartridges, or clogging of the holes. Record this information on the inspection form. The pre-filter cartridges can further be inspected by removing the cartridge tops and assessing the color of the BioMediaGREEN filter cubes (requires entry into pre-treatment chamber – see notes above regarding confined space entry). Record the color of the material. New material is a light green in color. As the media becomes clogged it will turn darker in color, eventually becoming dark brown or black. Using the below color indicator record the percentage of media exhausted.



- The biofiltration chamber is generally maintenance free due to the system's advanced pretreatment chamber. For units which have open planters with vegetation it is recommended that the vegetation be inspected. Look for any plants that are dead or showing signs of disease or other negative stressors. Record the general health of the plants on the inspection and indicate through visual observation or digital photographs if trimming of the vegetation is needed.
- The discharge chamber houses the orifice control structure, drain down filter and is connected to the outflow pipe. It is important to check to ensure the orifice is in proper operating conditions and free of any obstructions. It is also important to assess the condition of the drain down filter media which utilizes a block form of the BioMediaGREEN. Assess in the same manner as the cubes in the Pre-Filter Cartridge as mentioned above. Generally, the discharge chamber will be clean and free of debris. Inspect the water marks on the side walls. If possible, inspect the discharge chamber during a rain event to assess the amount of flow leaving the system while it is at 100% capacity (pre-treatment chamber water level at peak HGL). The water level of the flowing water should be compared to the watermark level on the side walls which is an indicator of the highest discharge rate the system achieved when initially installed. Record on the form is there is any difference in level from watermark in inches.

#### www.modularwetlands.com



 NOTE: During the first few storms the water level in the outflow chamber should be observed and a 6" long horizontal watermark line drawn (using a large permanent marker) at the water level in the discharge chamber while the system is operating at 100% capacity. The diagram below illustrates where a line should be drawn. This line is a reference point for future inspections of the system:







Using a permanent marker draw a 6 inch long horizontal line, as shown, at the higher water level in the MWS Linear discharge chamber.


- Water level in the discharge chamber is a function of flow rate and pipe size. Observation of water level during the first few months of operation can be used as a benchmark level for future inspections. The initial mark and all future observations shall be made when system is at 100% capacity (water level at maximum level in pre-treatment chamber). If future water levels are below this mark when system is at 100% capacity this is an indicator that maintenance to the pre-filter cartridges may be needed.
- Finalize inspection report for analysis by the maintenance manager to determine if maintenance is required.



#### **Maintenance Indicators**

Based upon observations made during inspection, maintenance of the system may be required based on the following indicators:

- Missing or damaged internal components or cartridges.
- Obstructions in the system or its inlet or outlet.
- Excessive accumulation of floatables in the pre-treatment chamber in which the length and width of the chamber is fully impacted more than 18".




• Excessive accumulation of sediment in the pre-treatment chamber of more than 6" in depth.



www.modularwetlands.com



 Excessive accumulation of sediment on the BioMediaGREEN media housed within the prefilter cartridges. The following chart shows photos of the condition of the BioMediaGREEN contained within the pre-filter cartridges. When media is more than 85% clogged replacement is required.



 Excessive accumulation of sediment on the BioMediaGREEN media housed within the drain down filter. The following photos show of the condition of the BioMediaGREEN contained within the drain down filter. When media is more than 85% clogged replacement is required.



www.modularwetlands.com



• Overgrown vegetation.





• Water level in discharge chamber during 100% operating capacity (pre-treatment chamber water level at max height) is lower than the watermark by 20%.



#### **Inspection Notes**

- Following maintenance and/or inspection, it is recommended the maintenance operator prepare a maintenance/inspection record. The record should include any maintenance activities performed, amount and description of debris collected, and condition of the system and its various filter mechanisms.
- The owner should keep maintenance/inspection record(s) for a minimum of five years from the date of maintenance. These records should be made available to the governing municipality for inspection upon request at any time.
- 3. Transport all debris, trash, organics and sediments to approved facility for disposal in accordance with local and state requirements.
- 4. Entry into chambers may require confined space training based on state and local regulations.
- 5. No fertilizer shall be used in the Biofiltration Chamber.
- 6. Irrigation should be provided as recommended by manufacturer and/or landscape architect. Amount of irrigation required is dependent on plant species. Some plants may not require irrigation after initial establishment.






## Maintenance Guidelines for Modular Wetland System - Linear

#### Maintenance Summary

- <u>Remove Sediment from Pre-Treatment Chamber</u> average maintenance interval is 12 to 24 months.
  - (10 minute average service time).
- Replace Pre-Filter Cartridge Media average maintenance interval 12 to 24 months.
  - (10-15 minute per cartridge average service time).
- Trim Vegetation average maintenance interval is 6 to 12 months.
  - (Service time varies).



#### www.modularwetlands.com

#### System Diagram



## **Maintenance Overview**

The time has come to maintain your Modular Wetland System Linear (MWS Linear). To ensure successful and efficient maintenance on the system we recommend the following. The MWS Linear can be maintained by removing the access hatches over the systems various chambers. All necessary pre-maintenance steps must be carried out before maintenance occurs, especially traffic control and other safety measures to protect the inspector and near-by pedestrians from any dangers associated with an open access hatch or manhole. Once traffic control has been set up per local and state regulations and access covers have been safely opened the maintenance process can begin. It should be noted that some maintenance activities require confined space entry. All confined space requirements must be strictly followed before entry into the system. In addition the following is recommended:

- Prepare the maintenance form by writing in the necessary information including project name, location, date & time, unit number and other info (see maintenance form).
- Set up all appropriate safety and cleaning equipment.
- Ensure traffic control is set up and properly positioned.
- Prepare a pre-checks (OSHA, safety, confined space entry) are performed.

#### Maintenance Equipment

Following is a list of equipment required for maintenance of the MWS Linear:

- Modular Wetland Maintenance Form
- Manhole hook or appropriate tools to access hatches and covers
- Protective clothing, flashlight and eye protection.
- 7/16" open or closed ended wrench.
- Vacuum assisted truck with pressure washer.
- Replacement BioMediaGREEN for Pre-Filter Cartridges if required (order from manufacturer).



www.modularwetlands.com



#### Maintenance Steps

- 1. Pre-treatment Chamber (bottom of chamber)
  - A. Remove access hatch or manhole cover over pre-treatment chamber and position vacuum truck accordingly.
  - B. With a pressure washer spray down pollutants accumulated on walls and pre-filter cartridges.
  - C. Vacuum out Pre-Treatment Chamber and remove all accumulated pollutants including trash, debris and sediments. Be sure to vacuum the floor until pervious pavers are visible and clean.
  - D. If Pre-Filter Cartridges require media replacement move onto step 2. If not, replace access hatch or manhole cover.




Removal of access hatch to gain access below.





Removal of trash, sediment and debris.

Insertion of vacuum hose into separation chamber.



Fully cleaned separation chamber.



# 2. Pre-Filter Cartridges (attached to wall of pre-treatment chamber)

- A. After finishing step 1 enter pre-treatment chamber.
- B. Unscrew the two bolts holding the lid on each cartridge filter and remove lid.



Pre-filter cartridges with tops on.



Inside cartridges showing media filters ready for replacement.



C. Place the vacuum hose over each individual media filter to suck out filter media.

Vacuuming out of media filters.

D. Once filter media has been sucked use a pressure washer to spray down inside of the cartridge and it's containing media cages. Remove cleaned media cages and place to the side. Once removed the vacuum hose can be inserted into the cartridge to vacuum out any remaining material near the bottom of the cartridge.



E. Reinstall media cages and fill with new media from manufacturer or outside supplier. Manufacturer will provide specification of media and sources to purchase. Utilize the manufacture provided refilling trey and place on top of cartridge. Fill trey with new bulk media and shake down into place. Using your hands slightly compact media into each filter cage. Once cages are full removed refilling trey and replace cartridge top ensuring bolts are properly tightened.



Refilling trey for media replacement.





Refilling trey on cartridge with bulk media.

F. Exit pre-treatment chamber. Replace access hatch or manhole cover.

#### 3. Biofiltration Chamber (middle vegetated chamber)

A. In general, the biofiltration chamber is maintenance free with the exception of maintaining the vegetation. Using standard gardening tools properly trim back the vegetation to healthy levels. The MWS Linear utilizes vegetation similar to surrounding landscape areas therefore trim vegetation to match surrounding vegetation. If any plants have died replace plants with new ones:







## 4. Discharge Chamber (contains drain down cartridge & connected to pipe)

- A. Remove access hatch or manhole cover over discharge chamber.
- B. Enter chamber to gain access to the drain down filter. Unlock the locking mechanism and left up drain down filter housing to remove used BioMediaGREEN filter block as shown below:



C. Insert new BioMediaGREEN filter block and lock drain down filter housing back in place. Replace access hatch or manhole cover over discharge chamber.



#### Inspection Notes

- Following maintenance and/or inspection, it is recommended the maintenance operator prepare a maintenance/inspection record. The record should include any maintenance activities performed, amount and description of debris collected, and condition of the system and its various filter mechanisms.
- The owner should keep maintenance/inspection record(s) for a minimum of five years from the date of maintenance. These records should be made available to the governing municipality for inspection upon request at any time.
- 3. Transport all debris, trash, organics and sediments to approved facility for disposal in accordance with local and state requirements.
- 4. Entry into chambers may require confined space training based on state and local regulations.
- 5. No fertilizer shall be used in the Biofiltration Chamber.
- Irrigation should be provided as recommended by manufacturer and/or landscape architect. Amount of irrigation required is dependent on plant species. Some plants may not require irrigation after initial establishment.




# **Inspection Form**



Modular Wetland System, Inc. P. 760.433-7640 F. 760-433-3176 E. Info@modularwetlands.com



# **Maintenance Report**



Modular Wetland System, Inc. P. 760.433-7640 F. 760-433-3176 E. Info@modularwetlands.com



5796 Armada Drive Suite 250 Carlsbad, CA 92008 855.566.3938 stormwater@forterrabp.com biocleanenvironmental.com

# **BIO-1:** Biofiltration



#### Definition

A biofiltration area is a vegetated shallow depression that is designed to receive and treat stormwater runoff from downspouts, piped inlets, or sheet flow from adjoining paved areas. A shallow ponding zone is provided above the vegetated surface for temporary storage of stormwater runoff. During storm events, stormwater runoff accumulates in the ponding zone and gradually infiltrates the surface and filters through the biofiltration soil media before being collected by an underdrain system.

Stormwater runoff treatment occurs through a

variety of natural mechanisms as stormwater runoff filters through the vegetation root zone. In biofiltration areas, microbes and organic material in the biofiltration soil media help promote the adsorption of pollutants (e.g., dissolved metals and petroleum hydrocarbons) into the soil matrix. Plants utilize soil moisture and promote the drying of the soil through transpiration. Biofiltration areas are typically planted with native, drought-tolerant plant species that do not require fertilization and can withstand wet soils for at least 96 hours.

A schematic of a typical biofiltration area is presented in Figure E-7.

## LID Ordinance Requirements

Biofiltration can be used as an alternative compliance measure.

| Pollutant of Concern    | Treated by Biofiltration? |  |  |  |
|-------------------------|---------------------------|--|--|--|
| Suspended solids        | No                        |  |  |  |
| Total phosphorus        | No                        |  |  |  |
| Total nitrogen          | Yes                       |  |  |  |
| Total Kjeldahl nitrogen | Yes                       |  |  |  |
| Cadmium, total          | No                        |  |  |  |
| Chromium, total         | Yes                       |  |  |  |
| Copper, total           | No                        |  |  |  |
| Lead, total             | Yes                       |  |  |  |
| Zinc, total             | No                        |  |  |  |


Source: Treatment Best Management Practices Performance, Los Angeles Regional Water Quality Control Board, December 9, 2013.

# Advantages

- Has a low cost for installation
- Enhances site aesthetics
- Requires little maintenance

# Disadvantages

• May require individual owner/tenants to perform maintenance



- ② PERFORATED 6" MIN PVC PIPE UNDERDRAIN SYSTEM. WHERE SOIL CONDITIONS ALLOW, OMIT THE UNDERDRAIN AND INSTALL AN APPROPRIATELY SIZED GRAVEL DRAINAGE LAYER (TYPICALLY A WASHED 57 STONE) BENEATH THE PLANTING MEDIA FOR ENHANCED INFILTRATION.
- ③ OPTIONAL CHOKING GRAVEL LAYER.
- ④ 2' MIN PLANTING MIX; 3' PREFERRED.

Figure E-7. Biofiltration Area Schematic

# **General Constraints and Implementation Considerations**

- Biofiltration areas can be applied in various settings including, but not limited to:
  - Individual lots for rooftop, driveway, and other on-site impervious surface
  - Shared facilities located in common areas for individual lots
  - Areas within loop roads or cul-de-sacs
  - Landscaped parking lot islands
  - Within right-of-ways along roads
  - Common landscaped areas in apartment complexes or other multi-family housing designs
  - Parks and along open space perimeter
- If tire curbs are provided and parking stalls are shortened, cars are allowed to overhang the biofiltration area.
- Biofiltration areas must be located sufficiently far from structure foundations to avoid damage to structures (as determined by a certified structural or geotechnical engineer).
- Any parking areas bordering the biofiltration area must be monolithically poured concrete or deepended curb concrete to provide structural stability to the adjacent parking section.
- Geomembrane liners must be used in areas subject to spills or pollutant hot spots.
- During construction activities should avoid compaction of native soils below planting media layer or gravel zone.
- Stormwater runoff must be diverted around the biofiltration area during the period of vegetation establishment. If diversion is not feasible, the graded and seeded areas must be protected with suitable sediment controls (i.e., silt fences).All damaged areas should be repaired, seeded, or re-planted immediately.
- The general landscape irrigation system should incorporate the biofiltration area, as applicable.

# **Design Specifications**

The following sections describe the design specifications for biofiltration areas.

## Geotechnical

Due to the potential to contaminate groundwater, cause slope instability, impact surrounding structures, and potential for insufficient infiltration capacity, an extensive geotechnical site investigation must be conducted during the site planning process to verify site suitability for biofiltration. All geotechnical investigations must be performed according to the most recent GMED Policy GS 200.1. Soil infiltration rates and the groundwater table depth must be evaluated to ensure that conditions are satisfactory for proper operation of a biofiltration area. The project applicant must demonstrate through infiltration testing, soil logs, and the written opinion of a licensed civil engineer that sufficiently permeable soils exist on-site to allow the construction of a properly functioning biofiltration system.

Biofiltration areas are appropriate for soils with a minimum corrected in-situ infiltration rate of 0.3 in/hr. The geotechnical report must determine if the proposed project site is suitable for a biofiltration area and must recommend a design infiltration rate (see "Design Infiltration Rate" under the "Sizing" section). The geotechnical investigation should be such that a good understanding is gained as to how the stormwater runoff will move through the soil (horizontally or vertically) and if there are any geological conditions that could inhibit the movement of water.

#### Pretreatment

Pretreatment refers to design features that provide settling of large particles before stormwater runoff enters a stormwater quality control measure in order to reduce the long-term maintenance burden. Pretreatment should be provided to reduce the sediment load entering a biofiltration area in order to maintain the infiltration rate of the biofiltration area. To ensure that biofiltration areas are effective, the project applicant must incorporate pretreatment devices that provide sediment removal (e.g., vegetated swales, vegetated filter strips, sedimentation manholes, and proprietary devices). The use of at least two pretreatment devices is highly recommended for biofiltration areas.

## Geometry

- Biofiltration areas must be sized to capture and treat 1.5 times the SWQDv that is not reliably retained on the project site with an 18-inch maximum ponding depth.
- The planting soil depth must be a minimum of two feet, although three feet is preferred. The planting soil depth should provide a beneficial root zone for the chosen vegetation and adequate water storage for the stormwater runoff. A deeper planting soil depth will also provide a smaller surface area footprint.
- A gravel storage layer below the biofiltration area soil media is required to provide adequate temporary storage to retain 1.5 times the SWQDv that is not reliably retained on the project site and to promote infiltration.

## Sizing

Biofiltration areas are sized using a simple sizing method where 1.5 times the SWQDv that is not reliably retained on the project site must be completely filtered within 96 hours. If the incoming stormwater runoff flow rate is lower than the long term filtration rate, above ground storage does not need to be provided. If the incoming stormwater runoff flow rate is higher than the long term filtration rate, above ground storage shall be provided (see steps below).

# Step 1: Calculate the design volume

Biofiltration areas should be sized to capture and treat 1.5 times the portion of the SWQDv (see Section 6 for SWQDv calculation procedures) that is not reliability retained on the project site, as calculated by the equation below:

$$V_B = 1.5 \times (SWQDv - V_R)$$

Where:

 $V_B$  = Biofiltration volume [ft<sup>3</sup>]; SWQDv = Stormwater quality design volume [ft<sup>3</sup>]; and  $V_R$  = Volume of stormwater runoff reliably retained on-site [ft<sup>3</sup>].

# Step 2: Calculate the design infiltration rate

Determine the corrected in-situ infiltration rate ( $f_{design}$ ) of the native soil using the procedures described in the most recent GMED Policy GS 200.1.

Step 3: Calculate the surface area

Select a surface ponding depth (d) that satisfies the geometric criteria and meets the site constraints. Selecting a deeper ponding depth (up to 1.5 ft) generally yields a smaller footprint, however, it will require greater consideration for public safety, energy dissipation, and plant selection.

Calculate the time for the selected ponding depth to filter through the planting media using the following equation:

$$d = t_p \times \frac{f_{\text{design}}}{12}$$

Where:

d = Ponding depth (max 1.5 ft) [ft]; t<sub>p</sub> = Required detention time for surface ponding (max 96 hr) [hr]; and  $f_{design}$  = Design infiltration rate [in/hr].

If  $t_p$  exceeds 96 hours, reduce surface ponding depth (d). In nearly all cases,  $t_p$  should not approach 96 hours unless  $f_{design}$  is low.

Calculate the required infiltrating surface (filter bottom area) using the following equation:

$$A = \frac{V_B}{d}$$

Where:

A = Bottom surface area of biofiltration area [ $ft^2$ ];

 $V_B$  = Biofiltration design volume [ft<sup>3</sup>]; and

d = Ponding depth (max 1.5 ft) [ft].

#### Flow Entrance and Energy Dissipation

Maintain a minimum slope of 1 percent for pervious surfaces and 0.5 percent for impervious surfaces to the biofiltration area inlet. The following types of flow entrance can be used for biofiltration cells:

- Level spreaders (i.e., slotted curbs) can be used to facilitate sheet flow.
- Dispersed, low velocity flow across a landscape area. Dispersed flow may not be possible given space limitations or if the biofiltration area is controlling roadway or parking lot flows where curbs are mandatory.
- Dispersed flow across pavement or gravel and past wheel stops for parking areas.
- Flow spreading trench around perimeter of biofiltration area. May be filled with pea gravel or vegetated with 3:1 side slopes similar to a swale. A vertical-walled open trench may also be used at the discretion of LACDPW.
- Curb cuts for roadside or parking lot areas, if approved by LACDPW: curb cuts should include rock or other erosion controls in the channel entrance to dissipate energy. Flow entrance should drop two to three inches from curb line and provide an area for settling and periodic removal of sediment and coarse material before flow dissipates to the remainder of the biofiltration area.
- Piped entrances, such as roof downspouts, should include rock, splash blocks, or other erosion controls at the entrance to dissipate energy and disperse flows.
- Woody plants (trees, shrubs, etc.) can restrict or concentrate flows and can be damaged by erosion around the root ball and must not be placed directly in the entrance flow path.

## Drainage

Biofiltration areas must be designed to drain below the planting soil in less than 96 hours. Soils must be allowed to dry out periodically in order to restore hydraulic capacity to receive stormwater runoff from subsequent storm events, maintain infiltration rates, maintain adequate soil oxygen levels for healthy soil biota and vegetation, and provide proper soil conditions for biodegradation and retention of pollutants.

## Underdrain

Biofiltration areas require an underdrain to collect and discharge stormwater runoff that has been filtered through the soil media, but not infiltrated, to another stormwater quality control measure, storm drain system, or receiving water. The underdrain must have a mainline diameter of eight inches using slotted PVC SDR 26 or PVC C9000. Slotted PVC allows for pressure water cleaning and root cutting, if necessary. The slotted pipe

should have two to four rows of slots cut perpendicular to the axis of the pipe or at right angles to the pitch of corrugations. Slots should be 0.04 to 0.1 inches wide with a length of 1 to 1.25 inches. Slots should be longitudinally-spaced such that the pipe has a minimum of one square inch opening per lineal foot and should face down.

The underdrain should be placed in a gravel envelope (Class 2 Permeable Material per Caltrans Spec. 68-1.025) that measures three feet wide and six inches deep. The underdrain is elevated from the bottom of the biofiltration area by six inches within the gravel envelope to create a fluctuating anaerobic/aerobic zone below the underdrain to facilitate denitrification within the anaerobic/anoxic zone and reduce nutrient concentrations. The top and sides of the underdrain pipe should be covered with gravel to a minimum depth of 12 inches. The underdrain and gravel envelope should be covered with a geomembrane liner to prevent clogging. The following aggregate should be used for the gravel envelope:

| Particle Size<br>(ASTM D422) | ,      |  |  |
|------------------------------|--------|--|--|
| ¾ inch                       | 100%   |  |  |
| 1⁄4 inch                     | 30-60% |  |  |
| #8                           | 20-50% |  |  |
| #50                          | 3-12%  |  |  |
| #200                         | 0-1%   |  |  |

Underdrains should be sloped at a minimum of 0.5 percent and must drain freely to an approved discharge point.

Rigid non-perforated observation pipes with a diameter equal to the underdrain diameter should be connected to the underdrain to provide a clean-out port as well as an observation well to monitor drainage rates. The wells/clean-outs should be connected to the perforated underdrain with the appropriate manufactured connections. The wells/clean-outs should extend six inches above the top elevation of the biofiltration area mulch, and should be capped with a lockable screw cap. The ends of underdrain pipes not terminating in an observation well/clean-out should also be capped.

## Hydraulic Restriction Layer

Lateral infiltration pathways may need to be restricted due to the close proximity of roads, foundations, or other infrastructure. A geomembrane liner, or other equivalent waterproofing, may be placed along the vertical walls to reduce lateral flows. This geomembrane liner must have a minimum thickness of 30 mils and meet the requirements of Table E-12. Generally, waterproof barriers should not be placed on the bottom of the biofiltration unit, as this would prevent incidental infiltration which is important to meeting the required pollutant load reduction.

#### Table E-12. Geomembrane Liner Specifications for Biofiltration Areas

| Parameter             | Test Method           | Specifications                   |  |
|-----------------------|-----------------------|----------------------------------|--|
| Material              |                       | Nonwoven geomembrane liner       |  |
| Unit weight           |                       | 8 oz/yd <sup>3</sup> (minimum)   |  |
| Filtration rate       |                       | 0.08 in/sec (minimum)            |  |
| Puncture strength     | ASTM D-751 (Modified) | 125 lbs (minimum)                |  |
| Mullen burst strength | ASTM D-751            | 400 lb/in <sup>2</sup> (minimum) |  |
| Tensile strength      | AST D-1682            | 300 lbs (minimum)                |  |
| Equiv. opening size   | US Standard Sieve     | No. 80 (minimum)                 |  |

#### Planting/Storage Media

- The planting media placed in the biofiltration area should achieve a long-term, inplace infiltration rate of at least 5 in/hr. Higher infiltration rates of up to 12 in/hr are permissible. The biofiltration soil media must retain sufficient moisture to support vigorous plant growth.
- The planting media mix must consist of 60 to 80 percent sand and 20 to 40 percent compost.
- Sand should be free of wood, waste, coatings such as clay, stone dust, carbonate, or any other deleterious material. All aggregate passing the No. 200 sieve size should be non-plastic. Sand for biofiltration should be analyzed by an accredited laboratory using #200, #100, #40, #30, #16, #8, #4, and 3/8 sieves (ASTM D422 or as approved by the local permitting authority) and meet the following gradations (Note: all sand complying with ASTM C33 for fine aggregate comply with the gradation requirements listed below):

| Particle Size<br>(ASTM D422) | % Passing by<br>Weight |
|------------------------------|------------------------|
| 3/8 inch                     | 100%                   |
| #4                           | 90-100%                |
| #8                           | 70-100%                |
| #16                          | 40-95%                 |
| #30                          | 15-70%                 |
| #40                          | 5-55%                  |
| #110                         | 0-15%                  |
| #200                         | 0-5%                   |

Note: The gradation of the sand component of the biofiltration soil media is believed to be a major factor in the infiltration rate of the media mix. If the desired hydraulic conductivity of the biofiltration soil media cannot be achieved within the specified proportions of sand and compost (#2), then it may be necessary to utilize sand at the coarser end of the range specified minimum percent passing.

- Compost should be a well-decomposed, stable, weed-free organic matter source derived from waste materials including yard debris, wood wastes, or other organic material not including manure or biosolids meeting standards developed by the USCC. The product shall be certified through the USCC STA Program (a compost testing and information disclosure program). Compost quality shall be verified via a laboratory analysis to be:
  - Feedstock materials must be specified and include one or more of the following: landscape/yard trimmings, grass clippings, food scraps, and agricultural crop residues.
  - pH between 6.5 and 8.0 (may vary with plant palette)
  - Organic Matter: 35 to 75 percent dry weight basis
  - Carbon and Nitrogen Ratio: 15:1 < C:N < 25:1
  - Maturity/Stability: Compost must have a dark brown color and a soil-like odor. Compost exhibiting a sour or putrid smell, containing recognizable grass or leaves, or is hot (120°F) upon delivery or rewetting is not acceptable.
  - Toxicity: any one of the following measures is sufficient to indicate nontoxicity:
    - NH<sub>4</sub>:NH<sub>3</sub> < 3
    - Ammonium < 500 ppm, dry weight basis
    - Seed germination > 80 percent of control
    - Plant trials > 80 percent of control
    - Solvita<sup>®</sup> > 5 index value
  - Nutrient content:
    - Total Nitrogen content  $\geq$  0.9 percent preferred
    - Total Boron should be < 80 ppm; soluble boron < 2.5 ppm</li>
  - Salinity: < 6.0 mmhos/cm
  - Compost for biofiltration area should be analyzed by an accredited laboratory using #200, ¼-inch, ½-inch, and 1-inch sieves (ASTM D422) and meet the gradation requirements in the table below:

| Particle Size<br>(ASTM D422) | % Passing by<br>Weight |
|------------------------------|------------------------|
| 1 inch                       | 99-100                 |
| 1⁄2 inch                     | 90-100                 |
| 1⁄4 inch                     | 40-90                  |
| #200                         | 2-10                   |

Tests should be sufficiently recent to represent the actual material that is anticipated to be delivered to the site. If processes or sources used by the supplier have changed significantly since the most recent testing, new tests should be requested.

The gradation of compost used in biofiltration soil media is believed to play an important role in the saturated infiltration rate of the media. To achieve a higher saturated infiltration rate, it may be necessary to utilize compost at the coarser end of the range (minimum percent passing). The percent passing the #200 sieve (fines) is believed to be the most important factor in hydraulic conductivity.

In addition, coarser compost mix provides more heterogeneity of the biofiltration soil media, which is believed to be advantageous for more rapid development of soil structure needed to support healthy biological processes. This may be an advantage for plant establishment with lower nutrient and water input.

 Biofiltration soil media not meeting the above criteria should be evaluated on a case-by-case basis. Alternative biofiltration soil media must meet the following specifications:

"Soils for biofiltration facilities must be sufficiently permeable to infiltrate stormwater runoff at a minimum of rate of 5 in/hr during the life of the facility, and provide sufficient retention of moisture and nutrients to support healthy vegetation." The following steps shall be followed by LACDPW to verify that alternative biofiltration soil media mixes meet the specification:

- Submittals The applicant must submit to LACDPW for approval:
  - A sample of mixed biofiltration soil media.
  - Certification from the soil supplier or an accredited laboratory that the biofiltration soil media meets the requirements of this specification.
  - Certification from an accredited geotechnical testing laboratory that the biofiltration soil media has an infiltration rate between 5 and 12 in/hr.
  - Organic content test results of the biofiltration soil media. Organic content test shall be performed in accordance with the Testing Methods for the Examination of Compost and Composting (TMECC) 05.07A, "Loss-On-Ignition Organic Matter Method".
  - Organic grain size analysis results of mixed biofiltration soil media performed in accordance with ASTM D422, Standard Test Method for Particle Size Analysis of Soils.
  - A description of the equipment and methods used to mix the sand and compost to produce the biofiltration soil media.
- The name of the testing laboratory(ies) and the following information:

- Contact person(s)
- Address(es)
- Phone contact(s)
- E-mail address(es)
- Qualifications of laboratory(ies) and personnel including date of current certification by STA, ASTM, or approved equal.
- Biofiltration soils shall be analyzed by an accredited laboratory using #200 and ½-inch sieves (ASTM D422 or as approved by LACDPW), and meet the gradation described in the table below:

| Particle Size<br>(ASTM D422) | % Passing by<br>Weight |
|------------------------------|------------------------|
| 1∕₂ inch                     | 97-100                 |
| #200                         | 2-5                    |

- Biofiltration soil media shall be analyzed by an accredited geotechnical laboratory for the following tests:
  - Moisture density relationships (compaction tests) must be conducted on biofiltration soil media. Biofiltration soil media for the permeability test shall be compacted to 85 to 90 percent of the maximum dry density (ASTM D1557).
  - Constant head permeability testing in accordance with ASTM D2434 shall be conducted on a minimum of two samples with a 6-inch mold and vacuum saturation.
- Mulch is recommended for the purpose of retaining moisture, preventing erosion, and minimizing weed growth. Projects subject to the California Model Water Efficiency Landscaping Ordinance (or comparable local ordinance) will be required to provide at least 2 inches of mulch. Aged mulch, also called compost mulch, reduces the ability of weeds to establish, keeps soil moist, and replenishes soil nutrients. Biofiltration areas must be covered with two to four inches (average three inches) of mulch at the start and an annual placement (preferably in June after weeding) of one to two inches of mulch beneath plants.
- The planting media design height must be marked appropriately, such as a collar on the overflow device or with a stake inserted two feet into the planting media and notched, to show biofiltration surface level and ponding level.

## Vegetation

Prior to installation, a licensed landscape architect must certify that all plants, unless otherwise specifically permitted, conform to the standards of the current edition of American Standard for Nursery Stock as approved by the American Standards Institute, Inc. All plant grades shall be those established in the current edition of American Standards for Nursery Stock.

• Shade trees must have a single main trunk. Trunks must be free of branches below the following heights:

| CALIPER (in) | Height (ft) |
|--------------|-------------|
| 1½-2½        | 5           |
| 3            | 6           |

- Plants must be tolerant of summer drought, ponding fluctuations, and saturated soil conditions for 96 hours.
- It is recommended that a minimum of three types of tree, shrubs, and/or herbaceous groundcover species be incorporated to protect against facility failure due to disease and insect infestations of a single species.
- Native plant species and/or hardy cultivars that are not invasive and do not require chemical inputs must be used to the maximum extent practicable.

The biofiltration area should be vegetated to resemble a terrestrial forest community ecosystem, which is dominated by understory trees, a shrub layer, and herbaceous ground cover. Select vegetation that:

- Is suited to well-drained soil;
- Will be dense and strong enough to stay upright, even in flowing water;
- Has minimum need for fertilizers;
- Is not prone to pests and is consistent with Integrated Pest Management practices; and
- Is consistent with local water conservation ordinance requirements.

## Irrigation System

Provide an irrigation system to maintain viability of vegetation, if applicable. The irrigation system must be designed to local code or ordinance specifications.

## Restricted Construction Materials

The use of pressure-treated wood or galvanized metal at or around a biofiltration area is prohibited.

## **Overflow Device**

An overflow device is required at the 18-inch ponding depth. The following, or equivalent, should be provided:

- A vertical PVC pipe (SDR 26) to act as an overflow riser.
- The overflow riser(s) should be eight inches or greater in diameter, so it can be cleaned without damage to the pipe.

 The inlet to the riser should be at the ponding depth (18 inches for fenced biofiltration areas and 6 inches for areas that are not fenced), and be capped with a spider cap to exclude floating mulch and debris. Spider caps should be screwed in or glued (e.g., not removable). The overflow device should convey stormwater runoff in excess of 1.5 times the SWQDv that is not reliably retained on the project site to an approved discharge location (another stormwater quality control measure, storm drain system, or receiving water).

#### Maintenance Requirements

Maintenance and regular inspections are important for proper function of biofiltration areas. Biofiltration areas require annual plant, soil, and mulch layer maintenance to ensure optimal infiltration, storage, and pollutant removal capabilities. In general, biofiltration maintenance requirements are typical landscape care procedures and include:

- Irrigate plants as needed during prolonged dry periods. In general, plants should be selected to be drought-tolerant and not require irrigation after establishment (two to three years).
- Inspect flow entrances, ponding area, and surface overflow areas periodically, and replace soil, plant material, and/or mulch layer in areas if erosion has occurred. Properly-designed facilities with appropriate flow velocities should not cause erosion except potentially during in extreme events. If erosion occurs, the flow velocities and gradients within the biofiltration area and flow dissipation and erosion protection strategies in the pretreatment area and flow entrance should be reassessed. If sediment is deposited in the biofiltration area, identify the source of the sediment within the tributary area, stabilize the source, and remove excess surface deposits.
- Prune and remove dead plant material as needed. Replace all dead plants, and if specific plants have a high mortality rate, assess the cause and, if necessary, replace with more appropriate species.
- Remove weeds as needed until plants are established. Weed removal should become less frequent if the appropriate plant species are used and planting density is attained.
- Select the proper soil mix and plants for optimal fertility, plant establishment, and growth to preclude the use of nutrient and pesticide supplements. By design, biofiltration facilities are located in areas where phosphorous and nitrogen levels are often elevated such that these should not be limiting nutrients. Addition of nutrients and pesticides may contribute pollutant loads to receiving waters.
- In areas where heavy metals deposition is likely (i.e., tributary areas to industrial, vehicle dealerships/repair, parking lots, roads), replace mulch annually. In areas where metals deposition is less likely (i.e., residential lots), replace or add mulch as needed to maintain a two to three inch depth at least once every two years.

- Analyze soil for fertility and pollutant levels if necessary. Biofiltration soil media are designed to maintain long-term fertility and pollutant processing capability.
- Eliminate standing water to prevent vector breeding.
- Inspect overflow devices for obstructions or debris, which should be removed immediately. Repair or replace damaged pipes upon discovery.
- Inspect, and clean if necessary, the underdrain.

A summary of potential problems that need to be addressed by maintenance activities is presented in Table E-13.

The County requires execution of a maintenance agreement to be recorded by the property owner for the on-going maintenance of any privately-maintained stormwater quality control measures. The property owner is responsible for compliance with the maintenance agreement. A sample maintenance agreement is presented in Appendix H.

| Problem                          | Conditions When Maintenance Is<br>Needed   | Maintenance Required   |
|----------------------------------|--|--|
| Vegetation                       | Overgrown vegetation   | Mow and prune vegetation as appropriate.   |
|                                  | Presence of invasive, poisonous,<br>nuisance, or noxious vegetation or<br>weeds                  | Remove this vegetation and plant native species as needed.   |
| Trash and Debris                 | Trash, plant litter, and dead leaves present   | Remove and properly dispose of trash and debris.   |
| Irrigation (if applicable)       | Not functioning correctly  | Check irrigation system for clogs<br>or broken lines and repair as<br>needed.  |
| Inlet/Overflow                   | Inlet/overflow areas clogged with sediment and/or debris   | Remove material.   |
|                                  | Overflow pipe blocked or broken  | Repair as needed.  |
| Erosion/Sediment<br>Accumulation | Splash pads or spreader incorrectly<br>placed<br>Presence of erosion or sediment<br>accumulation | Check inlet structure to ensure<br>proper function. Repair, or<br>replace if necessary, the inlet<br>device. Repair eroded areas<br>with gravel as needed. Re-grade<br>the biofiltration area as needed. |
| Contaminants and Pollution       | Any evidence of oil, gasoline, contaminants, or other pollutants                                 | Remove any evidence of visual contamination from floatables such as oil and grease.  |
| Standing water                   | Standing water observed more than 96 hours after storm event                                     | Inspect, and clean as needed,<br>the underdrain to ensure proper<br>function. Clear clogs as needed.<br>Remove and replace planter<br>media (sand, gravel, topsoil,<br>mulch) and vegetation.            |

 Table E-13. Biofiltration Troubleshooting Summary

# SECTION XI

# **Geotechnical Report (Infiltration Study)**

# GEOTECHNICAL INVESTIGATION PROPOSED WAREHOUSE

SEC Lakeland Road and Norwalk Boulevard Santa Fe Springs, California for Duke Realty



December 8, 2021

Duke Realty 200 Spectrum Center Drive, Suite 1600 Irvine, California 92618



Attention: Mr. D.J. Arellano, P.E. Director, Development Services

Project No.: **21G248-1** 

Subject: **Geotechnical Investigation** Proposed Warehouse SEC Lakeland Road and Norwalk Boulevard Santa Fe Springs, California

Dear Mr. Weber:

In accordance with your request, we have conducted a geotechnical investigation at the subject site. We are pleased to present this report summarizing the conclusions and recommendations developed from our investigation.

We sincerely appreciate the opportunity to be of service on this project. We look forward to providing additional consulting services during the course of the project. If we may be of further assistance in any manner, please contact our office.

Respectfully Submitted,

# SOUTHERN CALIFORNIA GEOTECHNICAL, INC. Daniel W. Nielsen, GE 3166 Senior Engineer Robert G. Trazo, M.Sc., GE 2655 Principal Engineer Distribution: (1) Addressee

# **TABLE OF CONTENTS**

| 1.0 EXECUTIVE SUMMARY   | 1  |
|---|--|
| 2.0 SCOPE OF SERVICES   | 3  |
| 3.0 SITE AND PROJECT DESCRIPTION  | 4  |
| <ul><li>3.1 Site Conditions</li><li>3.2 Proposed Development</li></ul>  | 4<br>4   |
| 4.0 SUBSURFACE EXPLORATION  | 6  |
| <ul><li>4.1 Scope of Exploration/Sampling Methods</li><li>4.2 Geotechnical Conditions</li></ul>   | 6<br>6   |
| 5.0 LABORATORY TESTING  | 8  |
| 6.0 CONCLUSIONS AND RECOMMENDATIONS   | 10   |
| <ul> <li>6.1 Seismic Design Considerations</li> <li>6.2 Geotechnical Design Considerations</li> <li>6.3 Site Grading Recommendations</li> <li>6.4 Construction Considerations</li> <li>6.5 Foundation Design and Construction</li> <li>6.6 Floor Slab Design and Construction</li> <li>6.7 Trash Enclosure Design Parameters</li> <li>6.8 Exterior Flatwork Design and Construction</li> <li>6.9 Retaining Wall Design and Construction</li> <li>6.10 Pavement Design Parameters</li> </ul> | 10<br>12<br>15<br>19<br>21<br>22<br>23<br>24<br>25<br>27 |
| 7.0 GENERAL COMMENTS  | 30   |
| APPENDICES  |  |

- A Plate 1: Site Location Map Plate 2: Boring Location Plan
- B Boring Logs
- C Laboratory TestingD Grading Guide Specifications
- E Seismic Design Parameters



Presented below is a brief summary of the conclusions and recommendations of this investigation. Since this summary is not all inclusive, it should be read in complete context with the entire report.

## **Geotechnical Design Considerations**

- Artificial fill soils were encountered at all of the boring locations, extending from the ground surface or beneath the pavements to depths of  $2\frac{1}{2}$  to  $6\frac{1}{2}$  ± feet.
- The fill soils and near-surface alluvial soils possess variable strengths and densities. The
  existing fill soils are considered to represent undocumented fill. These soils, in their present
  condition, are not considered suitable for support of the foundation loads of the new structure.
  Additionally, it is anticipated that demolition of the existing structures and associated
  improvements will cause disturbance of the upper 3 to 5± feet of soil.
- Remedial grading will be necessary within the proposed building area to remove the undocumented fill soils in their entirety, the upper portion of the near-surface native alluvial soils, and any soils disturbed during the demolition process, and replace these materials as compacted structural fill soils.

## **Site Preparation Recommendations**

- Demolition of the existing structures will be necessary to facilitate the proposed development. Demolition debris should be disposed of off-site. Alternatively, concrete and asphalt debris may be crushed into miscellaneous base (CMB) and used as fill on the site.
- If the existing trees will not remain with the proposed development, then the entire root mass should also be stripped from the site.
- Remedial grading is recommended to be performed within the proposed building area in order to remove all of the undocumented fill soils in their entirety, the upper portion of the near-surface native alluvial soils, and any soils disturbed during site stripping and demolition operations. The soils within the proposed building pad area should be overexcavated to a depth of 5 feet below existing grade and to a depth of at least 4 feet below proposed building pad subgrade elevations, whichever is greater.
- The depth of overexcavation should also be sufficient to remove any existing fill soils. The proposed foundation influence zones should be overexcavated to a depth of at least 3 feet below proposed foundation bearing grade.
- Based on conditions encountered at the exploratory boring locations, moist to very moist soils
  may be encountered at or near the base of the recommended overexcavation. Scarification
  and air drying of these materials may be sufficient to obtain a stable subgrade. However, if
  highly unstable soils are identified, and if the construction schedule does not allow for delays
  associated with drying, mechanical stabilization, usually consisting of coarse crushed stone
  and/or geotextile, may be necessary.
- After the overexcavation has been completed, the resulting subgrade soils should be evaluated by the geotechnical engineer to identify any additional soils that should be removed. The resulting subgrade should then be scarified to a depth of 12 inches and moisture conditioned (or air dried) to 2 to 4 percent above optimum. The previously excavated soils



may then be replaced as compacted structural fill. All structural fill soils should be compacted to at least 90 percent of the ASTM D-1557 maximum dry density.

- The new pavement and flatwork subgrade soils are recommended to be scarified to a depth of 12± inches, moisture conditioned and recompacted to at least 90 percent of the ASTM D-1557 maximum dry density.
- Based on the results of corrosivity testing, the on-site soils are considered to be severely corrosive to ductile iron pipe.

#### Foundation Design Recommendations

- Spread footing foundations, supported in newly placed structural fill soils.
- Maximum, net allowable soil bearing pressure: 2,500 lbs/ft<sup>2</sup>.
- Maximum, net allowable soil bearing pressure: 1,500 lbs/ft<sup>2</sup> for new footings if the full lateral extent of the recommended remedial grading cannot be achieved.
- Reinforcement consisting of at least six (6) No. 5 rebars (3 top and 3 bottom) in strip footings. Additional reinforcement may be necessary for structural considerations.

## **Building Floor Slab Design Recommendations**

- Conventional Slab-on-Grade: Minimum 6 inches thick.
- Modulus of Subgrade Reaction: k = 100 psi/in.
- Minimum slab reinforcement: No. 3 bars at 16 inches on-center, in both directions, due to the medium expansive potential of the near-surface soils. The actual thickness and reinforcement of the floor slab should be determined by the structural engineer.

| ASPHALT PAVEMENTS (R = 10) |   |          |          |          |          |
|----------------------------|---|----------|----------|----------|----------|
|                            | Thickness (inches)                            |          |          |          |          |
| Materiale                  | Auto Parking and Truck Traffic                |          |          |          |          |
| Materials                  | Auto Drive Lanes $(TI = 4.0 \text{ to } 5.0)$ | TI = 6.0 | TI = 7.0 | TI = 8.0 | TI = 9.0 |
| Asphalt Concrete           | 3   | 31⁄2     | 4        | 5        | 51⁄2     |
| Aggregate Base             | 9   | 12       | 15       | 16       | 19       |
| Compacted Subgrade         | 12  | 12       | 12       | 12       | 12       |

#### **Pavements**

| PORTLAND CEMENT CONCRETE PAVEMENTS (R = 10)    |                               |         |          |          |  |
|--|-------------------------------|---------|----------|----------|--|
|  | Thickness (inches)            |         |          |          |  |
| Materials                                      | Autos and Light Truck Traffic |         |          |          |  |
|  | (TI = 6.0)                    | TI =7.0 | TI = 8.0 | TI = 9.0 |  |
| PCC  | 5                             | 51⁄2    | 7        | 81⁄2     |  |
| Compacted Subgrade<br>(95% minimum compaction) | 12                            | 12      | 12       | 12       |  |



The scope of services performed for this project was in accordance with our Proposal No. 21P435, dated October 6, 2021. The scope of services included a visual site reconnaissance, subsurface exploration, field and laboratory testing, and geotechnical engineering analysis to provide criteria for preparing the design of the building foundations, building floor slab, and parking lot pavements along with site preparation recommendations and construction considerations for the proposed development. The evaluation of the environmental aspects of this site was beyond the scope of services for this geotechnical investigation.



# 3.1 Site Conditions

The site is located at the southeast corner of Lakeland Road and Norwalk Boulevard in Santa Fe Springs, California. The street address of the site is 12300 Lakeland Boulevard. The site is bounded to the north by Lakeland Road, to the west by Norwalk Boulevard and an existing aerospace manufacturing facility, to the south by a parking lot and a commercial/industrial building, and to the east by Getty Drive. The general location of the site is illustrated on the Site Location Map, included as Plate 1 of this report.

The site consists of an L-shaped parcel,  $8.45\pm$  acres in size. The site is developed with a twostory office building in the northeastern corner of the property, two small metal buildings in the western portion of the property, and a large steel-frame-supported canopy structure in the east/central portion of the site. This canopy structure possesses a footprint area of about 50,000 ft<sup>2</sup>. The northwesternmost portion of the site is covered with open-graded gravel, and is presently used as a parking lot. Large crane/lift equipment is present on the north and south sides of the large canopy structure. These cranes/lifts consist of permanent structures with elevated steel tracks, supported by steel frames which are presumably supported by a concrete foundation located beneath the pavements. The crane systems extend from the east property line along the north and south perimeters of the canopy to the west property line on the south side of the canopy structure, and about 250 feet west of the structure on the north side. These crane systems are about  $65\pm$  feet wide. No structural information for the existing structures has been provided to our office, but we assume that the buildings and crane/lift structures are supported by conventional shallow foundation systems.

The buildings are surrounded by asphaltic concrete pavements, with sparse areas of Portland Cement concrete (PCC) pavements. The pavements throughout the site are generally in poor condition, with extensive cracking throughout. he ground surface cover of the northwestern parking lot consists of open graded gravel.

Detailed topographic information was not available at the time of this report. Based on elevations obtained from Google Earth and visual observations made at the time of the subsurface investigation, the overall site is relatively flat, with less than  $4\pm$  feet of elevation differential throughout the site. The site slopes gently to the west with a gradient of less than  $1\pm$  percent.

## 3.2 Proposed Development

A conceptual site plan, identified as Scheme 1 and prepared by HPA, Inc., for the proposed development was provided to our office by the client. Based on this plan, the site will be developed with one (1) warehouse building. The building will be  $184,680 \pm ft^2$  in size and will be located in the east-central area of the subject site. Dock-high doors will be constructed along a portion of the west building wall. The building will be surrounded by asphaltic concrete pavements in the



parking and drive areas, Portland cement concrete pavements in the truck court areas, and limited areas of concrete flatwork and landscape planters throughout.

Detailed structural information has not been provided. It is assumed that the new building will be a single-story structure of tilt-up concrete construction, supported on a conventional shallow foundation system with a concrete slab-on-grade floor. Based on the assumed construction, maximum column and wall loads are expected to be on the order of 100 kips and 4 to 7 kips per linear foot, respectively.

No significant amounts of below grade construction, such as basements or crawl spaces, are expected to be included in the proposed development. Based on the assumed topography, cuts and fills of up to 3 to  $4\pm$  feet are expected to be necessary to achieve the proposed site grades. It should be noted that this estimate does not include any remedial grading, recommendations for which are presented in a subsequent section of this report.



# 4.0 SUBSURFACE EXPLORATION

# 4.1 Scope of Exploration/Sampling Methods

The subsurface exploration conducted for this project consisted of eight (8) borings advanced to depths of 15 to  $25\pm$  feet below the existing site grades. All of the borings were logged during drilling by a member of our staff.

The borings were advanced with hollow-stem augers, by a conventional truck-mounted drilling rig. Representative bulk and relatively undisturbed soil samples were taken during drilling. **Relatively undisturbed soil samples were taken with a split barrel "California Sampler" containing** a series of one inch long, 2.416± inch diameter brass rings. This sampling method is described in ASTM Test Method D-3550. In-situ samples were also taken using a 1.4± inch inside diameter split spoon sampler, in general accordance with ASTM D-1586. Both of these samplers are driven into the ground with successive blows of a 140-pound weight falling 30 inches. The blow counts obtained during driving are recorded for further analysis. Bulk samples were collected in plastic bags to retain their original moisture content. The relatively undisturbed ring samples were placed in molded plastic sleeves that were then sealed and transported to our laboratory.

The approximate locations of the borings are indicated on the Boring Location Plan, included as Plate 2 in Appendix A of this report. The Boring Logs, which illustrate the conditions encountered at the boring locations, as well as the results of some of the laboratory testing, are included in Appendix B.

## 4.2 Geotechnical Conditions

#### <u>Pavements</u>

Asphaltic concrete pavements (AC) were encountered at the ground surface of all boring locations, with the exception of Boring No. B-5. The AC pavements generally consist of 3 to  $5\pm$  inches in thickness with 0 to  $5\pm$  inches aggregate base at the boring locations.

#### Artificial Fill

Artificial fill soils were encountered at the ground surface or beneath the pavements at all boring locations, extending to depths of  $2\frac{1}{2}$  to  $6\frac{1}{2}$  to  $6\frac{1}{2}$  teet below existing site grades. The fill soils consist of medium stiff to very stiff fine sandy clays and silty clays, as well as loose to medium dense silty fine sands and fine sandy silts. The fill soils possess a disturbed and mottled appearance, resulting in their classification as artificial fill.



#### <u>Alluvium</u>

Native alluvium was encountered beneath the fill soils at all of the boring locations, extending to at least the maximum depth explored of  $25\pm$  feet below ground surface. The alluvium consists of stiff to very stiff fine sandy clays, silty clays, occasional very stiff to hard clayey silts, and loose to dense silty fine sands and fine sandy silts, stiff to hard clayey silts, medium dense clayey fine sands, and very stiff fine sandy clays. Various amounts of calcareous veining and nodules and iron oxide staining were encountered throughout various strata within the native soils.

#### Groundwater

Free water was not encountered during the drilling of any of the borings. Based on the moisture content of the recovered soil samples and the lack of free water in the borings, the static groundwater table is at a greater depth than  $25\pm$  feet below existing site grades.

As part of our research, we reviewed available groundwater data in order to determine the historic high groundwater level for the site. The primary reference used to determine the historic groundwater depths in this area is the California Geological Survey (CGS) Open File Report 98-28, the Seismic Hazard Zone Report for the Whittier 7.5-Minute Quadrangle, which indicates that the historic high groundwater level for the site was about 20 to 22± feet below the ground surface.

Recent water level data was obtained from the California State Water Resources Control Board, GeoTracker, website, <u>https://geotracker.waterboards.ca.gov/</u>. One monitoring wells on record is located 175± feet north of the site. Water level readings within this monitoring wells indicate a high groundwater level of 119± feet below the ground surface in June 2021.



The soil samples recovered from the subsurface exploration were returned to our laboratory for further testing to determine selected physical and engineering properties of the soils. The tests are briefly discussed below. It should be noted that the test results are specific to the actual samples tested, and variations could be expected at other locations and depths.

#### **Classification**

All recovered soil samples were classified using the Unified Soil Classification System (USCS), in accordance with ASTM D-2488. The field identifications were then supplemented with additional visual classifications and/or by laboratory testing. The USCS classifications are shown on the Boring Logs and are periodically referenced throughout this report.

#### Density and Moisture Content

The density has been determined for selected relatively undisturbed ring samples. These densities were determined in general accordance with the method presented in ASTM D-2937. The results are recorded as dry unit weight in pounds per cubic foot. The moisture contents are determined in accordance with ASTM D-2216, and are expressed as a percentage of the dry weight. These test results are presented on the Boring Logs.

#### **Consolidation**

Selected soil samples were tested to determine their consolidation potential, in accordance with ASTM D-2435. The testing apparatus is designed to accept either natural or remolded samples in a one-inch-high ring, approximately 2.416 inches in diameter. Each sample is then loaded incrementally in a geometric progression and the resulting deflection is recorded at selected time intervals. Porous stones are in contact with the top and bottom of the sample to permit the addition or release of pore water. The samples are typically inundated with water at an intermediate load to determine their potential for collapse or heave. The results of the consolidation testing are plotted on Plates C-1 through C-12 in Appendix C of this report.

#### Maximum Dry Density and Optimum Moisture Content

One representative bulk sample has been tested for its maximum dry density and optimum moisture content. The results have been obtained using the Modified Proctor procedure, per ASTM D-1557 and are presented on Plate C-13 in Appendix C of this report. This test is generally used to compare the in-situ densities of undisturbed field samples, and for later compaction testing. Additional testing of other soil types or soil mixes may be necessary at a later date.

#### Expansion Index

The expansion potential of the on-site soils was determined in general accordance with ASTM D-4829. The testing apparatus is designed to accept a 4-inch diameter, 1-in high, remolded sample. The sample is initially remolded to  $50 \pm 1$  percent saturation and then loaded with a surcharge



equivalent to 144 pounds per square foot. The sample is then inundated with water, and allowed to swell against the surcharge. The resultant swell or consolidation is recorded after a 24-hour period. The results of the EI testing are as follows:

| Sample Identification | Expansion Index | <b>Expansive Potential</b> |
|-----------------------|-----------------|----------------------------|
| B-3 @ 0 to 5 feet     | 83              | Medium                     |

### Soluble Sulfates

A representative sample of the near-surface soil was submitted to a subcontracted analytical laboratory for determination of soluble sulfate content. Soluble sulfates are naturally present in soils, and if the concentration is high enough, can result in degradation of concrete which comes into contact with these soils. The results of the soluble sulfate testing are presented below, and are discussed further in a subsequent section of this report.

| Sample Identification | Soluble Sulfates (%) | Sulfate Classification |
|-----------------------|----------------------|------------------------|
| B-8 @ 0 to 5 feet     | 0.003                | Not Applicable (S0)    |

# Corrosivity Testing

One representative sample of the near-surface soils was submitted to a subcontracted corrosion engineering laboratory to identify potentially corrosive characteristics with respect to common construction materials. The corrosivity testing included a determination of the electrical resistivity, pH, and chloride and nitrate concentrations of the soils, as well as other tests. The results of some of these tests are presented below.

| Sample Identification | <u>Saturated Resistivity</u><br><u>(ohm-cm)</u> | <u>рН</u> | <u>Chlorides</u><br>(mg/kg) | <u>Nitrates</u><br>(mg/kg) |
|-----------------------|---|-----------|-----------------------------|----------------------------|
| B-4 @ 0 to 5 feet     | 6,800   | 7.6       | 4.0                         | 3.6                        |



# **6.0 CONCLUSIONS AND RECOMMENDATIONS**

Based on the results of our review, field exploration, laboratory testing and geotechnical analysis, the proposed development is considered feasible from a geotechnical standpoint. The recommendations contained in this report should be taken into the design, construction, and grading considerations.

The recommendations are contingent upon all grading and foundation construction activities being monitored by the geotechnical engineer of record. The recommendations are provided with the assumption that an adequate program of client consultation, construction monitoring, and testing will be performed during the final design and construction phases to verify compliance with these recommendations. Maintaining Southern California Geotechnical, Inc., (SCG) as the geotechnical consultant from the beginning to the end of the project will provide continuity of services. The geotechnical engineering firm providing testing and observation services shall assume the responsibility of Geotechnical Engineer of Record.

The Grading Guide Specifications, included as Appendix D, should be considered part of this report, and should be incorporated into the project specifications. The contractor and/or owner of the development should bring to the attention of the geotechnical engineer any conditions that differ from those stated in this report, or which may be detrimental for the development.

# 6.1 Seismic Design Considerations

The subject site is located in an area which is subject to strong ground motions due to earthquakes. The performance of a site-specific seismic hazards analysis was beyond the scope of this investigation. However, numerous faults capable of producing significant ground motions are located near the subject site. Due to economic considerations, it is not generally considered reasonable to design a structure that is not susceptible to earthquake damage. Therefore, significant damage to structures may be unavoidable during large earthquakes. The proposed structure should, however, be designed to resist structural collapse and thereby provide reasonable protection from serious injury, catastrophic property damage and loss of life.

# Faulting and Seismicity

Research of available maps indicates that the subject site is not located within an Alquist-Priolo Earthquake Fault Zone. Furthermore, SCG did not identify any evidence of faulting during the geotechnical investigation. Therefore, the possibility of significant fault rupture on the site is considered to be low.

The potential for other geologic hazards such as seismically induced settlement, lateral spreading, tsunamis, inundation, seiches, flooding, and subsidence affecting the site is considered low.



# Seismic Design Parameters

The 2019 California Building Code (CBC) provides procedures for earthquake resistant structural design that include considerations for on-site soil conditions, occupancy, and the configuration of the structure including the structural system and height. The seismic design parameters presented below are based on the soil profile and the proximity of known faults with respect to the subject site.

Based on standards in place at the time of this report, the proposed development is expected to be designed in accordance with the requirements of the 2019 edition of the California Building Code (CBC), which was adopted on January 1, 2020.

The 2019 CBC Seismic Design Parameters have been generated using the <u>SEAOC/OSHPD Seismic</u> <u>Design Maps Tool</u>, a web-based software application available at the website www.seismicmaps.org. This software application calculates seismic design parameters in accordance with several building code reference documents, including ASCE 7-16, upon which the 2019 CBC is based. The application utilizes a database of risk-targeted maximum considered earthquake (MCE<sub>R</sub>) site accelerations at 0.01-degree intervals for each of the code documents. The table below was created using data obtained from the application. The output generated from this program is included as Plate E-1 in Appendix E of this report.

The 2019 CBC requires that a site-specific ground motion study be performed in accordance with Section 11.4.8 of ASCE 7-16 for Site Class D sites with a mapped S<sub>1</sub> value greater than 0.2. However, Section 11.4.8 of ASCE 7-16 also indicates an exception to the requirement for a site-specific ground motion hazard analysis for certain structures on Site Class D sites. The commentary for Section 11 of ASCE 7-16 (Page 534 of Section C11 of ASCE 7-16) indicates that **"In general, this exception effectively limits the requirements for site**-specific hazard analysis to very tall and or flexible structures at Site Class D sites." **Based on our understanding of the proposed development, the seismic design parameters presented below were calculated assuming that the exception in Section 11.4.8 applies to the proposed structure at this site. However, the structure Based on the exception, the spectral response accelerations presented below were calculated using the site coefficients (F<sub>a</sub> and F<sub>v</sub>) from Tables 1613.2.3(1) and 1613.2.3(2) presented in Section 16.4.4 of the 2019 CBC.** 

| Parameter   | Value           |       |
|---|-----------------|-------|
| Mapped Spectral Acceleration at 0.2 sec Period        | Ss              | 1.697 |
| Mapped Spectral Acceleration at 1.0 sec Period        | S <sub>1</sub>  | 0.607 |
| Site Class  |                 | D     |
| Site Modified Spectral Acceleration at 0.2 sec Period | Sms             | 1.697 |
| Site Modified Spectral Acceleration at 1.0 sec Period | S <sub>M1</sub> | 1.032 |
| Design Spectral Acceleration at 0.2 sec Period        | Sds             | 1.132 |
| Design Spectral Acceleration at 1.0 sec Period        | Sd1             | 0.688 |

# **2019 CBC SEISMIC DESIGN PARAMETERS**



It should be noted that the site coefficient  $F_v$  and the parameters  $S_{M1}$  and  $S_{D1}$  were not included in the <u>SEAOC/OSHPD Seismic Design Maps Tool</u> output for the ASCE 7-16. We calculated these parameters-based on Table 11.4-2 in Section 11.4.4 of ASCE 7-16 using the value of  $S_1$  obtained from the <u>Seismic Design Maps Tool</u>, assuming that a site-specific ground motion hazards analysis is not required for the proposed building at this site.

# Liquefaction

Liquefaction is the loss of the strength in generally cohesionless, saturated soils when the porewater pressure induced in the soil by a seismic event becomes equal to or exceeds the overburden pressure. The primary factors which influence the potential for liquefaction include groundwater table elevation, soil type and grain size characteristics, relative density of the soil, initial confining pressure, and intensity and duration of ground shaking. The depth within which the occurrence of liquefaction may impact surface improvements is generally identified as the upper 50 feet below the existing ground surface. Liquefaction potential is greater in saturated, loose, poorly graded fine sands with a mean ( $d_{50}$ ) grain size in the range of 0.075 to 0.2 mm (Seed and Idriss, 1971). Clayey (cohesive) soils or soils which possess clay particles (d<0.005mm) in excess of 20 percent (Seed and Idriss, 1982) are generally not considered to be susceptible to liquefaction, nor are those soils which are above the historic static groundwater table.

The <u>Earthquake Zones of Required Investigation</u>, <u>Whittier Quadrangle</u>, published by the CGS indicates that the subject site is not located within a designated liquefaction hazard zone. In addition, the subsurface conditions encountered at the subject site are not considered to be conducive to liquefaction. Based on the lack of a static groundwater table within the upper  $50 \pm$  feet, and the mapping performed by the CGS, liquefaction is not considered to be a significant design concern for this project.

# 6.2 Geotechnical Design Considerations

# <u>General</u>

Artificial fill soils were encountered at all of the boring locations, extending from the ground surface to depths of  $2\frac{1}{2}$  to  $6\frac{1}{2}\pm$  feet. The fill soils and near-surface alluvial soils possess varying strengths. The existing fill soils are considered to represent undocumented fill. These soils, in their present condition, are not considered suitable to support the foundation and floor slab loads of the new structure. Additionally, it is anticipated that demolition of the existing structures and associated improvements will cause disturbance within the upper 3 to  $5\pm$  feet of the near-surface soils. Therefore, remedial grading is considered warranted to remove the undocumented fill soils in their entirety, the upper portion of the near-surface native alluvial soils, and any soils disturbed during the demolition of the existing buildings and improvements, and replace these materials as compacted structural fill soils.



# <u>Settlement</u>

The recommended remedial grading will remove the existing undocumented fill soils and a portion of the near-surface native alluvial soils and replace these materials as compacted structural fill. The native soils that will remain in place below the recommended depth of overexcavation will not be subject to significant stress increases from the foundations of the new structure. Therefore, following completion of the recommended grading, post-construction settlements are expected to be within tolerable limits.

# Expansion

The near-surface soils at this site generally consists of silty clays, sandy clays, clayey sands, and silty sands and sandy silts. Laboratory testing performed on a representative sample of the near-surface soils indicates that these materials possess a medium expansion potential (EI = 83). Based on the presence of expansive soils at this site, care should be given to proper moisture conditioning of all building pad subgrade soils to a moisture content of 2 to 4 percent above the ASTM D-1557 optimum during site grading. In addition to adequately moisture conditioning the subgrade soils and fill soils during grading, special care must be taken to maintaining moisture content of these soils at 2 to 4 percent above the optimum moisture content. This will require the contractor to frequently moisture condition these soils throughout the grading process, unless grading occurs during a period of relatively wet weather. Additional design considerations related to the expansive soils are presented in Section 6.4 of this report.

# Soluble Sulfates

The result of the soluble sulfate testing indicates that the tested soil sample possesses a level of **soluble sulfates that is considered to be "not applicable" (S0) with respect to the American** Concrete Institute (ACI) Publication 318-14 <u>Building Code Requirements for Structural Concrete</u> <u>and Commentary</u>, Section 4.3. Therefore, specialized concrete mix designs are not considered to be necessary, with regard to sulfate protection purposes. It is, however, recommended that additional soluble sulfate testing be conducted at the completion of rough grading to verify the soluble sulfate concentrations of the soils which are present at pad grade within the building area.

# Corrosion Potential

The results of laboratory testing indicate that the tested sample of the on-site soils possesses a saturated resistivity value of 6,800 ohm-cm, and a pH value of 7.6. These test results have been evaluated in accordance with guidelines published by the Ductile Iron Pipe Research Association (DIPRA). The DIPRA guidelines consist of a point system by which characteristics of the soils are used to quantify the corrosivity characteristics of the site. Resistivity and pH are two of the five factors that enter into the evaluation procedure. Redox potential, relative soil moisture content and sulfides are also included. Although sulfide testing was not part of the scope of services for this project, we have evaluated the corrosivity characteristics of the on-site soils using resistivity, pH and moisture content. Based on these factors, and utilizing the DIPRA procedure, the tested soils are not considered to be corrosive to ductile iron pipe.

Based on American Concrete Institute (ACI) Publication 318 <u>Building Code Requirements for</u> <u>Structural Concrete and Commentary</u>, reinforced concrete that is exposed to external sources of



chlorides requires corrosion protection for the steel reinforcement contained within the concrete. **ACI 318 defines concrete exposed to moisture and an external source of chlorides as "severe" or** exposure category C2. ACI 318 does not clearly define a specific chloride concentration at which contact with the adjacent soil will constitute a "C2" or severe exposure. However, the Caltrans Memo to Designers 10-5, Protection of Reinforcement Against Corrosion Due to Chlorides, Acids and Sulfates, dated June 2010, indicates that soils possessing chloride concentrations greater than 500 mg/kg are considered to be corrosive to reinforced concrete. The results of the laboratory testing indicate a chloride concentration of 4.0 mg/kg. Therefore, a chloride exposure category of C1 is considered appropriate for this site.

Nitrates present in soil can be corrosive to copper tubing at concentrations greater than 50 mg/kg. The tested sample possesses a nitrate concentration of 3.6 mg/kg. Based on this test result, the on-site soils are not considered to be corrosive to copper pipe.

It should be noted that SCG does not practice in the field of corrosion engineering. Therefore, the client may wish to contact a corrosion engineer to provide a more thorough evaluation.

# Shrinkage/Subsidence

Removal and recompaction of the near-surface existing soils and bedrock materials is estimated to result in an average shrinkage of 4 to 12 percent. However, shrinkage estimates for the individual samples range between 1 and 22 percent based on the results of density testing and the assumption that the onsite soils will be compacted to about 92 percent of the ASTM D-1557 maximum dry density. It should be noted that the shrinkage estimate is based on the results of dry density testing performed on small-diameter samples of the existing soils taken at the boring locations. If a more accurate and precise shrinkage estimate is desired, SCG can perform a shrinkage study involving several excavated test-pits where in-place densities are determined using in-situ testing methods instead of laboratory density testing on small-diameter samples. Please contact SCG for details and a cost estimate regarding a shrinkage study, if desired.

Minor ground subsidence is expected to occur in the soils below the zone of removal, due to settlement and machinery working. The subsidence is estimated to be 0.1 feet. This estimate may be used for grading in areas that are underlain by native alluvial soils.

These estimates are based on previous experience and the subsurface conditions encountered at the boring locations. The actual amount of subsidence is expected to be variable and will be dependent on the type of machinery used, repetitions of use, and dynamic effects, all of which are difficult to assess precisely.

# Grading and Foundation Plan Review

Grading and foundation plans were not available at the time of this report. It is therefore recommended that we be provided with copies of the preliminary grading and foundation plans, when they become available, for review with regard to the conclusions, recommendations, and assumptions contained within this report.



# 6.3 Site Grading Recommendations

The grading recommendations presented below are based on the subsurface conditions encountered at the boring locations, and our understanding of the proposed development. We recommend that all grading activities be completed in accordance with the Grading Guide Specifications included as Appendix D of this report, unless superseded by site-specific recommendations presented below.

# Site Stripping and Demolition

Demolition of the existing pavements and structures will be necessary, in order to facilitate the construction of the proposed development. Any existing improvements that will not remain in place for use with the new development should be removed in their entirety. This should include all utilities, and any other subsurface improvements associated with the existing structures. The existing pavements are not expected to be reused with the new development. Debris resultant from demolition should be disposed of off-site. Concrete and asphalt debris may be re-used as compacted fill, provided they are pulverized to a maximum particle size of less than 2 inches and mixed with sandy soils. Mixing concrete and asphalt debris with clayey soils is not recommended. Alternatively, existing asphalt and concrete materials may be crushed into miscellaneous base (CMB) and re-used at the site.

Detailed structural information regarding the existing buildings and crane structures has not been provided to our office. Therefore, the foundation systems supporting the existing buildings and equipment are not known by SCG. We expect that the existing buildings and crane structures are supported on conventional shallow foundations. However, if the buildings or structures are supported on deep foundations, any existing piles or drilled piers located within the proposed building area should be cut off at a depth of at least 2 feet below the bottom of the planned overexcavation. Where drilled pier or pile foundations are encountered within proposed pavement areas, they should be cut off at a depth of at least 2 feet below the proposed pavement subgrade or at a depth of at least 1 foot below the bottom of any planned utilities.

If the trees in the northern parking lot area will not remain with the proposed development, then initial site stripping should also remove the root systems associated with the trees should be removed in their entirety, and the resultant excavations should be backfilled with compacted structural fill soils. Any organic materials should be removed and disposed of off-site, or in non-structural areas of the property. The actual extent of site stripping should be determined in the field by the geotechnical engineer, based on the organic content and stability of the materials encountered.

# Treatment of Existing Soils: Building Pad

Remedial grading should be performed within the proposed building area in order to remove the existing undocumented fill soils, and a portion of the near-surface alluvium. Based on conditions encountered at the boring locations, the existing soils within the proposed building area are recommended to be overexcavated to a depth of at least 5 feet below existing grades and to a depth of at least 4 feet below proposed building pad subgrade elevations, whichever is greater. The depth of the overexcavation should also extend to a depth sufficient to remove all



undocumented fill soils, which extend to depths of  $2\frac{1}{2}$  to  $6\frac{1}{2}\pm$  feet below the existing site grades. Within the influence zones of the new foundations, the overexcavation should extend to a depth of at least 3 feet below proposed foundation bearing grade.

The overexcavation areas should extend at least 5 feet beyond the building and foundation perimeters, and to an extent equal to the depth of fill placed below the foundation bearing grade, whichever is greater. If the proposed structure incorporates any exterior columns (such as for a canopy or overhang) the area of overexcavation should also encompass these areas.

Following completion of the overexcavation, the subgrade soils within the building area should be evaluated by the geotechnical engineer to verify their suitability to serve as the structural fill subgrade, as well as to support the foundation loads of the new structure. This evaluation should include proofrolling and probing to identify any soft, loose or otherwise unstable soils that must be removed. Some localized areas of deeper excavation may be required if additional fill materials or loose, porous, or low-density native soils are encountered at the base of the overexcavation.

After a suitable overexcavation subgrade has been achieved, the exposed soils should be scarified to a depth of at least 12 inches and moisture conditioned or air dried to achieve a moisture content of 2 to 4 percent above optimum moisture content. The subgrade soils should then be recompacted to at least 90 percent of the ASTM D-1557 maximum dry density. The building pad area may then be raised to grade with previously excavated soils or imported structural fill.

# Treatment of Existing Soils: Retaining Walls and Site Walls

The existing soils within the areas of any proposed retaining walls and site walls should be overexcavated to a depth of 3 feet below foundation bearing grade and replaced as compacted structural fill as discussed above for the proposed building pad. Any undocumented fill soils or disturbed native alluvium within any of these foundation areas should be removed in their entirety. The overexcavation areas should extend at least 3 feet beyond the foundation perimeters, and to an extent equal to the depth of fill below the new foundations. Any erection pads for tilt-up concrete walls are considered to be part of the foundation system. Therefore, these overexcavation recommendations are applicable to erection pads. The overexcavation subgrade soils should be evaluated by the geotechnical engineer prior to scarifying, moisture conditioning to within 2 to 4 percent above the optimum moisture content, and recompacting the upper 12 inches of exposed subgrade soils. The previously excavated soils may then be replaced as compacted structural fill.

If the full lateral recommended remedial grading cannot be completed for the proposed retaining walls and site walls located along property lines, the foundations for those walls should be designed using a reduced allowable bearing pressure. Furthermore, the contractor should take necessary precautions to protect the adjacent improvements during rough grading. Specialized grading techniques, such as A-B-C slot cuts or temporary shoring, will likely be required during remedial grading. The geotechnical engineer of record should be contacted if additional recommendations, such as shoring design recommendations, are required during grading.



# Treatment of Existing Soils: Parking and Drive Areas

Based on economic considerations, overexcavation of the existing near-surface existing soils in the new parking and drive areas is not considered warranted, with the exception of areas where lower strength or unstable soils are identified by the geotechnical engineer during grading. Subgrade preparation in the new parking and drive areas should initially consist of removal of all soils disturbed during stripping and demolition operations.

The geotechnical engineer should then evaluate the subgrade to identify any areas of additional unsuitable soils. Any such materials should be removed to a level of firm and unyielding soil. The exposed subgrade soils should then be scarified to a depth of  $12\pm$  inches, moisture conditioned to 2 to 4 percent above the optimum moisture content, and recompacted to at least 90 percent of the ASTM D-1557 maximum dry density. Based on the presence of variable strength surficial soils throughout the site, it is expected that some isolated areas of additional overexcavation may be required to remove zones of lower strength, unsuitable soils.

The grading recommendations presented above for the proposed parking and drive areas assume that the owner and/or developer can tolerate minor amounts of settlement within these areas. The grading recommendations presented above do not mitigate the extent of undocumented fill or compressible/collapsible native alluvium in the parking and drive areas. As such, some settlement and associated pavement distress could occur. Typically, repair of such distressed areas involves significantly lower costs than completely mitigating these soils at the time of construction. If the owner cannot tolerate the risk of such settlements, the parking and drive areas should be overexcavated to a depth of 2 feet below proposed pavement subgrade elevation, with the resulting soils replaced as compacted structural fill.

# Treatment of Existing Soils: Flatwork Areas

Subgrade preparation in the new flatwork areas should initially consist of removal of all soils disturbed during stripping and possible demolition operations. The geotechnical engineer should then evaluate the subgrade to identify any areas of additional unsuitable soils. The subgrade soils should then be scarified to a depth of  $12\pm$  inches, moisture conditioned or air dried to 2 to 4 percent above optimum, and recompacted to at least 90 percent of the ASTM D-1557 maximum dry density. Based on the presence of variable strength alluvial soils throughout the subject site, it is expected that some isolated areas of additional overexcavation may be required to remove zones of lower strength, unsuitable soils.

As noted previously, the subject site is underlain by medium expansive soils. Support of new flatwork on medium expansive soils carries additional risk with respect to flatwork movement and potential distress. This report provides recommendations for moisture conditioning and additional steel reinforcement in the flatwork areas in order to minimize the potential effects of the expansive soils. However, if additional protection is desired, the client should consider the placement of a 1 to 2-foot thick layer of non-expansive soil beneath all flatwork.

# Fill Placement

• Fill soils should be placed in thin (6± inches), near-horizontal lifts, moisture conditioned (or air dried) to 2 to 4 percent above the optimum moisture content, and compacted.



- On-site soils may be used for fill provided they are cleaned of any debris to the satisfaction of the geotechnical engineer. Some drying will likely be required to achieve a moisture content suitable for reuse as structural fill.
- All grading and fill placement activities should be completed in accordance with the requirements of the 2019 CBC and the grading code of the city of Santa Fe Springs.
- All fill soils should be compacted to at least 90 percent of the ASTM D-1557 maximum dry density. Fill soils should be well mixed.
- Compaction tests should be performed periodically by the geotechnical engineer as random verification of compaction and moisture content. These tests are intended to aid the contractor. Since the tests are taken at discrete locations and depths, they may not be indicative of the entire fill and therefore should not relieve the contractor of his responsibility to meet the job specifications.

# Imported Structural Fill

All imported structural fill should consist of very low to low expansive (EI < 50), well graded soils possessing at least 10 percent fines (that portion of the sample passing the No. 200 sieve). Additional specifications for structural fill are presented in the Grading Guide Specifications, included as Appendix D.

# Utility Trench Backfill

In general, all utility trench backfill should be compacted to at least 90 percent of the ASTM D-1557 maximum dry density. As an alternative, a clean sand (minimum Sand Equivalent of 30) may be placed within trenches and compacted in place (jetting or flooding is not recommended). Compacted trench backfill should conform to the requirements of the local grading code, and more restrictive requirements may be indicated by the city of Santa Fe Springs. All utility trench backfills should be witnessed by the geotechnical engineer. The trench backfill soils should be compaction tested where possible; probed and visually evaluated elsewhere.

Utility trenches which parallel a footing, and extending below a 1h:1v (horizontal to vertical) plane projected from the outside edge of the footing should be backfilled with structural fill soils, compacted to at least 90 percent of the ASTM D-1557 standard. Pea gravel backfill should not be used for these trenches.

Any soils used to backfill voids around subsurface utility structures, such as manholes or vaults, should be placed as compacted structural fill. If it is not practical to place compacted fill in these areas, then such void spaces may be backfilled with lean concrete slurry. Uncompacted pea gravel or sand is not recommended for backfilling these voids since these materials have a potential to settle and thereby cause distress of pavements placed around these subterranean structures.



# 6.4 Construction Considerations

# Excavation Considerations

The near-surface soils generally consist of silty clays, sandy clays, silty sands and sandy silts. Some of these materials may be subject to caving within shallow excavations. Where caving occurs within shallow excavations, flattened excavation slopes may be sufficient to provide excavation stability. On a preliminary basis, the inclination of temporary slopes should not exceed 2h:1v within sandy soils. In addition, the inclination of temporary slopes should not exceed 1.5h:1v within clayey soils. Deeper excavations may require some form of external stabilization such as shoring or bracing. Maintaining adequate moisture content within the near-surface soils will improve excavation stability. All excavation activities on this site should be conducted in accordance with Cal-OSHA regulations.

# Moisture Sensitive Subgrade Soils

Some of the near-surface soils possess appreciable silt and clay content and may become unstable if exposed to significant moisture infiltration or disturbance by construction traffic. The base of the recommended building pad overexcavation will also be subject to subgrade instability, due the clay content of the native soils at this depth. Based on their granular content, some of the on-site soils will also be susceptible to erosion. The site should, therefore, be graded to prevent ponding of surface water and to prevent water from running into excavations.

If the construction schedule dictates that site grading will occur during a period of wet weather, allowances should be made for costs and delays associated with drying the on-site soils or import of a less moisture sensitive fill material. Grading during wet or cool weather may also increase the depth of overexcavation in the pad areas as well as the need for and or the thickness of the crushed stone stabilization layer, discussed in Section 6.3 of this report.

# Expansive Soils

The near-surface soils within the subject site have been determined to possess a medium expansion potential. Therefore, care should be given to proper moisture conditioning of all subgrade soils to a moisture content of 2 to 4 percent above the Modified Proctor optimum during site grading. All imported fill soils should have low expansive (EI < 50) characteristics. In addition to adequately moisture conditioning the subgrade soils and fill soils during grading, special care must be taken to maintain the moisture content of these soils at 2 to 4 percent above the Modified Proctor optimum. This will require the contractor to frequently moisture condition these soils throughout the grading process, unless grading occurs during a period of relatively wet weather.

Due to the presence of expansive soils at this site, provisions should be made to limit the potential for surface water to penetrate the soils immediately adjacent to the new structure. These provisions should include directing surface runoff into rain gutters and area drains, reducing the extent of landscaped areas around the structures, and sloping the ground surface away from the building. Where possible, it is recommended that landscaped planters not be located immediately



adjacent to the proposed building. If landscaped planters around the building are necessary, it is recommended that drought tolerant plants or a drip irrigation system be utilized, to minimize the potential for deep moisture penetration around the structure. Presented below is a list of additional soil moisture control recommendations that should be considered by the owner, developer, and civil engineer:

- Ponding and areas of low flow gradients in unpaved walkways, grass and planter areas should be avoided. In general, minimum drainage gradients of 2 percent should be maintained in unpaved areas.
- Bare soil within five feet of proposed structure should be sloped at a minimum five percent gradient away from the structure (about three inches of fall in five feet), or the same area could be paved with a minimum surface gradient of one percent. Pavement is preferable.
- Decorative gravel ground cover tends to provide a reservoir for surface water and may hide areas of ponding or poor drainage. Decorative gravel is, therefore, not recommended and should not be utilized for landscaping unless equipped with a subsurface drainage system designed by a licensed landscape architect.
- Positive drainage devices, such as graded swales, paved ditches, and catch basins should be installed at appropriate locations within the area of proposed development.
- Concrete walks and flatwork should not obstruct the free flow of surface water to the appropriate drainage devices.
- Area drains should be recessed below grade to allow free flow of water into the drain. Concrete or brick flatwork joints should be sealed with mortar or flexible mastic.
- Gutter and downspout systems should be installed to capture all discharge from roof areas. Downspouts should discharge directly into a pipe or paved surface system to be conveyed off-site.
- Enclosed planters adjoining, or in close proximity to proposed structures, should be sealed at the bottom and provided with subsurface collection systems and outlet pipes.
- Depressed planters should be raised with soil to promote runoff (minimum drainage gradient two percent or five percent, see above), and/or equipped with area drains to eliminate ponding.
- Drainage outfall locations should be selected to avoid erosion of slopes and/or properly armored to prevent erosion of graded surfaces. No drainage should be directed over or towards adjoining slopes.
- All drainage devices should be maintained on a regular basis, including frequent observations during the rainy season to keep the drains free of leaves, soil and other debris.
- Landscape irrigation should conform to the recommendations of the landscape architect and should be performed judiciously to preclude either soaking or excessive drying of the foundation soils. This should entail regular watering during the drier portions of the year and little or no irrigation during the rainy season. Automatic sprinkler systems should, therefore, be switched to manual operation during the rainy season. Good irrigation practice typically requires frequent application of limited quantities of water that are sufficient to sustain plant growth, but do not excessively wet the soils. Ponding and/or run-off of irrigation water are indications of excessive watering.

Other provisions, as determined by the landscape architect or civil engineer, may also be appropriate.

# Groundwater

The static groundwater table is considered to have existed at a depth in excess of  $25\pm$  feet at the time of the subsurface exploration. Therefore, groundwater is not expected to impact the grading or foundation construction activities.



# 6.5 Foundation Design and Construction

Based on the preceding grading recommendations, it is assumed that the new building pad will be underlain by structural fill soils used to replace existing undocumented fill soils and a portion of the near-surface alluvial soils. These new structural fill soils are expected to extend to a depth of at least 3 feet below proposed foundation bearing grade, underlain by 1± foot of additional soil that has been densified and moisture conditioned in place. Based on this subsurface profile, the proposed structure may be supported on conventional shallow foundations.

# Building Foundation Design Parameters

New square and rectangular footings may be designed as follows:

- Maximum, net allowable soil bearing pressure: 2,500 lbs/ft<sup>2</sup>.
- Maximum, net allowable soil bearing pressure: 1,500 lbs/ft<sup>2</sup> if the full recommended lateral extent of remedial grading cannot be achieved, typically for new footings along the property lines.
- Minimum wall/column footing width: 14 inches/24 inches.
- Minimum longitudinal steel reinforcement within strip footings: Six (6) No. 5 rebars (3 top and 3 bottom) due to the presence of expansive soils.
- Minimum foundation embedment: 12 inches into suitable structural fill soils, and at least 18 inches below adjacent exterior grade. Interior column footings may be placed immediately beneath the floor slab.
- It is recommended that the perimeter building foundations be continuous across all exterior doorways. Any flatwork adjacent to the exterior doors should be doweled into the perimeter foundations in a manner determined by the structural engineer.

The allowable bearing pressures presented above may be increased by 1/3 when considering short duration wind or seismic loads. The minimum steel reinforcement recommended above is based on geotechnical considerations; additional reinforcement may be necessary for structural considerations. The actual design of the foundations should be determined by the structural engineer.

# Foundation Construction

The foundation subgrade soils should be evaluated at the time of overexcavation, as discussed in Section 6.3 of this report. It is further recommended that the foundation subgrade soils be evaluated by the geotechnical engineer immediately prior to steel or concrete placement. Soils suitable for direct foundation support should consist of newly placed structural fill, compacted to at least 90 percent of the ASTM D-1557 maximum dry density. Any unsuitable materials should be removed to a depth of suitable bearing compacted structural fill or suitable native alluvium (where reduced bearing pressures are utilized), with the resulting excavations backfilled with



compacted fill soils. As an alternative, lean concrete slurry (500 to 1,500 psi) may be used to backfill such isolated overexcavations.

The foundation subgrade soils should also be properly moisture conditioned to 2 to 4 percent above the Modified Proctor optimum, to a depth of at least 12 inches below bearing grade. Since it is typically not feasible to increase the moisture content of the floor slab and foundation subgrade soils once rough grading has been completed, care should be taken to maintain the moisture content of the building pad subgrade soils throughout the construction process.

# Estimated Foundation Settlements

Post-construction total and differential settlements of shallow foundations designed and constructed in accordance with the previously presented recommendations are estimated to be less than 1.0 and 0.5 inches, respectively. Differential movements are expected to occur over a 30-foot span, thereby resulting in an angular distortion of less than 0.002 inches per inch.

# Lateral Load Resistance

Lateral load resistance will be developed by a combination of friction acting at the base of foundations and slabs and the passive earth pressure developed by footings below grade. The following friction and passive pressure may be used to resist lateral forces:

- Passive Earth Pressure: 250 lbs/ft<sup>3</sup>
- Friction Coefficient: 0.28

These are allowable values, and include a factor of safety. When combining friction and passive resistance, the passive pressure component should be reduced by one-third. These values assume that footings will be poured directly against compacted structural fill. The maximum allowable passive pressure is 2,500 lbs/ft<sup>2</sup>.

# 6.6 Floor Slab Design and Construction

Subgrades which will support the new floor slab should be prepared in accordance with the recommendations contained in the *Site Grading Recommendations* section of this report. Based on the anticipated grading which will occur at this site, and based on the design considerations presented in Section 6.1 of this report, the floor of the proposed structure may be constructed as a conventional slab-on-grade supported on newly placed structural fill, extending to a depth of at least 4 feet below finished pad grade. Based on geotechnical considerations, the floor slab may be designed as follows:

- Minimum slab thickness: 6 inches.
- Minimum slab reinforcement: No. 3 bars at 16 inches on-center, in both directions, due to the medium expansive potential of the near-surface soils. The actual floor slab reinforcement should be determined by the structural engineer, based on the imposed loading.



- Modulus of Subgrade Reaction: k = 100 psi/in.
- Slab underlayment: If moisture sensitive floor coverings will be used then minimum slab underlayment should consist of a moisture vapor barrier constructed below the entire area of the proposed slab where such moisture sensitive floor coverings are anticipated. The moisture vapor barrier should meet or exceed the Class A rating as defined by ASTM E 1745-97 and have a permeance rating less than 0.01 perms as described in ASTM E 96-95 and ASTM E 154-88. A polyolefin material such as Stego<sup>®</sup> Wrap Vapor Barrier or equivalent will meet these specifications. The moisture vapor barrier should be properly constructed in accordance with all applicable manufacturer specifications. Given that a rock free subgrade is anticipated and that a capillary break is not required, sand below the barrier is not required. The need for sand and/or the amount of sand above the moisture vapor barrier should be specified by the structural engineer or concrete contractor. The selection of sand above the barrier is not a geotechnical engineering issue and hence outside our purview. Where moisture sensitive floor coverings are not anticipated, the vapor barrier may be eliminated.
- Moisture condition the floor slab subgrade soils to 2 to 4 percent above the Modified Proctor optimum moisture content, to a depth of 12 inches. The moisture content of the floor slab subgrade soils should be verified by the geotechnical engineer within 24 hours prior to concrete placement.
- Proper concrete curing techniques should be utilized to reduce the potential for slab curling or the formation of excessive shrinkage cracks.

The actual design of the floor slab should be completed by the structural engineer to verify adequate thickness and reinforcement.

# 6.7 Trash Enclosure Design Parameters

We expect that the proposed development will include a trash enclosure. It is expected that the trash enclosure as well as the approach slab will be subjected to relatively heavy wheel loads, imposed by trash removal equipment.

The subgrade soils in the area of the trash enclosure and the approach slab should be prepared in accordance with the recommendations for the parking areas, presented in Section 6.3 of this report. As such, it is expected that the trash enclosure will be underlain by structural fill soils, extending to a depth of 1 foot below proposed subgrade elevation. Based on geotechnical considerations, the following recommendations are provided for the design of the trash enclosure and the trash enclosure approach slab:

• The trash enclosure may consist of a 6-inch thick concrete slab incorporating a perimeter footing or a turned down edge, extending to a depth of at least 12 inches below adjacent finished grade. If the trash enclosure will incorporate rigid walls such as masonry block or tilt-up concrete, the perimeter foundations should be designed in accordance with the recommendations previously presented in Section 6.5 of this report.



- Reinforcement within the trash enclosure slab should consist of at least No. 4 bars at 18-inches on-center, in both directions.
- The trash enclosure approach slab should be constructed of Portland cement concrete, at least 6 inches in thickness. Reinforcement within the approach slab should consist of at least No. 4 bars at 18-inches on-center, in both directions.
- The trash enclosure and approach slab subgrades should be moisture conditioned to 2 to 4 percent above the optimum moisture content to a depth of 12 inches. The trash enclosure slab and the approach slab should be structurally connected, to reduce the potential for differential movement between the two slabs.
- The actual design of the trash enclosure and the trash enclosure approach slab should be completed by the structural engineer to verify adequate thickness and reinforcement.

# 6.8 Exterior Flatwork Design and Construction

Subgrades which will support new exterior slabs-on-grade for sidewalks, patios, and other concrete flatwork, should be prepared in accordance with the recommendations contained in the *Grading Recommendations* section of this report. Based on geotechnical considerations, exterior slabs on grade may be designed as follows:

- Minimum slab thickness: 4<sup>1</sup>/<sub>2</sub> inches.
- Minimum slab reinforcement: No. 4 bars at 18 inches on center, in both directions.
- The flatwork at building entry areas should be structurally connected to the perimeter foundation that is recommended to span across the door opening. This recommendation is designed to reduce the potential for differential movement at this joint.
- Moisture condition the slab subgrade soils to at least 2 to 4 percent of optimum moisture content, to a depth of at least 12 inches. Adequate moisture conditioning should be verified by the geotechnical engineer 24 hours prior to concrete placement.
- Proper concrete curing techniques should be utilized to reduce the potential for slab curling or the formation of excessive shrinkage cracks.
- Control joints should be provided at a maximum spacing of 8 feet on center in two directions for slabs and at 6 feet on center for sidewalks. Control joints are intended to direct cracking. Minor cracking of exterior concrete slabs on grade should be expected.

Expansion or felt joints should be used at the interface of exterior slabs on grade and any fixed structures to permit relative movement.



# 6.9 Retaining Wall Design and Construction

Retaining walls are expected to be necessary in the new truck dock areas. The parameters recommended for use in the design of these walls are presented below.

# Retaining Wall Design Parameters

Based on the soil conditions encountered at the boring locations, the following parameters may be used in the design of new retaining walls for this site. We have provided parameters assuming the use of clayey sands, silty sands, and sandy silts for retaining wall backfill. **The potentially expansive fine sandy clays and silty clays should not be used for retaining wall backfill.** Based on their composition, the on-site clayey sands, silty sands, and sandy silts have been assigned a friction angle of 28 degrees when compacted to at least 90 percent of the ASTM D-1557 maximum dry-density.

If desired, SCG could provide design parameters for an alternative select backfill material behind the retaining walls. The use of select backfill material could result in lower lateral earth pressures. In order to use the design parameters for the imported select fill, this material must be placed within the entire active failure wedge. This wedge is defined as extending from the heel of the retaining wall upwards at an angle of approximately 60° from horizontal. If select backfill material behind the retaining wall is desired, SCG should be contacted for supplementary recommendations.

|                  |                                       | Soil Type               |
|------------------|---------------------------------------|-------------------------|
| Des              | sign Parameter                        | On-Site Clayey Sands    |
| Interna          | Internal Friction Angle (\$)          |                         |
| Unit Weight      |                                       | 128 lbs/ft <sup>3</sup> |
|                  | Active Condition<br>(level backfill)  | 46 lbs/ft <sup>3</sup>  |
| Equivalent Fluid | Active Condition<br>(2h:1v backfill)  | 81 lbs/ft <sup>3</sup>  |
| Pressure:        | At-Rest Condition<br>(level backfill) | 68 lbs/ft <sup>3</sup>  |

# RETAINING WALL DESIGN PARAMETERS

Regardless of the backfill type, the walls should be designed using a soil-footing coefficient of friction of 0.28 and an equivalent passive pressure of 250 lbs/ft<sup>3</sup>. The structural engineer should incorporate appropriate factors of safety in the design of the retaining walls.

The active earth pressure may be used for the design of retaining walls that do not directly support structures or support soils that in turn support structures and which will be allowed to deflect. The at-rest earth pressure should be used for walls that will not be allowed to deflect such as those which will support foundation bearing soils, or which will support foundation loads directly.



Where the soils on the toe side of the retaining wall are not covered by a "hard" surface such as a structure or pavement, the upper 1 foot of soil should be neglected when calculating passive resistance due to the potential for the material to become disturbed or degraded during the life of the structure.

# Seismic Lateral Earth Pressures

In accordance with the 2019 CBC, any retaining walls more than 6 feet in height must be designed for seismic lateral earth pressures. If walls 6 feet or more are required for this site, the geotechnical engineer should be contacted for supplementary seismic lateral earth pressure recommendations.

# Retaining Wall Foundation Design

The retaining wall foundations should be supported within newly placed compacted structural fill, extending to a depth of at least 3 feet below the proposed bearing grade. Foundations to support new retaining walls should be designed in accordance with the general Foundation Design Parameters presented in a previous section of this report.

# Backfill Material

On-site soils may be used to backfill the retaining walls, provided that they are low expansive (El < 50) sandy soils. All backfill material placed within 3 feet of the back wall-face should have a particle size no greater than 3 inches. The retaining wall backfill materials should be well graded.

It is recommended that a minimum 1-foot thick layer of free-draining granular material (less than 5 percent passing the No. 200 sieve) be placed against the face of the retaining walls. This material should extend from the top of the retaining wall footing to within 1 foot of the ground surface on the back side of the retaining wall. This material should be approved by the geotechnical engineer. In lieu of the 1-foot thick layer of free-draining material, a properly installed prefabricated drainage composite such as the MiraDRAIN 6000XL (or approved equivalent), which is specifically designed for use behind retaining walls, may be used. If the layer of free-draining material is not covered by an impermeable surface, such as a structure or pavement, a 12-inch thick layer of a low permeability soil should be placed over the backfill to reduce surface water migration to the underlying soils. The layer of free draining granular material should be separated from the backfill soils by a suitable geotextile, approved by the geotechnical engineer.

All retaining wall backfill should be placed and compacted under engineering controlled conditions in the necessary layer thicknesses to ensure an in-place density between 90 and 93 percent of the maximum dry density as determined by the Modified Proctor test (ASTM D1557). Care should be taken to avoid over-compaction of the soils behind the retaining walls, and the use of heavy compaction equipment should be avoided.



# Subsurface Drainage

As previously indicated, the retaining wall design parameters are based upon drained backfill conditions. Consequently, some form of permanent drainage system will be necessary in conjunction with the appropriate backfill material. Subsurface drainage may consist of either:

- A weep hole drainage system typically consisting of a series of 2-inch diameter holes in the wall situated slightly above the ground surface elevation on the exposed side of the wall and at an approximate 10-foot on-center spacing. Alternatively, 4-inch diameter holes at an approximate 20-foot on-center spacing can be used for this type of drainage system. In addition, the weep holes should include a 2 cubic foot pocket of open graded gravel, surrounded by an approved geotextile fabric, at each weep hole location.
- A 4-inch diameter perforated pipe surrounded by 2 cubic feet of gravel per linear foot of drain placed behind the wall, above the retaining wall footing. The gravel layer should be wrapped in a suitable geotextile fabric to reduce the potential for migration of fines. The footing drain should be extended to daylight or tied into a storm drainage system. The actual design of this type of system should be determined by the civil engineer to verify that the drainage system possesses the adequate capacity and slope for its intended use.

Weep holes or a footing drain will not be required for building stem walls.

# 6.10 Pavement Design Parameters

Site preparation in the pavement area should be completed as previously recommended in the **Site Grading Recommendations** section of this report. The subsequent pavement recommendations assume proper drainage and construction monitoring, and are based on either PCA or CALTRANS design parameters for a twenty (20) year design period. However, these designs also assume a routine pavement maintenance program to obtain the anticipated 20-year pavement service life.

# Pavement Subgrades

It is anticipated that the new pavements will be primarily supported on a layer of compacted structural fill, consisting of scarified, thoroughly moisture conditioned and recompacted existing soils. The near-surface soils generally consist of silty clays, sandy clays, clayey sands, and silty sands and sandy silts. These soils are generally considered to possess poor to fair pavement support characteristics with estimated R-values ranging from 10 to 30. The subsequent pavement design is therefore based upon an assumed R-value of 10. Any fill material imported to the site should have support characteristics equal to or greater than that of the on-site soils and be placed and compacted under engineering-controlled conditions. It is recommended that R-value testing be performed after completion of rough grading. Depending upon the results of the R-value testing, it may be feasible to use thinner pavement sections in some areas of the site.



# Asphaltic Concrete

Presented below are the recommended thicknesses for new flexible pavement structures consisting of asphaltic concrete over a granular base. The pavement designs are based on the **traffic indices (TI's) indicated. The client and/or civil engineer should verify that these TI's are** representative of the anticipated traffic volumes. If the client and/or civil engineer determine that the expected traffic volume will exceed the applicable traffic index, we should be contacted for supplementary recommendations. The design traffic indices equate to the following approximate daily traffic volumes over a 20-year design life, assuming six operational traffic days per week.

| Traffic Index | No. of Heavy Trucks per Day |
|---------------|-----------------------------|
| 4.0           | 0                           |
| 5.0           | 1                           |
| 6.0           | 3                           |
| 7.0           | 11                          |
| 8.0           | 35                          |
| 9.0           | 93                          |

For the purpose of the traffic volumes indicated above, a truck is defined as a 5-axle tractor trailer unit with one 8-kip axle and two 32-kip tandem axles. All of the traffic indices allow for 1,000 automobiles per day.

| ASPHALT PAVEMENTS (R=10) |                                       |          |          |          |          |  |  |  |
|--------------------------|---------------------------------------|----------|----------|----------|----------|--|--|--|
|                          | Thickness (inches)                    |          |          |          |          |  |  |  |
|                          | Auto Parking and                      |          |          |          |          |  |  |  |
| Materials                | Auto Drive Lanes<br>(TI = 4.0 to 5.0) | TI = 6.0 | TI = 7.0 | TI = 8.0 | TI = 9.0 |  |  |  |
| Asphalt Concrete         | 3                                     | 31⁄2     | 4        | 5        | 51⁄2     |  |  |  |
| Aggregate Base           | 9                                     | 12       | 15       | 16       | 19       |  |  |  |
| Compacted Subgrade       | 12                                    | 12       | 12       | 12       | 12       |  |  |  |

The aggregate base course should be compacted to at least 95 percent of the ASTM D-1557 maximum dry density. The asphaltic concrete should be compacted to at least 95 percent of the batch plant-reported maximum density. The aggregate base course may consist of crushed aggregate base (CAB) or crushed miscellaneous base (CMB), which is a recycled gravel, asphalt and concrete material. The gradation, R-Value, Sand Equivalent, and Percentage Wear of the CAB or CMB should comply with appropriate specifications contained in the current edition of the **"Greenbook"** <u>Standard Specifications for Public Works Construction</u>.

# Portland Cement Concrete

The preparation of the subgrade soils within concrete pavement areas should be performed as previously described for proposed asphalt pavement areas. The minimum recommended thicknesses for the Portland Cement Concrete pavement sections are as follows:



| PORTLAND CEMENT CONCRETE PAVEMENTS (R = 10)    |                                  |               |          |          |  |  |  |  |
|--|----------------------------------|---------------|----------|----------|--|--|--|--|
|  | Thickness (inches)               |               |          |          |  |  |  |  |
| Materials                                      | Autos and Light<br>Truck Traffic | Truck Traffic |          |          |  |  |  |  |
|  | (TI = 6.0)                       | TI =7.0       | TI = 8.0 | TI = 9.0 |  |  |  |  |
| PCC  | 5                                | 51⁄2          | 81⁄2     |          |  |  |  |  |
| Compacted Subgrade<br>(95% minimum compaction) | 12                               | 12            | 12       | 12       |  |  |  |  |

The concrete should have a 28-day compressive strength of at least 3,000 psi. The maximum joint spacing within all of the PCC pavements is recommended to be equal to or less than 30 times the pavement thickness. Any reinforcement within the PCC pavements should be determined by the project structural engineer.



This report has been prepared as an instrument of service for use by the client, in order to aid in the evaluation of this property and to assist the architects and engineers in the design and preparation of the project plans and specifications. This report may be provided to the contractor(s) and other design consultants to disclose information relative to the project. However, this report is not intended to be utilized as a specification in and of itself, without appropriate interpretation by the project architect, civil engineer, and/or structural engineer. The reproduction and distribution of this report must be authorized by the client and Southern California Geotechnical, Inc. Furthermore, any reliance on this report by an unauthorized third **party is at such party's sole risk, and we acce**pt no responsibility for damage or loss which may **occur. The client(s)' reliance upon this report is subject to the Engineering Services Agreement,** incorporated into our proposal for this project.

The analysis of this site was based on a subsurface profile interpolated from limited discrete soil samples. While the materials encountered in the project area are considered to be representative of the total area, some variations should be expected between boring locations and sample depths. If the conditions encountered during construction vary significantly from those detailed herein, we should be contacted immediately to determine if the conditions alter the recommendations contained herein.


This report has been based on assumed or provided characteristics of the proposed development. It is recommended that the owner, client, architect, structural engineer, and civil engineer carefully review these assumptions to ensure that they are consistent with the characteristics of the proposed development. If discrepancies exist, they should be brought to our attention to verify that they do not affect the conclusions and recommendations contained herein. We also recommend that the project plans and specifications be submitted to our office for review to verify that our recommendations have been correctly interpreted.

The analysis, conclusions, and recommendations contained within this report have been promulgated in accordance with generally accepted professional geotechnical engineering practice. No other warranty is implied or expressed.



A P P E N D I X A









# - PROPOSED BORING LOCATION

# - PROPOSED PROPERTY LINE

NOTE: AERIAL PHOTOGRAPH OBTAINED FROM GOOGLE EARTH. CONCEPTUAL SITE PLAN PROVIDED BY HPA ARCHITECTURE.



PLATE 2

A P P E D I X B

# **BORING LOG LEGEND**

| SAMPLE TYPE | GRAPHICAL<br>SYMBOL | SAMPLE DESCRIPTION  |
|-------------|---------------------|---|
| AUGER       |                     | SAMPLE COLLECTED FROM AUGER CUTTINGS, NO FIELD<br>MEASUREMENT OF SOIL STRENGTH. (DISTURBED)   |
| CORE        |                     | ROCK CORE SAMPLE: TYPICALLY TAKEN WITH A<br>DIAMOND-TIPPED CORE BARREL. TYPICALLY USED<br>ONLY IN HIGHLY CONSOLIDATED BEDROCK.                          |
| GRAB        | N.                  | SOIL SAMPLE TAKEN WITH NO SPECIALIZED<br>EQUIPMENT, SUCH AS FROM A STOCKPILE OR THE<br>GROUND SURFACE. (DISTURBED)                                      |
| CS          |                     | CALIFORNIA SAMPLER: 2-1/2 INCH I.D. SPLIT BARREL<br>SAMPLER, LINED WITH 1-INCH HIGH BRASS RINGS.<br>DRIVEN WITH SPT HAMMER. (RELATIVELY<br>UNDISTURBED) |
| NSR         |                     | NO RECOVERY: THE SAMPLING ATTEMPT DID NOT<br>RESULT IN RECOVERY OF ANY SIGNIFICANT SOIL OR<br>ROCK MATERIAL.  |
| SPT         |                     | STANDARD PENETRATION TEST: SAMPLER IS A 1.4<br>INCH INSIDE DIAMETER SPLIT BARREL, DRIVEN 18<br>INCHES WITH THE SPT HAMMER. (DISTURBED)                  |
| SH          |                     | SHELBY TUBE: TAKEN WITH A THIN WALL SAMPLE<br>TUBE, PUSHED INTO THE SOIL AND THEN EXTRACTED.<br>(UNDISTURBED)   |
| VANE        |                     | VANE SHEAR TEST: SOIL STRENGTH OBTAINED USING<br>A 4 BLADED SHEAR DEVICE. TYPICALLY USED IN SOFT<br>CLAYS-NO SAMPLE RECOVERED.                          |

### **COLUMN DESCRIPTIONS**

| <u>DEPTH</u> :       | Distance in feet below the ground surface.  |
|----------------------|---|
| SAMPLE:              | Sample Type as depicted above.  |
| l                    | Number of blows required to advance the sampler 12 inches using a 140 lb hammer with a 30-inch drop. 50/3" indicates penetration refusal (>50 blows) at 3 inches. WH indicates that the weight of the hammer was sufficient to push the sampler 6 inches or more. |
|                      | Approximate shear strength of a cohesive soil sample as measured by pocket penetrometer.  |
| <b>GRAPHIC LOG</b> : | Graphic Soil Symbol as depicted on the following page.  |
| DRY DENSITY          | Dry density of an undisturbed or relatively undisturbed sample in lbs/ft <sup>3</sup> .   |
| MOISTURE CONTENT     | Moisture content of a soil sample, expressed as a percentage of the dry weight.   |
| LIQUID LIMIT         | The moisture content above which a soil behaves as a liquid.  |
| PLASTIC LIMIT        | The moisture content above which a soil behaves as a plastic.   |
| PASSING #200 SIEVE   | The percentage of the sample finer than the $#200$ standard sieve.  |
| UNCONFINED SHEAR     | The shear strength of a cohesive soil sample, as measured in the unconfined state.  |

# SOIL CLASSIFICATION CHART

| М  | AJOR DIVISI                            | ONS                              |          | BOLS   | TYPICAL   |
|--|--|----------------------------------|----------|--------|---|
|  |  | 0110                             | GRAPH    | LETTER | DESCRIPTIONS  |
|  | GRAVEL<br>AND                          | CLEAN<br>GRAVELS                 |          | GW     | WELL-GRADED GRAVELS, GRAVEL -<br>SAND MIXTURES, LITTLE OR NO<br>FINES   |
|  | GRAVELLY<br>SOILS                      | (LITTLE OR NO FINES)             |          | GP     | POORLY-GRADED GRAVELS,<br>GRAVEL - SAND MIXTURES, LITTLE<br>OR NO FINES   |
| COARSE<br>GRAINED<br>SOILS                                       | MORE THAN 50%<br>OF COARSE             | GRAVELS WITH<br>FINES            |          | GM     | SILTY GRAVELS, GRAVEL - SAND -<br>SILT MIXTURES   |
|  | FRACTION<br>RETAINED ON NO.<br>4 SIEVE | (APPRECIABLE<br>AMOUNT OF FINES) |          | GC     | CLAYEY GRAVELS, GRAVEL - SAND -<br>CLAY MIXTURES  |
| MORE THAN 50%<br>OF MATERIAL IS                                  | SAND<br>AND                            | CLEAN SANDS                      |          | SW     | WELL-GRADED SANDS, GRAVELLY<br>SANDS, LITTLE OR NO FINES  |
| LARGER THAN<br>NO. 200 SIEVE<br>SIZE                             | SANDY<br>SOILS                         | (LITTLE OR NO FINES)             |          | SP     | POORLY-GRADED SANDS,<br>GRAVELLY SAND, LITTLE OR NO<br>FINES  |
|  | MORE THAN 50%<br>OF COARSE             | SANDS WITH<br>FINES              |          | SM     | SILTY SANDS, SAND - SILT<br>MIXTURES  |
|  | FRACTION<br>PASSING ON NO.<br>4 SIEVE  | (APPRECIABLE<br>AMOUNT OF FINES) |          | SC     | CLAYEY SANDS, SAND - CLAY<br>MIXTURES   |
|  |  |                                  |          | ML     | INORGANIC SILTS AND VERY FINE<br>SANDS, ROCK FLOUR, SILTY OR<br>CLAYEY FINE SANDS OR CLAYEY<br>SILTS WITH SLIGHT PLASTICITY |
| FINE<br>GRAINED<br>SOILS   | SILTS<br>AND<br>CLAYS                  | LIQUID LIMIT<br>LESS THAN 50     |          | CL     | INORGANIC CLAYS OF LOW TO<br>MEDIUM PLASTICITY, GRAVELLY<br>CLAYS, SANDY CLAYS, SILTY CLAYS,<br>LEAN CLAYS                  |
| 00120  |  |                                  |          | OL     | ORGANIC SILTS AND ORGANIC<br>SILTY CLAYS OF LOW PLASTICITY  |
| MORE THAN 50%<br>OF MATERIAL IS<br>SMALLER THAN<br>NO. 200 SIEVE |  |                                  |          | МН     | INORGANIC SILTS, MICACEOUS OR<br>DIATOMACEOUS FINE SAND OR<br>SILTY SOILS   |
| SIZE   | SILTS<br>AND<br>CLAYS                  | LIQUID LIMIT<br>GREATER THAN 50  |          | СН     | INORGANIC CLAYS OF HIGH<br>PLASTICITY   |
|  |  |                                  |          | ОН     | ORGANIC CLAYS OF MEDIUM TO<br>HIGH PLASTICITY, ORGANIC SILTS  |
| н  | GHLY ORGANIC S                         | SOILS                            | <u> </u> | PT     | PEAT, HUMUS, SWAMP SOILS WITH<br>HIGH ORGANIC CONTENTS  |

NOTE: DUAL SYMBOLS ARE USED TO INDICATE BORDERLINE SOIL CLASSIFICATIONS



| JOB N<br>PROJE<br>I OCAT | ECT      | : Pro      | oposed               |             | DRILLING DATE: 11/4/21<br>nouse DRILLING METHOD: Hollow Stem Auger<br>gs, California LOGGED BY: Ryan Bremer          |                      | C                       | ATER<br>AVE DI | EPTH:            | 19 fe                     | eet | npletion |
|--------------------------|----------|------------|----------------------|-------------|--|----------------------|-------------------------|----------------|------------------|---------------------------|-----|----------|
| FIELD                    |          |            |                      |             |  | LA                   |                         |                |                  |                           |     |          |
| =EET)                    | SAMPLE   | BLOW COUNT | POCKET PEN.<br>(TSF) | GRAPHIC LOG | DESCRIPTION<br>SURFACE ELEVATION:  | DRY DENSITY<br>(PCF) | MOISTURE<br>CONTENT (%) |                | PLASTIC<br>LIMIT | PASSING<br>#200 SIEVE (%) | ()  | COMMENTS |
|                          |          |            |                      |             | 3± inches Asphaltic Concrete; 5± inches Aggregate Base   |                      |                         |                |                  |                           |     |          |
|                          | X        | 5          | 2.0                  |             | FILL: Brown Clayey fine Sand to Silty Clay, mottled, loose to medium stiff-moist                                     | -                    | 13                      |                |                  |                           |     |          |
| 5                        | X        | 14         | 3.0                  |             | ALLUVIUM: Brown fine Sandy Clay, stiff to very stiff-moist   | -                    | 14                      |                |                  |                           |     |          |
|                          | X        | 11         | 4.0                  |             |  | -                    | 12                      |                |                  |                           |     |          |
| 10                       | X        | 9          |                      |             | Light Brown fine Sandy Silt, loose-very moist<br>-   |                      | 15                      |                |                  |                           |     |          |
| 15                       | X        | 29         |                      |             | Light Brown Silty fine Sand, medium dense-damp   | -                    | 7                       |                |                  |                           |     |          |
| 20                       | $\times$ | 46         | 3.0                  |             | Light Gray Brown Clayey Silt, little Calcareous nodules, trace Iron<br>Oxide staining, very stiff to hard-very moist | -                    | 20                      |                |                  |                           |     |          |
| 25                       | X        | 27         |                      |             | Brown fine Sandy Silt, little Iron Oxide staining, medium<br>dense-very moist  | -                    | 16                      |                |                  |                           |     |          |
|                          |          |            |                      |             | Boring Terminated at 25'   |                      |                         |                |                  |                           |     |          |
|                          | <u>т</u> | R0         |                      |             | .OG  |                      |                         |                |                  |                           |     | LATE B   |



| JOB NO.:<br>PROJEC | T: Pr | oposed      | d Ware |  |                  | CA                      | EPTH:            | 14 fe                     | eet |          |
|--------------------|-------|-------------|--------|--|------------------|-------------------------|------------------|---------------------------|-----|----------|
| FIELD F            |       |             |        | gs, California LOGGED BY: Jamie Hayward  |                  |                         |                  |                           |     | npletion |
| DEPTH (FEET)       |       | POCKET PEN. |        | DESCRIPTION<br>SURFACE ELEVATION:  | DRY DENSITY PCF) | MOISTURE<br>CONTENT (%) | PLASTIC<br>LIMIT | PASSING<br>#200 SIEVE (%) |     | COMMENTS |
|                    |       |             |        | 3± inches Asphaltic Concrete, 4± inches Aggregate Base   |                  |                         |                  |                           |     |          |
|                    | 9     |             |        | FILL:         Gray Brown Silty fine Sand, mottled, porous, loose-moist           FILL:         Brown Silty fine Sand, little to some Clay, trace fine root fibers, porous, loose to medium dense-damp to moist | 96               | 10                      |                  |                           |     |          |
|                    | 27    |             |        |  | 119              | 6                       |                  |                           |     |          |
| 5                  | 16    | 4.5         |        | <u>ALLUVIUM:</u> Brown fine Sandy Clay, little Iron Oxide staining,<br>damp, slightly porous, stiff to very stiff-moist  | 109              | 10                      |                  |                           |     |          |
|                    | 12    | 4.5         |        | Brown Clayey fine Sand to fine Sandy Clay, stiff to very stiff-moist   | 117              | 11                      |                  |                           |     |          |
| 10                 | 19    | 4.5         |        | Gray Brown Silty Clay, little fine Sand, little Iron Oxide staining,<br>little Calcareous nodules/veining, stiff to very stiff-moist   | 116              | 13                      |                  |                           |     |          |
| 15                 | 16    |             |        | Light Gray Brown Silty fine Sand to fine Sandy Silt, little Iron Oxide<br>staining, medium dense-moist   | 101              | 13                      |                  |                           |     |          |
|                    | 20    |             |        | Light Gray Brown Silt, trace to little fine Sand, some Iron Oxide staining, medium dense-very moist  | 92               | 30                      |                  |                           |     |          |
| 20-                | 20    |             |        |  | 92               | 30                      |                  |                           |     |          |
|                    |       |             |        | Boring Terminated at 20'   |                  |                         |                  |                           |     |          |
| EST                | BC    | )<br>DRIN   | IG L   | .OG  |                  |                         |                  |                           | P   | LATE B   |



| PRO.<br>LOC/         | JECT<br>ATIO | T: Pro<br>N: S | anta F               | e Sprir     | DRILLING DATE: 11/3/21<br>house DRILLING METHOD: Hollow Stem Auger<br>ngs, California LOGGED BY: Ryan Bremer |                      | C                       | ATER<br>AVE DI<br>EADIN | EPTH:            | 14 fe                     | eet                    | npletion       |
|----------------------|--------------|----------------|----------------------|-------------|--|----------------------|-------------------------|-------------------------|------------------|---------------------------|------------------------|----------------|
| FIEL                 | DF           | RESL           | ILTS                 |             |  | LA                   | BOR                     | ATOF                    | RY RI            | ESUL                      | TS                     | -              |
| DEPTH (FEET)         | SAMPLE       | BLOW COUNT     | POCKET PEN.<br>(TSF) | GRAPHIC LOG | DESCRIPTION<br>SURFACE ELEVATION:  | DRY DENSITY<br>(PCF) | MOISTURE<br>CONTENT (%) | LIQUID<br>LIMIT         | PLASTIC<br>LIMIT | PASSING<br>#200 SIEVE (%) | ORGANIC<br>CONTENT (%) | COMMENTS       |
| <u> </u>             | •,           |                | <u> </u>             |             | 3± inches Asphaltic Concrete, no discernible Aggregate Base  |                      | 20                      |                         |                  |                           |                        |                |
| -                    | X            | 14             |                      |             | FILL: Brown Silty fine Sand, trace medium to coarse Sand,<br>mottled, loose-moist                            | 109                  | 11                      |                         |                  |                           |                        | EI = 83 @ 0 to |
| -                    |              | 23             | 4.5                  |             | ALLUVIUM: Brown fine Sandy Clay, very stiff-moist  | 123                  | 11                      |                         |                  |                           |                        |                |
| 5 -                  |              | 31             | 4.5                  |             |  | 122                  | 10                      |                         |                  |                           |                        |                |
| -                    |              | 24             | 4.5                  |             |  | 118                  | 13                      |                         |                  |                           |                        |                |
| 10-                  |              | 24             |                      |             | Brown to Light Brown Silty fine Sand, trace Clay, medium dense-damp  | 120                  | 6                       |                         |                  |                           |                        |                |
|                      |              |                |                      |             |  |                      |                         |                         |                  |                           |                        |                |
| -                    |              |                |                      |             | Light Brown fine Sandy Silt, dense-moist   | -                    |                         |                         |                  |                           |                        |                |
| -<br><del>15 -</del> | X            | 42             |                      |             | -  |                      | 12                      |                         |                  |                           |                        |                |
|                      |              |                |                      |             | Boring Terminated at 15'   |                      |                         |                         |                  |                           |                        |                |
|                      |              |                |                      |             |  |                      |                         |                         |                  |                           |                        |                |
|                      |              |                |                      |             |  |                      |                         |                         |                  |                           |                        |                |
|                      |              |                |                      |             |  |                      |                         |                         |                  |                           |                        |                |
|                      |              |                |                      |             |  |                      |                         |                         |                  |                           |                        |                |
|                      |              |                |                      |             |  |                      |                         |                         |                  |                           |                        |                |
|                      |              |                |                      |             |  |                      |                         |                         |                  |                           |                        |                |
|                      |              |                |                      |             |  |                      |                         |                         |                  |                           |                        |                |
|                      |              |                |                      |             |  |                      |                         |                         |                  |                           |                        |                |
|                      |              |                |                      |             | _OG  |                      |                         |                         |                  |                           | _                      | LATE B         |



| PRO                          | JECT           | T: Pr      |                   | d Ware      |  |                      | C                       | ATER         | EPTH:   | 18 fe                     | eet                    | anlation |
|------------------------------|----------------|------------|-------------------|-------------|--|----------------------|-------------------------|--------------|---------|---------------------------|------------------------|----------|
|                              |                |            | anta F<br>JLTS    |             | ngs, California LOGGED BY: Ryan Bremer   | IA                   |                         | adin<br>ATOF |         |                           |                        | npletion |
| DEPTH (FEET)                 | SAMPLE         | BLOW COUNT | POCKET PEN. (TSF) | GRAPHIC LOG | DESCRIPTION<br>SURFACE ELEVATION:  | DRY DENSITY<br>(PCF) | MOISTURE<br>CONTENT (%) |              | PLASTIC | PASSING<br>#200 SIEVE (%) | ORGANIC<br>CONTENT (%) | COMMENTS |
|                              |                |            |                   |             | 31/2± inches Asphaltic Concrete, 4± inches Aggregate Base  |                      |                         |              |         |                           |                        |          |
| -                            | X              | 12         |                   |             | FILL: Brown fine Silty fine Sand, trace Clay, trace fine Gravel, loose-damp to moist   | 118                  | 8                       |              |         |                           |                        |          |
|                              |                | 9          |                   |             |  | 113                  | 12                      |              |         |                           |                        |          |
| 5 -                          | X              | 18         |                   | ····        | @ 5 feet, little to some Clay, medium dense  | 123                  | 11                      |              |         |                           |                        |          |
| -                            |                | 20         | 4.5               |             | <u>ALLUVIUM:</u> Brown fine Sandy Clay, little Silt, very stiff-damp to moist  | 116                  | 12                      |              |         |                           |                        |          |
| 10—                          |                | 11         | 4.5               |             | -  | 102                  | 6                       |              |         |                           |                        |          |
| -<br>-<br>-<br>15 -          | X              | 37         |                   |             | Light Brown fine Sandy Silt, little Calcareous veining, little Iron<br>Oxide staining, medium dense to dense-moist to very moist |                      | 15                      |              |         |                           |                        |          |
| -<br>-<br>-<br><del>20</del> | X              | 29         |                   |             | -  | -                    | 10                      |              |         |                           |                        |          |
| 20                           |                |            |                   |             | Boring Terminated at 20'   |                      |                         |              |         |                           |                        |          |
|                              |                |            |                   |             |  |                      |                         |              |         |                           |                        |          |
|                              |                |            |                   |             |  |                      |                         |              |         |                           |                        |          |
|                              |                |            |                   |             |  |                      |                         |              |         |                           |                        |          |
|                              |                |            |                   |             |  |                      |                         |              |         |                           |                        |          |
|                              |                |            |                   |             |  |                      |                         |              |         |                           |                        |          |
|                              |                |            |                   |             |  |                      |                         |              |         |                           |                        |          |
| F                            | <u>.</u><br>Ст | RC         |                   | IG I        | _OG  |                      |                         |              |         | I                         | P                      | LATE B   |



|              | ECT    | : Pro      | posed                |             | DRILLING DATE: 11/3/21<br>nouse DRILLING METHOD: Hollow Stem Auger<br>gs, California LOGGED BY: Ryan Bremer           |                      | C                       | ATER<br>AVE D<br>EADIN | EPTH             | 21 f                      | eet                    | npletion |
|--------------|--------|------------|----------------------|-------------|---|----------------------|-------------------------|------------------------|------------------|---------------------------|------------------------|----------|
| FIEL         | DR     | ESŲ        | LTS                  |             |   | LA                   |                         | ATOF                   |                  |                           |                        | -        |
| DEPTH (FEET) | SAMPLE | BLOW COUNT | POCKET PEN.<br>(TSF) | GRAPHIC LOG | DESCRIPTION<br>SURFACE ELEVATION:   | DRY DENSITY<br>(PCF) | MOISTURE<br>CONTENT (%) | LIQUID<br>LIMIT        | PLASTIC<br>LIMIT | PASSING<br>#200 SIEVE (%) | ORGANIC<br>CONTENT (%) | COMMENTS |
|              | X      | 13         | 3.5                  |             | <u>FILL:</u> Brown fine Sandy Clay, little Silt, trace medium to coarse Sand, stiff-moist                             | -                    | 11                      |                        |                  |                           |                        |          |
| 5            | X      | 18         | 4.5                  |             | <u>FILL:</u> Brown Silty Clay, little fine Sand, trace medium to coarse Sand, mottled, very stiff-moist               | -                    | 13                      |                        |                  |                           |                        |          |
|              | X      | 18         |                      |             | ALLUVIUM: Brown fine Sandy Clay, little Silt, stiff-moist   | -                    | 11                      |                        |                  |                           |                        |          |
| 10-4         | X      | 28         |                      |             | Gray Brown to Brown fine Sandy Silt, trace Clay, trace Iron Oxide staining, medium dense to dense-moist to very moist | -                    | 14                      |                        |                  |                           |                        |          |
| 15           | X      | 35         |                      |             | Light Gray Brown Silty fine Sand to fine Sandy Silt, little Iron Oxide  | -                    | 13                      |                        |                  |                           |                        |          |
| 20-4         | X      | 28         |                      |             | staining, medium dense-moist to very moist  | -                    | 14                      |                        |                  |                           |                        |          |
| 25           | X      | 28         |                      |             |   | -                    | 10                      |                        |                  |                           |                        |          |
| -            |        |            |                      |             | Boring Terminated at 25'  |                      |                         |                        |                  |                           |                        |          |
|              |        | BU         | DIN                  |             | .OG   |                      |                         |                        |                  |                           |                        | LATE B   |



|                           | ECT    | : Pro      | oposec               | l Warel<br>e Sprin | DRILLING DATE: 11/4/21<br>nouse DRILLING METHOD: Hollow Stem Auger<br>gs, California LOGGED BY: Ryan Bremer |                      | C                       | ATER<br>AVE D | EPTH: | 20 f                      | eet                    | npletion |
|---------------------------|--------|------------|----------------------|--------------------|---|----------------------|-------------------------|---------------|-------|---------------------------|------------------------|----------|
|                           |        |            | JLTS                 |                    |   | LA                   |                         | ATOF          |       |                           |                        |          |
| =EET)                     | SAMPLE | BLOW COUNT | POCKET PEN.<br>(TSF) | <b>GRAPHIC LOG</b> | DESCRIPTION<br>SURFACE ELEVATION:   | DRY DENSITY<br>(PCF) | MOISTURE<br>CONTENT (%) | LIQUID        | 0     | PASSING<br>#200 SIEVE (%) | ORGANIC<br>CONTENT (%) | COMMENTS |
|                           |        |            |                      |                    | 5± inches Asphaltic Concrete, 4± inches Aggregate Base  |                      |                         |               |       |                           |                        |          |
|                           | X      | 10         | 3.0                  |                    | FILL: Brown Silty Clay, mottled, stiff-moist  |                      | 13                      |               |       |                           |                        |          |
| 5                         | X      | 14         | 2.5                  |                    | <u>ALLUVIUM</u> :Brown fine Sandy Clay, stiff-moist   | -                    | 13                      |               |       |                           |                        |          |
|                           | X      | 16         | 4.0                  |                    | Brown Clayey fine Sand to fine Sandy Clay, medium dense to very stiff-moist                                 |                      | 12                      |               |       |                           |                        |          |
| -<br>-<br>-<br>10         | X      | 16         |                      |                    | Brown Silty fine Sand to fine Sandy Silt, medium dense-moist  | -                    | 12                      |               |       |                           |                        |          |
| 15 -4                     | X      | 17         |                      |                    | Light Gray Brown fine Sandy Silt, trace Calcareous veining, medium dense-very moist                         |                      | 16                      |               |       |                           |                        |          |
| 1<br>-<br>-<br>-<br>-<br> | X      | 62         |                      |                    | @ 18½ feet, trace Iron Oxide staining, very dense   | -                    | 17                      |               |       |                           |                        |          |
|                           |        |            |                      |                    | Boring Terminated at 20'  |                      |                         |               |       |                           |                        |          |
|                           |        |            |                      |                    |   |                      |                         |               |       |                           |                        |          |
|                           |        |            |                      |                    |   |                      |                         |               |       |                           |                        |          |
|                           |        |            |                      |                    |   |                      |                         |               |       |                           |                        |          |
|                           |        |            |                      |                    |   |                      |                         |               |       |                           |                        |          |
|                           |        |            |                      |                    |   |                      |                         |               |       |                           |                        |          |
| <br>'ES                   | <br>T  | BO         | RIN                  | IG I               | .OG   |                      |                         |               |       |                           | <br>P                  | LATE B   |





| JOB NO.:<br>PROJEC | T: Pr | oposed            | d Ware |  |             | C                       | ATER<br>AVE DI | EPTH:            | 17 fe                     | eet |           |
|--------------------|-------|-------------------|--------|--|-------------|-------------------------|----------------|------------------|---------------------------|-----|-----------|
|                    |       |                   | -      | gs, California LOGGED BY: Jamie Hayward  |             |                         |                |                  |                           |     | npletion  |
| DEPTH (FEET)       |       | POCKET PEN. (TSF) |        | DESCRIPTION  | DRY DENSITY | MOISTURE<br>CONTENT (%) | ATOF           |                  | PASSING<br>#200 SIEVE (%) |     | COMMENTS  |
| DEPTH (I<br>SAMPLE | LOW   | OCK<br>[SF)       | RAP    | SURFACE ELEVATION:   | PCF)        | 10IST<br>NOT            | LIQUID         | PLASTIC<br>LIMIT | ASSI<br>200 S             | RGA | MMO       |
| D O                | В     |                   | G      | 4± inches Asphaltic Concrete; 4± inches Aggregate Base   |             | ≥o                      |                |                  | □ #                       | 00  | <u></u> о |
|                    | 16    |                   |        | FILL: Dark Brown Silty fine Sand, porous, medium dense-dry to damp to moist  | 109         | 8                       |                |                  |                           |     |           |
|                    | 27    | 4.5               |        | <u>ALLUVIUM</u> : Brown fine Sandy Clay to Silty Clay, trace Calcareous nodules/veining, very stiff-damp to moist                      | 124         | 8                       |                |                  |                           |     |           |
| 5                  | 25    | 4.5               |        |  | 123         | 12                      |                |                  |                           |     |           |
| X                  | 21    | 4.5               |        |  | 114         | 13                      |                |                  |                           |     |           |
| 10                 | 14    |                   |        | Gray Brown Silty fine Sand, little Clay, little Iron Oxide staining,<br>loose-moist to very moist                                      | 111         | 15                      |                |                  |                           |     |           |
| 15                 | 39    |                   |        | Light Gray Brown Silty fine Sand to fine Sandy Silt, little Iron Oxide staining, little Calcareous nodules/veining, medium dense-moist | 99          | 14                      |                |                  |                           |     |           |
| 20                 | 28    |                   |        |  | 96          | 10                      |                |                  |                           |     |           |
|                    |       |                   |        | Boring Terminated at 20'   |             |                         |                |                  |                           |     |           |
|                    |       |                   |        |  |             |                         |                |                  |                           |     |           |
|                    |       |                   |        |  |             |                         |                |                  |                           |     |           |
|                    |       |                   |        |  |             |                         |                |                  |                           |     |           |
|                    |       |                   |        |  |             |                         |                |                  |                           |     |           |
|                    |       |                   |        |  |             |                         |                |                  |                           |     |           |
| EST                |       |                   |        | 06   |             |                         |                |                  |                           |     | LATE B    |





| PRO.<br>LOC/   | JECT<br>ATIO | T: Pro<br>N: S | anta F               | l Ware<br>e Sprin | DRILLING DATE: 11/8/21<br>house DRILLING METHOD: Hollow Stem Auger<br>igs, California LOGGED BY: Jamie Hayward                |                      | C/<br>RI                |                 | epth:<br>g tak   | 17 fo<br>(EN: 1           | eet<br>At Con          | npletion |
|----------------|--------------|----------------|----------------------|-------------------|---|----------------------|-------------------------|-----------------|------------------|---------------------------|------------------------|----------|
|                | D R          |                | JLTS                 |                   |   | LA                   |                         | ATOF            | RY R             |                           | TS                     |          |
| DEPTH (FEET)   | SAMPLE       | BLOW COUNT     | POCKET PEN.<br>(TSF) | GRAPHIC LOG       | DESCRIPTION   | DRY DENSITY<br>(PCF) | MOISTURE<br>CONTENT (%) | LIQUID<br>LIMIT | PLASTIC<br>LIMIT | PASSING<br>#200 SIEVE (%) | ORGANIC<br>CONTENT (%) | COMMENTS |
| ä              | S            | ВГ             | ۵Ë                   | Ū                 | SURFACE ELEVATION:  | ЩĘ.                  | žΰ                      | ΞΞ              | 로크               | 4 <del>2</del>            | 62                     | ŏ        |
|                |              |                |                      |                   | 3± inches Asphaltic Concrete, 5± inches Aggregate Base <u>FILL:</u> Brown Silty fine Sand, some Iron Oxide staining, porous,  | _                    |                         |                 |                  |                           |                        |          |
| ]              |              | 7              |                      |                   | $\sim$ mottled, loose-moist   | _ 83                 | 9                       |                 |                  |                           |                        |          |
| -              |              | 28             |                      |                   | FILL: Light Gray Brown Silty fine Sand, some fine root fibers, loose to medium dense-moist                                    | 122                  | 10                      |                 |                  |                           |                        |          |
| 5 -            | X            | 14             |                      |                   | -   | 114                  | 11                      |                 |                  |                           |                        |          |
| -              |              | 22             | 4.5                  |                   | ALLUVIUM: Brown fine Sandy Clay, porous, very stiff-moist   | 118                  | 12                      |                 |                  |                           |                        |          |
| -<br>10 —<br>- |              | 18             |                      |                   | Brown Silty fine Sand, trace Clay, little Calcareous veining, little<br>Iron Oxide staining, medium dense-moist to very moist | 118                  | 13                      |                 |                  |                           |                        |          |
| -              |              |                |                      |                   | Light Gray Brown fine Sandy Silt, little Iron Oxide staining, trace<br>Calcareous veining, medium dense-moist                 |                      |                         |                 |                  |                           |                        |          |
| -<br>15 -<br>- |              | 16             |                      |                   | -<br>-  | 104                  | 13                      |                 |                  |                           |                        |          |
| -              |              |                |                      |                   | Gray Brown Silty fine Sand, little to some Iron Oxide staining, medium dense-moist  | -                    |                         |                 |                  |                           |                        |          |
| -              |              | 22             |                      |                   |   | 103                  | 10                      |                 |                  |                           |                        |          |
| <del>20</del>  |              |                |                      |                   | Gray Brown Silt, little Iron Oxide staining, little Calcareous<br>nodules/veining, medium dense-moist                         |                      |                         |                 |                  |                           |                        |          |
|                |              |                |                      |                   |   |                      |                         |                 |                  |                           |                        |          |
|                |              |                |                      |                   |   |                      |                         |                 |                  |                           |                        |          |
|                |              |                |                      |                   |   |                      |                         |                 |                  |                           |                        |          |
|                |              |                |                      |                   |   |                      |                         |                 |                  |                           |                        |          |


A P P E N D I X C



































A P P EN D I X 

# **GRADING GUIDE SPECIFICATIONS**

These grading guide specifications are intended to provide typical procedures for grading operations. They are intended to supplement the recommendations contained in the geotechnical investigation report for this project. Should the recommendations in the geotechnical investigation report conflict with the grading guide specifications, the more site specific recommendations in the geotechnical investigation report will govern.

### <u>General</u>

- The Earthwork Contractor is responsible for the satisfactory completion of all earthwork in accordance with the plans and geotechnical reports, and in accordance with city, county, and applicable building codes.
- The Geotechnical Engineer is the representative of the Owner/Builder for the purpose of implementing the report recommendations and guidelines. These duties are not intended to relieve the Earthwork Contractor of any responsibility to perform in a workman-like manner, nor is the Geotechnical Engineer to direct the grading equipment or personnel employed by the Contractor.
- The Earthwork Contractor is required to notify the Geotechnical Engineer of the anticipated work and schedule so that testing and inspections can be provided. If necessary, work may be stopped and redone if personnel have not been scheduled in advance.
- The Earthwork Contractor is required to have suitable and sufficient equipment on the jobsite to process, moisture condition, mix and compact the amount of fill being placed to the approved compaction. In addition, suitable support equipment should be available to conform with recommendations and guidelines in this report.
- Canyon cleanouts, overexcavation areas, processed ground to receive fill, key excavations, subdrains and benches should be observed by the Geotechnical Engineer prior to placement of any fill. It is the Earthwork Contractor's responsibility to notify the Geotechnical Engineer of areas that are ready for inspection.
- Excavation, filling, and subgrade preparation should be performed in a manner and sequence that will provide drainage at all times and proper control of erosion. Precipitation, springs, and seepage water encountered shall be pumped or drained to provide a suitable working surface. The Geotechnical Engineer must be informed of springs or water seepage encountered during grading or foundation construction for possible revision to the recommended construction procedures and/or installation of subdrains.

### Site Preparation

- The Earthwork Contractor is responsible for all clearing, grubbing, stripping and site preparation for the project in accordance with the recommendations of the Geotechnical Engineer.
- If any materials or areas are encountered by the Earthwork Contractor which are suspected of having toxic or environmentally sensitive contamination, the Geotechnical Engineer and Owner/Builder should be notified immediately.

- Major vegetation should be stripped and disposed of off-site. This includes trees, brush, heavy grasses and any materials considered unsuitable by the Geotechnical Engineer.
- Underground structures such as basements, cesspools or septic disposal systems, mining shafts, tunnels, wells and pipelines should be removed under the inspection of the Geotechnical Engineer and recommendations provided by the Geotechnical Engineer and/or city, county or state agencies. If such structures are known or found, the Geotechnical Engineer should be notified as soon as possible so that recommendations can be formulated.
- Any topsoil, slopewash, colluvium, alluvium and rock materials which are considered unsuitable by the Geotechnical Engineer should be removed prior to fill placement.
- Remaining voids created during site clearing caused by removal of trees, foundations basements, irrigation facilities, etc., should be excavated and filled with compacted fill.
- Subsequent to clearing and removals, areas to receive fill should be scarified to a depth of 10 to 12 inches, moisture conditioned and compacted
- The moisture condition of the processed ground should be at or slightly above the optimum moisture content as determined by the Geotechnical Engineer. Depending upon field conditions, this may require air drying or watering together with mixing and/or discing.

### Compacted Fills

- Soil materials imported to or excavated on the property may be utilized in the fill, provided each material has been determined to be suitable in the opinion of the Geotechnical Engineer. Unless otherwise approved by the Geotechnical Engineer, all fill materials shall be free of deleterious, organic, or frozen matter, shall contain no chemicals that may result in the material being classified as "contaminated," and shall be very low to non-expansive with a maximum expansion index (EI) of 50. The top 12 inches of the compacted fill should have a maximum particle size of 3 inches, and all underlying compacted fill material a maximum 6-inch particle size, except as noted below.
- All soils should be evaluated and tested by the Geotechnical Engineer. Materials with high expansion potential, low strength, poor gradation or containing organic materials may require removal from the site or selective placement and/or mixing to the satisfaction of the Geotechnical Engineer.
- Rock fragments or rocks less than 6 inches in their largest dimensions, or as otherwise determined by the Geotechnical Engineer, may be used in compacted fill, provided the distribution and placement is satisfactory in the opinion of the Geotechnical Engineer.
- Rock fragments or rocks greater than 12 inches should be taken off-site or placed in accordance with recommendations and in areas designated as suitable by the Geotechnical Engineer. These materials should be placed in accordance with Plate D-8 of these Grading Guide Specifications and in accordance with the following recommendations:
  - Rocks 12 inches or more in diameter should be placed in rows at least 15 feet apart, 15 feet from the edge of the fill, and 10 feet or more below subgrade. Spaces should be left between each rock fragment to provide for placement and compaction of soil around the fragments.
  - Fill materials consisting of soil meeting the minimum moisture content requirements and free of oversize material should be placed between and over the rows of rock or

concrete. Ample water and compactive effort should be applied to the fill materials as they are placed in order that all of the voids between each of the fragments are filled and compacted to the specified density.

- Subsequent rows of rocks should be placed such that they are not directly above a row placed in the previous lift of fill. A minimum 5-foot offset between rows is recommended.
- To facilitate future trenching, oversized material should not be placed within the range of foundation excavations, future utilities or other underground construction unless specifically approved by the soil engineer and the developer/owner representative.
- Fill materials approved by the Geotechnical Engineer should be placed in areas previously prepared to receive fill and in evenly placed, near horizontal layers at about 6 to 8 inches in loose thickness, or as otherwise determined by the Geotechnical Engineer for the project.
- Each layer should be moisture conditioned to optimum moisture content, or slightly above, as directed by the Geotechnical Engineer. After proper mixing and/or drying, to evenly distribute the moisture, the layers should be compacted to at least 90 percent of the maximum dry density in compliance with ASTM D-1557-78 unless otherwise indicated.
- Density and moisture content testing should be performed by the Geotechnical Engineer at random intervals and locations as determined by the Geotechnical Engineer. These tests are intended as an aid to the Earthwork Contractor, so he can evaluate his workmanship, equipment effectiveness and site conditions. The Earthwork Contractor is responsible for compaction as required by the Geotechnical Report(s) and governmental agencies.
- Fill areas unused for a period of time may require moisture conditioning, processing and recompaction prior to the start of additional filling. The Earthwork Contractor should notify the Geotechnical Engineer of his intent so that an evaluation can be made.
- Fill placed on ground sloping at a 5-to-1 inclination (horizontal-to-vertical) or steeper should be benched into bedrock or other suitable materials, as directed by the Geotechnical Engineer. Typical details of benching are illustrated on Plates D-2, D-4, and D-5.
- Cut/fill transition lots should have the cut portion overexcavated to a depth of at least 3 feet and rebuilt with fill (see Plate D-1), as determined by the Geotechnical Engineer.
- All cut lots should be inspected by the Geotechnical Engineer for fracturing and other bedrock conditions. If necessary, the pads should be overexcavated to a depth of 3 feet and rebuilt with a uniform, more cohesive soil type to impede moisture penetration.
- Cut portions of pad areas above buttresses or stabilizations should be overexcavated to a depth of 3 feet and rebuilt with uniform, more cohesive compacted fill to impede moisture penetration.
- Non-structural fill adjacent to structural fill should typically be placed in unison to provide lateral support. Backfill along walls must be placed and compacted with care to ensure that excessive unbalanced lateral pressures do not develop. The type of fill material placed adjacent to below grade walls must be properly tested and approved by the Geotechnical Engineer with consideration of the lateral earth pressure used in the design.

### **Foundations**

- The foundation influence zone is defined as extending one foot horizontally from the outside edge of a footing, and proceeding downward at a  $V_2$  horizontal to 1 vertical (0.5:1) inclination.
- Where overexcavation beneath a footing subgrade is necessary, it should be conducted so as to encompass the entire foundation influence zone, as described above.
- Compacted fill adjacent to exterior footings should extend at least 12 inches above foundation bearing grade. Compacted fill within the interior of structures should extend to the floor subgrade elevation.

#### Fill Slopes


- The placement and compaction of fill described above applies to all fill slopes. Slope compaction should be accomplished by overfilling the slope, adequately compacting the fill in even layers, including the overfilled zone and cutting the slope back to expose the compacted core
- Slope compaction may also be achieved by backrolling the slope adequately every 2 to 4 vertical feet during the filling process as well as requiring the earth moving and compaction equipment to work close to the top of the slope. Upon completion of slope construction, the slope face should be compacted with a sheepsfoot connected to a sideboom and then grid rolled. This method of slope compaction should only be used if approved by the Geotechnical Engineer.
- Sandy soils lacking in adequate cohesion may be unstable for a finished slope condition and therefore should not be placed within 15 horizontal feet of the slope face.
- All fill slopes should be keyed into bedrock or other suitable material. Fill keys should be at least 15 feet wide and inclined at 2 percent into the slope. For slopes higher than 30 feet, the fill key width should be equal to one-half the height of the slope (see Plate D-5).
- All fill keys should be cleared of loose slough material prior to geotechnical inspection and should be approved by the Geotechnical Engineer and governmental agencies prior to filling.
- The cut portion of fill over cut slopes should be made first and inspected by the Geotechnical Engineer for possible stabilization requirements. The fill portion should be adequately keyed through all surficial soils and into bedrock or suitable material. Soils should be removed from the transition zone between the cut and fill portions (see Plate D-2).


#### Cut Slopes


- All cut slopes should be inspected by the Geotechnical Engineer to determine the need for stabilization. The Earthwork Contractor should notify the Geotechnical Engineer when slope cutting is in progress at intervals of 10 vertical feet. Failure to notify may result in a delay in recommendations.
- Cut slopes exposing loose, cohesionless sands should be reported to the Geotechnical Engineer for possible stabilization recommendations.
- All stabilization excavations should be cleared of loose slough material prior to geotechnical inspection. Stakes should be provided by the Civil Engineer to verify the location and dimensions of the key. A typical stabilization fill detail is shown on Plate D-5.


#### Subdrains


- Subdrains may be required in canyons and swales where fill placement is proposed. Typical subdrain details for canyons are shown on Plate D-3. Subdrains should be installed after approval of removals and before filling, as determined by the Soils Engineer.
- Plastic pipe may be used for subdrains provided it is Schedule 40 or SDR 35 or equivalent. Pipe should be protected against breakage, typically by placement in a square-cut (backhoe) trench or as recommended by the manufacturer.
- Filter material for subdrains should conform to CALTRANS Specification 68-1.025 or as approved by the Geotechnical Engineer for the specific site conditions. Clean <sup>3</sup>/<sub>4</sub>-inch crushed rock may be used provided it is wrapped in an acceptable filter cloth and approved by the Geotechnical Engineer. Pipe diameters should be 6 inches for runs up to 500 feet and 8 inches for the downstream continuations of longer runs. Four-inch diameter pipe may be used in buttress and stabilization fills.




















A P P E D I X E

| SA                                     |                          | OSHPD   |  |  |
|--|--------------------------|---|--|--|
| atitud                                 | le, Longitude: 33.930    | 784, -118.071042  |  |  |
| Avé -                                  |                          | y Machinery CE V Western Water Works<br>Supply Company<br>Jones Environmental V<br>Crate & Barrel V<br>Warehouse                                    |  |  |
| Paddison Ave                           | Kalnar Ave               | Achilles St OUTC Aerospace Systems  |  |  |
|  | keland                   | Harbor Distributing 🜳   |  |  |
| Goo                                    | glentary School          | Map data ©2021  |  |  |
| Date                                   |                          | 12/8/2021, 1:23:40 PM   |  |  |
| Design C                               | Code Reference Document  | ASCE7-16  |  |  |
| Risk Category                          |                          | m   |  |  |
| Site Clas                              | 55                       | D - Stiff Soil  |  |  |
| Гуре                                   | Value                    | Description   |  |  |
| SS                                     | 1.697                    | MCE <sub>R</sub> ground motion. (for 0.2 second period)   |  |  |
| S <sub>1</sub>                         | 0.607                    | MCE <sub>R</sub> ground motion. (for 1.0s period)   |  |  |
| SMS                                    | 1.697                    | Site-modified spectral acceleration value   |  |  |
| S <sub>M1</sub>                        | null -See Section 11.4.8 | Site-modified spectral acceleration value   |  |  |
| SDS                                    | 1.132                    | Numeric seismic design value at 0.2 second SA   |  |  |
| S <sub>D1</sub>                        | null -See Section 11.4.8 | Numeric seismic design value at 1.0 second SA   |  |  |
| Гуре                                   | Value                    | Description   |  |  |
| SDC                                    | null -See Section 11.4.8 | Seismic design category   |  |  |
| Fa                                     | 1                        | Site amplification factor at 0.2 second   |  |  |
| Fv                                     | null -See Section 11.4.8 | Site amplification factor at 1.0 second   |  |  |
| PGA                                    | 0.73                     | MCE <sub>G</sub> peak ground acceleration   |  |  |
| FPGA                                   | 1.1                      | Site amplification factor at PGA  |  |  |
| PGAM                                   | 0.803                    | Site modified peak ground acceleration  |  |  |
| TL                                     | 8                        | Long-period transition period in seconds  |  |  |
|  |                          |   |  |  |
| SsRT<br>SsUH                           | 1.697<br>1.876           | Probabilistic risk-targeted ground motion. (0.2 second)<br>Eactored uniform-bazard (2% probability of exceedance in 50 years) spectral acceleration |  |  |
| SsD                                    | 2.355                    | Factored uniform-hazard (2% probability of exceedance in 50 years) spectral acceleration  |  |  |
| S1RT                                   | 0.607                    | Factored deterministic acceleration value, (0.2 second)<br>Probabilistic risk-targeted ground motion. (1.0 second)                                  |  |  |
|  | 0.673                    | Probabilistic risk-targeted ground motion. (1.0 second)<br>Factored uniform-hazard (2% probability of exceedance in 50 years) spectral acceleration |  |  |
|  | 0.788                    | Factored deterministic acceleration value. (1.0 second)   |  |  |
| S1UH                                   |                          |   |  |  |
| S1UH<br>S1D                            |                          | Factored deterministic acceleration value. (Peak Ground Acceleration)   |  |  |
| S1UH<br>S1D<br>PGAd<br>C <sub>RS</sub> | 0.95<br>0.905            | Factored deterministic acceleration value. (Peak Ground Acceleration)<br>Mapped value of the risk coefficient at short periods                      |  |  |

SOURCE: SEAOC/OSHPD Seismic Design Maps Tool <https://seismicmaps.org/>



December 13, 2021

Duke Realty 200 Spectrum Center Drive, Suite 1600 Irvine, California 92618



- Attention: Mr. D.J. Arellano, P.E. Director, Development Services
- Project No.: **21G248-2**
- Subject: **Results of Infiltration Testing** Proposed Warehouse SEC Lakeland Road and Norwalk Boulevard Santa Fe Springs, California
- Reference: <u>Geotechnical Investigation, Proposed Warehouse, SEC Lakeland Road and Norwalk</u> <u>Boulevard</u>, prepared by Southern California Geotechnical, Inc. (SCG) Duke Realty, SCG project No. 21G248-1.

Mr. Arellano:

In accordance with your request, we have conducted infiltration testing at the subject site. We are pleased to present this report summarizing the results of the infiltration testing and our design recommendations.

# Scope of Services

The scope of services performed for this project was in general accordance with our Proposal No. 21P435, dated October 6, 2021. The scope of services included site reconnaissance, subsurface exploration, field testing, and engineering analysis to determine the infiltration rates of the onsite soils. The infiltration testing was performed in general accordance with the <u>Guidelines for</u> <u>Geotechnical Investigation and Reporting – Low Impact Development Stormwater Infiltration</u> (<u>GS200.1</u>), prepared by Los Angeles County, Department of Public Works, Geotechnical and Materials Engineering Division, dated June 30, 2021.

## Site and Project Description

The site is located at the southeast corner of Lakeland Road and Norwalk Boulevard in Santa Fe Springs, California. The site is known by the address of 12300 Lakeland Boulevard. The site is bounded to the north by Lakeland Road, to the west by Norwalk Boulevard and an existing aerospace manufacturing facility, to the south by a parking lot with an existing commercial/industrial building, and to the east by Getty Drive. The general location of the site is illustrated on the Site Location Map, included as Plate 1 of this report.

The site consists of an L-shaped parcel,  $8.45\pm$  acres in size. Based on our visit to the site, the site is developed with four (4) commercial/industrial buildings with footprints ranging from 4,000 to  $50,000\pm$  ft<sup>2</sup>. The buildings are single-story structures of concrete tilt-up and metal frame construction, which are assumed to be supported on conventional shallow foundations with

concrete slab-on-grade floors. Several parallel steel beams transect the site east-to-west which are utilized to transport manufactured metal beams. The buildings are surrounded by asphaltic concrete pavements, with sparse regions of Portland Cement concrete (PCC). The pavements throughout the site are in poor condition, with extensive cracking throughout. The ground surface cover of the northwestern parking lot consists of open graded gravel.

Detailed topographic information was not available at the time of this report. Based on elevations obtained from Google Earth and visual observations made at the time of the subsurface investigation, the overall site is relatively flat, with less than  $4\pm$  feet of elevation differential throughout the site. The site slopes gently to the west with a gradient of less than  $1\pm$  percent.

## **Proposed Development**

SCG was provided with conceptual site plan by the client. Based on this plan, the site will be developed with one (1) warehouse building. The building will be  $184,680 \pm ft^2$  in size and will be located in the east-central area of the subject site. Dock-high doors will be constructed along a portion of the west building wall. The building will be surrounded by asphaltic concrete pavements in the parking and drive areas, Portland cement concrete pavements in the truck court areas, and limited areas of concrete flatwork and landscape planters throughout.

The proposed development will include on-site infiltration to dispose of storm water. Based on discussion with the project civil engineer, a total of two (2) below-grade chambers will be located on the western and northwestern portions of the site. These infiltration systems will be referenced **as Infiltration System "A"** and **"B"**. The bottoms of the chamber systems are expected to be  $10 \pm$  feet below existing site grades.

# **Concurrent Study**

Southern California Geotechnical, Inc. (SCG) concurrently performed a geotechnical investigation at the subject site, referenced above. As part of this investigation, SCG performed a total of eight (8) borings advanced to depths of 15 to  $25\pm$  feet below the existing site grades.

Asphaltic concrete pavements (AC) were encountered at the ground surface of all boring locations except for Boring No. B-5. The AC pavements measure 3 to  $5\pm$  inches in thickness with 0 to  $5\pm$  inches of discernible Aggregate Base (AB). Artificial fill soils were encountered at the ground surface or beneath the pavements at all boring locations, extending to depths of  $2\frac{1}{2}$  to  $6\frac{1}{2}\pm$  feet below existing site grades. The fill soils consist of medium stiff to very stiff silty clays, stiff fine sandy clays, loose gravelly fine to coarse sands, loose fine sandy silts, and loose to medium dense silty fine sands. Additionally, soils identified as possible fill were encountered at Boring No. B-6, extending to a depth of  $5\frac{1}{2}\pm$  feet below existing site grades. The possible fill consists of stiff silty clays. Native alluvium was encountered beneath the fill soils at all of the boring locations, extending to at least the maximum depth explored of  $25\pm$  feet below ground surface. The alluvium consists of stiff to very stiff silty clays, loose to medium dense silty fine sands, medium dense to very dense fine sandy silts, stiff to hard clayey silts, medium dense clayey fine sands, and very stiff fine sandy clays. Calcareous nodules and veining and various levels of iron oxide staining were encountered throughout various strata within the native soils.



# Subsurface Exploration

### Scope of Exploration

The subsurface exploration for the infiltration testing consisted of two (2) infiltration test borings advanced to a depth of  $10\pm$  feet below the existing site grades. The borings were logged during drilling by a member of our staff and were advanced using a truck-mounted drilling rig, equipped with 8-inch-diameter hollow stem augers. The approximate locations of the infiltration test borings (identified as I-1 and I-2) are indicated on the Infiltration Test Location Plan, enclosed as Plate 2 of this report.

Upon the completion of the infiltration borings, the bottom of each test boring was covered with  $2\pm$  inches of clean 3/4-inch gravel. A sufficient length of 3-inch-diameter perforated PVC casing was then placed into each test hole so that the PVC casing extended from the bottom of the test hole to the ground surface. Clean 3/4-inch gravel was then installed in the annulus surrounding the PVC casing.

### Geotechnical Conditions

Artificial fill soils were encountered beneath the pavements or open graded gravel at both of the infiltration boring locations, extending to a depth of  $5\frac{1}{2}\pm$  feet below existing site grades. The fill soils consist of stiff silty clays. Native alluvial soils were encountered beneath the fill soils, extending to at least the maximum explored depth of  $10\pm$  feet below existing site grades. The native alluvium consists of medium dense to very dense silty fine to medium sands and fine to medium sandy silts. The Boring Logs, which illustrate the conditions encountered at the infiltration test locations, are included with this report.

## Groundwater

Free water was not encountered during the drilling of the infiltration and geotechnical borings. Based on the lack of any water within the borings, and the moisture contents of the recovered soil samples, the static groundwater table is considered to have existed at a depth in excess of  $25\pm$  feet at the time of the subsurface exploration.

Recent water level data was obtained from the California State Water Resources Control Board, GeoTracker, website, <u>https://geotracker.waterboards.ca.gov/</u>. One monitoring wells on record is located 175± feet north of the site. Water level readings within this monitoring wells indicate a high groundwater level of 119± feet below the ground surface in June 2021.

## Infiltration Testing

As previously mentioned, the infiltration testing was performed in general accordance with the guidelines published by the County of Los Angeles – Department of Public Works Geotechnical and Materials Engineering Division, titled Guidelines for Design, Investigation, and Reporting Low Impact Development Stormwater Infiltration, GS200.1.



## <u>Pre-soaking</u>

The infiltration test borings were pre-soaked prior to the infiltration testing. The pre-soaking procedure consisted of filling each test boring with clean potable water to an elevation of at least  $12\pm$  inches above the bottom of each test boring. In accordance with the Los Angeles County guidelines, the borings were presoaked for 1 hour to ensure the soil around the annulus of the perforated pipe was fully saturated.

### Infiltration Testing Procedure

After the completion of the pre-soaking process, SCG performed the infiltration testing. A sufficient amount of water was added to the test borings so that the water level was approximately 12 to 24± inches higher than the bottom of the borings and less than or equal to the water level used during the pre-soaking process. Based on the pre-soaking procedure, Infiltration Nos. I-1 and I-2 require a falling head test with 30-minute intervals. Each test was infiltrating for a minimum of 3-hours. A stabilized rate of drop, where the highest and lowest readings from three consecutive readings are within 10 percent of each other, was obtained for each of the test borings. These water level readings are presented on the spreadsheets enclosed with this report. The infiltration rates for each of the timed intervals are also tabulated on the spreadsheets.

The infiltration rates for the falling head tests are tabulated in inches per hour. In accordance with the typically accepted practice, it is recommended that the most conservative reading from the latter part of the infiltration tests be used for design. Please note that the Porchet method was used for the falling head tests to account for non-vertical flow through the sides of the boring in addition to the bottom of the boring. These rates are summarized below:

| Infiltration<br>Test No. | <u>Test</u><br><u>Depth</u><br>(feet) | Soil Description                         | Infiltration Rate<br>(inches/hour) |
|--------------------------|---------------------------------------|--|------------------------------------|
| 1-1                      | 10                                    | Light Brown fine to medium Sandy Silt    | 0.5                                |
| I-2                      | 10                                    | Brown fine Sandy Silt, trace medium Sand | 0.8                                |

# Laboratory Testing

## Moisture Content

The moisture contents for the recovered soil samples within the borings were determined in accordance with ASTM D-2216 and are expressed as a percentage of the dry weight. These test results are presented on the Boring Logs.

## Grain Size Analysis

The grain size distribution of selected soils collected from the base of each infiltration test boring



have been determined using a range of wire mesh screens. These tests were performed in general accordance with ASTM D-422 and/or ASTM D-1140. The weight of the portion of the sample retained on each screen is recorded and the percentage finer or coarser of the total weight is calculated. The results of these tests are presented on Plates C-1 through C-2 of this report.

## **Design Recommendations**

Two (2) infiltration tests were performed at the subject site. As noted above, the infiltration rates at these locations vary from 0.5 to 0.8 inches per hour.

The <u>Guidelines for Geotechnical Investigation and Reporting Low Impact Development Stormwater</u> <u>Infiltration, GS200.1</u> prepared by the County of Los Angeles, Department of Public Works, Geotechnical and Materials Division (GMED) on June 30, 2021 dictate that a reduction factor be utilized in the design infiltration rate. The following reduction factors are considered in the design assumed infiltration rate:

| Reduction Factor  |                    |  |  |  |
|---|--------------------|--|--|--|
| Small Diameter Percolation  | $RF_t = 2$         |  |  |  |
| Site Variability, number of tests, and thoroughness of subsurface investigation | $RF_v = 1$         |  |  |  |
| Long-term siltation plugging and maintenance                                    | $RF_v = 1$         |  |  |  |
| Total Reduction Factor, $RF = RF_{t+}RF_{v+}RF_{v}$                             | RF = 4             |  |  |  |
| Design Infiltration Rate (DIR) = Measured Percolation Rate/RF                   | DIR = See<br>below |  |  |  |

Based on the results of the infiltration testing, the following infiltration rates should be used in the design of the infiltration systems in their respective locations and depths:

| Infiltration System | Infiltration Rate (inches/hour) |
|---------------------|---------------------------------|
| А                   | 0.1                             |
| В                   | 0.2                             |

We recommend that a representative from the geotechnical engineer be on-site during the construction of the proposed infiltration system to identify the soil classification at the base of the system. It should be confirmed that the soils at the base of the proposed infiltration system correspond with those presented in this report to ensure that the performance of the system will be consistent with the rates reported herein.

The design of the storm water infiltration systems should be performed by the project civil engineer, in accordance with the City of Santa Fe Springs and/or County of Los Angeles guidelines. It is recommended that the system be constructed so as to facilitate removal of silt and clay, or other deleterious materials from any water that may enter the system. The presence of such materials would decrease the effective infiltration rates. **It is recommended that the project civil engineer apply an appropriate factor of safety. The infiltration rate recommended above is based on the assumption that only clean water will be introduced to the subsurface profile. Any fines, debris, or organic materials could significantly impact** 



**the infiltration rate.** It should be noted that the recommended infiltration rates are based on infiltration testing at two (2) discrete locations and that the overall infiltration rates of the proposed infiltration systems could vary considerably.

# **Construction Considerations**

The infiltration rates presented in this report are specific to the tested locations and tested depths. Infiltration rates can be significantly reduced if the soils are exposed to excessive disturbance or compaction during construction. Compaction of the soils at the bottom of the infiltration system can significantly reduce the infiltration ability of the chambers and basins. Therefore, the subgrade soils within proposed infiltration system areas should not be over-excavated, undercut or compacted in any significant manner. **It is recommended that a note to this effect be added to the project plans and/or specifications.** 

We recommend that a representative from the geotechnical engineer be on-site during the construction of the proposed infiltration systems to identify the soil classification at the base of each system. It should be confirmed that the soils at the base of the proposed infiltration systems correspond with those presented in this report to ensure that the performance of the systems will be consistent with the rates reported herein.

We recommend that scrapers and other rubber-tired heavy equipment not be operated on the basin bottom, or at levels lower than 2 feet above the bottom of the system, particularly within basins. As such, the bottom 24 inches of the infiltration systems should be excavated with non-rubber-tired equipment, such as excavators.

# **Infiltration Chamber Maintenance**

The proposed project may include infiltration chambers. Water flowing into these chambers will carry some level of sediment. This layer has the potential to significantly reduce the infiltration rate of the chamber subgrade soils. Therefore, a formal chamber maintenance program should be established to ensure that these silt and clay deposits are removed from the chamber on a regular basis.

# Location of Infiltration Systems

The use of on-site storm water infiltration systems carries a risk of creating adverse geotechnical conditions. Increasing the moisture content of the soil can cause the soil to lose internal shear strength and increase its compressibility, resulting in a change in the designed engineering properties. Overlying structures and pavements in the infiltration area could potentially be damaged due to saturation of the subgrade soils. **The proposed infiltration systems for this site should be located at least 25 feet away from any structures, including retaining walls.** Even with this provision of locating the infiltration system at least 25 feet from the building(s), it is possible that infiltrating water into the subsurface soils could have an adverse effect on the proposed or existing structures. It should also be noted that utility trenches which happen to collect storm water can also serve as conduits to transmit storm water toward the structure, depending on the slope of the utility trench. Therefore, consideration should also be given to the proposed locations of underground utilities which may pass near the proposed infiltration system.



The infiltration system designer should also give special consideration to the effect that the proposed infiltration systems may have on nearby subterranean structures, open excavations, or descending slopes. In particular, infiltration systems should not be located near the crest of descending slopes, particularly where the slopes are comprised of granular soils. Such systems will require specialized design and analysis to evaluate the potential for slope instability, piping failures and other phenomena that typically apply to earthen dam design. This type of analysis is beyond the scope of this infiltration test report, but these factors should be considered by the infiltration system designer when locating the infiltration systems.

### **General Comments**

This report has been prepared as an instrument of service for use by the client in order to aid in the evaluation of this property and to assist the architects and engineers in the design and preparation of the project plans and specifications. This report may be provided to the contractor(s) and other design consultants to disclose information relative to the project. However, this report is not intended to be utilized as a specification in and of itself, without appropriate interpretation by the project architect, structural engineer, and/or civil engineer. The design of the proposed storm water infiltration system is the responsibility of the civil engineer. The role of the geotechnical engineer is limited to determination of infiltration rate only. By using the design infiltration rate contained herein, the civil engineer agrees to indemnify, defend, and hold harmless the geotechnical engineer for all aspects of the design and performance of the proposed storm water infiltration system. The reproduction and distribution of this report must be authorized by the client and Southern California Geotechnical, Inc. Furthermore, any reliance on this report by an unauthorized third party is at such party's sole risk, and we accept no responsibility for damage or loss which may occur.

The analysis of this site was based on a subsurface profile interpolated from limited discrete soil samples. While the materials encountered in the project area are considered to be representative of the total area, some variations should be expected between boring locations and testing depths. If the conditions encountered during construction vary significantly from those detailed herein, we should be contacted immediately to determine if the conditions alter the recommendations contained herein.

This report has been based on assumed or provided characteristics of the proposed development. It is recommended that the owner, client, architect, structural engineer, and civil engineer carefully review these assumptions to ensure that they are consistent with the characteristics of the proposed development. If discrepancies exist, they should be brought to our attention to verify that they do not affect the conclusions and recommendations contained herein. We also recommend that the project plans and specifications be submitted to our office for review to verify that our recommendations have been correctly interpreted. The analysis, conclusions, and recommendations contained within this report have been promulgated in accordance with generally accepted professional geotechnical engineering practice. No other warranty is implied or expressed.



### <u>Closure</u>

We sincerely appreciate the opportunity to be of service on this project. We look forward to providing additional consulting services during the course of the project. If we may be of further assistance in any manner, please contact our office.


Respectfully Submitted,

### SOUTHERN CALIFORNIA GEOTECHNICAL, INC.





Grain Size Distribution Results (2 pages)













APPROXIMATE INFILTRATION TEST LOCATION  $\oplus$ 

**GEOTECHNICAL LEGEND** 



# **BORING LOG LEGEND**

| SAMPLE TYPE | GRAPHICAL<br>SYMBOL | SAMPLE DESCRIPTION  |
|-------------|---------------------|---|
| AUGER       |                     | SAMPLE COLLECTED FROM AUGER CUTTINGS, NO FIELD<br>MEASUREMENT OF SOIL STRENGTH. (DISTURBED)   |
| CORE        |                     | ROCK CORE SAMPLE: TYPICALLY TAKEN WITH A<br>DIAMOND-TIPPED CORE BARREL. TYPICALLY USED<br>ONLY IN HIGHLY CONSOLIDATED BEDROCK.                          |
| GRAB        | N.                  | SOIL SAMPLE TAKEN WITH NO SPECIALIZED<br>EQUIPMENT, SUCH AS FROM A STOCKPILE OR THE<br>GROUND SURFACE. (DISTURBED)                                      |
| CS          |                     | CALIFORNIA SAMPLER: 2-1/2 INCH I.D. SPLIT BARREL<br>SAMPLER, LINED WITH 1-INCH HIGH BRASS RINGS.<br>DRIVEN WITH SPT HAMMER. (RELATIVELY<br>UNDISTURBED) |
| NSR         | $\bigcirc$          | NO RECOVERY: THE SAMPLING ATTEMPT DID NOT<br>RESULT IN RECOVERY OF ANY SIGNIFICANT SOIL OR<br>ROCK MATERIAL.  |
| SPT         |                     | STANDARD PENETRATION TEST: SAMPLER IS A 1.4<br>INCH INSIDE DIAMETER SPLIT BARREL, DRIVEN 18<br>INCHES WITH THE SPT HAMMER. (DISTURBED)                  |
| SH          |                     | SHELBY TUBE: TAKEN WITH A THIN WALL SAMPLE<br>TUBE, PUSHED INTO THE SOIL AND THEN EXTRACTED.<br>(UNDISTURBED)   |
| VANE        |                     | VANE SHEAR TEST: SOIL STRENGTH OBTAINED USING<br>A 4 BLADED SHEAR DEVICE. TYPICALLY USED IN SOFT<br>CLAYS-NO SAMPLE RECOVERED.                          |

### **COLUMN DESCRIPTIONS**

## SOIL CLASSIFICATION CHART

| М  | AJOR DIVISI                            | ONS                              |          | BOLS   | TYPICAL   |
|--|--|----------------------------------|----------|--------|---|
|  |  | 0110                             | GRAPH    | LETTER | DESCRIPTIONS  |
|  | GRAVEL<br>AND                          | CLEAN<br>GRAVELS                 |          | GW     | WELL-GRADED GRAVELS, GRAVEL -<br>SAND MIXTURES, LITTLE OR NO<br>FINES   |
|  | GRAVELLY<br>SOILS                      | (LITTLE OR NO FINES)             |          | GP     | POORLY-GRADED GRAVELS,<br>GRAVEL - SAND MIXTURES, LITTLE<br>OR NO FINES   |
| COARSE<br>GRAINED<br>SOILS                                       | MORE THAN 50%<br>OF COARSE             | GRAVELS WITH<br>FINES            |          | GM     | SILTY GRAVELS, GRAVEL - SAND -<br>SILT MIXTURES   |
|  | FRACTION<br>RETAINED ON NO.<br>4 SIEVE | (APPRECIABLE<br>AMOUNT OF FINES) |          | GC     | CLAYEY GRAVELS, GRAVEL - SAND -<br>CLAY MIXTURES  |
| MORE THAN 50%<br>OF MATERIAL IS                                  | SAND<br>AND                            | CLEAN SANDS                      |          | SW     | WELL-GRADED SANDS, GRAVELLY<br>SANDS, LITTLE OR NO FINES  |
| LARGER THAN<br>NO. 200 SIEVE<br>SIZE                             | SANDY<br>SOILS                         | (LITTLE OR NO FINES)             |          | SP     | POORLY-GRADED SANDS,<br>GRAVELLY SAND, LITTLE OR NO<br>FINES  |
|  | MORE THAN 50%<br>OF COARSE             | SANDS WITH<br>FINES              |          | SM     | SILTY SANDS, SAND - SILT<br>MIXTURES  |
|  | FRACTION<br>PASSING ON NO.<br>4 SIEVE  | (APPRECIABLE<br>AMOUNT OF FINES) |          | SC     | CLAYEY SANDS, SAND - CLAY<br>MIXTURES   |
|  |  |                                  |          | ML     | INORGANIC SILTS AND VERY FINE<br>SANDS, ROCK FLOUR, SILTY OR<br>CLAYEY FINE SANDS OR CLAYEY<br>SILTS WITH SLIGHT PLASTICITY |
| FINE<br>GRAINED<br>SOILS   | SILTS<br>AND<br>CLAYS                  | LIQUID LIMIT<br>LESS THAN 50     |          | CL     | INORGANIC CLAYS OF LOW TO<br>MEDIUM PLASTICITY, GRAVELLY<br>CLAYS, SANDY CLAYS, SILTY CLAYS,<br>LEAN CLAYS                  |
| 00120  |  |                                  |          | OL     | ORGANIC SILTS AND ORGANIC<br>SILTY CLAYS OF LOW PLASTICITY  |
| MORE THAN 50%<br>OF MATERIAL IS<br>SMALLER THAN<br>NO. 200 SIEVE |  |                                  |          | МН     | INORGANIC SILTS, MICACEOUS OR<br>DIATOMACEOUS FINE SAND OR<br>SILTY SOILS   |
| SIZE   | SILTS<br>AND<br>CLAYS                  | LIQUID LIMIT<br>GREATER THAN 50  |          | СН     | INORGANIC CLAYS OF HIGH<br>PLASTICITY   |
|  |  |                                  |          | ОН     | ORGANIC CLAYS OF MEDIUM TO<br>HIGH PLASTICITY, ORGANIC SILTS  |
| н  | GHLY ORGANIC S                         | SOILS                            | <u> </u> | PT     | PEAT, HUMUS, SWAMP SOILS WITH<br>HIGH ORGANIC CONTENTS  |

NOTE: DUAL SYMBOLS ARE USED TO INDICATE BORDERLINE SOIL CLASSIFICATIONS



| JOB NO.: 21G248-2       DRILLING DATE: 11/4/21       WATER DEPTH: Dry         PROJECT: Proposed Warehouse       DRILLING METHOD: Hollow Stem Auger       CAVE DEPTH:         LOCATION: Santa Fe Springs, California       LOGGED BY: Ryan Bremer       READING TAKEN: At Completion         FIELD RESULTS       LABORATORY RESULTS       VATER DEPTH: |        |            |                      |             |  |                      |                         |        |                  | mpletion                  |                        |          |
|---|--------|------------|----------------------|-------------|--|----------------------|-------------------------|--------|------------------|---------------------------|------------------------|----------|
|   |        |            |                      | _           |  | LAE                  |                         |        |                  |                           |                        | •        |
| DEPTH (FEET)  | SAMPLE | BLOW COUNT | POCKET PEN.<br>(TSF) | GRAPHIC LOG | DESCRIPTION<br>SURFACE ELEVATION:  | DRY DENSITY<br>(PCF) | MOISTURE<br>CONTENT (%) | LIQUID | PLASTIC<br>LIMIT | PASSING<br>#200 SIEVE (%) | ORGANIC<br>CONTENT (%) | COMMENTS |
|   |        | 12         | 4.5                  |             | ASPHALT: 41/2± inches Asphaltic Concrete with no discernible<br>Aggregate Base<br><u>FILL:</u> Brown Silty Clay, little fine Sand, stiff to very stiff-moist |                      | 14                      |        |                  |                           |                        | -        |
| 5   |        | 21         | 4.5                  |             |  |                      | 13                      |        |                  |                           |                        | -        |
|   |        | 17         |                      |             | · · ·  |                      | 10                      |        |                  |                           |                        |          |
| -10-  |        | 23         |                      |             | Light Brown fine Sandy Silt, trace medium Sand, little Iron<br>Oxide staining, medium dense-very moist   |                      | 19                      |        |                  |                           |                        |          |
|   |        |            |                      |             | Boring Terminated at 10'   |                      |                         |        |                  |                           |                        |          |
| TBL 21G248-2.GPJ SOCALGEO.GDT 12/13/21  | ST     | BC         | RIN                  | IGI         | _OG  |                      |                         |        |                  |                           | P                      | LATE B-1 |



| PRO                                | JOB NO.: 21G248-2DRILLING DATE: 11/8/21WATER DEPTH: DryPROJECT: Proposed WarehouseDRILLING METHOD: Hollow Stem AugerCAVE DEPTH:LOCATION: Santa Fe Springs, CaliforniaLOGGED BY: Jamie HaywardREADING TAKEN: At Completion |            |                      |             |   |                      |                         |                 |                  |                           |                        |          |
|------------------------------------|---|------------|----------------------|-------------|---|----------------------|-------------------------|-----------------|------------------|---------------------------|------------------------|----------|
|                                    | LOCATION: Santa Fe Springs, California LOGGED BY: Jamie Hayward FIELD RESULTS   |            |                      |             |   |                      |                         |                 |                  |                           |                        | mpletion |
| FIE                                |   | KESU       |                      |             |   | LAE                  | SOR/                    | ATOP            | ry Ri            | 2501                      | _15                    |          |
| DEPTH (FEET)                       | SAMPLE  | BLOW COUNT | POCKET PEN.<br>(TSF) | GRAPHIC LOG | DESCRIPTION SURFACE ELEVATION:  | DRY DENSITY<br>(PCF) | MOISTURE<br>CONTENT (%) | LIQUID<br>LIMIT | PLASTIC<br>LIMIT | PASSING<br>#200 SIEVE (%) | ORGANIC<br>CONTENT (%) | COMMENTS |
|                                    | 0,  | ш          |                      |             | <u>PAVEMENT:</u> 1± inch open graded Gravel   |                      | 20                      |                 |                  | ш #                       | 00                     | 0        |
|                                    |   | 31         |                      |             | ALLUVIUM: Brown Silty fine Sand, slightly cemented, dense to very dense-moist   | -                    | 14                      |                 |                  |                           |                        |          |
| 5                                  |   | 59         |                      | лин         | -<br>Brown Silty Clay, little fine Sand, very stiff-moist   | -                    | 13                      |                 |                  |                           |                        | -        |
|                                    |   | 25         | 4.5                  |             | · · · · ·   | -                    | 10                      |                 |                  |                           |                        | -        |
| -10-                               | X   | 30         |                      |             | Brown fine Sandy Silt, trace medium Sand, little Calcareous<br>nodules, little Iron Oxide staining, medium dense to<br>dense-very moist |                      | 19                      |                 |                  |                           |                        |          |
|                                    |   |            |                      |             | Boring Terminated at 10'  |                      |                         |                 |                  |                           |                        |          |
|                                    |   |            |                      |             |   |                      |                         |                 |                  |                           |                        |          |
|                                    |   |            |                      |             |   |                      |                         |                 |                  |                           |                        |          |
|                                    |   |            |                      |             |   |                      |                         |                 |                  |                           |                        |          |
| EO.GDT 12/13/21                    |   |            |                      |             |   |                      |                         |                 |                  |                           |                        |          |
| 21G248-2.GPJ SOCALGEO.GDT 12/13/21 |   |            |                      |             |   |                      |                         |                 |                  |                           |                        |          |
| TBL                                |   |            |                      |             | OG  |                      |                         |                 |                  |                           |                        | LATE B-2 |

### INFILTRATION CALCULATIONS

| Project Name     | Proposed Warehouse           |
|------------------|------------------------------|
| Project Location | Santa Fe Springs, California |
| Project Number   | 21G248-2                     |
| Engineer         | Caleb Brackett               |
|                  |                              |
| Test Hole Radius | 4 (in)                       |

Test Depth

Infiltration Test Hole

|                    | Soil Criteria Test |         |                        |                     |                                  |   |                                     |  |  |  |  |  |
|--------------------|--------------------|---------|------------------------|---------------------|----------------------------------|---|-------------------------------------|--|--|--|--|--|
| Interval<br>Number |                    | Time    | Time Interval<br>(min) | Water Depth<br>(ft) | Change in<br>Water Level<br>(in) | Did 12 inches of water<br>seep away in less than<br>25 minutes? | Sandy Soils or Non-<br>Sandy Soils? |  |  |  |  |  |
| 1                  | Initial            | 7:57 AM | 30.00                  | 7.10                | 7.10 10.92 N                     | NO  | NON-SANDY SOILS                     |  |  |  |  |  |
| 1                  | Final              | 8:27 AM | 30.00                  | 8.01                | 10.92                            | NO  | NUN-SANDY SUILS                     |  |  |  |  |  |
| 2                  | Initial            | 8:27 AM | 30.00                  | 7.10                | 9.12                             | NO  | NON-SANDY SOILS                     |  |  |  |  |  |
| 2 Final            | Final              | 8:57 AM | 30.00                  | 7.86                | 9.12                             | UNI   | NUN-SANDY SUILS                     |  |  |  |  |  |

|                    | Test Data |          |                        |                     |                                  |                             |                                |  |  |  |  |  |
|--------------------|-----------|----------|------------------------|---------------------|----------------------------------|-----------------------------|--------------------------------|--|--|--|--|--|
| Interval<br>Number |           | Time     | Time Interval<br>(min) | Water Depth<br>(ft) | Change in<br>Water Level<br>(ft) | Average Head Height<br>(ft) | Infiltration Rate Q<br>(in/hr) |  |  |  |  |  |
| 1                  | Initial   | 8:57 AM  | 30.00                  | 7.10                | 0.78                             | 2.61                        | 1.12                           |  |  |  |  |  |
| 1                  | Final     | 9:27 AM  | 30.00                  | 7.88                | 0.70                             | 2.01                        | 1.12                           |  |  |  |  |  |
| 2                  | Initial   | 9:27 AM  | 30.00                  | 7.10                | 0.76                             | 2.62                        | 1.09                           |  |  |  |  |  |
| 2                  | Final     | 9:57 AM  | 00.00                  | 7.86                | 0.70                             | 2.02                        | 1.00                           |  |  |  |  |  |
| 3                  | Initial   | 9:57 AM  | 30.00                  | 7.10                | 0.54                             | 2.73                        | 0.75                           |  |  |  |  |  |
| 5                  | Final     | 10:27 AM | 30.00                  | 7.64                | 0.04                             | 2.15                        | 0.15                           |  |  |  |  |  |
| 4                  | Initial   | 10:27 AM | 30.00                  | 7.10                | 0.40                             | 2.80                        | 0.54                           |  |  |  |  |  |
| 4                  | Final     | 10:57 AM | 30.00                  | 7.50                | 0.40                             | 2.00                        | 0.54                           |  |  |  |  |  |
| 5                  | Initial   | 10:57 AM | 30.00                  | 7.10                | 0.38                             | 2.81                        | 0.51                           |  |  |  |  |  |
| 5                  | Final     | 11:27 AM | 30.00                  | 7.48                | 0.30                             | 2.01                        | 0.51                           |  |  |  |  |  |
| 6                  | Initial   | 11:27 AM | 30.00                  | 7.10                | 0.35                             | 2.83                        | 0.46                           |  |  |  |  |  |
| 0                  | Final     | 11:57 AM | 50.00                  | 7.45                | 0.55                             | 2.05                        | 0.46                           |  |  |  |  |  |

Per County Standards, Infiltration Rate calculated as follows:

 $Q = \frac{\Delta H(60r)}{\Delta t(r+2H_{avg})}$ 

Where:

Q = Infiltration Rate (in inches per hour)

 $\Delta H$  = Change in Height (Water Level) over the time interval

r = Test Hole (Borehole) Radius

 $\Delta t = Time Interval$ 

 $H_{avg}$  = Average Head Height over the time interval

### INFILTRATION CALCULATIONS

| Desta de Nierra  |                              |
|------------------|------------------------------|
| Project Name     | Proposed Warehouse           |
| Project Location | Santa Fe Springs, California |
| Project Number   | 21G248-2                     |
| Engineer         | Caleb Brackett               |
|                  |                              |
| Test Hole Redius |                              |

Test Hole Radius Test Depth

Infiltration Test Hole

|                    | Soil Criteria Test |         |                        |                     |                                  |   |                                     |  |  |  |  |  |
|--------------------|--------------------|---------|------------------------|---------------------|----------------------------------|---|-------------------------------------|--|--|--|--|--|
| Interval<br>Number |                    | Time    | Time Interval<br>(min) | Water Depth<br>(ft) | Change in<br>Water Level<br>(in) | Did 12 inches of water<br>seep away in less than<br>30 minutes? | Sandy Soils or Non-<br>Sandy Soils? |  |  |  |  |  |
| 1                  | Initial            | 8:23 AM | 30.00                  | 7.00                | 8.52                             | NO  | NON-SANDY SOILS                     |  |  |  |  |  |
| 1                  | Final              | 8:53 AM | 30.00                  | 7.71                | 0.52                             | NO  | NON-SANDT SOILS                     |  |  |  |  |  |
| 2                  | Initial            | 8:53 AM | 30.00                  | 7.00                | 7.80                             | NO  | NON-SANDY SOILS                     |  |  |  |  |  |
| 2 Final            | Final              | 9:23 AM | 30.00                  | 7.65                | 7.00                             | NU  | NUN-SANDY SUILS                     |  |  |  |  |  |

|                    | Test Data |          |                        |                     |                                  |                             |                                |      |  |  |  |  |
|--------------------|-----------|----------|------------------------|---------------------|----------------------------------|-----------------------------|--------------------------------|------|--|--|--|--|
| Interval<br>Number |           | Time     | Time Interval<br>(min) | Water Depth<br>(ft) | Change in<br>Water Level<br>(ft) | Average Head Height<br>(ft) | Infiltration Rate Q<br>(in/hr) |      |  |  |  |  |
| 1                  | Initial   | 10:20 AM | 30.00                  | 7.00                | 0.90                             | 2.55                        | 1.33                           |      |  |  |  |  |
| I                  | Final     | 10:50 AM | 30.00                  | 7.90                | 0.30                             | 2.00                        | 1.00                           |      |  |  |  |  |
| 2                  | Initial   | 10:50 AM | 30.00                  | 7.00                | 0.89                             | 2.56                        | 1.31                           |      |  |  |  |  |
| 2                  | Final     | 11:20 AM | 00.00                  | 7.89                | 0.00                             | 2.00                        | 1.01                           |      |  |  |  |  |
| 3                  | Initial   | 11:20 AM | 30.00                  | 7.00                | 0.89                             | 2.56                        | 2 56                           | 1.31 |  |  |  |  |
| 5                  | Final     | 11:50 AM | 30.00                  | 7.89                | 0.05                             |                             | 1.01                           |      |  |  |  |  |
| 4                  | Initial   | 11:50 AM | 30.00                  | 7.00                | 0.60                             | 2.70                        | 0.84                           |      |  |  |  |  |
| -                  | Final     | 12:20 PM | 30.00                  | 7.60                | 0.00                             | 2.10                        | 0.04                           |      |  |  |  |  |
| 5                  | Initial   | 12:20 PM | 30.00                  | 7.00                | 0.59                             | 2.71                        | 0.82                           |      |  |  |  |  |
| 5                  | Final     | 12:50 PM | 30.00                  | 7.59                | 0.59                             | 2.71                        | 0.02                           |      |  |  |  |  |
| 6                  | Initial   | 12:50 PM | 30.00                  | 7.00                | 0.59                             | 2.71                        | 0.00                           |      |  |  |  |  |
| 6 Final            | 1:20 PM   | 50.00    | 7.59                   | 0.59                | 2.71                             | 0.82                        |                                |      |  |  |  |  |

Per County Standards, Infiltration Rate calculated as follows:

 $Q = \frac{\Delta H(60r)}{\Delta t(r+2H_{avg})}$ 

Where:

Q = Infiltration Rate (in inches per hour)

 $\Delta H$  = Change in Height (Water Level) over the time interval

r = Test Hole (Borehole) Radius

 $\Delta t = Time Interval$ 

 $H_{avg}$  = Average Head Height over the time interval

