Geotechnical Engineering Investigation

Proposed Industrial Warehouse Development 194 East Rider Street Perris, California

> Chartwell Real Estate Development 151 Innovation Drive Irvine, California 92617

> > Attn: Mr. Henry Pyle

Project Number 20844-18 September 21, 2020

NorCal Engineering

Soils and Geotechnical Consultants 10641 Humbolt Street Los Alamitos, CA 90720 (562) 799-9469 Fax (562) 799-9459

September 21, 2020

Project Number 20844-18

Chartwell Real Estate Development 151 Innovation Drive Irvine, California 92617

Attn: Mr. Henry Pyle

RE: Geotechnical Engineering Investigation - Proposed Industrial Warehouse Development - Located at 194 East Rider Street, in the City of Perris, California

Dear Mr. Pyle:

Pursuant to your request, this firm has performed a Geotechnical Engineering Investigation for the above referenced project. The purpose of this investigation is to evaluate the subsurface conditions of the subject site and to provide recommendations for the proposed industrial warehouse development.

The scope of work included the following: 1) site reconnaissance; 2) subsurface geotechnical exploration and sampling; 3) laboratory testing; 4) engineering analysis of field and laboratory data; 5) preparation of a geotechnical engineering report. It is the opinion of this firm that the proposed development is feasible from a geotechnical standpoint provided that the recommendations presented in this report are followed in the design and construction of the project.

1.0 Project Description

It is proposed to construct an industrial development consisting of 139,462 square feet building as shown on the attached Site Plan. The proposed structure will consist of a concrete tilt-up structure supported by a conventional slab-on-grade foundation system with perimeter-spread footings and isolated interior footings. Other improvements will consist of screen walls, concrete asphaltic pavement, landscaping and hardscape. It is assumed that the proposed grading will include cut and fill to achieve finished grade elevations. Final building plans shall be reviewed by this firm prior to submittal for city/county approval to determine the need for any additional study and revised recommendations pertinent to the proposed development, if necessary.

2.0 Site Description

The 6.29-acre subject property is located at the southwest corner of Redlands Avenue and Rider Street, in the City of Perris. The generally rectangular-shaped parcel is elongated in a north to south direction and with topography of the relatively level parcel descends gradually from south to north on the order of a few feet. The site is currently an undeveloped parcel covered with a low vegetation growth of natural grasses and weeds.

3.0 Site Exploration

The investigation consisted of the placement of seven (7) subsurface exploratory trenches by a backhoe to depths ranging between 5 and 15 feet below current ground elevations. The explorations were visually classified and logged by a field engineer with locations of the subsurface explorations shown on the attached Site Plan. The exploratory trenches revealed the existing earth materials to consist of fill and natural soil. A detailed description of the subsurface conditions is listed on the excavation logs in Appendix A.

Fill: A fill soil and disturbed top soils classifying as a brown, sandy SILT was encountered to a depth of 1 to 1½ feet. These soils were noted to be soft and moist.

Natural: An undisturbed alluvium soil classifying as a brown, sandy to clayey SILT was encountered directly beneath the fill and observed to be firm to stiff and moist.

The overall engineering characteristics of the earth material were relatively uniform with each excavation. No groundwater was encountered to the depth of our trenches and no caving occurred.

4.0 Laboratory Tests

Relatively undisturbed samples of the subsurface soils were obtained to perform laboratory testing and analysis for direct shear, consolidation tests, and to determine in-place moisture/densities. These relatively undisturbed ring samples were obtained by driving a thin-walled steel sampler lined with one-inch long brass rings with an inside diameter of 2.42 inches into the undisturbed soils. Bulk bag samples were obtained in the upper soils for expansion index tests and maximum density tests. All test results are included in Appendix B, unless otherwise noted.

- 4.1 **Field Moisture Content** (ASTM: D 2216) and the dry density of the ring samples were determined in the laboratory. This data is listed on the logs of explorations.
- 4.2 **Maximum Density tests** (ASTM: D 1557) were performed on typical samples of the upper soils. Results of these tests are shown on Table I.
- 4.3 **Expansion Index tests** (ASTM: D 4829) were performed on remolded samples of the upper soils. Results of these tests are provided on Table II.
- 4.4 Atterberg Limits (ASTM: D 4318) consisting of liquid limit, plastic limit and plasticity index were performed on representative soil samples. Results are shown on Table III.
- 4.5 **Corrosion tests** consisting of sulfate, pH, resistivity and chloride analysis to determine potential corrosive effects of soils on concrete and underground utilities. Test results are provided on Table IV.

- 4.6 **R-Value test** per California Test Method 301 was performed on a representative sample, which may be anticipated to be near subgrade to determine pavement design. Results are provided within the pavement design section of the report.
- 4.7 **Direct Shear tests** (ASTM: D 3080) were performed on undisturbed and disturbed samples of the subsurface soils. The test is performed under saturated conditions at loads of 1,000 lbs./sq.ft., 2,000 lbs./sq.ft., and 3,000 lbs./sq.ft. with results shown on Plate A.
- 4.8 **Consolidation tests** (ASTM: D 2435) were performed on undisturbed samples to determine the differential and total settlement which may be anticipated based upon the proposed loads. Water was added to the samples at a surcharge of one KSF and the settlement curves are plotted on Plates B and C.

5.0 Seismicity Evaluation

The proposed development lies outside of any Alquist Priolo Special Studies Zone and the potential for damage due to direct fault rupture is considered unlikely.

The following seismic design parameters are provided and are in accordance with the 2019 California Building Code (CBC) as determined using the ASCE 7 Hazard Tool (https://asce7hazardtool.online/) for the referenced project. Design map report from the website is included in Appendix C.

Seismic Design Parameters

Site Location – Region 1		33.829°
•	Longitude	-117.218°
Site Class		D
Risk Category		II
Maximum Spectral Response Acceleration	Ss	1.500g
	S ₁	0.572g
Adjusted Maximum Acceleration	S_{MS}	1.500g
Design Spectral Response Acceleration Parameters	S_{DS}	1.000g

The San Jacinto Fault zone is located approximately 13 kilometers from the site and is capable of producing a Magnitude 6.9 earthquake and a PGA_M of 0.550g. Ground shaking originating from earthquakes along other active faults in the region is expected to induce lower horizontal accelerations due to smaller anticipated earthquakes and/or greater distances to other faults.

6.0 <u>Liquefaction Evaluation</u>

The site is expected to experience ground shaking and earthquake activity that is typical of Southern California area. It is during severe ground shaking that loose, granular soils below the groundwater table can liquefy. Based upon information in the City of Riverside Public Safety Element "Liquefaction Zones (2006)", the subject site is not situated in an area of generalized liquefaction susceptibility. Our analysis indicates the potential for liquefaction at this site is considered to be very low due to the density of the subsurface soils and groundwater in excess of 50 feet based on review with the State of California Department of Water Resources of nearby water wells. Thus, the design of the proposed construction in conformance with the latest Building Code provisions for earthquake design is expected to provide mitigation of ground shaking hazards that are typical to Southern California.

7.0 Infiltration Characteristics

Infiltration tests within the site were performed to provide preliminary infiltration rates for the purpose of planning and design of an on-site water disposal system. The infiltration tests consisted of the double ring infiltration test per ASTM Method D 3385. Based upon the results of our testing, the soils encountered in the planned on-site drainage disposal system area exhibit the following infiltration rates. The field infiltration rate is listed below for two exploratory trenches at depths of 5 and 10 feet measured from existing ground surface with our calculations given in Appendix D.

Test No.	Depth	Infiltration Rate
T-1	5'	0.3 in/hr
T-2	10'	2.1 in/hr

The correction factors CFt, CFv and CFs are given below based on soils in the upper 5 to 10 feet from our field tests.

- a) $CFt = R_f = 1.0$ for our double ring infiltration test holes.
- b) $CF_v = 1.0$ based on uniform soils encountered in two (2) trenches for infiltration tests.
- c) CFs = 3.0 for long-term siltation, plugging and maintenance. The subsurface soils are likely to have some plugging and regular maintenance of storm water discharge devices is required.

Based on the results of our field testing, the subsurface soils encountered in the proposed onsite drainage disposal system in the upper 5 feet revealed very low water infiltration at the subject site. The design infiltration rate at 10 feet deep is 0.7 inch per hour and the disposal system should be at least 10 feet deep. All systems must meet the latest city and/or county specifications and the California Regional Water Quality Control Board (CRWQCB) requirements.

Foundations shall be set back a minimum distance of 10 feet from the drainage disposal system and the bottom of footing shall be a minimum of 10 feet from the expected zone of saturation. The boundary of the zone of saturation may be assumed to project downward from the top of the permeable portion of the disposal system at an inclination of 1 to 1 or flatter, as determined by the soils engineer.

8.0 Conclusions and Recommendations

Based upon our evaluations, the proposed development is acceptable from a geotechnical engineering standpoint. By following the recommendations and guidelines set forth in our report, the structures will be safe from excessive settlements under the anticipated design loadings and conditions. The proposed development shall meet all requirements of the County Building Ordinance and will not impose any adverse effect on existing adjacent structures.

The following recommendations are based upon geotechnical conditions encountered in our field investigation and laboratory data. Therefore, these surface and subsurface conditions could vary across the site. Variations in the soil conditions may not become evident until the commencement of grading operations and any unusual conditions which may be encountered in the course of the project development may require the need for additional study and revised recommendations.

It is recommended that site inspections be performed by a representative of this firm during all grading and construction of the development to verify the findings and recommendations documented in this report. The following sections present a discussion of geotechnical related requirements for specific design recommendations of different aspects of the project.

8.1 Site Grading Recommendations

Any vegetation and/or demolition debris shall be removed and hauled from proposed grading areas prior to the start of grading operations. Existing vegetation shall not be mixed or disced into the soils. Any removed soils may be reutilized as compacted fill once any deleterious material or oversized materials (in excess of eight inches) is removed. Grading operations shall be performed in accordance with the attached *Specifications for Placement of Compacted Fill*.

8.1.1 Removal and Recompaction Recommendations

All disturbed/fill soils (about 1 to 1½ feet below existing ground surface) shall be removed to competent native material, the exposed surface scarified to a depth of 12 inches, brought to within 2% of optimum moisture content and compacted to a minimum of 90% of the laboratory standard (ASTM: D 1557) prior to placement of any additional compacted fill soils, foundations, slabs-on-grade and pavement. Grading shall extend a minimum of five horizontal feet outside the edges of foundations or equidistant to the depth of fill placed, whichever is greater.

It is possible that isolated areas of undiscovered fill not described in this report are present on site. If found, these areas should be treated as discussed earlier. A diligent search shall also be conducted during grading operations in an effort to uncover any underground structures, irrigation or utility lines. If encountered, these structures and lines shall be either removed or properly abandoned prior to the proposed construction.

Any imported fill material should be preferably soil similar to the upper soils encountered at the subject site. All soils shall be approved by this firm prior to importing at the site and will be subjected to additional laboratory testing to assure concurrence with the recommendations stated in this report.

Care should be taken to provide or maintain adequate lateral support for all adjacent improvements and structures at all times during the grading operations and construction phase. Adequate drainage away from the structures, pavement and slopes should be provided at all times.

If placement of slabs-on-grade and pavement is not completed immediately upon completion of grading operations, additional testing and grading of the areas may be necessary prior to continuation of construction operations. Likewise, if adverse weather conditions occur which may damage the subgrade soils, additional assessment by the soils engineer as to the suitability of the supporting soils may be needed.

8.1.2 Fill Blanket Recommendations

Due to the potential for differential settlement of foundations placed on compacted fill and native materials, it is recommended that all foundations including floor slab areas be underlain by a uniform compacted fill blanket at least two feet in thickness. This fill blanket shall extend a minimum of five horizontal feet outside the edges of foundations or equidistant to the depth of fill placed, whichever is greater.

8.2 Shrinkage and Subsidence

Results of our in-place density tests reveal that the soil shrinkage will be less than 5 to 15% due to excavation and recompaction, based upon the assumption that the fill is compacted to 92% of the maximum dry density per ASTM standards. Subsidence should be 0.2 feet die to earthwork operations. The volume change does not include any allowance for vegetation or organic stripping, removal of subsurface improvements, or topographic approximations.

Although these values are only approximate, they represent our best estimate of lost yardage, which will likely occur during grading. If more accurate shrinkage and subsidence factors are needed, it is recommended that field testing the actual equipment and grading techniques should be conducted.

8.3 Temporary Excavations

Temporary unsurcharged excavations in the existing site materials less than 4 feet high may be made at a vertical gradient unless cohesionless soils are encountered. In areas where soils with little or no binder are encountered, where adverse geological conditions are exposed, or where excavations are adjacent to existing structures, shoring or flatter excavations may be required. The temporary cut slope gradients given above do not preclude local raveling and sloughing.

All excavations shall be made in accordance with the requirements of the soils engineer, CAL-OSHA and other public agencies having jurisdiction. Care should be taken to provide or maintain adequate lateral support for all adjacent improvements and structures at all times during the grading operations and construction phase.

8.4 Foundation Design

All foundations may be designed utilizing the following safe bearing capacities for an embedded depth of 18 inches into approved engineered fill with the corresponding widths:

	Allowable Bearing Capacity (psf)
Width (feet)	Continuous Foundation	Isolated Foundation
1.5	2000	2500
2.0	2075	2575
4.0	2375	2875
6.0	2500	3000

The bearing value may be increased by 500 psf for each additional foot of depth in excess of the 18-inch minimum depth, up to a maximum of 4,000 psf. A one-third increase may be used when considering short-term loading and seismic forces. Any foundations located along property lines or where lateral overexcavation is not possible shall utilize a safe bearing capacity of 1,500 psf. All foundations shall be reinforced a minimum of one, No. 4 bar, top and bottom. A representative of this firm shall inspect all foundation excavations prior to pouring concrete.

8.5 Settlement Analysis

Resultant pressure curves for the consolidation tests are shown on Plates B and C. Computations utilizing these curves and the recommended allowable soil bearing capacities reveal that the foundations will experience settlements on the order of $\frac{3}{4}$ inch and differential settlements of less than $\frac{1}{4}$ inch.

8.6 Lateral Resistance

The following values may be utilized in resisting lateral loads imposed on the structure. Requirements of the California Building Code should be adhered to when the coefficient of friction and passive pressures are combined.

Coefficient of Friction - 0.40

Equivalent Passive Fluid Pressure = 250 lbs./cu.ft.

Maximum Passive Pressure = 2,500 lbs./cu.ft.

The passive pressure recommendations are valid only for approved compacted fill soils.

8.7 Retaining Wall Design Parameters

Active earth pressures against retaining walls will be equal to the pressures developed by the following fluid densities. These values are for **granular backfill material** placed behind the walls at various ground slopes above the walls.

Surface Slope of Retained Materials (Horizontal to Vertical	Equivalent Fluid Density (lb./cu.ft.)
Level	30
5 to 1	35
4 to 1	38
3 to 1	40
2 to 1	45

Any applicable short-term construction surcharges and seismic forces should be added to the above lateral pressure values.

The seismic-induced lateral soil pressure for walls greater than 6 feet shall be computed using a triangular pressure distribution with the maximum value at the top of the wall. The maximum lateral pressure of (20 pcf) H where H is the height of the retained soils above the wall footing should be used in final design of retaining walls. Sliding resistance values and passive fluid pressure values and passive fluid pressures given in our referenced report may be increased by 1/3 during short-term wind and seismic loading conditions.

All walls shall be waterproofed as needed and protected from hydrostatic pressure by a reliable permanent subdrain system. The subsurface drainage system shall consist of 4-inch diameter perforated PVC pipe encased with gravel and wrapped with filter fabric. The granular backfill to be utilized immediately adjacent to the wall shall consist of an approved granular soil with a sand equivalency greater than 30. This backfill zone of free draining material shall consist of a wedge beginning a minimum of one horizontal foot from the base of the wall extending upward at an inclination of no less than 3/4 to 1 (horizontal to vertical).

8.8 Slab Design

All concrete slabs-on-grade shall be at least six inches in thickness for warehouse, four inches for office and hardscape, both reinforced a minimum of No. 3 bars, sixteen-inch spacing in each direction and positioned in the center of slab and placed on approved subgrade soils. These slabs shall be placed on approved subgrade soils moisture conditioned to optimum moisture content to a depth of one foot.

A vapor retarder (10-mil minimum thickness) should be utilized in areas which would be sensitive to the infiltration of moisture. This retarder shall meet requirements of ASTM E 96, Water Vapor Transmission of Materials and ASTM E 1745, Standard Specification for Water Vapor Retarders used in Contact with Soil or Granular Fill Under Concrete Slabs. The vapor retarder shall be installed in accordance with procedures stated in ASTM E 1643, Standard practice for Installation of Water Vapor Retarders used in Contact with Earth or Granular Fill Under Concrete Slabs. The vapor retarder shall be installed in accordance with procedures stated in ASTM E 1643, Standard practice for Installation of Water Vapor Retarders used in Contact with Earth or Granular Fill Under Concrete Slabs.

The moisture retarder may be placed directly upon approved subgrade soils, although one to two inches of sand beneath the membrane is desirable. The subgrade upon which the retarder is placed shall be smooth and free of rocks, gravel or other protrusions which may damage the retarder. Use of sand above the retarder is under the purview of the structural engineer; if sand is used over the retarder, it should be placed in a dry condition.

8.9 Pavement Section Design

The table below provides a preliminary pavement design based upon an R-Value of 33 for the proposed pavement areas. Final pavement design may need to be based on R-Value testing of the subgrade soils near the conclusion of rough grading to assure that these soils are consistent with those assumed in this preliminary design.

Type of Traffic	Traffic Index	Asphalt (in.)	Base Material (in.)
Automobile Parking Stalls	4.0	3.0	4.0
Light Vehicle Circulation Areas	5.5	3.5	5.5
Heavy Truck Access Areas	7.0	4.0	10.0
(GVW <90,000 lbs; 5-axle)			

All concrete slabs to be utilized for pavement for heavy trucks shall be a minimum of seven inches in thickness and placed on approved subgrade soils. The recommendations are based upon estimated traffic loads. Client should submit anticipated traffic loadings, when available, so that pavement sections may be reviewed to determine adequacy to support these loads.

Any approved base material shall consist of a Class II aggregate or equivalent and should be compacted to a minimum of 95% relative compaction. All pavement materials shall conform to the requirements set forth by the City of Perris. The base material; and asphaltic concrete should be tested prior to delivery to the site and during placement to determine conformance with the project specifications. A pavement engineer shall designate the specific asphalt mix design to meet the required project specifications.

All pavement areas shall have positive drainage toward an approved outlet from the site. Drain lines behind curbs and/or adjacent to landscape areas should be considered by client and the appropriate design engineers to prevent water from infiltrating beneath pavement. If such infiltration occurs, damage to pavement, curbs and flow lines, especially on sites with expansive soils, may occur during the life of the project.

8.10 Utility Trench and Excavation Backfill

Trenches from installation of utility lines and other excavations may be backfilled with on-site soils or approved imported soils compacted to a minimum of 90% relative compaction. All utility lines shall be properly bedded with clean sand having a sand equivalency 30 (SE > 30) or more. This bedding material shall be thoroughly water jetted around the pipe structure prior to placement of compacted backfill soils.

8.11 Corrosion Design Criteria

Representative samples of the surficial soils, typical of the subgrade soils expected to be encountered within foundation excavations and underground utilities were tested for corrosion potential. The minimum resistivity value obtained for the samples tested is representative of an environment that may be corrosive to metals. The soil pH value was considered mildly alkaline and may have a significant effect on soil corrosivity. Consideration should be given to corrosion protection systems for buried metal such as protective coatings, wrappings or the use of PVC where permitted by local building codes.

According to Table 4.3.1 of ACI 318 Building Code and Commentary, these contents revealed negligible sulfate concentrations. Therefore, a Type II cement according to latest CBC specifications may be utilized for building foundations at this time. Additional sulfate tests be performed at the completion of site grading to assure that the as graded conditions are consistent with the recommendations stated in this design. Corrosion test results may be found on the attached Table III.

8.12 Expansive Soil

If expansive soils are encountered (EI >20), special attention should be given to the project design and maintenance. The attached *Expansive Soil Guidelines* should be reviewed by the engineers, architects, owner, maintenance personnel and other interested parties and considered during the design of the project and future property maintenance.

9.0 Closure

The recommendations and conclusions contained in this report are based upon the soil conditions uncovered in our test excavations. No warranty of the soil condition between our excavations is implied. NorCal Engineering should be notified for possible further recommendations if unexpected to unfavorable conditions are encountered during construction phase. It is the responsibility of the owner to ensure that all information within this report is submitted to the Architect and appropriate Engineers for the project.

This firm should have the opportunity to review the final plans to verify that all our recommendations are incorporated. This report and all conclusions are subject to the review of the controlling authorities for the project.

A preconstruction conference should be held between the developer, general contractor, grading contractor, city inspector, architect, and geotechnical engineer to clarify any questions relating to the grading operations and subsequent construction. Our representative should be present during the grading operations and construction phase to certify that such recommendations are complied within the field.

This geotechnical investigation has been conducted in a manner consistent with the level of care and skill exercised by members of our profession currently practicing under similar conditions in the Southern California area. No other warranty, expressed or implied is made.

We appreciate this opportunity to be of service to you. If you have any further questions, please do not hesitate to contact the undersigned.

No. 841

Respectfully submitted, NORCAL ENGINEERING

Kellin I

Keith D. Tucker Project Engineer R.G.E. 841 Scott D. Spensiero Project Manager

SPECIFICATIONS FOR PLACEMENT OF COMPACTED FILL

Excavation

Any existing low-density soils and/or saturated soils shall be removed to competent natural soil under the inspection of the Geotechnical Engineering Firm. After the exposed surface has been cleansed of debris and/or vegetation, it shall be scarified until it is uniform in consistency, brought to the proper moisture content and compacted to a minimum of 90% relative compaction (in accordance with ASTM: D 1557).

In any area where a transition between fill and native soil or between bedrock and soil are encountered, additional excavation beneath foundations and slabs will be necessary in order to provide uniform support and avoid differential settlement of the structure.

Material for Fill

The on-site soils or approved import soils may be utilized for the compacted fill provided they are free of any deleterious materials and shall not contain any rocks, brick, asphaltic concrete, concrete or other hard materials greater than eight inches in maximum dimensions. Any import soil must be approved by the Geotechnical Engineering firm a minimum of 72 hours prior to importation of site.

Placement of Compacted Fill Soils

The approved fill soils shall be placed in layers not excess of six inches in thickness. Each lift shall be uniform in thickness and thoroughly blended. The fill soils shall be brought to within 2% of the optimum moisture content, unless otherwise specified by the Soils Engineering firm. Each lift shall be compacted to a minimum of 90% relative compaction (in accordance with ASTM: D 1557) and approved prior to the placement of the next layer of soil. Compaction tests shall be obtained at the discretion of the Geotechnical Engineering firm but to a minimum of one test for every 500 cubic yards placed and/or for every 2 feet of compacted fill placed.

The minimum relative compaction shall be obtained in accordance with accepted methods in the construction industry. The final grade of the structural areas shall be in a dense and smooth condition prior to placement of slabs-on-grade or pavement areas. No fill soils shall be placed, spread or compacted during unfavorable weather conditions. When the grading is interrupted by heavy rains, compaction operations shall not be resumed until approved by the Geotechnical Engineering firm.

Grading Observations

The controlling governmental agencies should be notified prior to commencement of any grading operations. This firm recommends that the grading operations be conducted under the observation of a Soils Engineering firm as deemed necessary. A 24-hour notice must be provided to this firm prior to the time of our initial inspection.

Observation shall include the clearing and grubbing operations to assure that all unsuitable materials have been properly removed; approve the exposed subgrade in areas to receive fill and in areas where excavation has resulted in the desired finished grade and designate areas of overexcavation; and perform field compaction tests to determine relative compaction achieved during fill placement. In addition, all foundation excavations shall be observed by the Geotechnical Engineering firm to confirm that appropriate bearing materials are present at the design grades and recommend any modifications to construct footings.

EXPANSIVE SOIL GUIDELINES

The following expansive soil guidelines are provided for your project. The intent of these guidelines is to inform you, the client, of the importance of proper design and maintenance of projects supported on expansive soils. You, as the owner or other interested party, should be warned that you have a duty to provide the information contained in the soil report including these guidelines to your design engineers, architects, landscapers and other design parties in order to enable them to provide a design that takes into consideration expansive soils.

In addition, you should provide the soil report with these guidelines to any property manager, lessee, property purchaser or other interested party that will have or assume the responsibility of maintaining the development in the future.

Expansive soils are fine-grained silts and clays which are subject to swelling and contracting. The amount of this swelling and contracting is subject to the amount of fine-grained clay materials present in the soils and the amount of moisture either introduced or extracted from the soils. Expansive soils are divided into five categories ranging from "very low" to "very high". Expansion indices are assigned to each classification and are included in the laboratory testing section of this report. If the expansion index of the soils on your site, as stated in this report, is 21 or higher, you have expansive soils. The classifications of expansive soils are as follows:

Classification of Expansive Soil*

Expansion Index	Potential Expansion
0-20	Very Low
21-50	Low
51-90	Medium
91-130	High
Above 130	Very High

*From Table 18A-I-B of California Building Code (1988)

When expansive soils are compacted during site grading operations, care is taken to place the materials at or slightly above optimum moisture levels and perform proper compaction operations. Any subsequent excessive wetting and/or drying of expansive soils will cause the soil materials to expand and/or contract. These actions are likely to cause distress of foundations, structures, slabs-on-grade, sidewalks and pavement over the life of the structure. It is therefore imperative that even after construction of improvements, the moisture contents are maintained at relatively constant levels, allowing neither excessive wetting or drying of soils.


Evidence of excessive wetting of expansive soils may be seen in concrete slabs, both interior and exterior. Slabs may lift at construction joints producing a trip hazard or may crack from the pressure of soil expansion. Wet clays in foundation areas may result in lifting of the structure causing difficulty in the opening and closing of doors and windows, as well as cracking in exterior and interior wall surfaces. In extreme wetting of soils to depth, settlement of the structure may eventually result. Excessive wetting of soils in landscape areas adjacent to concrete or asphaltic pavement areas may also result in expansion of soils beneath pavement and resultant distress to the pavement surface.

Excessive drying of expansive soils is initially evidenced by cracking in the surface of the soils due to contraction. Settlement of structures and on-grade slabs may also eventually result along with problems in the operation of doors and windows.

Projects located in areas of expansive clay soils will be subject to more movement and "hairline" cracking of walls and slabs than similar projects situated on non-expansive sandy soils. There are, however, measures that developers and property owners may take to reduce the amount of movement over the life the development. The following guidelines are provided to assist you in both design and maintenance of projects on expansive soils:

- Drainage away from structures and pavement is essential to prevent excessive wetting of expansive soils. Grades should be designed to the latest building code and maintained to allow flow of irrigation and rain water to approved drainage devices or to the street. Any "ponding" of water adjacent to buildings, slabs and pavement after rains is evidence of poor drainage; the installation of drainage devices or regrading of the area may be required to assure proper drainage. Installation of rain gutters is also recommended to control the introduction of moisture next to buildings. Gutters should discharge into a drainage device or onto pavement which drains to roadways.
- Irrigation should be strictly controlled around building foundations, slabs and
 pavement and may need to be adjusted depending upon season. This control is
 essential to maintain a relatively uniform moisture content in the expansive soils and
 to prevent swelling and contracting. Over-watering adjacent to improvements may
 result in damage to those improvements. NorCal Engineering makes no specific
 recommendations regarding landscape irrigation schedules.
- Planting schemes for landscaping around structures and pavement should be analyzed carefully. Plants (including sod) requiring high amounts of water may result in excessive wetting of soils. Trees and large shrubs may actually extract moisture from the expansive soils, thus causing contraction of the fine-grained soils.
- Thickened edges on exterior slabs will assist in keeping excessive moisture from entering directly beneath the concrete. A six-inch thick or greater deepened edge on slabs may be considered. Underlying interior and exterior slabs with 6 to 12 inches or more of non-expansive soils and providing presaturation of the underlying clayey soils as recommended in the soil report will improve the overall performance of ongrade slabs.

- Increase the amount of steel reinforcing in concrete slabs, foundations and other structures to resist the forces of expansive soils. The precise amount of reinforcing should be determined by the appropriate design engineers and/or architects.
- Recommendations of the soil report should always be followed in the development of the project. Any recommendations regarding presaturation of the upper subgrade soils in slab areas should be performed in the field and verified by the Soil Engineer.



NorCal Engineering soils and geotechnical consultants

PROJECT

List of Appendices (in order of appearance)

Appendix A - Log of Excavations

Log of Trenches T-1 to T-7

Appendix B - Laboratory Tests

Table I – Maximum Dry Density
Table II – Expansion Index
Table III – Atterberg Limits
Table IV - Corrosion
Plate A – Direct Shear
Plates B and C - Consolidation

Appendix C -ASCE Seismic Hazards Report and Maps

Appendix D - Soil Infiltration Data

Appendix A

MA	JOR DIVISION	·	GRAPHIC SYMBOL	LETTER SYMBOI	TYPICAL DESCRIPTIONS
	GRAVEL	CLEAN GRAVELS	000	GW	WELL-GRADED GRAVELS, GRAVEL, SAND MIXTURES, LITTLE OR NO FINES
COARSE	AND GRAVELLY SOILS	(LITTLE OR NO FINES)	***	GP	POORLY-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES
GRAINED SOILS	MORE THAN 50% OF COARSE	GRAVELS WITH FINES		GM	SILTY GRAVELS, GRAVEL-SAND- SILT MIXTURES
	FRACTION RETAINED ON NO. 4 SIEVE	(APPRECIABLE AMOUNT OF FINES)		GC	CLAYEY GRAVELS, GRAVEL-SAND- CLAY MIXTURES
	SAND	CLEAN SAND		sw	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
MORE THAN	AND SANDY SOILS	(LITTLE OR NO FINES)		SP	POORLY-GRADED SANDS, GRAVEL- LY SANDS, LITTLE OR NO FINES
MATERIAL IS <u>LARGER</u> THAN NO. 200 SIEVE	MORE THAN 50% OF COARSE	SANDS WITH		SM	SILTY SANDS, SAND-SILT MIXTURES
SIZE	FRACTION PASSING ON NO. 4 SIEVE	(APPRECIABLE AMOUNT OF FINES)		sc	CLAYEY SANDS, SAND-CLAY MIXTURES
				ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
FINE GRAINED	SILTS AND	LIQUID LIMIT		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
SOILS	CLAYS			OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
MODE THANK				МН	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS
MORE THAN 50% OF MATERIAL IS <u>SMALLER</u> THAN NO.	SILTS AND	LIQUID LIMIT GREATER THAN		СН	INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS
200 SIEVE SIZE	CLAYS 50		он	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS	
ŀ	I IGHLY ORGANIC	SOILS		РТ	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS

NOTE: DUAL SYMBOLS ARE USED TO INDICATE BORDERLINE SOIL CLASSIFICATIONS

UNIFIED SOIL CLASSIFICATION SYSTEM

KEY:

- Indicates 2.5-inch Inside Diameter. Ring Sample.
- Indicates 2-inch OD Split Spoon Sample (SPT).
- ☐ Indicates No Recovery.
- Indicates SPT with 140# Hammer 30 in. Drop.
- ☑ Indicates Bulk Sample.
- Indicates Small Bag Sample.
- Indicates Non-Standard
- Indicates Core Run.

COMPONENT PROPORTIONS

DESCRIPTIVE TERMS	RANGE OF PROPORTION
Trace Few Little Some And	1 - 5% 5 - 10% 10 - 20% 20 - 35% 35 - 50%

COMPONENT DEFINITIONS

COMPONENT	SIZE RANGE
Boulders Cobbles Gravel Coarse gravel Fine gravel Sand Coarse sand Medium sand Fine sand Silt and Clay	Larger than 12 in 3 in to 12 in 3 in to No 4 (4.5mm) 3 in to 3/4 in 3/4 in to No 4 (4.5mm) No. 4 (4.5mm) to No. 200 (0.074mm) No. 4 (4.5mm) to No. 10 (2.0 mm) No. 10 (2.0 mm) to No. 40 (0.42 mm) No. 40 (0.42 mm) to No. 200 (0.074 mm) Smaller than No. 200 (0.074 mm)

MOISTURE CONTENT

DRY	Absence of moisture, dusty, dry to the louch.
DAMP	Some perceptible moisture; below optimum
MOIST	No visible water; near optimum moisture content
WET	Visible free water, usually soil is below water table.

RELATIVE DENSITY OR CONSISTENCY VERSUS SPT N -VALUE

COHESIONLESS SOILS		COHESIVE SOILS			
Density	N (blows/ft)	Consistency	N (blows/ft)	Approximate Undrained Shear Strength (psf)	
Very Loose Loose Medium Dense Dense Very Dense	0 to 4 4 to 10 10 to 30 30 to 50 over 50	Very Soft Soft Medium Sliff Sliff Very Stiff Hard	0 to 2 2 to 4 4 to 8 8 to 15 15 to 30 over 30	< 250 250 - 500 500 - 1000 1000 - 2000 2000 - 4000 > 4000	

	Chartwell Real Estate Deve 20844-18	lopment	Lo	g of Tre	nch T	-1		
Boring Lo	ocation: 194 E Rider, Perris							
	rilling: 1/7/19	Groundwater Depth:	None Encountered					
	lethod: Backhoe							
Hammer	Weight:	Drop:						
Surface E	Elevation: Not Measured			1 6	nples	10	hornt	nn,
	th- Material Description					E La	oorato	ار د م
(feet) old	pgy Material Description			Type	Blow	Moisture	Dry Density	Fines Content %
-0 	FILL Sandy SILT Brown, soft, moist NATURAL Sandy SILT Brown, firm to stiff, moist Trench completed at depth of	5'					1	
_ 35	NorCal Engi	neering				1		

Chartwell Real Estate 20844-18	Development	Log	f Tre	nch T	-2		
Boring Location: 194 E Rider, Perris							
Date of Drilling: 1/7/19	Groundwater Depth	: None Encountered					
Drilling Method: Backhoe							
Hammer Weight:	Drop:						
Surface Elevation: Not Measured			San	ples	Lat	oorato)F)/
Depth (feet) Lith- ology Material Description					5		ν ×
FILL Sandy SILT Brown, soft, moist NATURAL Sandy SILT Brown, firm to stiff, moist Trench completed at complete at complete state of the	st		Туре	Blow	Moisture	Density Density	Fines Countaint 9,
NorCal E	ngineering				2	<u> </u>	

Depth Clayery SILT Brown, firm to stiff, wery moist		-3	nch T	f Trer	og o	Chartwell Real Estate Development Lo 20844-18						
Drilling Method: Backhoe Hammer Weight: Surface Elevation: Not Measured Depth Lith- (feet) clogy Fill. Sandy Sil.T Brown, soft, moist NATURAL Sandy Sil.T Brown, firm to stiff, wery moist Clayey Sil.T Grey-brown, stiff, very moist Trench completed at depth of 15' 17.33								Perris	94 E Rider,	on: 1	g Locatio	Borin
Hammer Weight: Samples Lab						ne Encountered	Groundwater Depth: No		7/19	g: 1/7	of Drillin	Date
Surface Elevation: Not Measured Depth (feet) Lith (fe									ackhoe	d: Ba	ng Metho	Drillin
Depth (feet) Lith-							Drop:			ht:	ner Weig	Hamr
Depth Cheek Chee	oratory	Lat	nles	Samr				ıred	Not Measu	tion:		Surfa
FILL Sandy SILT Brown, soft, moist NATURAL Sandy SILT Brown, firm to stiff, moist Clayey SiLT Grey-brown, stiff, very moist Trench completed at depth of 15' 17.3	Density Fines Content %	oisture						Description	Material D			
	114.0 107.7	9.8					f 15'	SILT SILT Tirm, moist	Sandy SI Brown, se NATURA Sandy SI Brown, fin Clayey S Grey-brown Sandy SI Brown, fin	GWT not encountered		10
NorCal Engineering 3		3					neering	Cal Engi	NorC	·		_ —35

	Chartwell Real Estate Development Lo			Lo	og of Tre	nch T	-4		
Borin	ng Locati	on: 194 E Rider, Perris							
Date	of Drillin	g: 1/7/19	Groundwater Depth: No	one Encountered					
Drilli	ng Metho	od: Backhoe							
Hami	mer Weig	ght:	Drop:						
		tion: Not Measured			Sam	ples	Lal	orato	rv
Depth (feet)		Material Description					5		s #
(1004)	0.097				Type	Blow	Moisture	Dry Density	Fines Content %
		FILL Sandy SILT Brown, soft, moist NATURAL Sandy SILT Brown, firm to stiff, moist Trench completed at depth of	F10'				12.4	108.4	
Section (NorCal Engi	neering				4		

Chartwell Real Estate Development Log of Ti			of Tre	nch T	-5				
Borin	ng Locati	on: 194 E Rider, Perris							
Date	of Drillin	ıg: 1/7/19	Groundwater Depth: No	ne Encountered					
Drilli	ing Metho	od: Backhoe							
Ham	mer Weig	ght:	Drop:						
Surfa	ace Eleva	ation: Not Measured			Sam	ples	lal	orato	nrv
Depth (feet)	Lith- ology	Material Description			Type	Blow	Moisture	Dry Density	Fines Content %
Superlog Civil tech Software, USA www.civilitech.com Tile: Crosuperlogan rockers are a superlogan rockers are a superlogan rockers. The crosuperlogan rockers are a superlogan rockers are a superlogan rockers. The crosuperlogan rockers are a superlogan rockers are a superlogan rockers. The crosuperlogan rockers are a superlogan rockers are a superlogan rockers. The crosuperlogan rockers are a superlogan rockers are a superlogan rockers. The crosuperlogan rockers are a superlogan rockers are a superlogan rockers. The crosuperlogan rockers are a superlogan rockers are a superlogan rockers are a superlogan rockers. The crosuperlogan rockers are a superlogan rockers are a superlogan rockers are a superlogan rockers are a superlogan rockers. The crosuperlogan rockers are a superlogan rockers ar		FILL Sandy SILT Brown, soft, moist NATURAL Sandy SILT Brown, firm, moist Trench completed at depth o	f 5'			ш ŏ	Mo	ď	- 63
- 35		NorCal Engi	ineering				5	1	

Chartwell Real Estate Dev 20844-18	velopment	Log	g of Tre	nch T	-6		
Boring Location: 194 E Rider, Perris					_		
Date of Drilling: 1/7/19	Groundwater Depth: No	one Encountered					
Drilling Method: Backhoe							
Hammer Weight:	Drop:						
Surface Elevation: Not Measured			Sam	ples	l al	orato)FV
Depth (feet) Ology Material Description							ν μ
(leat) ology			Type	Blow	Moisture	Dry Density	Fines Content %
FILL Sandy SILT Brown, soft, moist NATURAL Sandy SILT Brown, firm to stiff, moist Trench completed at depth Trench completed at depth 20 25 20 25 30	of 10'				6.5	105.5 112.3 111.2	
NorCal Eng	gineering				6		

	Chartwell Real Estate Development Lo 20844-18			g of Tre	nch T	-7			
Borir	ng Locati	on: 194 E Rider, Perris		1					
	of Drillin		Groundwater Depth:	None Encountered					
Drilli	ng Metho	d: Backhoe							
Hami	mer Weig	ht:	Drop:						
Surfa		tion: Not Measured			Sam	ples	l al	borato	rv
Depth (feet)		Material Description			Type	Blow	Moisture	Dry Density	Fines Content %
0 		FILL Sandy SILT Brown, soft, moist NATURAL Sandy SILT Brown, firm, moist			-	0		105.5	Ö
_ _ 10 _		Clayey SILT Brown, stiff, moist					10.6	106.1	
_ _ _ _ 15 _ _		Sandy SILT Brown, stiff, moist Trench completed at depth o	f 15!				7.9	100.4	
20									
-25 - -									
- - 30 - - -									
— 35		NorCal Engi	neering				7	,	

Appendix B

TABLE I MAXIMUM DENSITY TESTS

Sample	Classification	Optimum Moisture (%)	Maximum Dry Density (Ibs/cu.ft)
T-3 @ 2'	Sandy SILT	11.5	127.0

TABLE II EXPANSION TESTS

Sample	Classification	Expansion Index
T-3 @ 2'	Sandy SILT	10

TABLE III ATTERBERG LIMITS

Sample	Liquid Limit	Plastic Limit	Plasticity Index
T-3 @ 5'	23	19	4
T-3 @ 10'	33	20	13

TABLE IV CORROSION TESTS

Sample	рН	Electrical Resistivity	Sulfate (%)	Chloride (ppm)
T-3 @ 2'	7.2	2,446	0.003	189

% by weight ppm – mg/kg

T3@2' Sample No. Undisturbed-Saturated Sample Type: Sandy Silt Soil Description: 2 1 3 (psf) 1000 2000 3000 Normal Stress 2028 Peak Stress 780 1344 (psf) 0.125 0.075 0.200 Displacement (in.) 1320 1800 648 Residual Stress (psf) Displacement (in.) 0.250 0.250 0.250 Initial Dry Density 114.0 114.0 114.0 (pcf)

(%)

(in /min)

12.3

0.020

12,3

0.020


12,3


0.020

Initial Water Content

PROJECT NUMBER:

Strain Rate







DATE: 1/15/2019

NorCal Engineering SOILS AND GEOTECHNICAL CONSULTANTS

20844-18

DIRECT SHEAR TEST
ASTM D3080
Plate A





Appendix C



Address:

No Address at This Location

ASCE 7 Hazards Report

Standard: ASCE/SEI 7-16 **Elevation:** 1444.88 ft (NAVD 88)

33.829 Latitude: Risk Category: ||

Longitude: -117.218 D - Stiff Soil Soil Class:







Seismic

Site Soil Class:	D - Stiff Soil

Results:

S _s :	1.5	S _{D1} :	N/A
S ₁ :	0.572	T _L :	8
Fa:	1	PGA :	0.5
F _v :	N/A	PGA _M :	0.55
S _{MS} :	1.5	F _{PGA} :	1.1
S _{M1} :	N/A	l _e :	1
S _{DS} :	1	C _v :	1.4

Ground motion hazard analysis may be required. See ASCE/SEI 7-16 Section 11.4.8.

Data Accessed: Mon Sep 21 2020

Date Source: USGS Seismic Design Maps



The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

https://asce7hazardtool.online/ Page 3 of 3 Mon Sep 21 2020

Appendix D



SOILS AND GEOTECHNICAL CONSULTANTS

Project: Chartwell Real Estate Development	
Project No.: 20844-18	
Date: 1/7/19	
Test No. 1	
Depth: 5'	
Tested By: D.R.	

	TIME (hr/min)	CHANGE TIME (min)	CUMULATIVE TIME (min)	INNER RING READING (cm)	INNER RING CHANGE	INNER RING FLOW (cc)	OUTER RING READING (cm)	OUTER RING CHANGE (cm)	OUTER RING FLOW (cc)	INNER RING INF RATE (cm/hr)	OUTER RING INF RATE (cm/hr)	INNER RING INF RATE (ft/hr)
1	7:40			106.6			47.6					
	8:00	20	20	106.8	0.2		47.9	0.3				
2	8:00			106.8			47.9					
	8:20	20	40	107.0	0.2		48.2	0.3				
3	8:20			107.0			48.2					
	8:40	20	60	107.2	0.2		48.5	0.3				
4	8:40			107.2			48.5					
	9:00	20	80	107.4	0.2		48.7	0.2				
5	9:00			107.4			48.7					
	9:20	20	100	107.6	0.2		49.0	0.3				
6	9:20			107.6			49.0					
	9:40	20	120	107.6	0.2		49.3	0.3		0.6	0.9	
7	9:40			107.6			49.3					
	9:60	20	140	108.0	0.4		49.5	0.2		1.2	0.6	
8	9:60			108.0			49.5					
	10:00	20	160	108.2	0.2		49.7	0.2		0.6	0.6	
9	10:00			101.1			43.3					
	10:20	20	180	101.4	0.3		43.7	0.4		0.9	1.2	
10	10:20			101.4			43.7					
	10:40	20	200	101.7	0.3		44.3	0.5		0.9	1.5	
11	10:40			101.7			44.3					
	11:00	20	220	101.8	0.1		44.3	0.0		0.3	0.0	
12	11:00			101.8			44.3					
	11:20	20	240	102.0	0.2		44.6	0.3		0.6	0.9	
								Ä	verage =	0.7	/ 0.8 cm	/hr



SOILS AND GEOTECHNICAL CONSULTANTS

Project: Chartwell Real Estate Development	
Project No.: 20844-18	
Date: 1/7/19	
Test No. 2	
Depth: 10'	
Tested By: D.R.	

	TIME (hr/min)	CHANGE TIME (min)	CUMULATIVE TIME (min)	INNER RING READING (cm)	INNER RING CHANGE	INNER RING FLOW (cc)	OUTER - RING READING (cm)	OUTER RING CHANGE (cm)	OUTER RING FLOW (cc)	INNER RING INF RATE (cm/hr)	OUTER RING INF RATE (cm/hr)	INNER RING INF RATE (ft/hr)
1	9:22			71.7			39.7					
	9:42	20	20	73.7	2.0		42.1	2.4				
2	9:42			73.7			42.1					
	10:02	20	40	75.5	1.8		44.0	1.9				
3	10:02			75.5			44.0					
	10:22	20	60	77.2	1.7		45.9	1.9				
4	10:22			77.2			45.9					
	10:42	20	80	78.6	1.4		47.0	1.1				
5	10:42			72.1			41.5					
	11:02	20	100	74.2	2.1		42.6	1.1				
6	11:02			74.2			42.6					
	11:22	20	120	76.0	1.8		43.8	1.2				
7	11:22			76.0			43.8					
	11:42	20	140	77.7	1.7		44.9	1.1		5.1	3.3	
8	11:42			77.7			44.9					
	12:02	20	160	79.1	1.4		45.9	1.0		4.2	3.0	
9	12:02			79.1			45.9					
	12:22	20	180	80.7	1.6		47.0	1.1		4.8	3.3	
10	12:22			73.0			42.1					
	12:42	20	200	75.1	2.1		43.1	1.0		6.3	3.0	
11	12:42			75.1			43.1					
	1:02	20	220	77.0	1.9		44.1	1.0		5.7	3.0	
12	1:02			77.0			44.1					
	1:22	20	240	78.6	1.6		4 5.0	0.9		4.8	2.7	
								Δ	verage =	5.2	/ 3.1 cm	/hr