




Appendix H2

Airport Land Use Commission (ALUC) Development Review



RIVERSIDE COUNTY AIRPORT LAND USE COMMISSION

June 10, 2021

Ms. Deborah Bradford, Project Planner
Riverside County Planning Division
4080 Lemon Street, 12th Floor
Riverside CA 92501

CHAIR

Steven Stewart
Palm Springs

VICE CHAIR

Steve Manos
Lake Elsinore

COMMISSIONERS

Arthur Butler
Riverside

John Lyon
Riverside

Russell Betts
Desert Hot Springs

Richard Stewart
Moreno Valley

Gary Youmans
Temecula

STAFF

Director
Paul Rull

Simon A. Housman
Daniel Zerda
Barbara Santos

County Administrative Center
4080 Lemon St., 14th Floor.
Riverside, CA 92501
(951) 955-5132

www.rcaluc.org

RE: AIRPORT LAND USE COMMISSION (ALUC) DEVELOPMENT REVIEW

File No.: ZAP1466MA21
Related File Nos.: PPT210021 (Plot Plan)
Compatibility Zones: Zone C2
APNs: 305-090-049, 317-270-013

Dear Ms. Bradford:

On June 10, 2021, the Riverside County Airport Land Use Commission (ALUC) found County of Riverside Case No. PPT210021 (Plot Plan), a proposal to construct a truck trailer storage and maintenance facility including a 16,200 square foot maintenance building with mezzanine on 7.36 acres located northerly of Orange Avenue, easterly of Tobacco Road, southerly of Water Street, and westerly of Harvill avenue, **CONSISTENT** with the 2014 March Air Reserve Base/Inland Port Airport Land Use Compatibility Plan, subject to the following conditions:

CONDITIONS:

1. Any new outdoor lighting that is installed shall be hooded or shielded so as to prevent either the spillage of lumens or reflection into the sky. Outdoor lighting shall be downward facing.
2. The following uses/activities are not included in the proposed project and shall be prohibited at this site:
 - (a) Any use or activity which would direct a steady light or flashing light of red, white, green, or amber colors associated with airport operations toward an aircraft engaged in an initial straight climb following takeoff or toward an aircraft engaged in a straight final approach toward a landing at an airport, other than an FAA-approved navigational signal light or visual approach slope indicator.
 - (b) Any use or activity which would cause sunlight to be reflected towards an aircraft engaged in an initial straight climb following takeoff or towards an aircraft engaged in a straight final approach towards a landing at an airport.
 - (c) Any use or activity which would generate smoke or water vapor or which would attract large concentrations of birds, or which may otherwise affect safe air navigation within the area. (Such uses include landscaping utilizing water features, aquaculture, production of cereal grains, sunflower, and row crops, composting operations, wastewater management facilities, artificial marshes, trash transfer stations that are open on one or more sides, recycling centers containing putrescible wastes, construction and demolition debris facilities, fly ash disposal, and incinerators.)

- (d) Any use which would generate electrical interference that may be detrimental to the operation of aircraft and/or aircraft instrumentation.
 - (e) Highly noise sensitive outdoor nonresidential uses. Examples of noise-sensitive outdoor nonresidential uses that are prohibited include, but are not limited to, major spectator-oriented sports stadiums, amphitheaters, concert halls and drive-in theaters.
 - (f) Hazards to flight
3. The attached "Notice of Airport in Vicinity" shall be provided to all prospective purchasers and occupants of the property and be recorded as a deed notice. In the event that the Office of the Riverside County Assessor-Clerk-Recorder declines to record said notice, the text of the notice shall be included on the Environmental Constraint Sheet (ECS) of the final parcel map, if an ECS is otherwise required.
 4. Any proposed stormwater basins or facilities shall be designed and maintained to provide for a maximum 48-hour detention period following the design storm, and remain totally dry between rainfalls. Vegetation in and around the detention basins that would provide food or cover for birds would be incompatible with airport operations and shall not be utilized in project landscaping. Trees shall be spaced so as to prevent large expanses of contiguous canopy, when mature. Landscaping in and around the detention basin(s) shall not include trees or shrubs that produce seeds, fruits, or berries.

Landscaping in the detention basin, if not rip-rap, should be in accordance with the guidance provided in ALUC "LANDSCAPING NEAR AIRPORTS" brochure, and the "AIRPORTS, WILDLIFE AND STORMWATER MANAGEMENT" brochure available at RCALUC.ORG which list acceptable plants from Riverside County Landscaping Guide or other alternative landscaping as may be recommended by a qualified wildlife hazard biologist.

A notice sign, in a form similar to that attached hereto, shall be permanently affixed to the stormwater basin with the following language: "There is an airport nearby. This stormwater basin is designed to hold stormwater for only 48 hours and not attract birds. Proper maintenance is necessary to avoid bird strikes". The sign will also include the name, telephone number or other contact information of the person or entity responsible to monitor the stormwater basin.

5. March Air Reserve Base must be notified of any land use having an electromagnetic radiation component to assess whether a potential conflict with Air Base radio communications could result. Sources of electromagnetic radiation include radio wave transmission in conjunction with remote equipment inclusive of irrigation controllers, access gates, etc.
6. The project has been evaluated for on the first floor 13,800 square feet of manufacturing area, 169 square feet of reception area, 421 square feet of office area, and on the second floor mezzanine 1,028 square feet of office area, and 172 square feet of storage area. Any increase in building area, or change in use to any higher intensity use, will require an amended review to evaluate consistency with the ALUCP compatibility criteria, at the discretion of the ALUC Director.
7. The project does not propose rooftop solar panels at this time. However, if the project were to propose solar rooftop panels in the future, the applicant/developer shall prepare

a solar glare study that analyzes glare impacts, and this study shall be reviewed by the Airport Land Use Commission and March Air Reserve Base.

Supporting documentation was provided to the Airport Land Use Commission and is available online at www.rcaluc.org, click Agendas 6-10-21 Agenda, Bookmark Agenda Item No. 3.3.

If you have any questions, please contact me at (951) 955-6893.

Sincerely,
RIVERSIDE COUNTY AIRPORT LAND USE COMMISSION



Paul Rull, ALUC Director

Attachments: Notice of Airport in Vicinity

cc: Lake Creek Industrial (applicant)
Christine Saunders (representative)
Robert D. Aust, Trustee (property owner)
Gary Gosliga, March Inland Port Airport Authority
David Shaw, Base Civil Engineer, March Air Reserve Base
ALUC Case File

Y:\AIRPORT CASE FILES\March\ZAP1466MA21\ZAP1466MA21.LTR.doc


NOTICE OF AIRPORT IN VICINITY

This property is presently located in the vicinity of an airport, within what is known as an airport influence area. For that reason, the property may be subject to some of the annoyances or inconveniences associated with proximity to airport operations (for example: noise, vibration, or odors). Individual sensitivities to those annoyances [can vary from person to person. You may wish to consider what airport annoyances], if any, are associated with the property before you complete your purchase and determine whether they are acceptable to you. Business & Professions Code Section 11010 (b) (13)(A)

NOTICE

**THERE IS AN AIRPORT NEARBY.
THIS STORM WATER BASIN IS DESIGNED TO HOLD
STORM WATER FOR ONLY 48 HOURS AND
NOT TO ATTRACT BIRDS**

**PROPER MAINTENANCE IS NECESSARY TO AVOID
BIRD STRIKES**



IF THIS BASIN IS OVERGROWN, PLEASE CONTACT:

Name: _____

Phone: _____