Print Form

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: P Street Lift Station Project

Lead Agency: City of Live Oak

Contact Name: Ron Walker

Email: rwalker@liveoakcity.org Phone Number: (530) 846-3631

Project Location: City of Live Oak (*City*) Sutter County (*County*)

Project Decription (Proposed actions, location, and/or consequences).

The Project consists of the demolition of approximately 0.14 miles of existing sewage and storm drain pipelines; construction of a new wet well, installation of three new pumps, valves, piping, and a flowmeter with associated vaults; replacement of the existing motor control center, backup generator, and other electrical improvements; replacement of gravity wastewater piping and structures; a new perimeter CMU wall with two access gates; improvements to the electrical and controls building including a new roof; asphalt paving of the Site; drainage infrastructure within the adjacent roadway ROW of Date Street and P Street; the installation of a new box culvert within the drainage ditch onsite (between the lift station and the proposed staging area); and other various improvements.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

Air Quality: Exceed NOx thresholds during construction. Mitigation requires all construction equipment to be Tier 4.
Bio Resources: Potential impacts to nesting birds, bats, and oak trees. mitigation includes preconstruction surveys by qualified personnel and contact CDFW if found.
Cultural Resources: Potential impacts to unknown cultural resources. Mitigation requires notification of discovered resources and investigation by professional archaeologist and proper handling of the resource.
Paleontological Resources: Potential impacts to unknown paleo resources. Mitigation requires notification of discovered resources and investigation by professional paleontologist and proper handling of the resource.
Noise: Exceeds city noise standards during construction. Mitigation includes equipment mufflers, turning off equipment when not in use, direct noise sources away from nearby residences, no amplified music.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

No areas of controversy surrounding the project are currently known for this project.

Provide a list of the responsible or trustee agencies for the project.

California Department of Fish and Wildlife, Region 2
Regional Water Quality Control Board, Central Valley Region (Region 5)
Feather River Air Quality Management District