ANAHEIM HIGH SCHOOL TRACK & FIELD PROJECT INITIAL STUDY Anaheim, CA (Orange County)

Prepared for:

ANAHEIM UNION HIGH SCHOOL DISTRICT

Facilities Planning – Design - Construction 501 Crescent Way Anaheim, CA 92801



Prepared by:

CHAMBERS GROUP, INC.

5 Hutton Centre Drive, Suite 750 Santa Ana, California 92707 (949) 261-5414

February 2023

TABLE OF CONTENTS

		<u>Page</u>
SECTION	N 1.0 – PROJECT DESCRIPTION AND ENVIRONMENTAL SETTING	5
1.1	PROJECT PURPOSE	5
1.2	PROJECT BACKGROUND	5
1.3	PROJECT LOCATION AND SITE CHARACTERISTICS	5
	1.3.1 Location	5
	1.3.2 General Plan Designation/Zoning	5
	1.3.3 Surrounding Land Uses and Project Setting	5
1.4	PROJECT DESCRIPTION	6
	1.4.1 Project Schedule	6
	1.4.2 Best Management Practices	7
1.5	REQUIRED PERMITS AND APPROVALS	9
	N 2.0 – ENVIRONMENTAL DETERMINATION	
2.1	ENVIRONMENTAL FACTORS POTENTIALLY AFFECTED:	
2.2	DETERMINATION	12
SECTION	N 3.0 – EVALUATION OF ENVIRONMENTAL IMPACTS	13
SECTION	N 4.0 – CHECKLIST OF ENVIRONMENTAL ISSUES	15
4.1	AESTHETICS	
	4.1.1 Impact Analysis	
4.2	AGRICULTURE & FORESTRY RESOURCES	17
	4.2.1 Environmental Setting	18
	4.2.2 Impact Analysis	19
4.3	AIR QUALITY	20
	4.3.1 Environmental Setting	20
	4.3.2 Impact Analysis	22
4.4	BIOLOGICAL RESOURCES	23
	4.4.1 Impact Analysis	24
4.5	CULTURAL RESOURCES	26
	4.5.1 Impact Analysis	26
4.6	ENERGY	27
	4.6.1 Impact Analysis	27
4.7	GEOLOGY AND SOILS	28
	4.7.1 Impact Analysis	29
4.8	GREENHOUSE GAS EMISSIONS	31
	4.8.1 Environmental Setting	32
	4.8.2 Impact Analysis	32
4.9	HAZARDS AND HAZARDOUS MATERIALS	33

Anaheim High School Track & Field Project Anaheim, California

	4.9.1 Impact Analysis	33
4.10	HYDROLOGY AND WATER QUALITY	36
	4.10.1 Impact Analysis	36
4.11	LAND USE AND PLANNING	39
	4.11.1 Impact Analysis	39
4.12	MINERAL RESOURCES	40
	4.12.1 Impact Analysis	40
4.13	NOISE	40
	4.13.1 Environmental Setting	41
	4.13.2 Impact Analysis	42
4.14	POPULATION AND HOUSING	43
	4.14.1 Impact Analysis	44
4.15	PUBLIC SERVICES	44
	4.15.1 Impact Analysis	44
4.16	RECREATION	46
	4.16.1 Impact Analysis	46
4.17	TRANSPORTATION	47
	4.17.1 Environmental Setting	47
	4.17.2 Impact Analysis	47
4.18	TRIBAL CULTURAL RESOURCES	49
	4.18.1 Impact Analysis	49
4.19	UTILITIES AND SERVICE SYSTEMS	50
	4.19.1 Impact Analysis	50
4.20	WILDFIRE	52
	4.20.1 Impact Analysis	52
4.21	MANDATORY FINDINGS OF SIGNIFICANCE	53
	4.21.1 Impact Analysis	53
SECTION	5.0 – REFERENCES	55

APPENDIX A – Anaheim High School Illumination Summary

APPENDIX B – Noise Study

APPENDIX C – VMT Analysis & Trip Generation Memo

Anaheim High School Track & Field Project Anaheim, California

LIST OF TABLES

<u>Pa</u>	age
able 1. Surrounding Land Use and Zoning	6
able 2: Footcandle Use Estimates	. 16
able 3: Band Practice Noise Level	. 42
LIST OF FIGURES	
<u>Pa</u>	age
igure 1: Project Vicinity Map	. 10
igure 2: Project Location Map	. 11

SECTION 1.0 – PROJECT DESCRIPTION AND ENVIRONMENTAL SETTING

1.1 PROJECT PURPOSE

Anaheim High School is currently experiencing deteriorating campus buildings and athletic facilities. Anaheim Union High School District (District) proposes to improve athletic facilities by providing an all-weather track & artificial turf field facility, with tiered bleachers, field lighting, and a press box (Project).

1.2 PROJECT BACKGROUND

The District serves a student population of approximately 28,000 students in 19 public schools and is considered one of the largest school districts in California. Anaheim High School is located at 811 W Lincoln Avenue, Anaheim, CA 92805, and is situated in a residential area surrounded by housing on all sides and commercial establishments on the south side. The school accommodates students from Grade 9 -12.

Anaheim High School was established in 1896 with the current Art Deco main building, library, Cook Auditorium, gymnasium, and shop buildings completed in 1936 after the 1933 Long Beach Earthquake. Additional construction occurred in 1957 and 1972. A new two-story classroom building was completed in 2008 adding 47 standard classrooms and 2 science labs. A childcare relocatable was added in 2004 and 15 relocatable classrooms and restrooms were added in 2008.

1.3 PROJECT LOCATION AND SITE CHARACTERISTICS

1.3.1 Location

Anaheim High School is located on a 35-acre property comprised of 15 permanent buildings and 17 portable buildings. Anaheim High School is the oldest school in the District, and the Project is part of the improvements to the field to replace the previous Clayes Stadium that was demolished in 2019. Anaheim High School was established in 1896 with the current Art Deco main building, library, Cook Auditorium, gymnasium and shop buildings completed in 1936 after the 1933 Long Beach Earthquake.

1.3.2 General Plan Designation/Zoning

The Project site is designated as School within the General Plan. Additionally, the Project size is zoned Multifamily Residential (City 2021a; City 2021b).

1.3.3 <u>Surrounding Land Uses and Project Setting</u>

Land uses and zoning designations surrounding the Proposed Project are provided below in Table 1. The Project site is located in the central portion of the City of Anaheim, and bound by Sycamore Street to the north, Citron Street to the east, Lincoln Avenue to the south, North West Street to the west.

There is an existing joint-use agreement with the City regarding field use where the fields could be rented out for private groups when they are not being used by the school.

Table 1. Surrounding Land Use and Zoning

Direction	Land Use	Zoning
North	Low Density Residential	Single-Family Residential (RS-2)
East	Low Density Residential	Single-Family Residential (RS-2, RS-3), Transitional (T), General Commercial (C- G)
South	Mixed Use – High	General Commercial (C-G)
West	Low Density Residential and Park	Single-Family Residential (RS-2) and Multiple Family Residential (RM-4)

1.4 PROJECT DESCRIPTION

The cement bleachers built by the track in 1928 were condemned/demolished in 2019 and must be replaced. The Project consists of the replacement of the existing playfield with artificial turf and synthetic all-weather track, new irrigation system, and goalposts, field lighting, stormwater drainage improvements in the field by the introduction of rainwater collection chambers/retention basins, tiered bleachers, solar/shade canopies over the bleachers, new wall-mounted scoreboard, and path-of-travel improvements including concrete paving, fencing, and landscaping. The upgraded facility will offer enhanced exterior learning opportunities and increased safety for sports and student assemblies.

The Proposed Project will consist of the following upgrades:

- Replacement of the existing playfield with artificial turf and synthetic track including infiltration systems
- Replacement of goalposts
- Installation of field lighting
- Addition of metal solar shade structures with low voltage systems and solar panels
- Installation of tiered bleachers under the shade structures with lighting and Wi-Fi
- Addition of a new wall-mounted scoreboard
- Addition of an observational press box/band tower
- Provision of landscaping and access improvements
- Storm/rainwater retention system
- Flagpole
- Drinking fountains

1.4.1 **Project Schedule**

The Proposed Project is expected to occur over a 12-month period, approximately between the first quarter of 2023 and the first quarter of 2024. Construction activities will take place between the hours of 7:00 a.m. to 4:00 p.m. on Monday through Friday and 8:00 a.m. to 5:00 p.m. on Saturday.

Construction Activities

The LLB contractor selection of the Proposed Project was approved by the District's Board of Trustees on July 14, 2022, project construction activities will begin in the first quarter of 2023. The construction would begin after the Division of the State Architect (DSA) approval of plans and specifications is obtained and the contract for construction is awarded.

Construction equipment to be used during construction of the Proposed Project upgrades include the following items:

- Loaders
- Pick-up trucks
- Backhoe
- Water truck
- Asphalt roller
- Excavators
- Grader
- Scraper
- Roller
- Paving machine
- Skidsteer
- Reachfork
- Drill rig
- Utility truck
- Crew truck
- Dump truck and transfer trailer

Demolition and Excavation

The existing concrete bleachers were demolished in 2019 making room for the new bleachers and field amenities. The existing turf field will be excavated for installation of the new artificial turf and synthetic all-weather track.

Staging Areas

Construction trailers and staging areas will be located northwest portion of the field.

1.4.2 Best Management Practices

During construction activities, the following Best Management Practices (BMPs) will be implemented:

BMP-1: Nesting Bird Survey

If tree or vegetation removal is to occur between February 1 and September 15, the contractor or District shall retain a qualified biologist to conduct a survey to identify active bird nests no more than 2 weeks before the start of construction. Removal of any mature trees with active bird nests will be delayed until a qualified biologist determines that the subject bird(s) are no longer nesting or until juveniles have fledged.

A nesting bird pre-construction survey will be conducted by a qualified biologist and submitted to the District 3 days prior to demolition and/or vegetation removal activities during nesting bird season (February 15 through August 31) within 250 feet of the Project site for passerines and 500 feet for raptors and/or listed species, where feasible. Should nesting birds be found, an exclusionary buffer will be established by a qualified biologist. The buffer may be up to 500 feet in diameter depending on the species of nesting bird found. This buffer will be clearly marked in the field by construction personnel under guidance of the qualified biologist, and construction or clearing will not be conducted within this zone

Chambers Group, Inc.

until the qualified biologist determines that the young have fledged, or the nest is no longer active. Nesting bird habitat within the Project site will be resurveyed during bird breeding season if a lapse in construction activities lasts longer than 7 days.

BMP-2: Cultural Resources

The District will require that the construction contractor, in the event a cultural resource (i.e., historic or prehistoric artifact, fossilized shell, or bone) is discovered during ground-disturbing activities, stop all work within the immediate area and notify the District, and that the find be evaluated by a qualified archaeologist. If the find is determined to be potentially significant, the archaeologist, in consultation with the District and contractor, will develop a treatment plan. All work in the immediate vicinity of the unanticipated discovery will cease until the qualified archaeologist has evaluated the discovery or the treatment plan has been implemented.

BMP-3: Human Remains

If human remains or funerary objects are unearthed during any activities associated with the Project, *State Health and Safety Code* Section 7050.5 requires that no further disturbance shall occur within a 100-foot buffer of the find until the County Coroner has made the necessary findings as to origin and disposition pursuant to *Public Resources Code* Section 5097.98.

If the remains are determined to be of Native American descent, the Coroner has 24 hours to notify the Native American Heritage Commission (NAHC), or any Tribes known to have history in the region. The NAHC will then contact the deceased Native American's most likely descendant, who will then serve as consultant on how to proceed with the remains (i.e., avoid, rebury).

BMP-4: Air Quality Emissions

All off-road diesel-powered equipment (non-street legal), that is greater than 50 horsepower that is used onsite during construction of the project shall meet United States Environmental Protection Agency (USEPA) Tier 4 off-road emission standards. If substantial evidence is provided by the permittee or its contractor that such equipment is not commercially available, then Tier 3 equipment may be utilized.

Commercial on-road and off-road diesel vehicles are subject to the idling limits of California Code of Regulations Title 13, Sections 2485 and 2449(d)(3), respectively. Construction equipment shall not idle for more than five consecutive minutes. The idling limit does not apply to: 1) idling when queuing beyond 100 feet from any restricted areas; 2) idling to verify that the vehicle is in safe operating condition; (3), idling for testing, servicing, repairing, or diagnostic purposes; 4) idling necessary to provide a power source for equipment or operations; to accomplish work for which the vehicle was designed (such as operating a crane); and 6) idling necessary to ensure safe operation of the vehicle.

Idling Equipment engines should be maintained in good condition and in proper tune, as per manufacturer's specifications.

BMP-5: Noise Ordinance

Per the Code of Ordinances of Orange County, Division 6 – Noise Control, noise sources associated with construction, repair, remodeling or grading of any property shall not take place between the hours of 8:00 p.m. and 7:00 a.m. on weekdays, including Saturday, or at any time Sunday or a Federal Holiday. Noise sources associated with the maintenance of property shall take place between 7:00 a.m. and 8:00 p.m.

on any day except Sunday or a Federal holiday, or between the hours of 9:00 a.m. and 8:00 p.m. on Sunday or a federal holiday.

BMP-6: Fugitive Dust

During clearing, grading, earth moving, excessive fugitive dust emissions shall be controlled by regular watering and other dust preventive measures including but not limited to the following:

- Materials excavated or graded shall be sufficiently watered to prevent excessive amounts of dust, at least twice daily with complete coverage, preferably late morning and after work is completed for the day.
- Exposed soil areas and graded materials shall be treated to prevent fugitive dust. This may include
 watering, applying environmentally safe soil stabilization materials, and/or roll-compaction as
 appropriate.
- Clearing, grading and other earth moving activities shall cease during periods of high winds (i.e., greater than 20 miles per hour averaged over 1 hour) so as to prevent excessive amounts of dust.
- Transported materials off-site shall be either watered or securely covered to prevent excessive dust.

BMP-7: Site Runoff and Erosion

The Proposed Project shall implement site specific BMPs under the guidelines of the Stormwater Pollution Prevention Plan (SWPPP) to address site runoff and erosion. Measures will include but are not limited to, site watering, covering soil in inactive areas, placing gravels and fiber rolls to divert runoff, temporary sediment control fences to divert or create barriers to surface flows, or inlet inserts to trap/filter construction and stormwater flows leaving the site.

1.5 REQUIRED PERMITS AND APPROVALS

A public agency, other than the Lead Agency, that has discretionary approval power over a project is referred to under the *CEQA Guidelines* as a "Responsible Agency." The Responsible Agencies and their corresponding approvals for this Proposed Project include:

State Agencies

- School Facilities Planning Division (Plan Approval)
- Office of Public School Construction (Approval of Funding)
- Division of the State Architect (Approval of Structural Fire, Life & Safety, and Access Compliance)

Regional Agencies

Orange County Fire Department (Approval of Site Plan for Emergency Access)

Figure 1: Project Vicinity Map





Figure 2: Project Location Map



SECTION 2.0 – ENVIRONMENTAL DETERMINATION

2.1 ENVIRONMENTAL FACTORS POTENTIALLY AFFECTED:

The environmental factors checked below would potentially be affected by this project, involving at least one impact that is a "Potentially Significant Impact," as indicated by the checklists on the following pages. For each of the potentially affected factors, mitigation measures are recommended that would reduce the impacts to less than significant levels.

	Aesthetics Biological Resources Geology /Soils Hydrology /Water Quality Noise Recreation Utilities /Service Systems	Cultural I Greenhoo	rre and Forestry Resources Resources use Gas Emissions or / Planning on / Housing tation	☐ Er ☐ Ho ☐ M ☐ Po ☐ Tr	ir Quality nergy azards & Hazardous Materials Nineral Resources ublic Services ribal Cultural Resources Nandatory Findings of Significa	
2.2	DETERMINATION	I				
On th	ne basis of this initial ex	aluation:				
1.	NEGATIVE DECLARAT	FION will be p	repared.		e environment, and a	
2.	environment, there v	will not be a s nade by or a	ignificant effect in the greed to by the pro	is case be	nificant effect on the ecause revisions in the conent. A MITIGATED	
3.				ect on the	e environment, and an	
4.	"potentially significa effect (1) has been a legal standards, and (posed project nt unless mit dequately ana (2) has been ac d on attached	t may have a "pot igated impact" on the alyzed in an earlier de ddressed by mitigation d sheets. An ENVIRO	e environ ocument p on measure ONMENTA	ignificant impact" or ment, but at least one pursuant to applicable es based on the earlier AL IMPACT REPORT is ddressed.	
5.	I find that although environment, becau adequately in an ear and (b) have been	the propose se all poten lier EIR or Ne avoided or n g revisions o	ed project could ha tially significant eff gative Declaration pu nitigated pursuant t r mitigation measur	ve a sigr fects (a) ursuant to o that ea	hificant effect on the have been analyzed applicable standards, arlier EIR or Negative re imposed upon the	
Signa	ture		Date			
Name	9		Title			

Chambers Group, Inc.

SECTION 3.0 – EVALUATION OF ENVIRONMENTAL IMPACTS

- 1. A brief explanation is required for all answers except "No Impact" answers that are adequately supported by the information sources a lead agency cites. A "No Impact" answer is adequately supported if the referenced information sources show that the impact simply does not apply to projects like the one involved (e.g., the project falls outside a fault rupture zone). A "No Impact" answer should be explained where it is based on project-specific factors as well as general standards (e.g., the project will not expose sensitive receptors to pollutants, based on a project-specific screening analysis).
- 2. All answers must take account of the whole action involved, including offsite as well as onsite, cumulative as well as project-level, indirect as well as direct, and construction as well as operational impacts.
- 3. Once the lead agency has determined that a particular physical impact may occur, then the checklist answers must indicate whether the impact is potentially significant, less than significant with mitigation, or less than significant. "Potentially Significant Impact" is appropriate if substantial evidence exists that an effect may be significant. If one or more "Potentially Significant Impact" entries are marked when the determination is made, an EIR is required.
- 4. "Negative Declaration: Less Than Significant With Mitigation Incorporated" applies where the incorporation of mitigation measures has reduced an effect from "Potentially Significant Impact" to a "Less Than Significant Impact." The lead agency must describe the mitigation measures and briefly explain how they reduce the effect to a less than significant level (mitigation measures from earlier analyses may be cross-referenced).
- 5. Earlier analyses may be used where, pursuant to the tiering, program EIR, or other CEQA process, an effect has been adequately analyzed in an earlier EIR or negative declaration. Section 15063(c)(3)(D). In this case, a brief discussion should identify the following:
 - a. Earlier Analysis Used. Identify and state where they are available for review.
 - b. Impacts Adequately Addressed. Identify which effects from the above checklist were within the scope of and adequately analyzed in an earlier document pursuant to applicable legal standards, and state whether such effects were addressed by mitigation measures based on the earlier analysis.
 - c. Mitigation Measures. For effects that are "Less than Significant with Mitigation Measures Incorporated," describe the mitigation measures which were incorporated or refined from the earlier document and the extent to which they address site-specific conditions for the project.
- 6. Lead agencies are encouraged to incorporate into the checklist references to information sources for potential impacts (e.g., general plans, zoning ordinances). Reference to a previously prepared or outside document should, where appropriate, include a reference to the page or pages where the statement is substantiated.
- 7. Supporting Information Sources: A source list should be attached, and other sources used or individuals contacted should be cited in the discussion.

- 8. The explanation of each issue should identify:
 - a. the significance criteria or threshold, if any, used to evaluate each question; and
 - b. the mitigation measure identified, if any, to reduce the impact to less than significant.

*Note: Instructions may be omitted from final document.

SECTION 4.0 - CHECKLIST OF ENVIRONMENTAL ISSUES

4.1 AESTHETICS

1.	AESTHETICS. Except as provided in Public Resources Code Section 21099, would the project:	Potentially Significant Impact	Less Than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Have a substantial adverse effect on a scenic vista?				\boxtimes
(b)	Substantially damage scenic resources, including, but not limited to, trees, rock outcroppings, and historic buildings within a state scenic highway?			\boxtimes	
(c)	In non-urbanized areas, substantially degrade the existing visual character or quality of public views of the site and its surroundings? (Public views are those that are experienced from publicly accessible vantage point). If the project is in an urbanized area, would the project conflict with applicable zoning and other regulations governing scenic quality?				
(d)	Create a new source of substantial light or glare which would adversely affect day or nighttime views in the area?			\boxtimes	

4.1.1 <u>Impact Analysis</u>

a) Would the project have a substantial adverse effect on a scenic vista?

No Impact. The Proposed Project site is bounded by residential developments on all sides, including commercial developments along Lincoln Avenue. Scenic views from the Project site may include the San Gabriel Mountains to the north and the Saddleback Mountains to the east. No scenic vistas would be obstructed by the Proposed Project. The City of Anaheim identifies the area east of State Route 55 and State Route 91, west of the Orange County Line, south of the Santa Fe Railroad right-of-way, and north of the present south city limits as part of its Scenic Corridor, however the Proposed Project is not located within this zone (City 2022a). The Project would involve the demolition of the existing football/soccer field and track, and installation of a new artificial turf field and synthetic track with bleachers and shade structures with solar panels. The addition of the press box/band tower would create a new feature that would be a maximum height of 33'10". The press box/band tower would be located toward the interior of the school, and no impact would occur to nearby residents. There would be no impact to scenic vistas.

b) Would the project substantially damage scenic resources, including, but not limited to, trees, rock outcroppings, and historic buildings within a state scenic highway?

Less Than Significant Impact. The nearest highways to the Project site are Interstate 5 (I-5), California State Highway 55, and California State Highway 91. The Project site is approximately 0.4 mile east of Interstate 5, 2.8 miles west of the California State Highway 55. A portion of California State Highway 91, approximately 5.9 miles east of the Project site, is designated as a state scenic highway (Caltrans 2022); however, due to distance and intervening topography, the Project site is not within view of the scenic portion of the highway. The Proposed Project site is located in a developed, urban area with all

work associated with the Proposed Project being located on the interior of the campus, away from West Lincoln Avenue. The Proposed Project would, therefore, have a less than significant impact.

c) Would the project, in non-urbanized areas, substantially degrade the existing visual character or quality of public views of the site and its surroundings? (Public views are those that are experienced from publicly accessible vantage point). If the project is in an urbanized area, would the project conflict with applicable zoning and other regulations governing scenic quality?

Less Than Significant Impact. The Proposed Project includes the demolition of the existing track and field, the installation of a new all-weather field, synthetic track, bleachers, and other associated improvements. These changes would result in changes to the overall visual character and create new structures that were not previously part of the existing school. The Project would be consistent with the character of the surrounding structures, with the press box tower reaching a height of 33'10". The improved installations would not degrade the existing visual character or quality of the site or its immediate surroundings. The Proposed Project would also be consistent with zoning regulations. Impacts would be less than significant.

d) Create a new source of substantial light or glare which would adversely affect day or nighttime views in the area?

Less Than Significant Impact. The Proposed Project would not substantially increase lighting in the surrounding area relative to existing levels by inclusion of lighting standards established by the District. The Proposed Project site is in an urbanized area surrounded by residential neighborhoods. While the existing track and field does not have any lighting features onsite other nearby lighting features include streetlight, lighting existing on the campus to support security of the campus and classrooms, and Founders Park. The Proposed Project would include installation a new track and field and bleachers in place of the existing field which would introduce new sources of lighting, including four light poles to support operation and use of the practice field along with a new scoreboard. Lighting would be designed in accordance with District standards with lighting features designed to be angled towards the field and shielded to minimize spillover outside of the field. The Proposed Project is not expected to create new sources of glare by use of glare reducing surfaces, which would minimize impacts on nearby residents.

Musco Lighting prepared illumination summaries for the Proposed Project to calculate the illuminance, the energy of light hitting the surface of an area, of the proposed operations of the Project (Appendix A). The summaries provided the measurements for horizontal and vertical footcandles. The unit of measurement used is a footcandle (fc). A footcandle is a measurement of light that is able to saturate one square foot. Horizontal footcandles are the light intensity measured as it lands on a flat surface, while vertical footcandles are light intensity measured as it lands on a vertical wall. Application examples of footcandle measurements are provided below. These measurements are estimates as they may vary on the model and type of lighting used.

Table 2: Footcandle Use Estimates

USE	ESTIMATED FOOTCANDLES (FC)
Food Courts	30 fc
Cashier Stands	20-50 fc
Hotel Bathrooms	20-50 fc

USE	ESTIMATED FOOTCANDLES (FC)
Department Store	20-80 fc
Office Reception and Conference Rooms	10-50 fc
Convention Center Stairways	5 fc
Exterior Parking Garages and Vehicle Storage	1-5 fc
School Classrooms	30-50 fc
School Hallways	10 fc
School Gymnasiums	30-100 fc
High School Football fields	30-70 fc
Baseball and Softball fields	30-100 fc

^{*}Source: LED Lighting Supply Recommended Foot Candle Chart

According to the vertical and horizontal footcandles measurements at Anaheim High School, the maximum measured intensity outside of the proposed field along the residences at West Sycamore Street is 0.3 fc. Based on the comparison with the footcandle estimates, the Proposed Project would result in the addition of light and glare to the residences. However, the intensity of the field lights at the nearest residences would be a significantly reduced intensity than on the field itself. Due to the design of the lights and being shielded towards the field, so significant light spillover beyond the boundary of the school would not occur. Furthermore, the Proposed Project would only permit the use of the field and field lights during school hours and some special sporting events which would not go beyond 9:00 p.m. Because the Proposed Project would not create significant spillover of lights during school events, in addition to the design of the lighting features to further reduce spillover onto nearby properties, impacts to a level less than significant. Therefore, the Project would not create a new source of substantial light or glare that would adversely affect the area. Impacts would be less than significant.

4.2 AGRICULTURE & FORESTRY RESOURCES

2.	AGRICULTURE & FOREST RESOURCES. (In determining whether impacts to agricultural resources are significant environmental effects, lead agencies may refer to the California Agricultural Land Evaluation and Site Assessment Model (1997) prepared by the California Department of Conservation as an optional model to use in assessing impacts on agriculture and farmland. In determining whether impacts to forest resources, including timberland, are significant environmental effects, lead agencies may refer to information compiled by the California Department of Forestry and Fire Protection regarding the state's inventory of forest land, including the Forest and Range Assessment Project and the Forest Legacy Assessment project; and forest carbon measurement methodology provided in Forest Protocols adopted by the California Air Resources Board. Would the project:	Potentially Significant Impact	Less Than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
----	---	--------------------------------------	--	------------------------------------	--------------

(a)	Convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland), as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, to non-agricultural use?		\boxtimes
(b)	Conflict with existing zoning for agricultural use, or a Williamson Act contract?		
(c)	Conflict with existing zoning for, or cause rezoning of, forest land (as defined in Public Resources Code section 12220(g)), timberland (as defined by Public Resources Code section 4526), or timberland zoned Timberland Production (as defined by Government Code section 51104(g))?		
(d)	Result in the loss of forest land or conversion of forest land to non-forest use?		
(e)	Involve other changes in the existing environment which, due to their location or nature, could result in conversion of Farmland, to non-agricultural use or the conversion of forest land to non-forest use?		

4.2.1 <u>Environmental Setting</u>

Agricultural resources include prime farmland, farmland of statewide importance, unique farmland, farmland of local importance, and commercial grazing land as defined in the Guidelines for the Farmland Mapping and Monitoring Program, pursuant to Section 65570 of the Government Code, as well as land in a Williamson Act contract.

Prime farmland is land that has the best combination of physical and chemical characteristics for producing food, feed, fiber, forage, oilseed, and other agricultural crops with minimum inputs of fuel, fertilizer, pesticides, and labor and without intolerable soil erosion. (7U.S.C. 4201(c)(1)(A))

Unique farmland is land other than prime farmland that is used for the production of specific high-value food and fiber crops such as, citrus, tree nuts, olives, cranberries, fruits, and vegetables. (7 U.S.C. 4201(c)(1)(B))

Additional farmland of statewide or local importance is land identified by state or local agencies for agricultural use but not of national significance. (7 U.S.C. 4201(c)(1)(C))

The California Legislature passed the Williamson Act in 1965 to preserve agricultural and open-space lands by discouraging premature and unnecessary conversion to urban uses. The Act creates an arrangement whereby private land owners contract with counties and cities to voluntarily restrict their land to agricultural and compatible open-space uses.

The Williamson Act is a means to restrict the uses of agricultural and open-space lands to farming and ranching uses during the length of the contract period. The Williamson Act Program was also envisioned as a way for local governments to integrate the protection of open space and agricultural resources into their overall strategies for planning urban growth patterns.

4.2.2 <u>Impact Analysis</u>

a) Would the project convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland), as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, to non-agricultural use?

No Impact. The Proposed Project site is designated in the City of Anaheim General Plan as Schools and zoned as Multi-Family Residential (City 2021a; City 2021b). Land uses surrounding the Proposed Project include low density residential, mixed-use and park. Surrounding zoning includes Single-Family and Multiple-Family residential, and General Commercial. The Proposed Project site is not identified as Prime Farmland, Unique Farmland, or Farmland of Statewide Importance as shown on maps prepared pursuant to the Department of Conservation (DOC 2022a). Implementation of the Proposed Project would include improvements only within the existing campus and no offsite land would be affected. Therefore, the Proposed Project would not result in an impact associated with the conversion of farmland to non-agricultural use.

b) Would the project conflict with existing zoning for agricultural use, or a Williamson Act contract?

No Impact. There are no areas zoned for agricultural use on or near the Proposed Project site. Additionally, the City of Anaheim does not include any properties subject to the Williamson Act and has not reported to the DOC in 2020 and 2021 (DOC 2022b). Therefore, the Proposed Project would not result in an impact associated with Williamson Act lands or agricultural zoning.

c) Would the project conflict with existing zoning for, or cause rezoning of, forest land (as defined in Public Resources Code section 12220(g)), timberland (as defined by Public Resources Code section 4526), or timberland zoned Timberland Production (as defined by Government Code section 51104(g))?

No Impact. The City of Anaheim does not include any forest lands or timberland. Ornamental trees exist on the Proposed Project site; however, the proposed updates to the practice field and new construction associated with the improvements would not result in any disturbance to the existing ornamental trees on site because the Project would take place within the existing practice field. The Proposed Project would not result in an impact associated with forest land or timberland.

d) Would the project result in the loss of forest land or conversion of forest land to non-forest use?

No Impact. Implementation of the Proposed Project would not result in any change to land use on site. Therefore, the Proposed Project would not result in an impact associated with forest land or the conversion of forest land to non-forest use.

e) Would the project involve other changes in the existing environment which, due to their location or nature, could result in conversion of Farmland, to non-agricultural use or the conversion of forest land to non-forest use?

No Impact. The Proposed Project site is located within a fully urbanized area. As per the City of Anaheim General Plan land use designations, the Proposed Project site is designated as School (City 2021a). Surrounding land use designations include Low and Medium Density Residential. Implementation of the Proposed Project would be consistent with existing uses and would not change

the existing land use and zoning of the site. The Project site is not within an area identified as Prime Farmland, Unique Farmland or Farmland of Statewide Importance (DOC 2022b). The Proposed Project would, therefore, have no impact.

4.3 AIR QUALITY

3.	AIR QUALITY. Where available, the significance criteria established by the applicable air quality management district or air pollution control district may be relied upon to make the following determinations. Would the project:	Potentially Significant Impact	Less Than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Conflict with or obstruct implementation of the applicable air quality plan?			\boxtimes	
(b)	Result in a cumulatively considerable net increase of any criteria pollutant for which the project region is non-attainment under an applicable federal or state ambient air quality standard?				
(c)	Expose sensitive receptors to substantial pollutant concentrations?				
(d)	Result in other emissions (such as those leading to odors) adversely affecting a substantial number of people?			\boxtimes	

4.3.1 <u>Environmental Setting</u>

The Project site is located within the City of Anaheim in central Orange County. The Proposed Project site is located within the South Coast Air Basin (SCAB), and air quality regulation is administered by the South Coast Air Quality Management District (SCAQMD). The SCAQMD implements the programs and regulations required by the federal and state Clean Air Acts.

Atmospheric Setting

Air quality is a function of both the rate and location of pollutant emissions under the influence of meteorological conditions and topographical features. Atmospheric conditions such as wind speed, wind direction, and air temperature gradients interact with physical features of the landscape to determine their movement and dispersal and, consequently, their effect on air quality. The combination of topography and inversion layers generally prevents dispersion of air pollutants in the SCAB.

The climate of the SCAB is influenced by the semi-permanent high-pressure zone of the eastern Pacific, which results in a mild climate tempered by cool sea breezes. Although the SCAB has a semiarid climate, the air near the surface is typically moist due to the presence of a shallow marine layer. Except for infrequent periods when dry air is brought into the basin by offshore winds, the ocean effect is dominant. Periods of heavy fog are frequent; and low stratus clouds, often referred to as "high fog," are a characteristic climate feature. Average temperatures for Anaheim, which is the nearest monitoring station to the Proposed Project site (WRCC 2017), range from an average low of 46.9 degrees Fahrenheit (°F) in December to an average high of 87.1 °F in August. Rainfall averages approximately 14.09 inches a year, with almost all annual rainfall coming from the fringes of mid-latitude storms from late October to early April and summers being almost completely dry.

Winds are an important parameter in characterizing the air quality environment of a project site because they determine the regional pattern of air pollution transport and control the rate of dispersion near a source. Daytime winds in the SCAB are usually light breezes from off the coast as air moves regionally onshore from the cool Pacific Ocean. These winds are usually the strongest in the dry summer months. Nighttime winds in the SCAB result mainly from the drainage of cool air off the mountains to the east, and they occur more often during the winter months and are usually lighter than the daytime winds. Between the periods of dominant airflow, periods of air stagnation may occur, both in the morning and evening hours. Whether such a period of stagnation occurs is one of the critical determinants of air quality conditions on any given day.

During the winter and fall months, surface high-pressure systems north of the SCAB, combined with other meteorological conditions, can result in very strong winds from the northeast called "Santa Ana winds." These winds normally have durations of a few days before predominant meteorological conditions are reestablished. The highest wind speed typically occurs during the afternoon due to daytime thermal convection caused by surface heating. This convection brings about a downward transfer of momentum from stronger winds aloft. It is not uncommon to have sustained winds of 60 miles per hour with higher gusts during a Santa Ana wind.

Regulatory Setting

The Proposed Project site lies within the SCAB, which is managed by the SCAQMD. National Ambient Air Quality Standards (NAAQS) and California Ambient Air Quality Standards (CAAQS) have been established for the following criteria pollutants: carbon monoxide (CO), ozone (O_3) , sulfur dioxide (SO_2) , nitrogen dioxide (NO_2) , inhalable particulate matter (PM_{10}) , fine particulate matter $(PM_{2.5})$, and lead. The CAAQS also set standards for sulfates, hydrogen sulfide, and visibility.

Areas are classified under the Federal Clean Air Act as either "attainment" or "nonattainment" areas for each criteria pollutant, based on whether the NAAQS have been achieved or not. Attainment relative to the state standards is determined by the California Air Resources Board (CARB). The SCAB has been designated by the Federal Environmental Protection Agency (EPA) as a nonattainment area for O_3 and suspended $PM_{2.5}$. Currently, the SCAB is in attainment with the ambient air quality standards for CO, SO_2 , PM_{10} and NO_2 . The SCAB is designated as partial nonattainment for lead based on two source specific monitors in Vernon and in the City of Industry that are both near battery recycling facilities.

The EPA has designated the SCAB to be in extreme nonattainment for the 8-hour average ozone standard. The 1997 8-hour ozone NAAQS was strengthened from 0.08 ppm to 0.075 parts per million (ppm), effective May 27, 2008. The 1997 8-hour ozone standard was revoked in implementation rules for the 2008 ozone NAAQS, effective April 6, 2015. On October 1, 2015, the EPA again strengthened the 8-hour ozone NAAQS to 0.070 ppm, effective December 28, 2015, retaining the same form as the previous 1997 and 2008 standards. The 2008 ozone NAAQS is a primary focus of the 2016 Air Quality Management Plan (AQMP).

Additionally, the EPA has designated the SCAB as nonattainment for $PM_{2.5}$. In 1997, the EPA established standards for $PM_{2.5}$ (particles less than 2.5 micrometers), which were not implemented until March 2002. $PM_{2.5}$ is a subset of the PM_{10} emissions whose standards were developed to complement the PM_{10} standards that cover a full range of inhalable particle matter. For the PM_{10} health standards, the annual PM_{10} standard was revoked by the EPA on October 17, 2006; and the 24-hour average PM_{10} nonattainment status was redesignated to attainment (maintenance) on July 26, 2013.

The 2012 AQMP provides measures to reduce $PM_{2.5}$ emissions to within the federal standard by 2015. On January 25, 2013, the CARB approved the 2012 AQMP that was prepared per the federal Clean Air Act requirements to show attainment of the $PM_{2.5}$ standard by the revised date of 2014. The 2012 AQMP built upon the approaches taken in the 2007 AQMP utilized to reduce $PM_{2.5}$ emissions in the SCAB. On December 14, 2012, the EPA revised the primary annual $PM_{2.5}$ NAAQS from 15 micrograms per cubic meter ($\mu g/m^3$) to 12 $\mu g/m^3$. On March 3, 2017, the CARB approved the 2016 AQMP, which includes implementation strategies to meet the revised $PM_{2.5}$ standard.

The SCAB has been designated by CARB as a nonattainment area for O_3 , NO_2 , PM_{10} , $PM_{2.5}$, and lead. Currently, the SCAB is in attainment with the CAAQS for CO, SO_2 , and sulfates and is unclassified for visibility-reducing particles and hydrogen sulfide. The 2007, 2012, and 2016 AQMPs provide measures to meet the state standards for O_3 , NO_2 , PM_{10} , and $PM_{2.5}$.

4.3.2 <u>Impact Analysis</u>

a) Would the project conflict with or obstruct implementation of the applicable air quality plan?

Less Than Significant Impact. The South Coast Air Quality Management Plan (SCAQMP) is the air quality plan applicable to the Proposed Project site. The purpose of the AQMP is to provide direction that brings an area into compliance with federal and state air quality standards. The Proposed Project involves the demolition of the existing field and replacement of the track and field, as well as the addition of new bleachers and related accessory structures. Construction of the Project would not introduce substantial emissions in the area. During construction equipment required would introduce new temporary increases in emissions including carbon dioxide, nitrogen dioxide, and particulate matter. Additionally, the Project site would be watered at least once a day to SCAQMD Rule 403 to reduce dust emissions resulting from Project site activities. Other standard SCAQMD construction requirements that limit the time of day when construction may occur as well as SCAQMD Rule 1108 that limits VOC content in asphalt and Rule 1113 that limits the VOC content in paints and solvents to minimize odor impacts from construction would be complied with as well. Operational emissions associated with the Project are expected to be similar to existing conditions. Implementation of the Proposed Project would result in a less than significant impact.

b) Would the project result in a cumulatively considerable net increase of any criteria pollutant for which the project region is non-attainment under an applicable federal or state ambient air quality standard?

Less Than Significant Impact. Implementation of the Project would not result in a substantial increase of emissions during construction of the Project because construction would be temporary and short-term in nature, with construction activities expected to have a 12-month duration. Operational emissions would remain similar to existing conditions because there is no change in land uses. Additionally, compliance with existing regulations set by the SCAQMD would ensure no net increase in criteria pollutants would occur. The Proposed Project would result in a less than significant impact.

c) Would the project expose sensitive receptors to substantial pollutant concentrations?

Less Than Significant Impact. The Proposed Project would not involve substantial construction activities and land uses would remain the same. The nearest sensitive receptors to the Proposed Project include students and staff at Anaheim High School, Benjamin Franklin Elementary School (approximately 0.5 mile southeast of the Project site), and the residential land uses adjacent to the site. Construction of the Proposed Project would create air emissions that include fugitive dust and toxic air contaminant emissions from the operation of construction equipment; however, construction will only occur intermittently over a 12-month period. The ongoing operation of the Proposed Project is not anticipated to generate emissions from any sources that would create substantial pollutant concentrations. Reconstruction of the practice field and addition of bleachers would not introduce a new use that is not currently onsite due to the existing practice field. Impacts would, therefore, be less than significant.

d) Would the project result in other emissions (such as those leading to odors) adversely affecting a substantial number of people?

Less Than Significant Impact. Individual responses to odors are highly variable and can result in a variety of effects. Generally, the impact of an odor results from a variety of factors such as frequency, duration, offensiveness, location, and sensory perception. The frequency is a measure of how often an individual is exposed to an odor in the ambient environment. The intensity refers to an individual's or group's perception of the odor strength or concentration. The duration of an odor refers to the elapsed time over which an odor is experienced. The offensiveness of the odor is the subjective rating of the pleasantness or unpleasantness of an odor. The location accounts for the type of area in which a potentially affected person lives, works, or visits; the type of activity in which he or she is engaged; and the sensitivity of the impacted receptor.

The Proposed Project would not generate substantial emissions such objectionable odors or dust during operations. The objectionable odors that may be produced during the construction process would be temporary and would not likely be noticeable for extended periods of time beyond the Proposed Project site's boundaries. Minor sources of odors associated with the Proposed Project would be associated primarily with the diesel equipment used during construction. As discussed in Section 4.3.2 Impact (a), construction activities are anticipated to be minor and would not include a significant amount of grading or demolition. Exhaust odors from diesel engines may be considered offensive to some individuals; however, diesel emissions would occur during construction periods and be short term in nature and any emissions would disperse rapidly. Impacts would, therefore, be less than significant.

4.4 BIOLOGICAL RESOURCES

4.	BIOLOGICAL RESOURCES. Would the project:	Potentially Significant Impact	Less Than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Have a substantial adverse effect, either directly or through habitat modifications, on any species identified as a candidate, sensitive, or special status species in local or regional plans, policies, or regulations, or by the California Department of Fish and Game or U.S. Fish and Wildlife Service?				

Chambers Group, Inc. 23

4.	BIOLOGICAL RESOURCES. Would the project:	Potentially Significant Impact	Less Than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(b)	Have a substantial adverse effect on any riparian habitat or other sensitive natural community identified in local or regional plans, policies, regulations or by the California Department of Fish and Wildlife or U.S. Fish and Wildlife Service?				
(c)	Have a substantial adverse effect on state or federally protected wetlands (including, but not limited to, marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means?				
(d)	Interfere substantially with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native wildlife nursery sites?				
(e)	Conflict with any local policies or ordinances protecting biological resources, such as a tree preservation policy or ordinance?				\boxtimes
(f)	Conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan?				

4.4.1 <u>Impact Analysis</u>

a) Would the project have a substantial adverse effect, either directly or through habitat modification, on any species identified as candidate, sensitive or special status species in local or regional plans, policies or regulations, or by the California Department of Fish and Game or U.S. Fish and Wildlife Service?

Less Than Significant Impact. The Proposed Project is located in a highly urbanized setting and is currently developed with Anaheim High School, which consists of multiple one- and two- story structures. Vegetation at the Project site includes ornamental landscaping around the school buildings. The Proposed Project would include construction which would occur only at the football/soccer practice field adjacent to the existing pool, gymnasium, and shop. There would be ground disturbing activities which include the demolition of the football and soccer field and replacement with an all-weather track and synthetic turf field along with a new bleachers and shade features and solar panels. While the potential for nesting birds within the existing nearby trees is present, a nesting bird survey would be completed as part of the best management practices. Impacts would be less than significant.

b) Would the project have a substantial adverse effect on any riparian habitat or other sensitive natural community identified in local or regional plans, policies or regulations, or by the California Department of Fish and Wildlife or U.S. Fish and Wildlife Service?

No Impact. The Project site does not contain any riparian habitat or sensitive natural communities. The Project site does not contain any vegetation or biological habitat that provides habitat for sensitive or special status species. The ornamental trees would not be altered during the construction of the Proposed Project. No impacts would occur.

- c) Would the project have a substantial adverse effect on state or federally protected wetlands (including but not limited to marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means?
 - **No Impact.** The Project site is not located on a federally protected wetland, and no features are found onsite (USFWS 2022). The nearest wetland features are located approximately .3 mile east at Pearson Park which includes a freshwater Pond. No impact would occur.
- d) Would the project Interfere substantially with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native wildlife nursery sites?
 - **No Impact.** There are no native biological habitats on the Project site nor any wildlife corridors. The Project site is currently urbanized and developed with only ornamental vegetation onsite. The implementation of the Project would have no impact to wildlife corridors or native wildlife nursery sites.
- e) Would the project conflict with any local policies or ordinances protecting biological resources, such as a tree preservation policy or ordinance?
 - **No Impact.** No local policies or ordinances protecting biological resources, apply to the Project site. The District would not be required to comply with the City's tree protection ordinance which applies to developments within the Scenic Overlay Zone, as discussed in 4.1.1(a) the Proposed Project is located outside of this zone. There would be no impact.
- f) Would the project conflict with the provisions of an adopted Habitat Conservation Plan, Natural Conservancy Conservation Plan, or other approved local, regional, or state habitat conservation plan?
 - **No Impact.** The Project site is not within the area of any adopted Habitat Conservation Plan, Natural Community Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan. The Proposed Project consists of the demolition of an existing field and the installation of a new artificial turf field facility with press box, and bleacher seating with shade structures and photovoltaic panels. The Project would not result in any impacts to any adopted habitat conservation plans.

4.5 CULTURAL RESOURCES

5.	CULTURAL RESOURCES. Would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Cause a substantial adverse change in the significance of a historical resource pursuant to §15064.5?				\boxtimes
(b)	Cause a substantial adverse change in the significance of an archaeological resource pursuant to §15064.5?				\boxtimes
(c)	Disturb any human remains, including those interred outside of formal cemeteries?				\boxtimes

4.5.1 <u>Impact Analysis</u>

a) Would the project cause a substantial adverse change in the significance of a historical resource pursuant to §15064.5?

No Impact. Anaheim High School is located on a 35-acre property comprised of 15 permanent buildings and 17 portable buildings. The school was established in 1896 with the current Art Deco main building, library, Cook Auditorium, gymnasium, and shop buildings completed in 1936 after the 1933 Long Beach Earthquake. Additional construction occurred in 1957 and 1972. A new two-story classroom building was completed in 2008 adding 47 standard classrooms and two science labs. A childcare relocatable was added in 2004 and 15 relocatable classrooms and restrooms were added in 2008. The Proposed Project is located within the Anaheim Colony Historic District which includes multiple architectural styles, with most homes in the area being built between 1910 to 1935 (City 2004). This district aims to preserve and protect existing buildings within the District. Work associated with the Proposed Project would be completed on the existing field and would not involve any improvements on the existing permanent buildings. The Proposed Project would, therefore, have no impacts to any historical resources.

b) Would the project cause a substantial adverse change in the significance of an archaeological resource pursuant to §15064.5?

No Impact. No known archaeological resources are located on the Proposed Project site. In addition, if any archaeological resources are encountered during construction activities, the District's Construction BMPs (see Section 1.4.3) related to cultural resources would be followed. Further, ground disturbance of any native soils or soils not previously disturbed would not occur as part of the Proposed Project. Therefore, no impacts are expected.

c) Would the project disturb any human remains, including those interred outside of formal cemeteries?

No Impact. The Proposed Project site is located in an urbanized area previously disturbed by past activities. In addition, if any human remains are encountered during construction activities, the District's Construction BMPs (see Section 1.4.3) related to cultural resources and procedures required

by state law would be followed. Further, ground disturbance of any native soils or soils not previously disturbed would not occur as part of the Proposed Project. Therefore, no impacts are expected.

4.6 ENERGY

6.	ENERGY Would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Result in potentially significant environmental impact due to wasteful, inefficient, or unnecessary consumption of energy resources, during project construction or operation?				
(b)	Conflict with or obstruct a state or local plan for renewable energy or energy efficiency?			\boxtimes	

4.6.1 Impact Analysis

a) Would the project result in potentially significant environmental impact due to wasteful, inefficient, or unnecessary consumption of energy resources, during project construction or operation?

Less Than Significant Impact.

Construction Related Energy Consumption

During construction the Proposed Project would consume electricity to construct the new field and infrastructure. Electricity would be supplied to the Project site by Southern California Edison and would be obtained from the existing electrical lines near the Project site. The use of electricity from existing power lines rather than temporary diesel or gasoline powered generators would minimize impacts on fuel consumption. Electricity consumed during Project construction would vary throughout the construction period based on the construction activities being performed. Such electricity demand would be temporary and, nominal, and would cease upon the completion of construction. Overall, construction activities associated with the Proposed Project would require limited electricity consumption that would not be expected to have an adverse impact on available electricity supplies and infrastructure. Therefore, the use of electricity during Project construction would not be wasteful, inefficient, or unnecessary.

Construction of the Proposed Project typically would not involve the consumption of natural gas. Natural gas would not be supplied to support construction activities, thus there would be no demand generated by construction. Given that the Project site is currently has natural gas service in the vicinity of the Project site, construction of the Proposed Project would be limited to installation of new natural gas connections within the Project site. Development of the Proposed Project would likely not require extensive infrastructure improvements to serve the Project site. Construction-related energy usage impacts associated with the installation of natural gas connections are expected to be confined to trenching in order to place the lines below surface. In addition, prior to ground disturbance, the Proposed Project would notify and coordinate with SoCalGas to identify the locations and depth of all existing gas lines and avoid disruption of gas service.

Construction activities associated with the Proposed Project would be required to adhere to all state and SCAQMD regulations for off-road equipment and on-road trucks, which provide minimum fuel efficiency standards. As such, construction activities for the Proposed Project would not result in the wasteful, inefficient, and unnecessary consumption of energy resources. Impacts regarding transportation energy would be less than significant. Development of the Project would not result in the need to manufacture construction materials or create new building material facilities specifically to supply the Proposed Project.

Operations Related Energy Consumption

The Proposed Project would comply with all federal, state, and county requirements related to the consumption of natural gas, that includes CCR Title 24, Part 6 *Building Energy Efficiency Standards* and CCR Title 24, Part 11: *California Green Building Standards*. The CCR Title 24, Part 6 and Part 11 standards require numerous energy efficiency measures to be incorporated into the proposed practice facility. Therefore, it is anticipated the Proposed Project will be designed and built to minimize electricity and natural gas use and that existing and planned electric and natural gas capacity and natural gas supplies would be sufficient to support the Proposed Project's natural gas demand. Thus, impacts with regard to electricity and natural gas supply and infrastructure capacity would be less than significant and no mitigation measures would be required.

It should be noted the Proposed Project will be designed and built to minimize transportation energy and it is anticipated that existing and planned capacity and supplies of transportation fuels would be sufficient to support the Proposed Project's demand. Thus, impacts with regard transportation energy supply and infrastructure capacity would be less than significant and no mitigation measures would be required.

b) Would the project Conflict with or obstruct a state or local plan for renewable energy or energy efficiency?

Less Than Significant Impact. The Proposed Project would, at a minimum, comply with CCR Title 24, which regulates the amount of energy consumed by new development for heating, cooling, ventilation, and lighting. In addition, the City of Anaheim published its Greenhouse Emissions Reduction Plan which included reduction targets for 2030, and 2045; this plan included improvements in electric consumption, and Project implementation would utilize energy efficient infrastructure to comply with the plan (City 2020). Therefore, the Proposed Project would result in less than significant impacts associated with renewable energy or energy efficiency plans.

4.7 GEOLOGY AND SOILS

7.	GEOLOGY AND SOILS. Would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Directly or indirectly cause potential substantial adverse effects, including the risk of loss, injury, or death involving:				

7.	GEOLOGY AND SOILS. Would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
	i) Rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault? Refer to Division of Mines and Geology Special Publication 42.				
	ii) Strong seismic ground shaking?			\boxtimes	
	iii) Seismic-related ground failure, including liquefaction?			\boxtimes	
	iv) Landslides?				
(b)	Result in substantial soil erosion or the loss of topsoil?			\boxtimes	
(c)	Be located on a geologic unit or soil that is unstable, or that would become unstable as a result of the project, and potentially result in on- or off-site landslide, lateral spreading, subsidence, liquefaction or collapse?			\boxtimes	
(d)	Be located on expansive soil, as defined in Table 18- 1-B of the Uniform Building Code (1994), creating substantial direct or indirect risks to life or property?			\boxtimes	
(e)	Have soils incapable of adequately supporting the use of septic tanks or alternative waste water disposal systems where sewers are not available for the disposal of waste water?				\boxtimes
(f)	Directly or indirectly destroy a unique paleontological resource or site or unique geological feature?				\boxtimes

4.7.1 <u>Impact Analysis</u>

a) i) Would the project directly or indirectly cause potential substantial adverse effects, including the risk of loss, injury, or death involving rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault? Refer to Division of Mines and Geology Special Publication 42.

Less Than Significant Impact. The Project site is located approximately 8 miles southwest of the Whittier Fault Zone (DOC 2022c). Although the Proposed Project is near a fault, the Project site is not located within a designated Alquist-Priolo Special Study Zone. Construction of the Proposed Project would not require deep excavation work that could affect any faults, nor would it create structures with long occupation periods that could face substantial impacts during earthquake events. The Project would be consistent with the City's safety codes and requirements. Impacts would be less than significant.

ii)Would the project directly or indirectly cause potential substantial adverse effects, including the risk of loss, injury, or death involving strong seismic ground shaking?

Less Than Significant Impact. The Proposed Project site would include upgrades and creation of a new artificial turf field facility with bleacher seating. The Project site is located approximately 8 miles southwest of the Whittier Fault Zone (DOC 2022c). The renovations to the field and new bleacher and shade structure would be consistent with the current seismic safety and building codes and American with Disabilities Act (ADA) accessibility requirements. Impacts would be less than significant.

iii)Would the project directly or indirectly cause potential substantial adverse effects, including the risk of loss, injury, or death involving seismic-related ground failure, including liquefaction?

Less Than Significant Impact. Liquefaction is a process where soil behaves temporarily as a viscous liquid. Liquefaction typically occurs in areas where sediment is water-saturated during moderate to great earthquakes. The Department of Conservation (DOC 2022c) identifies that the area as not susceptible to liquefaction. The Proposed Project includes construction of a new artificial turf field facility with bleacher seating with associated improvements which would be constructed to current building code. The Proposed Project would, therefore, result in a less than significant impact and not be subject to ground failure.

iv) Would the project directly or indirectly cause potential substantial adverse effects, including the risk of loss, injury, or death involving landslides?

No Impact. The Proposed Project site is not identified as an area prone to seismically induced landslides (DOC 2022c). The Project site is relatively flat which would not induce or facilitate landslides. Implementation of the Project would result in no impact.

b) Would the project result in substantial soil erosion or the loss of topsoil?

Less Than Significant Impact. The Proposed Project includes the demolition of the existing football and soccer field and the installation of an artificial turf field facility with bleacher seating. The construction activities, including the demolition of the existing track and field, have the potential to result in soil erosion or the loss of topsoil. With implementation of District BMPs including the minimization of soil drop height during dumping, the application of water every 4 hours during active demolition, debris removal to reduce vehicle trackout, and the prohibition of demolition activities when wind speeds exceed 25 miles per hour, impacts would be less than significant.

c) Would the project be located on a geologic unit or soil that is unstable, or that would become unstable as a result of the project, and potentially result in on- or off-site landslide, lateral spreading, subsidence, liquefaction, or collapse?

No Impact. As discussed above, the Project site is not located in an area of slope instability and is not susceptible to liquefaction (DOC 2022c). The Project site is relatively flat, and the Proposed Project includes replacement of the field and creation of an artificial turf field facility with bleacher seating and associated improvements which would not result in an increased risk for landslide, lateral spreading, subsidence, and is not located in an area with the potential for liquefaction or collapse. No impacts would occur.

d) Would the project be located on expansive soil, as defined in Table 18-1-B of the Uniform Building Code (1994), creating substantial direct or indirect risks to life or property?

Less Than Significant Impact. The Project site has been previously graded and developed with a school and track. The United States Department of Agriculture (USDA) classifies the landform underlaying the Proposed Project site as Metz loamy sand and San Emigdio fine sandy loam with soil containing minimal amounts of clay (USDA 2017). The native materials are capped locally by artificial fill where previously existing natural grades have been modified as part of urbanization. Due to minimal clay content in soil underlaying the Proposed Project site and previous grading and development on-site, it is unlikely that the Proposed Project site contains expansive soils, which are soils that are prone to expansion or shrinkage due to variation in water volume. Due to the Project type and activities, the Proposed Project would result in a less than significant impact.

e) Would the project have soils incapable of adequately supporting the use of septic tanks or alternative waste water disposal systems where sewers are not available for the disposal of wastewater?

No Impact. The Proposed Project would rely on existing sewer infrastructure to accommodate wastewater disposal requirements. The Project would not involve the use of septic tanks or any other alternative waste water disposal systems. No impact would occur.

f) Would the project directly or indirectly destroy a unique paleontological resource or site or unique geological feature?

No Impact. No known paleontological resources are located on the Proposed Project site. The Proposed Project site is located in an urbanized area previously disturbed by past activities. In addition, if any paleontological resources are encountered during construction activities, the District's Construction BMPs (see Section 1.4.2) related to cultural resources would be followed. Further, ground disturbance of any native soils or soils not previously disturbed would not occur as part of the Proposed Project. Therefore, no impacts are expected.

4.8 GREENHOUSE GAS EMISSIONS

8.	GREENHOUSE GAS EMISSIONS. Would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Generate greenhouse gas emissions, either directly or indirectly, that may have a significant impact on the environment?			\boxtimes	
(b)	Conflict with an applicable plan, policy, or regulation adopted for the purpose of reducing the emissions of greenhouse gases?				

Chambers Group, Inc.

4.8.1 Environmental Setting

Significant legislative and regulatory activities directly and indirectly affect climate change and greenhouse gases (GHGs) in California. The primary climate change legislation in California is Assembly Bill (AB) 32, the California Global Warming Solutions Act of 2006. AB 32 focuses on reducing GHG emissions in California, and AB 32 requires that GHGs emitted in California be reduced to 1990 levels by the year 2020.

The CARB is the state agency charged with monitoring and regulating sources of emissions of GHGs in California that contribute to global warming in order to reduce emissions of GHGs. The CARB Governing Board approved the 1990 GHG emissions level of 427 million tonnes of CO₂ equivalent (MtCO₂e) on December 6, 2007. Therefore, in 2020, annual emissions in California are required to be at or below 427 MtCO₂e. In January 2017, the CARB Board approved the 2017 Climate Change Scoping Plan (Scoping Plan). The Scoping Plan aims to reduce 1990 levels by 40 percent by 2030. The Scoping Plan continues programs and activities that will be implemented primarily by state agencies but also includes actions by local government agencies. Primary strategies addressed in the Scoping Plan include new industrial and emission control technologies; alternative energy generation technologies; advanced energy conservation in lighting, heating, cooling, and ventilation; reduced-carbon fuels; hybrid and electric vehicles; and other methods of improving vehicle mileage. Local government will have a part in implementing some of these strategies. The Scoping Plan also calls for reductions in vehicle associated GHG emissions through smart growth that will result in reductions in vehicle miles traveled (CARB 2017).

4.8.2 Impact Analysis

- a) Would the project generate greenhouse gas emissions, either directly or indirectly, that may have a significant impact on the environment?
 - Less Than Significant Impact. The Proposed Project would not increase the capacity of the school nor the number of activities that would occur at the Proposed Project site. During construction equipment required would introduce new temporary increases in emissions; however, these would be temporary in nature and not result in a substantial increase short term emissions. No increases in long-term operational GHG emissions are anticipated to occur from the Proposed Project. Additionally, there would be no change in the current land uses. Therefore, implementation of the Proposed Project would result in a less than significant impact associated with GHG emissions.
- b) Would the project conflict with an applicable plan, policy, or regulation adopted for the purpose of reducing the emissions of greenhouse gases?
 - Less Than Significant Impact. Neither the County nor SCAQMD have any specific plans, policies, or regulations adopted for reducing the emissions of GHGs. In 2020 the City of Anaheim published its Greenhouse Emissions Reduction Plan which included reduction targets for 2030, and 2045; this plan included improvements in both electric consumption and conservation along with water usage (City 2020). The Proposed Project construction-related emissions are short-term and anticipated to be insignificant, and the operation of the Proposed Project would not create an increase in GHG emissions. The Proposed Project would not introduce a new use and would exist within the existing Anaheim High School Campus while also being required to comply with current California Building Code; therefore, implementation of the Proposed Project would result in a less than significant impact associated with an applicable plan, policy, or regulation adopted for reducing the emissions of GHGs.

4.9 HAZARDS AND HAZARDOUS MATERIALS

9.	HAZARDS AND HAZARDOUS MATERIALS. Would the project:	Potentially Significant Impact	Less Than Significant with Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Create a significant hazard to the public or the environment through the routine transport, use, or disposal of hazardous materials?				
(b)	Create a significant hazard to the public or the environment through reasonably foreseeable upset and accident conditions involving the release of hazardous materials into the environment?				
(c)	Emit hazardous emissions or handle hazardous or acutely hazardous materials, substances, or waste within one-quarter mile of an existing or proposed school?				
(d)	Be located on a site which is included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 and, as a result, would it create a significant hazard to the public or the environment?			\boxtimes	
(e)	For a project located within an airport land use plan or, where such a plan has not been adopted, within 2 miles of a public airport or public use airport, would the project result in a safety hazard or excessive noise for people residing or working in the project area?				
(f)	Impair implementation of or physically interfere with an adopted emergency response plan or emergency evacuation plan?				
(g)	Expose people or structures, either directly or indirectly, to a significant risk of loss, injury, or death involving wildland fires?				

4.9.1 <u>Impact Analysis</u>

a) Would the project create a significant hazard to the public or the environment through the routine transport, use, or disposal of hazardous materials?

Less Than Significant Impact. The Proposed Project will not include any significant structural renovations that would result in the accidental release of hazardous materials to the environment.

The Proposed Project would involve the use of heavy equipment during construction that would emit emissions associated with internal combustion engines, (i.e., diesel and gasoline); however, once operational, the Proposed Project would only use chemicals associated with maintenance operations including the use of commercial cleansers, lubricants, solvents, and paints, among other things typically used in educational facilities. Maintenance materials would not be considered acutely hazardous and would be used in limited quantities at the Proposed Project site. Compliance with the

existing regulations, including the manufacturer's product label and Safety Data Sheets, would ensure that no significant hazard to the public, the students, or the environment would result through the routine transport, use, or disposal of hazardous materials; therefore, implementation of the Proposed Project would result in less than significant impacts associated with the routine transport, use, or disposal of hazardous materials.

b) Would the project create a significant hazard to the public or the environment through reasonably foreseeable upset and accident conditions involving the release of hazardous materials into the environment?

Less Than Significant Impact. The Proposed Project will not include any significant structural renovations that would result in the accidental release of hazardous materials to the environment. Because work would all be completed on the existing track area of the school, no asbestos containing materials or lead containing materials are expected to be discovered.

Additionally, as mentioned in Section 4.9.2 Impact (a), the construction phase of the Proposed Project would involve the use of equipment during construction that would emit emissions associated with internal combustion engines (i.e., diesel and gasoline); however, the use of fuels is regulated by the state and would be in compliance with all state regulations during construction. Implementation of the Proposed Project would result in a less than significant impact associated with the release of hazardous materials.

c) Would the project emit hazardous emissions or handle hazardous or acutely hazardous materials, substances, or waste within one-quarter mile of an existing or proposed school?

Less Than Significant Impact. The implementation of the Proposed Project includes creation of an artificial turf field facility with bleacher seating at Anaheim High School. The school closest to the Proposed Project site is Benjamin Franklin Elementary School, located .45 mile southeast of the Proposed Project site. As noted in the previous responses, the Proposed Project would involve the use of construction equipment that would emit emissions associated with internal combustion engines (i.e., diesel and gasoline). Once operational, the Proposed Project would involve minimal amounts of cleaning solvents and fuel for janitorial purposes and landscaping maintenance which would be subject to federal, state, and local health and safety requirements, with materials being limited to staff use and access to students being prohibited. Use and storage of these items would be stored and used within manufacturer guidelines. As discussed above in Impact 4.9.2 Impact (a), adherence to all local, county, state, and federal policies and regulations would reduce impacts to a level less than significant. Therefore, implementation of the Proposed Project would result in less than significant impacts associated with hazardous materials, substances, or waste within one-quarter mile of an existing or proposed school.

d) Would the project be located on a site which is included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 and, as a result, would it create a significant hazard to the public or the environment?

Less Than Significant Impact. The Proposed Project site is not on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 (State Water Resources Control Board [SWRCB] 2022); the Anaheim High School site is located immediately adjacent to an existing clean-up

site (600021055) however this site has gone inactive in its remediation activities based on data available on the Envirostor website (Department of Toxic Substances Control [DTSC 2022]). Detail available on the Envirostor website the City of Anaheim and District were in negotiations about cleanup responsibility however no decision was made about the soil contamination and no construction activities have occurred on the site. While the site is located adjacent to the school, access is restricted to this area and no work would occur on the listed site. Therefore, implementation of the Proposed Project would result in a less than significant impact associated with known hazardous materials sites.

e) For a project located within an airport land use plan or, where such a plan has not been adopted, within 2 miles of a public airport or public use airport, would the project result in a safety hazard or excessive noise for people residing or working in the project area?

No Impact. The Proposed Project site is located approximately 11 miles northwest of John Wayne Airport. Additionally, the Proposed Project site is not located within the Airport Influence Area for the John Wayne Airport or within its Runway Protection Zones Orange County Airport Land Use Commission (OCALUC 2008). Due to the nature of the Proposed Project rehabilitating an existing field with additional track facilities and bleachers with shade structures no impacts would occur to nearby airport. Therefore, implementation of the Proposed Project would not result in an impact.

f) Would the project impair implementation of or physically interfere with an adopted emergency response plan or emergency evacuation plan?

Less Than Significant Impact. The Project site is surrounded by urbanized areas and residential structures. The Proposed Project would involve replacement of the football and soccer field with a new artificial turf field facility with bleacher seating. These activities would not interfere with established emergency response or emergency evacuation plans as there is no proposed alteration of infrastructure utilized in an evacuation plan. Implementation of the Proposed Project would be the similar to the existing operations and would not require change in existing emergency response or evacuation plans; therefore, implementation of the Proposed Project would result in a less than significant impact associated with an emergency evacuation plan.

g) Would the project expose people or structures, either directly or indirectly, to a significant risk of loss, injury or death involving wildland fires?

No Impact. The Proposed Project site is identified as a Non-Very High Fire Hazard Safety Zone (CAL FIRE 2022). Additionally, the Proposed Project is not located within or adjacent to wildlands or identified Very High Fire Hazard Safety Zones. Therefore, implementation of the Proposed Project would not result in an impact associated with wildland fires.

4.10 HYDROLOGY AND WATER QUALITY

10.	HYDROLOGY AND WATER QUALITY. Would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Violate any water quality standards or waste discharge requirements or otherwise substantially degrade surface or ground water quality?				
(b)	Substantially decrease groundwater supplies or interfere substantially with groundwater recharge such that the project may impede sustainable groundwater management of the basin?			\boxtimes	
(c)	Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river or through the addition of impervious surfaces, in a manner which would:				
	i) Result in substantial erosion or siltation on- or off- site;			\boxtimes	
	ii) Substantially increase the rate or amount of surface runoff in a manner which would result in flood on- or off-site;				
	iii) Create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff; or				
	iv) Impede or redirect flood flows?				
(d)	In flood hazard, tsunami, or seiche zones, risk release of pollutants due to project inundation?				\boxtimes
(e)	Conflict with or obstruct implementation of a water quality control plan or sustainable groundwater management plan?				

4.10.1 <u>Impact Analysis</u>

a) Would the project violate any water quality standards or waste discharge requirements, or otherwise substantially degrade surface or ground water quality?

Less Than Significant Impact. The Proposed Project involves installation of an artificial turf field facility with bleacher seating at the existing Anaheim High School campus. Work would be conducted outdoors and would require soil disturbance. The disturbance would result in short-term impacts to site drainage during construction periods. If soil is not contained and is directly exposed to rain, soil erosion and sediment could flow into the storm drain system, resulting in the potential degradation of water quality; however, the likelihood of a violation of water quality standards or waste discharge requirements would be reduced due to compliance with industry standard BMPs.

BMPs reduce the potential for erosion by implementing erosion and sediment control measures that regulate the amount and quality of runoff from a construction site. Due to the amount of soil disturbance approximately 4.5 acres, the Proposed Project would apply for a National Pollutant

Discharge Elimination System (NPDES) permit and prepare a SWPPP based on the overall size of impacts associated with the Proposed Project. Implementation of BMPs, and installation of water retention systems with the artificial turf field would be implemented to comply with water quality standards or waste discharge requirements. Implementation of the SWPPP would reduce polluted stormwater runoff from the Project site and ensure compliance with the Orange County Water District (OCWD) Basin Alternative Plan. Therefore, implementation of the Proposed Project would result in less than significant impacts associated with water quality standards or waste discharge requirements.

b) Would the project substantially decrease groundwater supplies or interfere substantially with groundwater recharge such that the project may impede sustainable groundwater management of the basin?

Less Than Significant Impact. The Proposed Project involves installation of a new artificial turf field facility with bleacher seating. The Proposed Project site is currently developed, and the majority of ground cover is pervious surface. The Proposed Project would not substantially increase the amount of impervious surface associated with the facility and would not interfere with groundwater recharge. The turf would include infiltration systems, and storm/rainwater retention systems to allow for additional groundwater recharge. Additionally, the Proposed Project would not increase the number of students or staff, and additional water resources would not be required to accommodate any such growth. Therefore, implementation of the Proposed Project would not result in impacts associated with groundwater recharge or groundwater depletion.

- c) Would the project substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river or through the addition of impervious surfaces, in a manner which would:
 - i) result in substantial erosion or siltation on- or off-site,

Less Than Significant Impact. The Proposed Project site is in an urbanized location and is currently developed and mostly covered in impervious surfaces except for areas that landscaped with grass and trees in addition to the athletic fields. Ground disturbing activities would occur; and approximately 3,000 square feet of impervious surface would result from the practice facility with storm water and water retention systems. However, the Proposed Project would not substantially increase the area of impervious surfaces at the Proposed Project site by using ground infiltration features associated with the artificial turf. In addition, any construction which would result in ground disturbing activities would be required to utilize BMPs that would reduce any potential erosion or siltation on- or offsite. Further, the drainage pattern of the Proposed Project site and surrounding area is well established, and no streams or rivers are located on or near the Proposed Project site. Therefore, implementation of the Proposed Project would result in less than significant impacts associated with the existing drainage pattern.

ii) substantially increase the rate or amount of surface runoff in a manner which would result in flooding on- or off-site;

Less Than Significant Impact. The Proposed Project would not involve alteration of a stream or river. The Project site is located in an urban area and is partially covered with impervious surfaces.

37

Demolition of the current track and field will involve re-grading for the replacement of the field with synthetic turf and infiltration features. The new practice field which may incrementally increase the runoff to the nearest storm drain on North Citron Avenue; however, this would not result in flooding on- or off-site from use of stormwater and water retention systems. Implementation of the Project would result in a less than significant impact.

iii) create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources or polluted runoff; or

Less Than Significant Impact. The Proposed Project would not impede any current stormwater drainage systems existing at the project site. The Project includes improvements to the field with additional infiltration and rainwater systems and would not create a substantial increase in runoff. Approximately 3,000 square feet of impervious material would be introduced from the Proposed Project, and the infiltration systems associated with the artificial turf would reduce runoff and maintenance required by artificial turf. The Proposed Project would remove the need for fertilizer and pesticides associated with turf fields that can runoff into stormwater systems. Impacts would, therefore, be less than significant.

iv) impede or redirect flood flows?

Less Than Significant Impact. The Project site is in a 0.2 percent flood hazard zone as per the Federal Management Agency (FEMA 2022). The Project site is located in Flood Zone X (Map # 06059C0133J) which is an area of 0.2 percent minimal flood hazard. General site flows are directed towards the south and southwest, with infiltration systems and site design allowing for flows to continue and maintain their existing directions. Flood impacts would be less than significant.

d) Would the project in flood hazard, tsunami, or seiche zones, risk release of pollutants due to project inundation?

No Impact. The Project site is located approximately 11.5 miles from the Pacific coast. Seiches are large waves generated by ground shaking effects within enclosed bodies of water. Tsunamis are tidal waves generated by fault displacement or major ground movement The Project site is relatively flat and not located in any flood hazard, tsunami, or seiche zones. No impacts are expected.

e) Would the project conflict with or obstruct implementation of a water quality control plan or sustainable groundwater management plan?

No Impact. The Project would comply with all city, State, and federal regulations. Any construction that would result in ground disturbing activities would be required to utilize BMPs that would reduce any potential erosion or siltation on- or offsite. The Coastal Plain of Orange County Groundwater Basin has an approved alternative plan that established four management areas within the Basin, with the Proposed Project being located within the Orange County Water District Management area. The Basin Alternative Plan contains the Region's water quality regulations and programs to implement the regulations (OCWD 2016). This Plan allows OCWD to project future water demands based on historic water availability and demand.

As previously mentioned, the Project would apply for a NPDES permit and prepare a SWPPP. Implementation of the SWPPP would reduce polluted stormwater runoff from the Project site and ensure compliance with the OCWD Basin Alternative Plan. Additionally, the Proposed Project would still allow groundwater recharge and not create need for additional water needs. No impacts are expected to occur.

4.11 LAND USE AND PLANNING

11.	LAND USE/PLANNING Would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Physically divide an established community?				\boxtimes
(b)	Cause a significant environmental impact due to a conflict with any land use plan, policy, or regulation adopted for the purpose of avoiding or mitigating an environmental effect?				

4.11.1 Impact Analysis

a) Would the project physically divide an established community?

No Impact. The public school at the Project site is bounded by Sycamore Street to the north, Citron Street to the east, Lincoln Avenue to the south, north West street and multifamily developments to the west. The school is surrounded by residential developments with some commercial development along Lincoln Avenue. The Proposed Project does not introduce new roads or facilities that would divide an established community. The Proposed Project includes the demolition and replacement of the track and field and new practice facility which would not change current existing land uses. No impact would occur.

b) Would the project cause a significant environmental impact due to a conflict with any land use plan, policy, or regulation adopted for the purpose of avoiding or mitigating an environmental effect? Partially pending traffic results

No Impact. The Project site is zoned Multi-family residential and has a land use designation of School (City 2021a, City 2021b) and the area surrounding the site includes low density residential and general commercial. The Proposed Project would not alter the function of the existing structure and would be compliant with the General Plan, as well as all relevant policies and regulations. No impacts are expected.

4.12 MINERAL RESOURCES

12.	MINERAL RESOURCES Would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state?				
(b)	Result in the loss of availability of a locally-important mineral resource recovery site delineated on a local general plan, specific plan or other land use plan?				

4.12.1 <u>Impact Analysis</u>

a) Would the project result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state?

No Impact. It has not been determined if there are significant mineral deposits present at the Proposed Project site. The State of California Division of Mines and Geology classified the Project site as a Mineral Resource Zone 3. There is no adequate information indicating that the area could contain mineral deports but cannot be evaluated from available data (DOC 2022d). Additionally, the Project site supports an existing high school campus, with no mineral resource recovery occurring onsite. No impact would occur.

b) Would the project result in the loss of availability of a locally-important mineral resource recovery site delineated on a local general plan, specific plan or other land use plan?

No Impact. There are no existing or historic mineral resource sites in or near the Proposed Project site (DOC 2022d). In addition, the Project involves improvement of a field within an existing school and would not involve any mining or loss of mineral resources. Implementation of the Project would result in no impact.

4.13 NOISE

13.	NOISE Would the project result in:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Generation of a substantial temporary or permanent increase in ambient noise levels in the vicinity of the project in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies?				
(b)	Generation of excessive groundborne vibration or groundborne noise levels?				

(c)	For a project located within the vicinity of a private airstrip or an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the project expose people residing or working in the project area.		\boxtimes
	expose people residing or working in the project area to excessive noise levels?		

4.13.1 <u>Environmental Setting</u>

A Noise Study was prepared by Ldn Consulting, Inc. for the Proposed Project (Appendix B) that analyzes the potential noise impacts associated with the construction and operational activities at the site. Property lines surrounding the Project site are predominantly residential therefore a 60 decibel (dBA) hourly noise standard would typically be applied per the City's Municipal Code. However, the school operations would be exempt under Chapter 6.70 of the Municipal Code.

Section 6.72.040 states that the following uses of sound-amplifying equipment and activities shall be exempt from the provisions of this chapter: "Equipment and devices used as an integral part of any public or private institutional use lawfully permitted pursuant to this Code, including but not limited to, public and private educational institutions, and places of religious worship."

Events conducted within the athletic field currently include football, soccer, track and field, and band practices. The highest use of the field would be from evening football games. These events are existing and would occur only periodically.

Anaheim High School did not have any home football games scheduled after October 14, 2022 but played an away game against Western High School. Western High School is an Anaheim Unified School District school located within an urbanized area and surrounded by residential uses. The football game was held at Handel Stadium, a stadium used for District-wide events located at the northwestern portion of the campus. To determine the noise levels anticipated during an evening football game, noise measurements of a football game were conducted on Friday, October 28, 2022 between the hours of 6:00 p.m. and 9:00 p.m. at Western High School. The measurements were taken in the evening hours when community noise levels are lower due to lower traffic volumes on adjacent roadways.

The noise levels during the measurements included people arriving to the game, crowds cheering, the high school band playing between plays and during intermissions along with the public announcements (PA) system and then people leaving after the game. The primary noise levels consisted of crowds cheering, the high school band playing along with the public announcements (PA) system. The results of the noise level measurements are presented in Table 4-1. The average noise levels during the entire measurements were found to be roughly 58-65 dBA equivalent continuous sound level (Leq).

To determine the noise levels anticipated during a band event, noise measurements of a band practice were conducted on Wednesday, November 16, 2022 between 3:30 p.m. and 4:30 pm at Anaheim High School. Practice was held at the existing football field at the site of the proposed athletic field upgrades. The practice included approximately 80 members of the school's marching band. The measurements were taken during the afternoon after normal school hours. The noise levels measured during the band practice were found to be roughly 71-79 dBA Leq, in close proximity of the band within the field, during the entire practice.

4.13.2 <u>Impact Analysis</u>

a) Would the project result in generation of a substantial temporary or permanent increase in ambient noise levels in the vicinity of the project in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies?

Less Than Significant Impact

Operational Impacts

Based on the noise measurements taken during an evening football game at Western High School, it is possible to apply the noise levels to the Anaheim High School project site. It was determined that noise levels could be as high as 68 dBA approximately 200-feet from the playing field. The nearest residences at the Anaheim High School are located approximately 300-feet to the north across West Sycamore Avenue and east across North Citron Street. The increased distance would reduce the noise levels at the existing residences by 3.5 dBA and therefore would not be enough to meet the City's noise threshold of 60 dBA. As stated above, these activities are existing and are exempt from the provisions of Section 6.70.010 of the City of Anaheim's Municipal Code.

Based on the noise measurements taken during band practice, it is possible to determine the noise levels at the nearest residences. The noise levels from the band practice along with the calculated hourly noise levels based upon the distances are shown below in Table 3 for the residential properties to the west, north, and east. Residential properties to the south of Lincoln Avenue are located over 800-feet away and will be shielded by existing school buildings.

Resultant Noise Reference Noise Reference **Minimum** Noise Reduction due to distance (dBA) **Property Line** Level (dBA) **Distance (Feet) Distance** Level (dBA Leq) West 78.9 75 620 -18.3 60.6 -7.4 North 73.7 150 350 66.3 71.1 380 -14.1 East 75 57

Table 3: Band Practice Noise Level

Based upon the property line noise levels determined from the football games and band practices, the high school's operational noise levels currently exceed and would likely continue to exceed the City's property line noise threshold at the surrounding residential uses. Though these events would occur only periodically, they would be expected to generate noise exceeding City standards at the nearest residences. As stated above, these activities are existing and are exempt from the provisions of Section 6.70.010 of the City of Anaheim's Municipal Code.

The equipment and devices used during the football games and band practices are an integral part of a public educational institution and therefore are exempt from the provisions of Section 6.70.010 of the City of Anaheim's Municipal Code. Pursuant to the City's Municipal Code, the existing and future operational uses are lawfully permitted.

Construction Noise Impacts

Project construction noise levels are considered exempt if activities occur within the hours specified in the City of Anaheim Municipal Code, Section 6.70.010 of 7:00 a.m. and 7:00 p.m. unless approval is obtained from the City Building Official or City Engineer. At the time of this analysis, no Project construction activity is planned outside of the specified hours. Therefore, no impacts are anticipated, and no mitigation is required during construction of the Project. Additionally, all equipment should be properly fitted with mufflers and all staging and maintenance should be conducted as far away for the existing residence as possible. Impacts would, therefore, be less than significant.

b) Would the project result in generation of excessive groundborne vibration or groundborne noise levels?

Less Than Significant Impact. Ground borne vibration is an oscillatory motion that is often described by the average amplitude of its velocity in inches per second or more specifically, peak particle velocity. Groundborne vibration is much less common than airborne noise. The Proposed Project would not cause groundbourne vibration impacts to sensitive receptors due to the demolition and replacement of the field and turf and other upgrades around the existing field. The construction activities are not expected to create a significant amount of groundborne vibration or groundborne noise. Impacts would be less than significant.

c) For a project located within the vicinity of a private airstrip or an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public us airport, would the project expose people residing or working in the project area to excessive noise levels?

No Impact. As discussed in Section 4.9.2 Impact (e), the Proposed Project would not be located within an airport influence area and would not conflict with adopted or planned airport land use plans. The Project site is located over 11 miles northwest of John Wayne Airport and approximately 12.8 miles northeast of the Long Beach Municipal Airport. The Proposed Project would not be located within any airport influence areas (OCALUC 2008). No impacts are expected to occur.

4.14 POPULATION AND HOUSING

14.	POPULATION AND HOUSING. Would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Induce substantial unplanned population growth in an area, either directly (for example, by proposing new homes and businesses) or indirectly (for example, through extension of roads or other infrastructure)?				\boxtimes
(b)	Displace substantial numbers of existing people or housing, necessitating the construction of replacement housing elsewhere?				

4.14.1 <u>Impact Analysis</u>

a) Would the project induce substantial unplanned population growth in an area, either directly (for example, by proposing new homes and businesses) or indirectly (for example, through extension of roads or other infrastructure)?

No Impact. The Proposed Project consists of demolition and replacement of the existing football/ soccer field and track, and creation of a new artificial turf field facility with bleacher seating. The Project would not create the need for additional housing in the area, as the Project would not increase the capacity or student enrollment at Anaheim High School. The Project would be located on an already existing school site with several roadways currently providing access to the site. The implementation of the Proposed Project would not result in an impact associated with population growth.

b) Would the project displace substantial numbers of existing people or housing, necessitating the construction of replacement housing elsewhere?

No Impact. The Proposed Project would be contained within the existing Anaheim High School Campus. Addition of the new track and field, with bleachers and other associated improvements would not displace any persons or require replacement housing. No impact would occur.

4.15 PUBLIC SERVICES

15.	PUBLIC SERVICES.	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Would the project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for any of the public services:				
	i) Fire Protection?				
	ii) Police Protection?				
	iii) Schools?			\square	
	iv) Parks?				
	v) Other public facilities?				\square

4.15.1 <u>Impact Analysis</u>

a) Would the project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for fire protection?

No Impact. Fire protection services for the Project site would be provided the City of Anaheim Fire Department. The closest fire station located near the Project site is No. 1 approximately one mile east of the school. Fire protection service needs are generally related to the size of the population and geographic area served, the number and types of calls for service, and other community and physical characteristics. Because land uses at the Proposed Project site would remain the same as under current conditions, an increase in the demand for fire services resulting from the Proposed Project is not anticipated. The implementation of the Proposed Project would, therefore, not result in an impact.

- b) Would the project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for police protection?
 - **No Impact.** The Proposed Project involves the demolition and replacement of the field and track among other upgrades in the existing field. The Anaheim Unified High School District maintains its own safety department to provide security for schools. The closest police station, City of Anaheim Main Station to the Project site is located at 425 South Harbor Boulevard, approximately 0.45 mile southeast of the Project site. While currently no bleachers exist at the practice field, addition of the bleachers would create capacity for 991 spectators. The Anaheim Unified High School District would be notified large events in order to provide appropriate safety officers during on campus events. The Project would not introduce an increase in population which would not require additional police services. The Project would not result in an impact associated with police protection.
- c) Would the project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for schools?
 - Less than Significant Impact. The Proposed Project includes the removal of the existing track facilities and the creation of a new artificial turf field facility with bleacher seating. The renovations would occur on school property at football/soccer practice field, which is located north of the existing pool, gymnasium, and shop. The Proposed Project would provide new state-of-the-art track and field facilities, that currently do not exist at the campus and would reduce the need to travel off campus to use track facilities. The Proposed Project site's use would be limited during construction for a short period of time. Since the Proposed Project site is a school, there will be interruptions in the usage of the field. The implementation of the Project would have a less than significant impact.
- d) Would the project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for parks?

No Impact. The Proposed Project would not result in adverse physical impacts associated with the provision of new or physically altered facilities to maintain acceptable opportunities for parks. The closest parks to the Proposed Project site are Pearson Park at 400 North Harbor Boulevard (approximately 0.45 miles east of the Proposed Project site) and George Washington Park (approximately 0.75 miles east of the Proposed Project site). The Proposed Project would not induce population growth and would not increase the need for park facilities within the City. Therefore, implementation of the Proposed Project would not result in an impact associated with parks.

e) Would the project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for other public facilities?

No Impact. The Proposed Project would reconstruct the existing practice field and create a new practice field with synthetic track and turf, along with bleachers and shade structures. Construction and Operation of the Proposed Project would not increase demand for any other public facilities, it would serve demand associated with the students and staff of Anaheim High School. The Proposed Project is not expected to impact any other public facilities.

4.16 RECREATION

16.	RECREATION. Would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Would the project increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated?				\boxtimes
(b)	Does the project include recreational facilities or require the construction or expansion of recreational facilities which might have an adverse physical effect on the environment?				\boxtimes

4.16.1 <u>Impact Analysis</u>

a) Would the project increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated?

No Impact. The Project includes the demolition and replacement of the field and track, and of a new practice facility at Anaheim High School. The Proposed Project would not directly or indirectly induce population which would increase the use of existing neighborhood, regional parks, or any other recreational facilities. As discussed above in Section 4.15.1 Impact (d), two recreational facilities are in close proximity to the Proposed Project site: Pearson Park (approximately 0.45 mile from Proposed Project site) and George Washington Park (approximately 0.75 mile from the Proposed Project site)

(Google 2022). Anaheim High School does not use either of the nearby parks as the school provides its own recreational facilities to fulfill student recreational needs. No impact would occur.

b) Does the project include recreational facilities or require the construction or expansion of recreational facilities which might have an adverse physical effect on the environment?

No Impact. The Proposed Project site is located at Anaheim High School, which provides students with on-campus recreational facilities. Implementation of the Proposed Project would not require the construction or expansion of offsite recreational facilities. The Proposed Project is intended to upgrade school facilities for an existing student population and would not burden any facility beyond capacity by generating additional recreational users. Therefore, implementation of the Proposed Project would not result in an impact associated with the construction or expansion of recreational facilities.

4.17 TRANSPORTATION

17.	TRANSPORTATION. Would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Conflict with a program, plan, ordinance or policy addressing the circulation system, including transit, roadways, bicycle and pedestrian facilities?				
(b)	Conflict or be inconsistent with CEQA Guidelines section 15064.3, subdivision (b)?			\boxtimes	
(c)	Substantially increase hazards due to a geometric design feature (e. g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment)?				
(d)	Result in inadequate emergency access?				\boxtimes

4.17.1 <u>Environmental Setting</u>

A memorandum was prepared by General Technologies and Solutions (GTS) to describe the Vehicle Miles Traveled (VMT) screening analysis as well as a trip generation study for the Project (Appendix C).

4.17.2 <u>Impact Analysis</u>

a) Would the project conflict with a program, plan, ordinance, or policy addressing the circulation system, including transit, roadways, bicycle and pedestrian facilities?

Less Than Significant Impact. As the Project will serve the current student population and is not intended to increase the student enrollment, the Project will not generate net new trips. The trips on Saturdays, Sundays, as well as weekday PM peak hours are typically associated with sports practice, games, and other after school activities. The District reported that there is an existing joint-use agreement with the City regarding field use where the fields could be rented out for private groups when they are not being used by the school. However, trips for those private events renting the school

facilities are local trips and considered as diverted trips from other sites and not net new trips (that is events that would have taken place in other locations within the City).

The Proposed Project would not change the ongoing use of any existing roadways, bicycle lanes, or pedestrian paths. The Proposed Project includes creation of a new practice facility within the school's boundary, away from existing campus facilities. The Project is not expected to change any of the overall current traffic levels during operation. Although a minor increase in traffic would occur during construction, this impact will be short term and limited in nature. A less than significant impact would occur.

b) Would the project Conflict or be inconsistent with CEQA Guidelines section 15064.3, subdivision (b)?

Less Than Significant Impact. The Proposed Project would be consistent with all City, State, and federal regulations. Pursuant to Senate Bill (SB) 743 technical guidance published by Office of Planning and Research (OPR) and The City of Anaheim Traffic Impact Analysis Guidelines for CEQA (June 2020), there are several screening procedures to potentially streamline project analysis (i.e., provide a presumptive non-impact finding and remove the need for a VMT analysis). Prime among these are local-serving K-12 schools that can be presumed to have a less than significant transportation impact as well as project generating less than 110 daily trips. The Project, at hand, satisfies both criteria being a school with grades 9-12 school as well as generating less that 110 net new trips. Therefore, based on the VMT screening criteria, the Project represents a less than significant transportation impact based on VMT and no further VMT analysis is required.

c) Would the project substantially increase hazards due to a geometric design feature (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment)?

No Impact. The Proposed Project would not change any design features of the existing structures. There would be no change to the existing roadways and would not involve any incompatible uses. Implementation of the Project would not result in an impact.

d) Would the project result in inadequate emergency access?

No Impact. The Proposed Project would occur entirely within the Anaheim High School campus and does not include changes to nearby roadways or emergency access routes. All lanes in the vicinity of the Proposed Project would remain open for emergency use; therefore, implementation of the Proposed Project would not result in an impact associated with emergency access.

4.18 TRIBAL CULTURAL RESOURCES

18.	TRIBAL CULTURAL RESOURCES. Would the project cause a substantial adverse change in the significance of a tribal cultural resource, defined in Public Resources Code section 21074 as either a site, feature, place, cultural landscape that is geographically defined in terms of the size and scope of the landscape, sacred place, or object with cultural value to a California Native American tribe, and that is:	Potentially Significant Impact	Less Than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Listed or eligible for listing in the California Register of Historical Resources, or in a local register of historical resources as defined in Public Resources Code section 5020.1(k), or				
(b)	A resource determined by the lead agency, in its discretion and supported by substantial evidence, to be significant pursuant to criteria set forth in subdivision (c) of Public Resources Code Section 5024.1. In applying the criteria set forth in subdivision (c) of Public Resources Code Section 5024.1, the lead agency shall consider the significance of the resource to a California Native American tribe.				

4.18.1 <u>Impact Analysis</u>

- a) Would the project cause a substantial adverse change in the significance of a tribal cultural resource, defined in Public Resources Code section 21074 as either a site, feature, place, cultural landscape that is geographically defined in terms of the size and scope of the landscape, sacred place, or object with cultural value to a California Native American tribe, and that is Listed or eligible for listing in the California Register of Historical Resources (CRHR), or in a local register of historical resources as defined in Public Resources Code section 5020.1(k)?
- b) Would the project cause a substantial adverse change in the significance of a tribal cultural resource, defined in Public Resources Code section 21074 as either a site, feature, place, cultural landscape that is geographically defined in terms of the size and scope of the landscape, sacred place, or object with cultural value to a California Native American tribe, and that is a resource determined by the lead agency, in its discretion and supported by substantial evidence, to be significant pursuant to criteria set forth in subdivision (c) of Public Resources Code Section 5024.1. In applying the criteria set forth in subdivision (c) of Public Resources Code Section 5024.1, the lead agency shall consider the significance of the resource to a California Native American tribe?
 - a) and b) Less Than Significant Impact. The Proposed Project involves the replacement of the existing track and field, and creation of new practice facilities at Anaheim High School. Ground disturbance of any native soils or soils not previously disturbed will not occur as part of the Proposed Project. Previously, Tribal Cultural Resources have been discovered in creek areas, ridgelines, and vistas (City 2004) however the Proposed Project site does not contain any of these features and it is unlikely inadvertent discovery would occur. Additionally, AB 52 consultation was not required as part of the Project due to the Project resulting in less than significant impacts and the Proposed Project being filed as a Notice of Exemption (NOE). Therefore, the Proposed Project would not result in an impact associated with tribal cultural resources.

4.19 UTILITIES AND SERVICE SYSTEMS

19.	UTILITIES/SERVICE SYSTEMS. Would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Require or result in the relocation or construction of new or expanded water, wastewater treatment or storm water drainage, electric power, natural gas, or telecommunications facilities, the construction or relocation of which could cause significant environmental effects?				
(b)	Have sufficient water supplies available to serve the project and reasonably foreseeable future development during normal, dry and multiple dry years?				
(c)	Result in a determination by the wastewater treatment provider which serves or may serve the project that it has adequate capacity to serve the project's projected demand in addition to the provider's existing commitments?				
(d)	Generate solid waste in excess of State or local standards, or in excess of the capacity of local infrastructure, or otherwise impair the attainment of solid waste reduction goals?			\boxtimes	
(e)	Comply with federal, state, and local management and reduction statutes and regulations related to solid wastes?			\boxtimes	

4.19.1 <u>Impact Analysis</u>

a) Would the project require or result in the relocation or construction of new or expanded water, wastewater treatment or stormwater drainage, electric power, natural gas, or telecommunications facilities, the construction or expansion of which could cause significant environmental effects?

Less Than Significant Impact. Implementation of the Proposed Project would not directly result in an increase in student or staff population. Post construction, the generation of wastewater and water usage on the Proposed Project site would not differ substantially from existing conditions. The demolition of the track and field and creation of the new artificial turf field facility with bleacher seating will decrease the perviousness of the area but would not substantially increase the generation of wastewater. Additionally, the site is already served by Anaheim Public Utilities (APU) and SoCal Gas, and addition of the new practice field would not substantially increase the need for electricity or natural gas onsite. Wastewater treatment is provided by Orange County Sanitation District (OCSD) via wastewater connections from the City of Anaheim. Water supplies to the area are provided by the City of Anaheim which includes both groundwater and water purchased from the Metropolitan Water District. Telecommunications infrastructure would be expanded by use of wifi systems to connect to the existing network at Anaheim High School. Therefore, implementation of the Proposed Project would result in less than significant impacts associated with water and/or wastewater facilities, or other utility facilities.

b) Would the project have sufficient water supplies available to serve the project and reasonably foreseeable future development during normal dry and multiple dry years?

No Impact. The City of Anaheim is responsible for supplying water to the Proposed Project site and for ensuring that the delivered water meets applicable California Department of Health Services standards for drinking water. Currently the turf on the field is watered by water supplies provided by the City of Anaheim. While construction of the Proposed Project would require expansion of water and wastewater infrastructure onsite, no new restrooms are proposed support the existing student and staff population. The Proposed Project would not directly increase the student or staff population, once operational the Proposed Project would support the existing student population and no water would be required for maintenance of the turf on the field. Accordingly, there would be no substantial increase in water supply requirements and would result in a decrease in water demand. In addition, the District would comply with local, regional, and state water conservation policies and would follow standard BMPs, including Title 22 regulations, in order to reduce water consumption. Implementation of the Proposed Project would not result in an impact associated with sufficient water supplies.

c) Would the project result in a determination by the wastewater treatment provider which serves or may serve the project that it has adequate capacity to serve the project's projected demand in addition to the provider's existing commitments?

No Impact. As discussed above, the City of Anaheim is responsible for providing sewer lines that connect to OCSD which treats wastewater within Orange County. No expansion of restrooms is proposed as part of the Proposed Project. The Proposed Project would not result in an increase in demand for wastewater treatment. No impact would occur.

d) Generate solid waste in excess of State or local standards, or in excess of the capacity of local infrastructure, or otherwise impair the attainment of solid waste reduction goals?

Less Than Significant Impact. During construction and operation of the Proposed Project, the District would comply with all city, county, and state solid waste diversion, reduction, and recycling mandates, including compliance with the county-wide Integrated Waste Management Plan (IWMP) (City 2004). Additionally, the Proposed Project would comply with City of Anaheim construction recycling requirements which would require 65 percent of all debris be recycled/diverted (City 2022b). Therefore, implementation of the Proposed Project would result in a less than significant impact associated with waste regulations.

e) Would the project comply with federal, state, and local management and reduction statutes and regulations related to solid waste?

Less than Significant Impact. The Proposed Project would not directly involve an increase in student or staff population and would not result in an operational increase in waste generation; however, construction of the Proposed Project would result in the generation of solid waste including scrap lumber, concrete, residual waste, packaging material, plastics, and vegetation. To ensure optimal diversion of solid waste resources by a project, the District requires its contractors to comply with City regulations regarding recycling or salvage nonhazardous waste materials generated during demolition and/or construction, to foster material recovery and reuse, and to minimize disposal in landfills, and meeting a goal of 65% of debris diversion (City 2022). Furthermore, impacts from construction activities will be short-term and intermittent, and will be mitigated by BMPs and compliance with

existing state solid waste reduction statutes. With the incorporation of these requirements into the Proposed Project, implementation of the Proposed Project would result in a less than significant impact associated with sufficient landfill capacity and would comply with all applicable regulations.

4.20 WILDFIRE

20.	WILDFIRE. If located in or near state responsibility areas or lands classified as very high fire hazard severity zones, would the project:	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Substantially impair an adopted emergency response plan or emergency evacuation plan?			\boxtimes	
(b)	Due to slope, prevailing winds, and other factors, exacerbate wildfire risks, and thereby expose project occupants to, pollutant concentrations from a wildfire or the uncontrolled spread of a wildfire?			\boxtimes	
(c)	Require the installation or maintenance of associated infrastructure (such as roads, fuel breaks, emergency water sources, power lines or other utilities) that may exacerbate fire risk or that may result in temporary or ongoing impacts to the environment?				
(d)	Expose people or structures to significant risks, including downslope or downstream flooding or landslides, as a result of runoff, post-fire slope instability, or drainage changes?			\boxtimes	

4.20.1 <u>Impact Analysis</u>

a) Would the project impair an adopted emergency response plan or emergency evacuation plan?

Less Than Significant Impact. The Proposed Project will not impair an adopted emergency response plan or evacuation plan. The Proposed Project does not include any modifications of main roads that could be designated as emergency evacuation routes, nor does the Project include construction of facilities that would interfere with an emergency response or evacuation plan. Impacts would be less than significant.

b) Would the project, due to slope, prevailing winds, and other factors, exacerbate wildfire risks, and thereby expose project occupants to, pollutant concentrations from a wildfire or the uncontrolled spread of a wildfire?

Less Than Significant Impact. The Proposed Project is not located within a very high fire hazard severity zone and therefore will not exacerbate wildfire risks (CalFire 2022). Impacts would be less than significant.

c) Would the project require the installation or maintenance of associated infrastructure (such as roads, fuel breaks, emergency water sources, power lines, or other utilities) that may exacerbate fire risk or that may result in temporary or ongoing impacts to the environment?

Less Than Significant Impact. The Proposed Project does not include installation of any maintenance associated infrastructures that would exacerbate a fire risk. In addition, the Proposed Project is not located within a very high fire hazard severity zone. Impacts would be less than significant.

d) Would the project expose people or structures to significant risks, including downslope or downstream flooding or landslides, as a result of runoff, post-fire slope instability or drainage changes?

Less Than Significant Impact. The Proposed Project site does not include structures that would be exposed to downstream flooding or landslides. The Project does not include activities which would change the drainage or slope of the Project site. Impacts would, therefore, be less than significant.

4.21 MANDATORY FINDINGS OF SIGNIFICANCE

21.	MANDATORY FINDINGS OF SIGNIFICANCE.	Potentially Significant Impact	Less than Significant With Mitigation Incorporated	Less Than Significant Impact	No Impact
(a)	Does the project have the potential to substantially degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, substantially reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California history or prehistory?				
(b)	Does the project have impacts that are individually limited, but cumulatively considerable? ("Cumulatively considerable" means that the incremental effects of a project are considerable when viewed in connection with the effects of past projects, the effects of other current projects, and the effects of probable future projects?)				
(c)	Does the project have environmental effects which will cause substantial adverse effects on human beings, either directly or indirectly?			\boxtimes	

4.21.1 Impact Analysis

a) Does the project have the potential to substantially degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, substantially reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California history or prehistory?

Less Than Significant Impact. The Project involves the demolition and replacement of the track and field, and creation of a new artificial turf field facility with bleacher seating. The upgrades would not result in the destruction or significant modification of character defining features of the current structures. As discussed in Section 4.3, the Project site is located in an urbanized are that lack native biological habitats. As discussed under Section 4.4, there were no historic resources or known

archaeological or paleontological resources onsite. In addition, if any archaeological resources are encountered during construction activities, the District's Construction BMPs related to cultural resources will be followed. The Proposed Project will not have a significant impact on any fish, wildlife, or habitat. There are no streams, drainage courses, or wetlands located within the Project site vicinity. Therefore, the Proposed Project activities, including the implementation of the project design features noted in the project description, will have a less than significant impact regarding degrading the quality of the environment including biological and cultural resources.

b) Does the project have impacts that are individually limited, but cumulatively considerable? ("Cumulatively considerable" means that the incremental effects of a project are considerable when viewed in connection with the effects of past projects, the effects of other current projects, and the effects of probable future projects?)

Less Than Significant Impact. In combination with other planned and pending development in the area, development of the Proposed Project would have less than significant cumulative impacts. Cumulative impacts for each applicable resource area have been addressed in the individual sections. Based on the preceding discussion, with implementation of the BMPs and Project Design Features included in this Initial Study (IS), and compliance with existing regulations, the Proposed Project would not result in any significant adverse impacts. Impacts for other issue areas would be project specific. There are no other known projects currently in development that would affect the resource areas.

c) Does the project have environmental effects which will cause substantial adverse effects on human beings, either directly or indirectly?

Less Than Significant Impact. Effects to human beings are generally associated with air quality, noise, traffic safety, geology/soils, and hazards/hazardous materials. As discussed in this IS, with standard regulatory compliance the Proposed Project would result in less than significant impacts related to these issues.

SECTION 5.0 – REFERENCES

The following is a list of references used in the preparation of this document.

Caltrans

2022. Scenic Highway Mapper. Accessed August 16, 2022 at:
https://caltrans.maps.arcgis.com/apps/webappviewer/index.html?id=465dfd3d807c46c
c8e8057116f1aacaa

CalFire

2022. FHSV. Accessed August 16, 2022 at: https://egis.fire.ca.gov/FHSZ/

California Air Resources Board (CARB)

2017. 2017 Scoping Plan. Accessed August 22, 2022 at: https://ww2.arb.ca.gov/our-work/programs/ab-32-climate-change-scoping-plan/2017-scoping-plan-documents

California Department of Conservation (DOC)

2022a. Important Farmland Finder. Accessed August 12, 2022 at: https://maps.conservation.ca.gov/DLRP/CIFF/

2022b. 2020/2021 Williamson Act Report. Accessed August 16, 2022 at:
https://www.conservation.ca.gov/dlrp/wa/Documents/stats_reports/2022%20WA%20Status%20Report.pdf

2022c. EQ App. Accessed August 15, 2022 at: https://maps.conservation.ca.gov/cgs/EQZApp/app/

2022d. Mineral Land Classification. Accessed August 12, 2022 at: https://maps.conservation.ca.gov/cgs/informationwarehouse/index.html?map=mlc

2022e. Mines Online. Accessed September 21, 2022 at: https://maps.conservation.ca.gov/mol/index.html

California Department of Toxic Substances Control (DTSC)

2022. Envirostor Database. Accessed August 16, 2022 at: https://www.envirostor.dtsc.ca.gov

City of Anaheim (City)

2004. Final Anaheim General Plan and Zoning Code Update Environmental Impact Report. Accessed September 20, 2022 at:

https://www.anaheim.net/DocumentCenter/View/2207/Cover-and-Table-of-Contents?bidId=

2020. Greenhouse Gas Reduction Plan. Accessed September 20, 2022 at: <a href="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.net/DocumentCenter/View/7987/Greenhouse-Gas-Reduction-Plan?bidId="https://anaheim.punction-plan?bidId="https://anaheim.punction-plan?bidId="https://anaheim.punction-plan?bidId="https://anaheim.punction-plan?bidId="https://anaheim.punction-plan?bidId="https://anaheim.punction-plan?bidId="https://anaheim.punction-plan?bidId="https://anaheim.punction-plan?bidId="https://anaheim.punction-plan?bi

2021a. General Plan Land Use Map. Accessed August 16, 2022 at:
https://www.anaheim.net/DocumentCenter/View/9519/Z0-GeneralPlan 24x55 Map?bidId=

2021b. Zoning Map. Accessed August 16, 2022 at: <a href="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map?bidId="https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map."https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map."https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map."https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map."https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map."https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map."https://www.anaheim.net/DocumentCenter/View/1871/Zoning-Map.

**The Addit Ad

2022. Anaheim Municipal Code 18.18.020. Accessed August 16, 2022 at: https://codelibrary.amlegal.com/codes/anaheim/latest/anaheim_ca/0-0-66483

FEMA

2022. Flood Map Service Center. Accessed August 16, 2022 at:
https://msc.fema.gov/portal/search?AddressQuery=anaheim%20high%20school#search
resultsanchor

Google

2022. Google Earth. Accessed August 17, 2022 at: https://earth.google.com/web/

Orange County Airport Land Use Commission

2008. Land Use Plan for John Wayne Airport. Accessed August 17, 2008 at: https://files.ocair.com/media/2021-02/JWA_AELUP-April-17-2008.pdf?VersionId=cB0byJjdad9OuY5im7Oaj5aWaT1FS.vD

Orange County Water District

2016. 8-1 Basin Alternative Plan. Accessed August 17, 2022 at: https://sgma.water.ca.gov/portal/alternative/print/3

State Water Resources Control Board (SWRCB)

2022. Geotracker Database. Accessed August 16, 2022 at: https://geotracker.waterboards.ca.gov/

USDA

2017. Web Soil Survey. Accessed August 16, 2022 at: https://websoilsurvey.sc.egov.usda.gov/App/WebSoilSurvey.aspx

USFWS.

2022 National Wetlands Inventory. Accessed August 16, 2022 at:
https://fwsprimary.wim.usgs.gov/server/rest/directories/arcgisoutput/Utilities/PrintingTools_GPServer/ags_58c2579b5b51410781255d5b13f6aab1.pdf

Western Regional Climate Center

2016. Anaheim Climate Summary. Accessed August 22, 2022 at: https://wrcc.dri.edu/cgi-bin/cliMAIN.pl?ca0192

Anaheim,CA

Lighting System

Pole / Fixture Summary										
Pole ID	Pole Height	Mtg Height	Fixture Qty	Luminaire Type	Load	Circuit				
F1-F2	90'	90'	11	TLC-LED-1500	15.73 kW	Α				
		90'	2	TLC-LED-400	0.80 kW	В				
		16'	2	TLC-BT-575	1.15 kW	Α				
F3-F4	90'	90'	11	TLC-LED-1500	15.73 kW	Α				
		16'	2	TLC-BT-575	1.15 kW	Α				
4			56		69.12 kW					

Circuit Summ	ary		
Circuit	Description	Load	Fixture Qty
Α	Football	67.52 kW	52
В	Egress	1.6 kW	4

Fixture Type Summary							
Type	Source	Wattage	Lumens	L90	L80	L70	Quantity
TLC-LED-1500	LED 5700K - 75 CRI	1430W	160,000	>120,000	>120,000	>120,000	44
TLC-BT-575	LED 5700K - 75 CRI	575W	52,000	>120,000	>120,000	>120,000	8
TLC-LED-400	LED 5700K - 75 CRI	400W	46,500	>120,000	>120,000	>120,000	4


Light Level Summary

Calculation Grid Summary											
Grid Name	Calculation Metric			Illumination			Circuits	Fixture Qty			
Cha Namo	Guicalation metric	Ave	Min	Max	Max/Min	Ave/Min	Onouno	1 Ixture Qty			
Bleacher	Horizontal	4.70	2.60	6.60	2.54	1.81	В	4			
D Zone	Horizontal	35.9	15.2	51.3	3.38	2.36	Α	52			
Football	Horizontal Illuminance	52.1	47.8	55.7	1.17	1.09	Α	52			
Property Line Spill	Horizontal	0.02	0	0.10	0.00		A,B	56			
Property Line Spill	Max Candela (by Fixture)	1217	2.40	6802	2835.59	507.47	A,B	56			
Property Line Spill	Max Vertical Illuminance Metric	0.05	0	0.32	0.00		A,B	56			
Soccer	Horizontal Illuminance	51.7	47.9	56	1.17	1.08	Α	52			
Track	Horizontal Illuminance	28	8	42.4	5.29	3.50	Α	52			

From Hometown to Professional














Anaheim,CA

GRID SUMMARY

Name: Soccer
Size: 360' x 195'
Spacing: 30.0' x 30.0'
Height: 3.0' above grade

ILLUMINATION S	ILLUMINATION SUMMARY						
MAINTAINED HORIZONTA	MAINTAINED HORIZONTAL FOOTCANDLES						
	Entire Grid						
Guaranteed Average:	50						
Scan Average:	51.7						
Maximum:	56.0						
Minimum:	47.9						
Avg / Min:	1.08						
Guaranteed Max / Min:	2						
Max / Min:	1.17						
UG (adjacent pts):	1.11						
CU:	0.54						
No. of Points:	84						
LUMINAIRE INFORMATIO	N						
Applied Circuits:	A						
No. of Luminaires:	52						
Total Load:	67.52 kW						


Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty document and includes a 0.95 dirt depreciation factor.

Field Measurements: Individual field measurements may vary from computer-calculated predictions and should be taken in accordance with IESNA RP-6-15.

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "Musco Control System Summary" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.





Anaheim,CA

Rame: Football
Size: 360' x 160'
Spacing: 30.0' x 30.0'
Height: 3.0' above grade

ILLUMINATION SUMMARY Entire Grid Guaranteed Average: Scan Average: 52.1 Maximum: 55.7 47.8 Minimum: Avg / Min: 1.09 Guaranteed Max / Min: Max / Min: 1.17 UG (adjacent pts): 1.10 CU: 0.47 No. of Points: 72 Applied Circuits: A No. of Luminaires: 52 Total Load: 67.52 kW

Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty document and includes a 0.95 dirt depreciation factor.

Field Measurements: Individual field measurements may vary from computer-calculated predictions and should be taken in accordance with IESNA RP-6-15.

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "Musco Control System Summary" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.



EQUIPMENT LIST FOR AREAS SHOWN LOCATION 15.5' TLC-BT-575 TLC-LED-1500 TLC-BT-575 F3-F4 15.5' 90' TLC-LED-1500 TOTALS SYCAMORE ST 38 39 39 36 37 38 20 30 40 30 20 50 F4 |< _____i F3 SCALE IN FEET 1:60 to 0,0 reference point(s) \otimes **ENGINEERED DESIGN** By: Vashon Alexander · File #218322A · 31-Mar-22

Anaheim High School Football

Anaheim,CA



ILLUMINATION S	ILLUMINATION SUMMARY						
MAINTAINED HORIZONTA	MAINTAINED HORIZONTAL FOOTCANDLES						
	Entire Grid						
Guaranteed Average:	25						
Scan Average:	28.0						
Maximum:	42.4						
Minimum:	8.0						
Avg / Min:	3.50						
Guaranteed Max / Min:	6						
Max / Min:	5.29						
UG (adjacent pts):	0.00						
CU:	0.17						
No. of Points:	48						
LUMINAIRE INFORMATIO	N						
Applied Circuits:	A						
No. of Luminaires:	52						
Total Load:	67.52 kW						


Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty document and includes a 0.95 dirt depreciation factor.

Field Measurements: Individual field measurements may vary from computer-calculated predictions and should be taken in accordance with IESNA RP-6-15.

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "Musco Control System Summary" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.





Height: 3.0' above grade

Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty document and

from computer-calculated predictions and should be taken


Draw Chart and/or the "Musco Control System Summary"

nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.



EQUIPMENT LIST FOR AREAS SHOWN										
	P	ole			Luminaires	;				
QTY	LOCATION	SIZE	GRADE ELEVATION	MOUNTING HEIGHT	LUMINAIRE Type	QTY / POLE	THIS GRID	OTHER GRIDS		
2	F1-F2	90'	-	90'	TLC-LED-400	2	2	0		
				15.5'	TLC-BT-575	2	0	2		
				90'	TLC-LED-1500	11	0	11		
2	TOTALS 30 4 26									

ENGINEERED DESIGN By: Vashon Alexander · File #218322A · 31-Mar-22



Anaheim High School Football

Anaheim,CA

GRID SUMMARY Name: Bleacher Spacing: 10.0' x 10.0'

ILLUMINATION SUMMARY MAINTAINED HORIZONTAL FOOTCANDLES **Entire Grid** Scan Average: Maximum: Minimum: 2.6 Avg / Min: 1.83 Max / Min: 2.54 UG (adjacent pts): 1.39 CU: 0.08 No. of Points: 42 LUMINAIRE INFORMATION Applied Circuits: B No. of Luminaires: 4 Total Load: 1.6 kW

Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty document and includes a 0.95 dirt depreciation factor.

Field Measurements: Individual field measurements may vary from computer-calculated predictions and should be taken in accordance with IESNA RP-6-15.

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "Musco Control System Summary" for electrical sizing.


Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.



Not to be reproduced in whole or part without the written consent of Musco Sports Lighting, LLC. ©1981, 2022 Musco Sports Lighting, LLC.

to 0,0 reference point(s) \otimes

EQUIPMENT LIST FOR AREAS SHOWN										
	P	ole			Luminaires					
QTY	LOCATION	SIZE	GRADE ELEVATION	MOUNTING HEIGHT	LUMINAIRE Type	QTY / POLE	THIS GRID	OTHER GRIDS		
2	F1-F2	90'	-	90'	TLC-LED-400	2	2	0		
				15.5'	TLC-BT-575	2	2	0		
				90'	TLC-LED-1500	11	11	0		
2	F3-F4	90'	-	15.5'	TLC-BT-575	2	2	0		
				90'	TLC-LED-1500	11	11	0		
4			56	56	0					



SCALE IN FEET 1 : 150 0' 150' 300

Pole location(s) \bigoplus dimensions are relative to 0,0 reference point(s) \bigotimes

Anaheim High School Football

Anaheim,CA

Rame: Spacing: Height: Solution Spacing: Height: Spacing: Height: Spacing: Height: Height: Spacing: Height: He

ILLUMINATION S	UMMARY	
HORIZONTAL FOOTCAND	LES	
	Entire Grid	
Scan Average:	0.015	
Maximum:	0.101	
Minimum:	0.000	
No. of Points:	77	
LUMINAIRE INFORMATIO	N	
Applied Circuits:	A, B	
No. of Luminaires:	56	
Total Load:	69.12 kW	

Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty


Field Measurements: Individual field measurements may vary from computer-calculated predictions and should be taken in accordance with IESNA RP-6-15.

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "**Musco Control System Summary**" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.



EQUIPMENT LIST FOR AREAS SHOWN											
Pole					Luminaires						
QTY	LOCATION	SIZE	GRADE ELEVATION	MOUNTING HEIGHT	LUMINAIRE TYPE	QTY / POLE	THIS GRID	OTHER GRIDS			
2	F1-F2	90'	-	90'	TLC-LED-400	2	2	0			
				15.5'	TLC-BT-575	2	2	0			
				90'	TLC-LED-1500	11	11	0			
2	F3-F4	90'	-	15.5'	TLC-BT-575	2	2	0			
				90'	TLC-LED-1500	11	11	0			
4			56	56	0						



SCALE IN FEET 1 : 150 0' 150' 300'

ENGINEERED DESIGN By: Vashon Alexander · File #218322A · 31-Mar-22

Pole location(s) \bigoplus dimensions are relative to 0,0 reference point(s) \bigotimes

Anaheim High School Football

Anaheim,CA

Rame:
Spacing:
Height:
30.0'
30.0'
30.0'
30.0' above grade

ILLUMINATION SUMMARY

MAX VERTICAL FOOTCANDLES

Entire Grid

Scan Average: 0.048

Maximum: 0.320

Minimum: 0.000

No. of Points: 77

LUMINAIRE INFORMATION

Applied Circuits: A, B

No. of Luminaires: 56

Total Load: 69.12 kW

Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty document.


Field Measurements: Individual field measurements may vary from computer-calculated predictions and should be taken in accordance with IESNA RP-6-15.

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "**Musco Control System Summary**" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.



EQ	EQUIPMENT LIST FOR AREAS SHOWN										
	P	ole			Luminaires						
QTY	LOCATION	SIZE	GRADE ELEVATION	MOUNTING HEIGHT	LUMINAIRE Type	QTY / POLE	THIS GRID	OTHER GRIDS			
2	F1-F2	90'	-	90'	TLC-LED-400	2	2	0			
				15.5'	TLC-BT-575	2	2	0			
				90'	TLC-LED-1500	11	11	0			
2	F3-F4	90'	-	15.5'	TLC-BT-575	2	2	0			
				90'	TLC-LED-1500	11	11	0			
4			TOTALS			56	56	0			



SCALE IN FEET 1 : 150 0' 150' 30

Pole location(s) \bigoplus dimensions are relative to 0,0 reference point(s) \bigotimes

Anaheim High School Football

Anaheim,CA

GRID SUMMARY Name: Spacing: Spacing: Height: 30.0' 30.0' 30.0' above grade

ILLUMINATION SUMMARY

CANDELA (PER FIXTURE)

Entire Grid
1217.409

Maximum:
6802.074
2.399
No. of Points:
77

LUMINAIRE INFORMATION
Applied Circuits:
No. of Luminaires:
Total Load:
69.12 kW

Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty

Field Measurements: Individual field measurements may vary from computer-calculated predictions and should be taken in accordance with IESNA RP-6-15.

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "**Musco Control System Summary**" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.



F2 4

Anaheim High School Football

Anaheim,CA

EQUIPMENT LAYOUT

INCLUDES: · Football

·Soccer · Track

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "Musco Control System Summary" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.

EQUIPMENT LIST FOR AREAS SHOWN									
	Po	ole			Luminaires				
QTY	LOCATION	SIZE	GRADE ELEVATION	MOUNTING HEIGHT	LUMINAIRE Type	QTY / POLE			
2	F1-F2	90'	-	90'	TLC-LED-400	2			
				15.5'	TLC-BT-575	2			
				90'	TLC-LED-1500	11			
2	F3-F4	90'	-	15.5'	TLC-BT-575	2			
				90'	TLC-LED-1500	11			
4			TOTAL	S		56			

SINGLE LUMINAIRE AMPERAGE DRAW CHART											
Ballast Specifications (.90 min power factor)	Line Amperage Per Luminaire (max draw)										
Single Phase Voltage	208	220	240	277 (60)	347	380	480				
TLC-LED-1500	8.5	8.1	7.4	6.4	5.1	4.7	3.7				
TLC-BT-575	3.4	3.2	2.9	2.5	2.0	1.8	1.5				
TLC-LED-400	2.3	2.2	2.0	1.7	1.4	1.3	1.0				



Pole location(s) \bigoplus dimensions are relative to 0,0 reference point(s) \bigotimes



NOISE STUDY

Anaheim High School Track and Field Facility Project

City of Anaheim CA

Prepared For:

Chambers Group, Inc.
5 Hutton Centre Dr, Suite 750
Santa Ana, CA 92707

Prepared by:

Ldn Consulting, Inc.

42428 Chisolm Trail Murrieta, CA 92562 760-473-1253

January 4, 2023

TABLE OF CONTENTS

TAB	LE OF	CONTENTS	II
LIST	OF F	IGURES	
		ABLES	
		Y OF TERMS	
		/E SUMMARY	
		JECT INTRODUCTION	
1.0	1 1	Purpose of this Study	
	1.1	PROJECT LOCATION	
	1.3	Project Description	
2.0	ACO	USTICAL FUNDAMENTALS	6
3.0	SIGN	IIFICANCE THRESHOLDS AND STANDARDS	7
	3.1	OPERATIONAL NOISE	7
	3.2	Construction Noise	
4.0	OPE	RATIONAL NOISE LEVELS	
	4.1	PROPERTY LINE NOISE LEVELS	
	4.2	FINDINGS AND CONCLUSIONS	
5.0		STRUCTION NOISE LEVELS	
	5.1	CONCLUSIONS	.14 15
	1	CONCILISIONS	רו

LIST OF FIGURES

FIGURE 1-A: PROJECT VICINITY MAP	3				
FIGURE 1-B: EXISTING SITE LAYOUT	4				
FIGURE 1-C: DEVELOPMENT PLAN	5				
FIGURE 4-A: NOISE MONITORING RESULTS – HOURLY INTERVALS	9				
FIGURE 4-B: NOISE MONITORING LOCATIONS (FOOTBALL GAME)	0				
FIGURE 4-C: NOISE MONITORING LOCATIONS (BAND PRACTICE)	2				
<u>LIST OF TABLES</u>					
TABLE 4-1: MEASURED NOISE LEVELS (DURING THE ENTIRE GAME)	9				
TABLE 4-2: MEASURED NOISE LEVELS (DURING ENTIRE BAND PRACTICE)	1				
TABLE 4-3: BAND PRACTICE NOISE LEVELS	3				
<u>ATTACHMENTS</u>					
NOISE MEASUREMENT DATA	6				

GLOSSARY OF TERMS

Sound Pressure Level (SPL): a ratio of one sound pressure to a reference pressure (L_{ref}) of 20 μ Pa. Because of the dynamic range of the human ear, the ratio is calculated logarithmically by 20 $\log (L/L_{ref})$.

A-weighted Sound Pressure Level (dBA): Some frequencies of noise are more noticeable than others. To compensate for this fact, different sound frequencies are weighted more.

Minimum Sound Level (L_{min}): Minimum SPL or the lowest SPL measured over the time interval using the A-weighted network and slow time weighting.

Maximum Sound Level (L_{max}): Maximum SPL or the highest SPL measured over the time interval the A-weighted network and slow time weighting.

Equivalent sound level (L_{eq}): the true equivalent sound level measured over the run time. Leq is the A-weighted steady sound level that contains the same total acoustical energy as the actual fluctuating sound level.

Day Night Sound Level (LDN): Representing the Day/Night sound level, this measurement is a 24 –hour average sound level where 10 dB is added to all the readings that occur between 10 pm and 7 am. This is primarily used in community noise regulations where there is a 10 dB "Penalty" for night time noise. Typically LDN's are measured using A weighting.

Community Noise Exposure Level (CNEL): The accumulated exposure to sound measured in a 24-hour sampling interval and artificially boosted during certain hours. For CNEL, samples taken between 7 pm and 10 pm are boosted by 5 dB; samples taken between 10 pm and 7 am are boosted by 10 dB.

Octave Band: An octave band is defined as a frequency band whose upper band-edge frequency is twice the lower band frequency.

Third-Octave Band: A third-octave band is defined as a frequency band whose upper band-edge frequency is 1.26 times the lower band frequency.

Response Time (F,S,I): The response time is a standardized exponential time weighting of the input signal according to fast (F), slow (S) or impulse (I) time response relationships. Time response can be described with a time constant. The time constants for fast, slow and impulse responses are 1.0 seconds, 0.125 seconds and 0.35 milliseconds, respectively.

EXECUTIVE SUMMARY

This noise study has been completed to determine the noise impacts associated with the construction or operational activities from the Anaheim High School Track and Field Improvements Project at the Anaheim High School site in the City of Anaheim. The project consists of the construction and operation of upgraded athletic facilities on the Anaheim High School campus.

The Project consists of replacement of the existing playfield with artificial turf and synthetic all-weather track, new irrigation system, and goalposts, observational press box, field lighting, stormwater drainage improvements in the field by the introduction of rainwater collection chambers/retention basins, tiered bleachers, solar/shade canopies over the bleachers, new wall-mounted scoreboard, path-of-travel improvements including concrete paving, fencing, and landscaping. The upgraded facility will offer enhanced exterior learning opportunities and increased safety for sports and student assemblies.

Operational Noise Levels

Based upon the property line noise levels determined from the football/soccer games and band practices, the high school's operational noise levels currently exceed and would likely continue to exceed the City's property line noise threshold at the surrounding residential uses. Though these events would occur only periodically, they would be expected to generate noise exceeding City standards at the nearest residences.

The noise generated from the on-field activities and crowds as well as the equipment and devices used during the football games and band practices are an integral part of a public educational institution and therefore are exempt from the provisions of Section 6.70.010 of the City of Anaheim's Municipal Code. Pursuant to the City's Municipal Code, the existing and future operational uses are lawfully permitted and therefore no impacts are anticipated.

Construction Noise Levels

Project construction noise levels are considered exempt if activities occur within the hours specified in the City of Anaheim Municipal Code, Section 6.70.010 of 7:00 a.m. and 7:00 p.m. unless approval is obtained from the City Building Official or City Engineer. At the time of this analysis, no Project construction activity is planned outside of the specified hours. Therefore, no impacts are anticipated and no mitigation is required during construction of the Project. Additionally, all equipment should be properly fitted with mufflers and all staging and maintenance should be conducted as far away for the existing residence as possible.

1.0 PROJECT INTRODUCTION

1.1 Purpose of this Study

The purpose of this Noise study is to determine both construction and operational noise levels generated from the project to offsite uses.

1.2 Project Location

The project is located on the Anaheim Unified School District's Anaheim High School Campus at 811 W Lincoln Avenue within the City of Anaheim. Anaheim High School is located in a built-out, urban area and is predominantly surrounded by residential and commercial uses. The campus is bound by W Sycamore Street and residential to the north; N Citron, residential and commercial to the east; N West Street, residential and Anaheim Founders' Park to the west; and Lincoln Avenue, residential, commercial, and vacant land to the south. Lincoln Avenue provides primary access to the school vicinity. Access to the parking lots is provided off of N West Street. A general project vicinity map is shown in Figure 1-A on Page 3 of this report; additionally, a site aerial map of the existing site is shown in Figure 1-B on Page 4 of this report.

1.3 Project Description

Anaheim High School was established in 1896 with the current Art Deco main building, library, Cook Auditorium, gymnasium and shop buildings completed in 1936 after the 1933 Long Beach Earthquake. Additional construction occurred in 1957 and 1972. A new two-story classroom building was completed in 2008 adding 47 standard classrooms and 2 science labs. A child care relocatable was added in 2004 and fifteen relocatable classrooms and restrooms were added in 2008.

Anaheim High School is currently dealing with deteriorating campus buildings as well as athletic facilities. Anaheim Union High School District (District) proposes to improve the existing track & field facility (Project).

The cement bleachers built by the track in 1928 were condemned/demolished in 2019 and must be replaced. The Project consists of replacement of the existing playfield with artificial turf and synthetic all-weather track, new irrigation system, and goalposts, field lighting, stormwater drainage improvements in the field by the introduction of rainwater collection chambers/retention basins, portable tiered bleachers, solar/shade canopies over the bleachers, new wall-mounted scoreboard, path-of-travel improvements including concrete paving, fencing, and landscaping. The upgraded facility will offer enhanced exterior learning opportunities and increased safety for

sports and student assemblies. The development plan is shown in Figure 1-C on Page 5 of this report.

The Project will consist of the following upgrades:

- Replacement of the existing playfield with artificial turf and synthetic track including infiltration systems;
- Replacement of goalposts;
- Installation of field lighting;
- Addition of metal solar shade structures with low voltage systems and solar panels;
- Provision of portable tiered bleachers under the shade structures with lighting and wifi;
- Addition of a new wall-mounted scoreboard:
- Provision of landscaping and access improvements;
- Storm/rain water retention system;
- Flagpole

The project purpose supports the existing school and community population. The proposed athletic facilities component of the project does not include the construction of any new classrooms, and would not increase the student enrollment capacity of the campus. Furthermore, the project site is located in a fully developed urban area. Consequently, the project would not induce additional growth. It should be noted that an existing joint-use agreement with the City of Anaheim allows the fields to be rented out for private groups when not being used by the school.

W Malvern Ave Alta Vista St Placentia vealth Ave Fullerton E Commonwealth Ave D E Crowther Ave W Valenc/a Dr W Valencia Dr Orangethorpe Ave Orangethorpe Ave E Orangethorpe Ave **(3)** Riverside Fwy E Romneya Dr NORTHEAST NORTHWEST La Palma Ave ANAHEIM ANAHEIM Anaheim EBroadway Olive E Santa Ana St Lincoln Ave 5 roject Site W Ball Rd W Ball Rd SOUTHEAST ANAHEIM Taft Ave **HERMOSA** VILLAGE E Cerritos Ave E Katella Ave SOUTHWEST ANAHEIM PLATINUM W Katella Ave TRIANGLE E Collins Ave CONVENTION CENTER S Orangewood Ave Walnut Ave E Walnut Ave ANAHEIM Chapman Ave RESORT W Chapman Ave Orange OLD TOWNE Lampson Ave 5 ₩ La Veta Ave Garden Grove S Trask Ave W Santa Clara Ave (22) W 17th St 17th St Westminster Ave Mazard Ave Z Hazard Ave ARTESIA PILAR

Figure 1-A: Project Vicinity Map

Source: Google Maps, 2022

Figure 1-B: Existing Site Layout

Source: Nearmap, 2022

H AREA OF WORK (E) TURE **NEW TRACK & FIELD** 4 BLDG 13 (E) ACCESSIBLE D.F. PER — A#04-115830 POOL BLDG: BLDG 14 GYMNASIUM AF45001 (1985) A04-105015 A04-115830 (E) TURF BLDG 12 SHOP A13864 (1855) A04-105515 DAYCARE CLASSROOM 404-100949 (E) ACCESSIBLE POT PER A∯04-110401, 04-11039 & 04-109514 BLDG 5 CITHON ST. BLDG 8 BLDG 15 BLDG 5 CLASSROOM A13884 (1955) A56288 (1992) A54-100515 BLDG 7-SCIENCE M13865 (1965) M194-100515 · · · () • D) BLDG 4 ART A/34792 (1972) A/04-105815 BLDG 1 BLDG 3-MUSIC M34792 (1994) 404-100516 (E) TURF (E) TURF LINCOLN AVE.

Figure 1-C: Development Plan

2.0 ACOUSTICAL FUNDAMENTALS

Noise is defined as unwanted or annoying sound which interferes with or disrupts normal activities. Exposure to high noise levels has been demonstrated to cause hearing loss. The individual human response to environmental noise is based on the sensitivity of that individual, the type of noise that occurs and when the noise occurs.

Sound is measured on a logarithmic scale consisting of sound pressure levels known as a decibel (dB). The sounds heard by humans typically do not consist of a single frequency but of a broadband of frequencies having different sound pressure levels. The method for evaluating all the frequencies of the sound is to apply an A-weighting to reflect how the human ear responds to the different sound levels at different frequencies. The A-weighted sound level adequately describes the instantaneous noise whereas the equivalent sound level depicted as Leq represents a steady sound level containing the same total acoustical energy as the actual fluctuating sound level over a given time interval.

The Community Noise Equivalent Level (CNEL) is the 24 hour A-weighted average for sound, with corrections for evening and nighttime hours. The corrections require an addition of 5 decibels to sound levels in the evening hours between 7 p.m. and 10 p.m. and an addition of 10 decibels to sound levels at nighttime hours between 10 p.m. and 7 a.m. These additions are made to account for the increased sensitivity during the evening and nighttime hours when sound appears louder.

A vehicles noise level is from a combination of the noise produced by the engine, exhaust and tires. The cumulative traffic noise levels along a roadway segment are based on three primary factors: the amount of traffic, the travel speed of the traffic, and the vehicle mix ratio or number of medium and heavy trucks. The intensity of traffic noise is increased by higher traffic volumes, greater speeds and increased number of trucks.

Because mobile/traffic noise levels are calculated on a logarithmic scale, a doubling of the traffic noise or acoustical energy results in a noise level increase of 3 dBA. Therefore the doubling of the traffic volume, without changing the vehicle speeds or mix ratio, results in a noise increase of 3 dBA. Mobile noise levels radiant in an almost oblique fashion from the source and drop off at a rate of 3 dBA for each doubling of distance under hard site conditions and at a rate of 4.5 dBA for soft site conditions. Hard site conditions consist of concrete, asphalt and hard pack dirt while soft site conditions exist in areas having slight grade changes, landscaped areas and vegetation. On the other hand, fixed/point sources radiate outward uniformly as it travels away from the source. Their sound levels attenuate or drop off at a rate of 6 dBA for each doubling of distance.

3.0 SIGNIFICANCE THRESHOLDS AND STANDARDS

3.1 Operational Noise

Stationary sources of noise are governed under the local Municipal Code, Chapter 6.70, Sound Pressure Levels. Section 6.70.010 simply states that "No person shall, within the City, create any sound, radiated for extended periods from any premises which produces a sound pressure level at any point on the property in excess of sixty decibels (Re 0.0002 Microbar) read on the A-scale of a sound level meter. Readings shall be taken in accordance with the instrument manufacturer's instructions, using the slowest meter response."

Exceptions

Section 6.72.040 states that the following uses of sound-amplifying equipment and activities shall be exempt from the provisions of this chapter: "Equipment and devices used as an integral part of any public or private institutional use lawfully permitted pursuant to this Code, including but not limited to, public and private educational institutions, and places of religious worship."

3.2 Construction Noise

The City recognizes that construction noise is difficult to control and restricts allowable hours for this intrusion. Section 6.70.010 of the City Municipal Code states that the sound created by construction or building repair of any premises within the City shall be exempt from the applications of the chapter between the hours of 7:00 a.m. and 7:00 p.m. Compliance with these provisions is mandatory and as such, does not constitute mitigation under CEQA. Still, construction, even when restricted to within these hours, presents a nuisance value when conducted in proximity to sensitive receptors and the impact is considered as potentially significant.

4.0 OPERATIONAL NOISE LEVELS

This section examines the potential operational noise source levels associated with the operation of the project. Noise from a fixed or point source drops off at a rate of 6 dBA for each doubling of distance. Which means a noise level of 70 dBA at 5 feet would be 64 dBA at 10 feet and 58 dBA at 20 feet. Property lines surrounding the project site are predominantly residential therefore a 60 dBA hourly noise standard would typically be applied per the City's Municipal Code. However, the school operations would be exempt under Chapter 6.70 of the Municipal Code.

4.1 Property Line Noise Levels

Events conducted within the athletic field currently include football, soccer, track and field, and band practices. The highest use of the field would be from evening football games. These events are existing and would occur only periodically.

Football Games


Anaheim High School did not have any home football games scheduled after October 14th but played an away game against Western High School. Western High School is an Anaheim Unified School District school located within an urbanized area and surrounded by residential uses. The football game was held at Handel Stadium, a stadium used for District-wide events located at the northwestern portion of the campus. To determine the noise levels anticipated during an evening football game, noise measurements of a football game were conducted on Friday, October 28th between the hours of 6 pm and 9 pm at Western High School. The measurements were taken in the evening hours when community noise levels are lower due to lower traffic volumes on adjacent roadways.

The noise levels during the measurements included people arriving to the game, crowds cheering, the high school band playing between plays and during intermissions along with the public announcements (PA) system and then people leaving after the game. The primary noise levels consisted of crowds cheering, the high school band playing along with the public announcements (PA) system. The results of the noise level measurements are presented in Table 4-1. The average noise levels during the entire measurements were found to be roughly 58-65 dBA Leq as seen in Table 4-1. The hourly noise levels ranged from 51-68 dBA Leq as can be seen graphically in Figure 4-A below.

Table 4-1: Measured Noise Levels (during the entire game)

Location	Primary Noise Source	Date and Time	Average Noise Levels (dBA Leq)
M1			58.5
M2	Football Game Activities	October 28, 2022	65.4
М3	(combination of PA System, Band playing and Crowd cheering)	6:00-9:00 p.m.	62.8
M4			59.5
Source: Western High Sc	hool Football Game.		

Figure 4-A: Noise Monitoring Results – Hourly Intervals



The noise measurements were taken using Larson-Davis Spark 706 Type 2 sound level meters, programmed, in "slow" mode, to record noise levels in "A" weighted form. The sound level meters were equipped with a windscreen during all measurements. The sound level meters were calibrated before and after the monitoring using a Larson-Davis calibrator, Model CAL 150. The noise monitoring locations are provided in Figure 4-B.




Figure 4-B: Noise Monitoring Locations (Football Game)

Band Practice

To determine the noise levels anticipated during a band event, noise measurements of a band practice were conducted on Wednesday, November 16th between 3:30 pm and 4:30 pm at Anaheim High School. Practice was held at the existing football field at the site of the proposed athletic field upgrades. The practice included approximately 80 members of the school's marching band. The measurements were taken during the afternoon after normal school hours. The results of the noise level measurements are presented in Table 4-2. The noise levels measured during the band practice were found to be roughly 71-79 dBA Leq, in close proximity of the band within the field, during the entire practice.

Table 4-2: Measured Noise Levels (during entire band practice)

Location	Primary Noise Source	Date and Time	Average Noise Levels (dBA Leq)
M1			78.9
M2	Band Practice	November 16, 2022 3:30-4:30 p.m.	73.7
М3			71.1
M4			72.2
Source: Anaheim High Scho	ool Band Practice.	l l	

The noise measurements were taken using Larson-Davis Spark 706 Type 2 sound level meters, programmed, in "slow" mode, to record noise levels in "A" weighted form. The sound level meters were equipped with a windscreen during all measurements. The sound level meters were calibrated before and after the monitoring using a Larson-Davis calibrator, Model CAL 150. The noise monitoring locations are provided in Figure 4-C.




Figure 4-C: Noise Monitoring Locations (Band Practice)

4.2 Findings and Conclusions

Findings

Based on the noise measurements taken during an evening football game at Western High School, it is possible to apply the noise levels to the Anaheim High School project site. It was determined that noise levels could be as high as 68 dBA approximately 200-feet from the playing field. The nearest residences at the Anaheim High School are located approximately 300-feet to the north across W Sycamore Avenue and east across N Citron Street. The increased distance would reduce the noise levels at the existing residences by 3.5 dBA and therefore would not be enough to meet

the City's noise threshold of 60 dBA. As stated above, these activities are existing and are exempt from the provisions of Section 6.70.010 of the City of Anaheim's Municipal Code.

Based on the noise measurements taken during band practice, it is possible to determine the noise levels at the nearest residences. The noise levels from the band practice along with the calculated hourly noise levels based upon the distances are shown below in Table 4-3 for the residential properties to the west, north, and east. Residential properties to the south of Lincoln Avenue are located over 800-feet away and will be shielded by existing buildings.

Table 4-3: Band Practice Noise Levels

Property Line	Reference Noise Level (dBA)	Reference Distance (Feet)	Minimum Distance to Property Line (Feet)	Noise Reduction due to distance (dBA)	Resultant Noise Level (dBA Leq)
West	78.9	75	620	-18.3	60.6
North	73.7	150	350	-7.4	66.3
East	71.1	75	380	-14.1	57.0

Based upon the property line noise levels determined from the football games and band practices, the high school's operational noise levels currently exceed and would likely continue to exceed the City's property line noise threshold at the surrounding residential uses. Though these events would occur only periodically, they would be expected to generate noise exceeding City standards at the nearest residences. As stated above, these activities are existing and are exempt from the provisions of Section 6.70.010 of the City of Anaheim's Municipal Code.

Conclusions

The equipment and devices used during the football games and band practices are an integral part of a public educational institution and therefore are exempt from the provisions of Section 6.70.010 of the City of Anaheim's Municipal Code. Pursuant to the City's Municipal Code, the existing and future operational uses are lawfully permitted.

5.0 CONSTRUCTION NOISE LEVELS

Construction noise represents a short-term impact on the ambient noise levels. Noise generated by construction equipment includes haul trucks, water trucks, graders, dozers, loaders and scrapers can reach relatively high levels. Grading activities typically represent one of the highest potential sources for noise impacts. The most effective method of controlling construction noise is through local control of construction hours and by limiting the hours of construction to normal weekday working hours. Division 4 of Article 9.5 of the City of San Diego Municipal Code (SDMC) addresses the limits of disturbing or offensive construction noise. The SDMC states that, with the exception of an emergency, it is unlawful to conduct any construction activity as to cause, at or beyond the property lines of any property zoned residential, an average sound level greater than 75 decibels during the 12-hour period from 7:00 a.m. to 7:00 p.m.

The U.S. Environmental Protection Agency (U.S. EPA) has compiled data regarding the noise generating characteristics of specific types of construction equipment. Noise levels generated by heavy construction equipment can range from 60 dBA to in excess of 100 dBA when measured at 50 feet. However, these noise levels diminish rapidly with distance from the construction site at a rate of approximately 6 dBA per doubling of distance. For example, a noise level of 75 dBA measured at 50 feet from the noise source to the receptor would be reduced to 69 dBA at 100 feet from the source to the receptor and reduced to 63 dBA at 200 feet from the source.

The project site is generally flat with existing grades already near proposed grades. Therefore, no significant grading activities are anticipated. Grading activities would be limited to minor grade adjustments required for the preparation of the proposed surface improvements.

5.1 Construction Noise Levels

The Project is expected to occur over a 12 month period, approximately between the 4th Quarter of 2022 and the 4th Quarter of 2023. Construction activities will take place between the hours of 7:00 a.m. to 4:00 p.m. on Monday through Friday and 8:00 a.m. to 5:00 p.m. on Saturday. The Project was approved by the District's Board of Trustees on July 14, 2022, project construction activities could begin in the 4th Quarter of 2022. The construction would begin after the Division of the State Architect (DSA) approval of plans and specifications is obtained and the contract for construction is awarded.

The existing concrete bleachers were demolished in 2019 making room for the new bleachers and field amenities. The existing turf field will be excavated for installation of the new artificial turf and synthetic all-weather track.

Construction equipment to be used during construction of the Project upgrades include the following items: loaders, pick-up trucks, backhoe, water truck, asphalt roller, excavators, grader, scraper, roller, paving machine, skidsteer, reachfork, drill rig, utility truck, crew truck, dump truck and transfer trailer.

5.2 Conclusions

Project construction noise levels are considered exempt if activities occur within the hours specified in the City of Anaheim Municipal Code, Section 6.70.010 of 7:00 a.m. and 7:00 p.m. unless approval is obtained from the City Building Official or City Engineer. At the time of this analysis, no Project construction activity is planned outside of the specified hours. Therefore, no impacts are anticipated and no mitigation is required during construction of the Project. Additionally, all equipment should be properly fitted with mufflers and all staging and maintenance should be conducted as far away for the existing residence as possible.

ATTACHMENT A

NOISE MEASUREMENT DATA

Summary Report: Western High School User: LDN Location: North


Job Description: Football Game

02996	Start:	28 Oct 2022 18:18:11
706	Stop:	28 Oct 2022 21:09:11
A Weighting	Run Time:	02:51:00
Unweighted	Pre Calibration:	None
Slow	Post Calibration:	29 Oct 2022 20:39 13.50 dBA
30 dB	Deviation:	-
60 seconds	Periods:	171
	706 A Weighting Unweighted Slow 30 dB	706 Stop: A Weighting Run Time: Unweighted Pre Calibration: Slow Post Calibration: 30 dB Deviation:

Exchange Rate:	3		Dose:	0.0	%
Threshold:	30.0 c	dBA	Projected Dose:	0.1	%
Criterion Level:	90.0 c	dBA	Leq:	58.5	dBA
Criterion Duration:	8.0 h	nours	TWA:	58.5	dBA
			TWA (8):	55.1	dBA
L10:	60.5 c	dBA	Lmax:	84.6	dBA
L30:	56.5 c	dBA	Lpeak (max):	120.9	dB
L50:	53.5 c	dBA	SEA:	120.9	dB
L70:	51.0 c	dBA	Lep (8):	55.1	dBA
L90:	48.0 c	dBA	SE:	0.0	Pa²hr

Note:		

Time History



Summary Report: Western High School User: LDN Location: West


Job Description: Football Game

17806	Start:	28 Oct 2022 17:21:34
706RC	Stop:	28 Oct 2022 21:04:34
A Weighting	Run Time:	03:43:00
Unweighted	Pre Calibration:	None
Slow	Post Calibration:	29 Oct 2022 14:15 13.60 dBA
30 dB	Deviation:	-
60 seconds	Periods:	223
	706RC A Weighting Unweighted Slow 30 dB	706RC Stop: A Weighting Run Time: Unweighted Pre Calibration: Slow Post Calibration: 30 dB Deviation:

Exchange Rate:	3	Dose:	0.2 %
Threshold:	30.0 dBA	Projected Dose:	0.3 %
Criterion Level:	90.0 dBA	Leq:	65.4 dBA
Criterion Duration:	8.0 hours	TWA:	65.4 dBA
		TWA (8):	62.0 dBA
L10:	68.0 dBA	Lmax:	86.9 dBA
L30:	63.5 dBA	Lpeak (max):	116.7 dB
L50:	60.5 dBA	SEA:	dB
L70:	58.0 dBA	Lep (8):	62.0 dBA
L90:	55.0 dBA	SE:	0.0 Pa²hr

Note:		

Time History



Summary Report: Western High School User: LDN Location: South


Job Description: Football Game

Serial Number:	02996	Start:	28 Oct 2022 18:18:11
Model Number:	706	Stop:	28 Oct 2022 21:09:11
RMS Weighting:	A Weighting	Run Time:	02:51:00
Peak Weighting:	Unweighted	Pre Calibration:	None
Detector:	Slow	Post Calibration:	29 Oct 2022 20:39 13.50 dBA
Gain:	30 dB	Deviation:	-
Sample Period:	60 seconds	Periods:	171

Exchange Rate:	3		Dose:	0.1	%
Threshold:	30.0 d	IBA	Projected Dose:	0.2	%
Criterion Level:	90.0 d	IBA	Leq:	62.8	dBA
Criterion Duration:	8.0 h	ours	TWA:	62.8	dBA
			TWA (8):	58.3	dBA
L10:	67.0 d	IBA	Lmax:	82.5	dBA
L30:	60.0 d	IBA	Lpeak (max):	112.2	dB
L50:	56.0 d	IBA	SEA:		dB
L70:	53.5 d	IBA	Lep (8):	58.3	dBA
L90:	51.0 d	IBA	SE:	0.0	Pa²hr

Note:			

Time History



Summary Report: Western High School User: LDN Location: East


Job Description: Football Game

Serial Number:	02998	Start:	28 Oct 2022 17:28:11
Model Number:	706	Stop:	28 Oct 2022 21:14:11
RMS Weighting:	A Weighting	Run Time:	03:46:00
Peak Weighting:	Unweighted	Pre Calibration:	None
Detector:	Slow	Post Calibration:	29 Oct 2022 21:25 13.10 dBA
Gain:	30 dB	Deviation:	-
Sample Period:	60 seconds	Periods:	226

Exchange Rate:	3		Dose:	0.0	%
Threshold:	30.0	dBA	Projected Dose:	0.1	%
Criterion Level:	90.0	dBA	Leq:	59.5	dBA
Criterion Duration:	8.0	hours	TWA:	59.5	dBA
			TWA (8):	56.3	dBA
L10:	60.5	dBA	Lmax:	95.3	dBA
L30:	56.0	dBA	Lpeak (max):	122.1	dB
L50:	53.5	dBA	SEA:	122.1	dB
L70:	51.5	dBA	Lep (8):	56.3	dBA
L90:	49.5	dBA	SE:	0.0	Pa²hr

Note:			

Time History



Summary Report: Anaheim High School User: LDN Location: West


Job Description: Band Practice

Serial Number:	17806	Start:	16 Nov 2022 15:43:27
Model Number:	706RC	Stop:	16 Nov 2022 16:17:27
RMS Weighting:	A Weighting	Run Time:	00:34:00
Peak Weighting:	Unweighted	Pre Calibration:	16 Nov 2022 10:43 12.80 dBA
Detector:	Slow	Post Calibration:	5 Dec 2022 08:48 12.80 dBA
Gain:	30 dB	Deviation:	0.0 dB
Sample Period:	60 seconds	Periods:	34

Exchange Rate:	3		Dose:	887.8	%
Threshold:	0.0	dBA	Projected Dose:	12533.8	%
Criterion Level:	60.0	dBA	Leq:	81.0	dBA
Criterion Duration:	8.0	hours	TWA:	81.0	dBA
			TWA (8):	69.5	dBA
L10:	83.0	dBA	Lmax:	102.2	dBA
L30:	76.5	dBA	Lpeak (max):	122.5	dB
L50:	73.0	dBA	SEA:	122.5	dB
L70:	65.5	dBA	Lep (8):	69.5	dBA
L90:	56.5	dBA	SE:	0.0	Pa²hr

Note:

Time History



Summary Report: Anaheim High School User: LDN Location: North

Job Description: Band Practice

Serial Number:	02998	Start:	16 Nov 2022 15:46:54
Model Number:	706	Stop:	16 Nov 2022 16:20:54
RMS Weighting:	A Weighting	Run Time:	00:34:00
Peak Weighting:	Unweighted	Pre Calibration:	10 Nov 2022 09:25 13.30 dBA
Detector:	Slow	Post Calibration:	5 Dec 2022 08:33 13.10 dBA
Gain:	30 dB	Deviation:	-0.2 dB
Sample Period:	60 seconds	Periods:	34

Exchange Rate:	3		Dose:	165.5	%
Threshold:	0.0	dBA	Projected Dose:	2336.5	%
Criterion Level:	60.0	dBA	Leq:	73.7	dBA
Criterion Duration:	8.0	hours	TWA:	73.7	dBA
			TWA (8):	62.2	dBA
L10:	78.0	dBA	Lmax:	82.5	dBA
L30:	75.0	dBA	Lpeak (max):	122.3	dB
L50:	70.0	dBA	SEA:	122.3	dB
L70:	60.0	dBA	Lep (8):	62.2	dBA
L90:	54.5	dBA	SE:	0.0	Pa²hr

Note:

Time History



Summary Report: Anaheim High School User: LDN

Location: East

Job Description: Band Practice

Serial Number:	02995	Start:	16 Nov 2022 15:35:36
Model Number:	706	Stop:	16 Nov 2022 16:25:36
RMS Weighting:	A Weighting	Run Time:	00:50:00
Peak Weighting:	Unweighted	Pre Calibration:	16 Nov 2022 10:50 12.80 dBA
Detector:	Slow	Post Calibration:	5 Dec 2022 08:28 12.90 dBA
Gain:	30 dB	Deviation:	0.1 dB
Sample Period:	60 seconds	Periods:	50

Exchange Rate:	3		Dose:	168.8	%
Threshold:	0.0	dBA	Projected Dose:	1620.3	%
Criterion Level:	60.0	dBA	Leq:	72.1	dBA
Criterion Duration:	8.0	hours	TWA:	72.1	dBA
			TWA (8):	62.3	dBA
L10:	76.5	dBA	Lmax:	82.7	dBA
L30:	73.5	dBA	Lpeak (max):	112.9	dB
L50:	63.5	dBA	SEA:		dB
L70:	52.5	dBA	Lep (8):	62.3	dBA
L90:	49.5	dBA	SE:	0.0	Pa²hr

Note:

Time History



Summary Report: Anaheim High School

User: LDN Location: South


Job Description: Band Practice

Serial Number:	02996	Start:	16 Nov 2022 15:33:15
Model Number:	706	Stop:	16 Nov 2022 16:23:15
RMS Weighting:	A Weighting	Run Time:	00:50:00
Peak Weighting:	Unweighted	Pre Calibration:	16 Nov 2022 10:48 13.20 dBA
Detector:	Slow	Post Calibration:	5 Dec 2022 08:30 13.30 dBA
Gain:	30 dB	Deviation:	0.1 dB
Sample Period:	60 seconds	Periods:	50

Exchange Rate:	3		Dose:	746.7	%
Threshold:	0.0	dBA	Projected Dose:	7168.3	%
Criterion Level:	60.0	dBA	Leq:	78.6	dBA
Criterion Duration:	8.0	hours	TWA:	78.6	dBA
			TWA (8):	68.7	dBA
L10:	83.0	dBA	Lmax:	97.3	dBA
L30:	77.0	dBA	Lpeak (max):	122.9	dB
L50:	70.5	dBA	SEA:	126.2	dB
L70:	58.5	dBA	Lep (8):	68.7	dBA
L90:	51.5	dBA	SE:	0.0	Pa²hr

Note:		

Time History





MEMORANDUM

Date:	January 2, 2023	GTS : 220509
То:	Eunice Bagwan, Chambers Group	
From:	Rawad Hani, GTS	
Subject:	Anaheim High School Field Project Vehicle Miles Traveled (VMT) Analysis and Trip Generation	

This memorandum describes the vehicle miles traveled (VMT) screening analysis for the proposed Anaheim High School Field Project (Project), in Anaheim, CA.

The Project will upgrade the school's athletic fields located at 811 W Lincoln Avenue in the City of Anaheim to offer enhanced exterior learning opportunities and increased safety for sports and student assemblies.

The VMT analysis evaluated the project using the City of Anaheim VMT guidelines outlined in the June 2020 *City of Anaheim Traffic Impact Analysis Guidelines for California Environmental Quality Act* (Guidelines).

Analysis Background

On December 28, 2018, the California Office of Administrative Law cleared the revised California Environmental Quality Act (CEQA) guidelines for use. Among the changes to the guidelines was removal of vehicle delay and level of service from consideration under CEQA. With the adopted guidelines, transportation impacts are to be evaluated based on a project's effect on vehicle miles traveled (VMT).

Project Background

Anaheim High School is located at 811 W Lincoln Avenue, Anaheim, CA 92805 and is situated in a residential area surrounded by housing on all sides and commercial establishments on the south side. The school accommodates students from Grade 9 -12.

The Project consists of replacing the existing playfield and track with artificial turf and synthetic all-weather track, new irrigation system, and goalposts, observational press box, field lighting, stormwater drainage improvements in the field by the introduction of rainwater collection chambers/retention basins, portable tiered bleachers, solar/shade canopies over the bleachers, new wall-mounted scoreboard, path-of-travel improvements including concrete paving, fencing, and landscaping. The upgraded facility will offer enhanced exterior learning opportunities and increased safety for sports and student assemblies.

The project will serve the current student population and is not intended to increase the student enrollment.



Trip Generation

The Institute of Transportation Engineers (ITE) *Trip Generation Manual (most recent edition is 11th Edition, 2021)* is typically utilized to estimate daily project trip generation. The Trip Generation Manual does not include data for school practice fields as these uses are typically incorporated in the trip generation rates for the school.

The daily trip generation for Anaheim High School is presented in Table 1 for weekday and weekend. The number of students of 3,099 is used for these calculations as per the California Department of Education enrollment figures.

Land Use	ITE Land Use Code	Units -	Weekday		Saturday ²	
Land USE			Rate	Estimated Trips	Rate	Estimated Trips
High School	525	Students ¹	1.94 per Student	6,013	0.68 per Student	2,108
Net New Trips				0		0

^{1.} Enrollment is 3,099 per California Department of Education (https://www.cde.ca.gov/sdprofile/details.aspx?cds=30664313038239)

As the Project will serve the current student population and is not intended to increase the student enrollment, the project will not generate net new trips. The trips on Saturdays, Sundays, as well as weekday PM peak hours are typically associated with sports practice, games, and other after school activities.

The district reported that there is an existing joint-use agreement with the City regarding field use where the fields could be rented out for private groups when they are not being used by the school. However, trips for those private events renting the school facilities are local trips and considered as diverted trips from other sites and not net new trips (that is events that would have taken place in other locations within the City).

VMT Screening Analysis

Pursuant to SB 743 technical guidance published by OPR and *The City of Anaheim Traffic Impact Analysis Guidelines for California Environmental Quality Act (June 2020)*, there are several screening procedures to potentially streamline project analysis (i.e., provide a presumptive non-impact finding and remove the need for a VMT analysis). Prime among these are local-serving K-12 schools that can be presumed to have a less than significant transportation impact as well as project generating less than 110 daily trips.

The Project at hand satisfies both criteria being a school with grades 9-12 school as well as generating less than 110 net new trips.

Therefore, based on the VMT screening criteria, the proposed Project represents a less than significant transportation impact based on VMT and no further VMT analysis is required.

^{2.} Saturday Rates are reported as they are typically higher (more conservative) than Sundays. Sunday rate is 0.25 versus 0.68 for Saturday

Conclusion

Based on the VMT analysis as shown above, the project doesn't constitute a significant impact for VMT.