# **Appendix J**

Stormwater Compliance Study



# STORMWATER COMPLIANCE STUDY

FOR PARCEL MAP: 4013

### (FOR PLANNING AND ZONING PERMIT ###)

1300 Lawrence Drive Thousand Oaks, CA 91320

### **Prepared for:**

Cruzan 9171 Wilshire Blvd Beverly Hills, CA 90210

Project No: LAX20-0077

Prepared by: 08-18-2022
Signature Date

Engineer: Keith Malloy Registration No. C84456

### **Ware Malcomb**

915 Wilshire Blvd, Suite 2150 Los Angeles, CA 90017 Phone: (310) 903-4019

Prepare Date: August 18, 2022 Revised:



architecture | planning | interiors | branding | civil

### **Table of Contents**

I.	Project Description	3
II.	References	3
III.	Objectives	
IV.	Procedure	3
٧.	Stormwater Quality	4
VI.	Conclusions	6
Δ	Appendix A – Vicinity Map	
Δ	Appendix B – BMP Information	
Δ	Appendix C – Geotechnical Report and Percolation Test	
Δ	Appendix D – LID and Grading Plan	
Δ	Appendix E – Soil Map	
Δ	Appendix F – Environmental Sensitive Area Map	
Δ	Appendix G -VenturaTC Calculations	



### I. Project Description

### **Background**

The project is located at 1300 Lawrence Drive, Thousand Oaks, CA. The total project area is 6.64 +/-acres.

The site is bounded by Corporate Center Drive to the north, commercial property to the east and south, and Lawrence Drive to the west. The site is currently an existing parking lot. See Appendix A for the Vicinity map and legal description of the property.

The proposed project will demolish the existing parking lot, construct new industrial building, access roadway and parking lot, landscaped areas, and hardscape improvements.

### **Existing Drainage Condition**

Currently, there are no water quality treatment devices on the property.

The current parking lot drains into concrete gutters spread throughout the site that flow into two catch basins located at the northwest corner. The flows are then conveyed into a public catch basin at the southeast corner of Corporate Center Drive and Lawrence Drive via an 18" storm drain pipe. There is an approximately 4' wide landscaping area along the eastern property line that surface flows into a concrete channel located on the adjacent property. The concrete channel flows northeasterly towards Corporate Center Drive where it discharges through a parkway drain. Along the Northeast and Northwest property lines, there are landscaped slope along the site perimeter. This landscaped area sheet flows into both Corporate Center Drive and Lawrence Drive.

The project site is underlain by Diablo Clay (Soil Type 1), Rincon silty clay loam (Soil Type 2), and Vina loam (Soil Type 5). See Appendix E for soil map. The site is not located near environmentally sensitive habitat areas. See Appendix F for environmental sensitive habitat areas map.

### **Proposed Drainage Condition**

For the proposed condition, the overall drainage pattern will remain unchanged. Stormwater will drain into proposed onsite gutters and be collected by series of onsite catch basins. The stormwater will then be treated and discharged into an existing 18" storm drain line at the northwestern portion of the site. The existing 18" storm drain line joins the public storm drain line by connecting into the catch basin at the corner of Lawrence Drive and Corporate Center Drive.

### II. References

- a. "Ventura County Design Hydrology Manual," Ventura County Watershed Protection District, Updated 2017.
- b. "Ventura County Technical Guidance Manual for Stormwater Quality Control Measures," Ventura Countywide Stormwater Quality Management Program, Updated June 2018.

### III. Objectives

The purpose of this stormwater compliance study is to discuss the long-term post-construction Best Management Practices (BMPs) that will be implemented to mitigate the impacts of development.

### IV. Procedure

Per Ventura Technical Guidance Manual, section 1.5, the project falls within the following listed new development project conditions: industrial parks with 10,000 square feet or more of total altered surface area and parking lots with 5,000 square feet or more of impervious surface area, or with 25 or more



architecture | planning | interiors | branding | civil

parking spaces. As a result, the project requires post-construction storm water management control measures.

Soil properties were identified through field investigation to determine available treatment methods, i.e., if infiltration is feasible. The Stormwater Quality Design Flow was calculated by following the technical guidance manual. BMPs were sized based off the calculated treatment flows. Part V goes into more technical detail.

### V. Stormwater Quality

Since the proposed project will disturb more than 50% of the existing impervious area, stormwater from the entire project area is required to be treated.

Pollutants of concern anticipated for the project are sediment (TSS and Turbidity), Nutrients, Pesticides, Organic Materials/Oxygen Demanding Substances, Oil and Grease, Organics Associated with Petroleum, Bacteria and Viruses, and Trash and Debris.

The project area disturbs a total of 6.64 acres. Pre and post construction impervious and pervious areas are summarized in the table below.

	Impervious Area	Pervious Area
	(acres)	(acres)
Existing Condition	6.10	0.54
Proposed Condition	5.82	0.82

Section 3.1 of the Ventura County Technical Guidance Manual lists several conditions where a project can be subjected to infiltration BMPs. One of these conditions specifies a minimum infiltration rate of 0.5 in/hr. Per percolation tests performed on site, the measured infiltration rate is 0.07 in/hr and the design infiltration rate is 0.02 in/hr. Therefore, infiltration is not feasible onsite. See Appendix C for geotechnical report and percolation test results.

Since infiltration is infeasible, biofiltration will be used to treat the stormwater. With biofiltration, the project is required to the treat the Stormwater Quality Design Flow, or SQDF.

The Stormwater Quality Design Flow, SQDF, was calculated using Method 1 (runoff produced by 0.2 inches per hour rainfall intensity) per the technical guidance manual. The time of concentration for the 50-year storm is 17 minutes and flow-based biofiltration BMP design intensity for 150% has been applied. See calculations below.

See Appendix G for VenturaTC calculator results for post-development 50-year storm.



architecture | planning | interiors | branding | civil

Determine Water Quali	ty Design Flow		
1-1. Enter watershed area	A =	6.64	acres
1-2. Enter rainfall intensity (in/hr) (0.2in/hr) Table 2.1, with tc=17 minutes, i=0.268	i =	0.268	in/hr
1-3. Enter impervious fraction, <i>imp</i>	imp =	0.8765	
1-4. Determine pervious runoff coefficient using Table E-1, $C_p$	$C_p =$	0.05	(Soil Type 5)
1-5. Calculate the runoff coefficient, $C = 0.95*imp + C_p(1-imp)$	C =	0.839	
1-6. Calculate the water quality design flow (cfs), $SQDF = CiA$ Note: 1 acre-in/hr = 1.0083 cfs	SQDF =	1.49 acre in/hr or 1.51 cfs	

To treat SQDF, the three modular wetland systems will be installed on site. Modular wetland systems A-1, A-2, and A-3 will treat 0.56, 0.32, and 0.63 CFS of runoff, respectively. Prior to the biofiltration systems, runoff will be pretreated using catch basin filters at each inlet. See Appendix D for the LID plans identifying the LID drainage boundaries. See Appendix B for modular wetland system and full capture filter details and sizing information.

Due to the fall that exists across the site, and the invert elevation of the existing 18" storm drain and catch basin, a pump will be required to empty discharge the flow through the biofilters. Due to the depth of the biofiltration outlets and the join inverts, there is no way to get stormwater to flow by gravity from the site. A pump will be installed after the biofiltration systems to raise the flow above the existing catch basin that the site currently discharges to. After the pump, the stormwater will gravity flow off of the site.

The pump will only be required for the low flows that are required to be treated. High flows, beyond what is required to be treated, will be diverted prior to the biofiltration systems. The inverts of the high flow storm drain lines will allow them to discharge from the site via gravity flow and connection in the existing catch basin. See Appendix B for pump details and sizing information.

See Appendix D for LID and Grading Plans.

The VenturaTC calculator was used to calculate the runoffs for the existing and proposed condition. Pre and post construction runoffs are summarized in the table below.

	10-year storm (CFS)	25-year storm (CFS)	50-year storm (CFS)
Existing Condition	11.31	14.36	17.18
Proposed Condition	7.57	9.69	11.63



Flows discharging from the site and into the public storm drain are required to be limited to the existing 10-year storm flow rate, 11.31 CFS. Pipe sizing and orifice control will be used to limit the flows discharging the site to 11.31 CFS.

See Appendix G for VenturaTC calculator results for the pre and post development storm events. To control the discharge flow, an orifice will be sized to ensure that the maximum flow rate that enters the public system is 11.31 CFS.

### VI. Conclusions

The proposed development will have storm drain and water quality facilities to treat the required amount of stormwater and to mitigate the impact on existing downstream facilities.


For stormwater treatment, three (3) Modular wetland systems will be installed to treat the SQDF. The treated water will then need to be pumped from the site in order to join the catch basin at the southeast corner of Lawrence Drive and Corporate Center Drive. High flows that bypass treatment will be able to gravity flow from the site.

To mitigate downstream impacts, the site cannot discharge flows greater than the existing 10-yr flow rate. Pipe sizes and orifices will be implemented on site and sized to limit the stormwater discharge.

The project has been designed to comply with all requirements of the Ventura County Technical Guidance Manual for Stormwater Quality Control Measures.



## **Appendix A – Vicinity Map**



### LEGAL DESCRIPTION:

REAL PROPERTY IN THE CITY OFTHOUSAND OAKS, COUNTY OFVENTURA, STATE OF CALIFORNIA, DESCRIBED AS FOLLOWS:

PARCELS 1, 2 AND 3 OF PARCEL MAP NO. 4013, IN THE CITY OF THOUSAND OAKS, COUNTY OF VENTURA, STATE OF CALIFORNIA, AS PER MAP FILED IN BOOK 41, PAGES 13 TO 15 INCLUSIVE OF PARCEL MAPS, IN THE OFFICE OF THE COUNTY RECORDER OF SAID COUNTY, AS MAY HAVE BEEN AMENDED BY THAT CERTIFICATE OF CORRECTION EXECUTED BY JAMES C. ROACH, DATED JANUARY 08, 1987, RECORDED ON JANUARY 21, 1987 AS INSTRUMENT NO. 1987–8920 OF OFFICIAL RECORDS.


EXCEPT ALL OIL, GAS AND HYDROCARBON SUBSTANCES IN, UNDER AND UPON SAID LAND, WITHOUT THE RIGHT TO DRILL, DIG OR MINE THROUGH THE SURFACE OF SAID LAND THEREFOR, AND WITHOUT THE RIGHT TO ENTER OR ENCROACH UPON ANY PORTION OF SAID LAND LYING WITHIN 500 FEET OF THE SURFACE, RECORDED IN BOOK 1592, PAGE 511, RE—RECORDED BOOK 1712, PAGE 32, JANUARY 30, 1958 IN BOOK 1586, PAGE 229, ALL OF OFFICIAL RECORDS.


ALSO EXCEPT ALL SURFACE AND UNDERGROUND WATER AND WATER RIGHTS IN, ON AND UNDER SAID LAND, AS GRANTED TO RANCHO CONEJO MUTUAL WATER CO., IN DEED RECORDED OCTOBER 6, 1959, IN BOOK 1784 PAGE 393, OF OFFICIAL RECORDS, AND RE-RECORDED ON DECEMBER 17, 1959 IN BOOK 1808 PAGE 175, OF OFFICIAL RECORDS.

APN: 667-0-172-015 (AFFECTS: PARCEL 1), 667-0-172-025 (AFFECTS: PARCEL 2) 667-0-172-035 (AFFECTS: PARCEL 3)



## **Appendix B – BMP Information**






### **INSTALLATION NOTES**

- CONTRACTOR TO PROVIDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS REQUIRED TO OFFLOAD AND INSTALL THE SYSTEM AND APPURTENANCES IN ACCORDANCE WITH THIS DRAWING AND THE MANUFACTURERS SPECIFICATIONS, UNLESS OTHERWISE STATED IN MANUFACTURERS CONTRACT.
- 2. UNIT MUST BE INSTALLED ON LEVEL BASE. MANUFACTURER
  RECOMMENDS A MINIMUM 6" LEVEL ROCK BASE UNLESS SPECIFIED BY
  THE PROJECT ENGINEER. CONTRACTOR IS RESPONSIBLE TO VERIFY
  PROJECT ENGINEERS RECOMMENDED BASE SPECIFICATIONS.
- 4. CONTRACTOR TO SUPPLY AND INSTALL ALL EXTERNAL CONNECTING IE IN PIPES. ALL PIPES MUST BE FLUSH WITH INSIDE SURFACE OF CONCRETE. (PIPES CANNOT INTRUDE BEYOND FLUSH). INVERT OF OUTFLOW PIPE MUST BE FLUSH WITH DISCHARGE CHAMBER FLOOR. ALL PIPES SHALL BE SEALED WATER TIGHT PER MANUFACTURERS STANDARD CONNECTION DETAIL.
- 5. CONTRACTOR RESPONSIBLE FOR INSTALLATION OF ALL RISERS, MANHOLES, AND HATCHES. CONTRACTOR TO GROUT ALL MANHOLES AND HATCHES TO MATCH FINISHED SURFACE UNLESS SPECIFIED OTHERWISE.
- 6. VEGETATION SUPPLIED AND INSTALLED BY OTHERS. ALL UNITS WITH VEGETATION MUST HAVE DRIP OR SPRAY IRRIGATION SUPPLIED AND INSTALLED BY OTHERS.
- 7. CONTRACTOR RESPONSIBLE FOR CONTACTING BIO CLEAN FOR ACTIVATION OF UNIT. MANUFACTURERS WARRANTY IS VOID WITH OUT PROPER ACTIVATION BY A BIO CLEAN REPRESENTATIVE.

### GENERAL NOTES

- 1. MANUFACTURER TO PROVIDE ALL MATERIALS UNLESS OTHERWISE NOTED.
- ALL DIMENSIONS, ELEVATIONS, SPECIFICATIONS AND CAPACITIES ARE SUBJECT TO CHANGE. FOR PROJECT SPECIFIC DRAWINGS DETAILING EXACT DIMENSIONS, WEIGHTS AND ACCESSORIES PLEASE CONTACT BIO CLEAN.



THIS PRODUCT MAY BE PROTECTED BY ONE OR MORE OF 16,7473, 30,30,316, RELIER FOREIGN FRHISTS OR

### PROPRIETARY AND CONFIDENTIAL:

THE INFORMATION CONTAINED IN THIS DOCUMENT IS THE SOLE PROPERTY OF FORTERRA AND ITS COMPANIES. THIS DOCUMENT, FOR ANY PART THEREOF, MAY BE USED, REPRODUCED OR MODIFIED IN ANY MANNER WITH OUT THE WRITTEN CONSENT OF FORTERRA.





MWS-L-8-24-V STORMWATER BIOFILTRATION SYSTEM STANDARD DETAIL

OPERATING HEAD (FT)

PRETREATMENT LOADING RATE (GPM/SF)
WETLAND MEDIA LOADING RATE (GPM/SF)


	SITE SPEC	IFIC DATA	
PROJECT NUMBE	T.R		
PROJECT NAME			
PROJECT LOCATI	ON		
STRUCTURE ID			
	TREATMENT	REQUIRED	
VOLUME B	ASED (CF)	FLOW BAS	ED (CFS)
N,	/A		
PEAK BYPASS R	EQUIRED (CFS) -	IF APPLICABLE	
PIPE DATA	I.E.	MATERIAL	DIAMETER
INLET PIPE 1			
INLET PIPE 2			
OUTLET PIPE			
	PRETREATMENT	BIOFILTRATION	DISCHARGE
RIM ELEVATION			
SURFACE LOAD			
FRAME & COVER	2EA Ø30"		ø24"






### **INSTALLATION NOTES**

- 1. CONTRACTOR TO PROVIDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS REQUIRED TO OFFLOAD AND INSTALL THE SYSTEM AND APPURTENANCES IN ACCORDANCE WITH THIS DRAWING AND THE MANUFACTURERS SPECIFICATIONS, UNLESS OTHERWISE STATED IN MANUFACTURERS CONTRACT.
- 2. UNIT MUST BE INSTALLED ON LEVEL BASE. MANUFACTURER
  RECOMMENDS A MINIMUM 6" LEVEL ROCK BASE UNLESS SPECIFIED BY
  THE PROJECT ENGINEER. CONTRACTOR IS RESPONSIBLE TO VERIFY
  PROJECT ENGINEERS RECOMMENDED BASE SPECIFICATIONS.
- 4. CONTRACTOR TO SUPPLY AND INSTALL ALL EXTERNAL CONNECTING PIPES. ALL PIPES MUST BE FLUSH WITH INSIDE SURFACE OF CONCRETE. (PIPES CANNOT INTRUDE BEYOND FLUSH). INVERT OF OUTFLOW PIPE MUST BE FLUSH WITH DISCHARGE CHAMBER FLOOR. ALL PIPES SHALL BE SEALED WATER TIGHT PER MANUFACTURERS STANDARD CONNECTION DETAIL.
- 5. CONTRACTOR RESPONSIBLE FOR INSTALLATION OF ALL RISERS, MANHOLES, AND HATCHES. CONTRACTOR TO GROUT ALL MANHOLES AND HATCHES TO MATCH FINISHED SURFACE UNLESS SPECIFIED OTHERWISE.
- 6. VEGETATION SUPPLIED AND INSTALLED BY OTHERS. ALL UNITS WITH VEGETATION MUST HAVE DRIP OR SPRAY IRRIGATION SUPPLIED AND INSTALLED BY OTHERS.
- 7. CONTRACTOR RESPONSIBLE FOR CONTACTING BIO CLEAN FOR ACTIVATION OF UNIT. MANUFACTURERS WARRANTY IS VOID WITH OUT PROPER ACTIVATION BY A BIO CLEAN REPRESENTATIVE.





WETLAND MEDIA LOADING RATE (GPM/SF)	
PRETREATMENT LOADING RATE (GPM/SF)	
OPERATING HEAD (FT)	
TREATMENT FLOW (CFS)	

### **GENERAL NOTES**

- 1. MANUFACTURER TO PROVIDE ALL MATERIALS UNLESS OTHERWISE NOTED.
- ALL DIMENSIONS, ELEVATIONS, SPECIFICATIONS AND CAPACITIES ARE SUBJECT TO CHANGE. FOR PROJECT SPECIFIC DRAWINGS DETAILING EXACT DIMENSIONS, WEIGHTS AND ACCESSORIES PLEASE CONTACT BIO CLEAN.





PROPRIETARY AND CONFIDENTIAL:

THE INFORMATION CONTAINED IN THIS DOCUMENT IS THE SOLE PROPERTY OF FORTERRA AND ITS COMPANIES. THIS DOCUMENT, FOR ANY PART THEREOF, MAY BE USED, REPRODUCED OR MODIFIED IN ANY MANNER WITH OUT THE WRITTEN CONSENT OF FORTERRA.



MWS-L-8-16-V STORMWATER BIOFILTRATION SYSTEM STANDARD DETAIL






### **INSTALLATION NOTES**

- CONTRACTOR TO PROVIDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS REQUIRED TO OFFLOAD AND INSTALL THE SYSTEM AND APPURTENANCES IN ACCORDANCE WITH THIS DRAWING AND THE MANUFACTURERS SPECIFICATIONS, UNLESS OTHERWISE STATED IN MANUFACTURERS CONTRACT.
- 2. UNIT MUST BE INSTALLED ON LEVEL BASE. MANUFACTURER
  RECOMMENDS A MINIMUM 6" LEVEL ROCK BASE UNLESS SPECIFIED BY
  THE PROJECT ENGINEER. CONTRACTOR IS RESPONSIBLE TO VERIFY
  PROJECT ENGINEERS RECOMMENDED BASE SPECIFICATIONS.
- 4. CONTRACTOR TO SUPPLY AND INSTALL ALL EXTERNAL CONNECTING IE IN PIPES. ALL PIPES MUST BE FLUSH WITH INSIDE SURFACE OF CONCRETE. (PIPES CANNOT INTRUDE BEYOND FLUSH). INVERT OF OUTFLOW PIPE MUST BE FLUSH WITH DISCHARGE CHAMBER FLOOR. ALL PIPES SHALL BE SEALED WATER TIGHT PER MANUFACTURERS STANDARD CONNECTION DETAIL.
- 5. CONTRACTOR RESPONSIBLE FOR INSTALLATION OF ALL RISERS, MANHOLES, AND HATCHES. CONTRACTOR TO GROUT ALL MANHOLES AND HATCHES TO MATCH FINISHED SURFACE UNLESS SPECIFIED OTHERWISE.
- 6. VEGETATION SUPPLIED AND INSTALLED BY OTHERS. ALL UNITS WITH VEGETATION MUST HAVE DRIP OR SPRAY IRRIGATION SUPPLIED AND INSTALLED BY OTHERS.
- 7. CONTRACTOR RESPONSIBLE FOR CONTACTING BIO CLEAN FOR ACTIVATION OF UNIT. MANUFACTURERS WARRANTY IS VOID WITH OUT PROPER ACTIVATION BY A BIO CLEAN REPRESENTATIVE.

### GENERAL NOTES

- 1. MANUFACTURER TO PROVIDE ALL MATERIALS UNLESS OTHERWISE NOTED.
- ALL DIMENSIONS, ELEVATIONS, SPECIFICATIONS AND CAPACITIES ARE SUBJECT TO CHANGE. FOR PROJECT SPECIFIC DRAWINGS DETAILING EXACT DIMENSIONS, WEIGHTS AND ACCESSORIES PLEASE CONTACT BIO CLEAN.



THIS PRODUCT MAY BE PROTECTED BY ONE OR MORE OF 16,7473, 30,30,316, RELIER FOREIGN FRHISTS OR

### PROPRIETARY AND CONFIDENTIAL:

THE INFORMATION CONTAINED IN THIS DOCUMENT IS THE SOLE PROPERTY OF FORTERRA AND ITS COMPANIES. THIS DOCUMENT, FOR ANY PART THEREOF, MAY BE USED, REPRODUCED OR MODIFIED IN ANY MANNER WITH OUT THE WRITTEN CONSENT OF FORTERRA.



MWS-L-8-24-V STORMWATER BIOFILTRATION SYSTEM STANDARD DETAIL

OPERATING HEAD (FT)

PRETREATMENT LOADING RATE (GPM/SF)
WETLAND MEDIA LOADING RATE (GPM/SF)

### PACKAGED PUMP LIFT STATION LAX022-0077 1300 LAWRENCE DR. THOUSAND OAKS, CA. 91320

Furnish and install complete pre-packaged duplex Lift Station model #PSI-WAR081622 as manufactured by Pacific Southwest Industries (national phone # 800-

This pre-packaged Lift Station shall incorporate a quick removal system manufactured by the pump manufacturer. The pump(s) shall be guided to the discharge base elbow by a single or double guide rail and shall be stainless steel and shall extend from the discharge base elbow to the upper guide bracket mounted on 1-5/8" x 1-5/8" channel strut just below the basin cover. Stainless steel lifting chain or cable shall be supplied and properly installed to remove the pump from the wet well. The internal discharge piping shall be completely pre-plumbed with pressure rated schedule 40 or 80 PVC pipe as indicated and extend 12" beyond the wet well and valve vault side wall for contractor connection to the force main piping. The pump(s) discharge piping shall have a check and ball valve installed on each pump discharge. The Lift Station shall include control panel and level control floats. The control panel shall be suitable for surface mounting or free standing on a leg kit if the site conditions require it.

Furnish and install Tsurumi, VANC'S series submersible pump(s). Each unit shall be shall be designed to pump waste water, sewage or effluent containing 1.5-inch (40mm) diameter solids without damage during operation. The pump(s) shall be designed so that the shaft power required (BHP) / (kW) shall not exceed the motor rated output throughout the entire operating range of the pump performance curve. A two-year warranty "out of the box" shall be standard.

### **MATERIALS OF CONSTRUCTION:**

Construction of major parts of the pumping unit(s) including pump casing, impeller, motor head cover and intermediate brackets shall be manufactured from recyclable, application appropriate resins. The need for a protective coating shall not be required. All exposed fasteners shall be stainless steel and shall have stainless mating anchors integrally cast into the mating part. All units shall be furnished with a NPT discharge companion flange. Impellers shall be of the multivane, semi-vortex, solids handling design and shall be slip fit to the shaft. The motor shaft shall be machined to provide a positive drive of the impeller. The pump casing shall incorporate an air relief valve.

### **MECHANICAL SEAL:**

All units shall be furnished with a dual inside mechanical shaft seal located completely out of the pumpage, running in a separate oil filled chamber. Units shall be fitted with a device that shall provide positive lubrication of top mechanical seal, (down to one third of the standard oil level). The device shall not consume any additional electrical power. Units shall have silicon carbide mechanical seal faces. Mechanical seal hardware shall be stainless steel

Motor(s) shall have a 1.15 service factor and shall be rated for 10 starts per hour. Motor(s) shall be air filled, copper wound, class E insulated with built-in thermal protection. Motor shaft shall be 403 stainless steel and shall be supported by two permanently lubricated, high temperature ball bearings, with a B-10 life rating at best efficiency point of 60,000 hours. The bearings shall be single row, double shielded, C3, deep groove type ball bearings. Bearing seats shall be rolled carbon steel or aluminum die casting. Motor housing shall be 304 stainless steel. Motors shall be suitable variable speed applications, utilizing a properly sized variable frequency drive.

POWER CABLE AND CABLE ENTRANCE:

The pump power cable shall be suitable for submersible pump applications. The cable entrance shall incorporate built in strain relief, a one-piece, three-way process and the strain relief. mechanical compression seal with a fatigue reducing cable boot. The cable entrance assembly shall contain an anti-wicking block to eliminate water incursion into the motor due to Capillary wicking should the power cable be accidentally damaged.

### **QUICK REMOVAL SYSTEM:**

The pumping unit(s) shall be equipped with quick removal system (QRS). The construction shall be such that the pump(s) will automatically connect to the discharge piping when lowered into place on the discharge connector. There shall be no need for personnel to enter the wet well to accomplish installation or removal of the pump(s). The pumping unit(s) shall be fitted with stainless steel lifting chain(s) of sufficient length and strength to permit the raising and lowering of the unit(s). The chain(s) shall be fastened at the top of the structure near the access opening. The need for a protective coating shall not be required. A sliding guide bracket shall be an integral part of the pumping unit and the pump casing shall have a machined connection with a bracket to connect with the discharge connection. Sealing of the pumping unit to the discharge connection shall be accomplished by a single linear downward motion of the pump with the entire weight of the pumping unit guided by a pawl, thereby wedging the pumping unit tightly against the discharge connector. No portion of the pump shall bear directly on the floor of the sump nor shall a rotary motion of the pump be required for sealing. All fasteners coming into contact with the pumpage shall be stainless steel. Two corrosion resistant guide pipes shall be furnished and installed for each pump to permit raising and lowering of the pump.

### FIBERGLASS WET WELL:

The fiberglass wet well with an anti-flotation flange shall have the proper diameter and depth below the lowest inlet to promote proper cycling while maintaining the rim at grade. The fiberglass wet well shall be manufactured using a process that is filament wound and or chopped spray. The wet well shall be constructed with a anti flotation flange. Lifting lugs shall be required for those wet wells 48 inches in diameter and larger for setting of the wet well. The laminate shall have a Barco hardness of at least 90% of the resin manufactures minimum specified hardness for cured resin on both the interior and exterior surfaces. The minimum wall thickness of the wet well shall not be less than 1/4". Stainless steel studs will be encapsulated in the bottom of the wet well to allow the mounting of the guick removal system. The top rim flange will be a minimum of 2" wide to allow for the installation of the pedestrian rated aluminum cover to the rim flange or shall be rimless if the cover is specified for H20 off street locations. The wet well shall be provided with "unseal" fittings that can be installed in the field to insure proper elevation of the inlet, vent, and electrical on the side of the wet well. The valve box will house 2 - swing check valves, and 2 - shut off valves.


The wet well cover shall always be gasketed and bolted to the rim flange of the fiber glass tank using 7/16" stainless steel hex head bolts unless the cover is to be in a H20 off street location. The type of material to be used for the cover shall be as indicated on this plan sheet.


### **DUPLEX ALTERNATING CONTROL PANEL:**

The duplex control panel, as a minimum, shall include the appropriate enclosure type for the environment it is to be installed in and should include the following: Motor starters, motor circuit protectors or variable frequency drives (VFD), pump run indicator(s), operation selector switch(es), high water alarm and light, silence switch, dry contact for alarm, numbered terminals for all incoming power, pump motor(s) and level controls. The control panel shall be UL listed 508 or 913.

The following options marked "x" shall be included and specific for this site.

			-		
NEMA 4X X NE	EMA 3R	LEG KIT	_ <b>ETM'</b> s	SEAL FAIL	THERMAL
CUTOUTS PH	ASE LOSS MO	NITOR	SOFT START	GENSET HO	OKUP
DOOR IN DOOR	DEAD FRONT	Γ THRO	DUGH DOOR	MAIN DISCON	INECT
TRANSDUCER OP	ERATED I	FLOAT BACK	(UP CUR	RENT CENSOR	AUTO
DIALER REDU	NDANT OFF _	INTRINS	ICALLY SAFE	SMART REL	AY WHICH
INCLUDES EXERCIS	SER, RUN COU	NT, ALARM	COUNT AND	FLOAT POSITION	٧X





D	Ts	UR	UMI	Pu	/IP (FR	P) SEM				ERIES GE & WAS			S	F		ORM <i>A</i> RVE	ANC
		MO	DEL		BORE	Е Н	ΙР	KW	RPM	SOLIDS	: DIA	LIQL	חוו	SG.	VISCO	OSITY	TEN
	80P		V)22.2	-61	3"/80m		3	2.2	3490	1.81"/46		Wat		1.0		3 cSt	60°F
			TYPE		PHAS	E V	/OLT/	AGE	AM	PERAGE	HZ	STA	RTING	METHO	DD	INS. C	LAS
Sem	-Vorte	x - Sev	wage & \	Vastewate	er 3	208-	-220/4	160/575	9.1-8	3.5/4.2/ <u>3.3</u>	60		Direct O	n Line		Е	Ξ
	CURV	/E No	).	DATE	PHAS	E \	/OLT/	AGE	AM	PERAGE	HZ	STA	RTING	METHO	DD	INS. C	LAS
		-		-	-		-			-	-		-			-	•
	TOTA	L HD.			J. J. J. J.		1 1					REMA	RKS:				
%	М.	Ft.		-  -  -  - 	_  _			- +			- 	165	CDI	1 @	24 (	06, T	. רו
	- 1				7-7-1-7-			- + - + -	 		    :	100	GPN	/I (W	21.0	00 1	וטו
	24 -	80 -										_					
	H					-					-						
	22																
	ł	70		1	TH-Q		- 1 - 1		<u> </u>					<u> </u>		L L	_
	20-					: i - i - d -	- i - i · - i - i ·	- <del>i</del> -   -	 		- 	1-:-:-	i - i - i -		- <del>+</del> - <del>+</del> -		
	1	60 -		-    -					+ - + - + -						- + - + -		-
	18-	00 .															
	4.0													<del>-</del> - <del>-</del> <del>-</del> - <del>-</del> - <del>-</del> - <del>-</del> <del>-</del>	-+-+-		
100 -	16	50 -												1-1-			
	14								 					I	- + - + -		-
90 -	'"]								L - L - L -					<u> </u>	- + - + -		
80 -	12 -	40		-    - 	-1111111111111-	1 1 1	1 1	- + - + -	+ - + - + - 				1 - 1 - 1 -	+ - + - +	-+-+-	F - F - F	-
70						·		- + - + -	L _ L _ L _ 			1		1 - 1 - 1 1 - 1 - 1	- + - + -		-
70 -	10-					·									- <del> </del> - <del> </del> - - ± - ± -		-
60 -	-	30 -	1 1	1 1			1 1	1		1 1 1			1 1	1 1	1 1	1 1	1
50 -	8 -								-   -   -    -   -   -   -						- + - + -		
	-			-    - -    -			- + - +	- + -   - - <del> </del> -   -	+ - + - + -			1-1-1-		+ - + - <del> </del> <del> </del> - <del> </del> <del> </del> - <del> </del> <del> </del> - <del> </del> <del> </del> - <del> </del> - <del> </del> <del> </del> - <del> </del>	$\begin{array}{cccccccccccccccccccccccccccccccccccc$		-     -
40 -	6 -	20						- +						+	- + - + -	<u> </u>	-
30 -					EFF.									1	- <del> </del> - <del> </del> - - 1 - 1 -		
_	4 -	4.0		-    -	E		- <del></del> - + -		+ - + - + -					-	+ - + -		- <del></del>
20 -	_	10 -													1		-
10 -	2 -					·	- + - + · 	- + - <b> </b> - - <del> </del> -   -	+ - + - + - 	 			<b>-</b> -	+ - + - <b>1</b>	- + - <del>1</del>	F F	-     -
_ , ]	_ [	<u> —</u> ი -												1 - 1		<u> </u>	-
-	S GPN	1 (	0	20	40	60	)	80	10	00 12	20	140	160	18	0	200	
	PACIT			<del></del>		<del></del>	• •	• •		<del></del>	<del></del>			• • • •	<del></del>		-
	√l³min.		.0	0.	1	0.2		0.3		0.4	0.5		0.6		0.7		8.0
SHA!	FT PO	WER BHP	<b>!</b> -	-   -		·	- + - <del>+</del> - - <del> </del> - <del> </del> -	- + -   -	+ - + - <del>-</del> -   + - <del>-</del> - <del>-</del> -	<del>-</del> - <del>-</del>	-     -	-   -   -   -	-   - <b> </b> -	+ - + - + - + - + - + - + - + - + - + -	- + - <del>+</del> - - <del>+</del> - <del>+</del> -	+	-
	$\neg$		<b> </b>			7-7-1	- <del>-</del> - <del>-</del> - <del>-</del>	- + -   -	T - T - T -   T - T - T -			1-:-::	<b>-</b> -	T - T - 1	- + - + -		
2.:	2 -	3.0		-  -	-		- + - +	- +	+-+-+-					+ - + -	-+-+-	+	- H -
2.	0 🖠								+					<del></del>			
1.8	8 -	2.5			TPOWE						-,		- 1 - 1 -				
1.0	<sub>3</sub> -		<u> </u>	SHAF			- + - + · - + - + ·		+ - + - + -					+ - + - 1	- + - + -		- <del> -</del> -
1.4	- 1	2.0															
	- 1								<del>-</del> - <del>-</del> - <del>-</del>					+ - + -	- + - + -		
1.3	<b>4</b> 1		L - L - L	-1					L _ L _ L _	L _ L _ L _		4	J - J - <b>I</b> -	1 - 1 - 1		L _ L _ L	_


LIFT STATION PROFILE & CALCULATIONS									
4" SCH 40 = 4.03 SCH 80 = 3.83									
4" PVC PIP	E	(QTY)	50	Х	1	FT	50 FT		
4" PVC 90 ELB	OW	(QTY)	2	Х	11	FT	22 FT		
4" PVC 45 BE	ND	(QTY)	2	X	5	FT	10 FT		
4" PVC TEE	<u>-</u>	(QTY)	0	X	21	FT	0 FT		
4" BALL VAL	VE	(QTY)	1	X	2.7	FT	2.7 FT		
4" CHECK VA	LVE	(QTY)	1	Х	22	FT	22 FT		
TOTAL EQUIVALENT LEN	IGTH					-	106.7 FT		
FRICTION LOSS PER 100	PER	100 FT							
FRICTION LOSS 4" 106.7 / 100 x 2.1 FT 2.22 FT							2.22 FT		
TOTAL DYNAMIC HEAD									
4" FRICTION LOSS 2.22 FT									
	STATIC	HEAD				+	19.64 FT		
PERFORMANCE	165 GPM	@ 21.86		FT TDI	I THROUG	6H 4" F	PVC LINE		

HAZEN-WILLIAMS EQU	JATION/HE	AD LOSS IN WATER PIPE	
(f) = 0.2083	$(100 / c)^{1.852}$	η <sup>1.852</sup> / dh <sup>4.8655</sup>	
C=	1	40 HDPE / PVC	
q=		165 GPM	
dh=	dh= 4'		
FRICTION LOSS PER	2.08		
Velocity (ft/s	s) =	4.60	

TATION DETAILS			STORM PU	
LAWRENCE DR. ND OAKS, CA. 91320				
			PSI Pacific Southwest Industries	
08/16/22 Scale: NTS	SLN		ENGINEERED- PUMPS/FLUID HANDLING & DISPOSAL SYSTEMS	
EM Sheet No.	t No.		18541 COLLIER AVE., LAKE ELSINORE, CA 92530 PH: 800 358-9095	
1 OF 1	F 1			

### BIO CLEAN FULL CAPTURE FILTER


### FOR USE IN GRATE INLETS




TOP VIEW

### NOTES:

- 1. ALL HARDWARE, FLANGE, FRAME, SCREENS SHALL BE STAINLESS STEEL
  2. HYDROCARBON BOOM SHALL BE 2" DIAMETER AND CONNECTED,
  MECHANICALLY TO THE FILTER FRAME WITH RAILS ALLOWING IT TO FLOAT
  ON THE WATER SURFACE REGARDLESS OF HEIGHT
  3. SEE PERFORMANCE REPORTS IN MANUFACTURES SPECIFICATIONS
  4. OTHER STANDARD AND CUSTOM MODEL SIZES AVAILABLE CONTACT
  BIO CLEAN FOR MORE INFORMATION.
  5. BASED ON 37% OPEN AREA.
  6. CONSIDERS A SAFETY FACTOR OF 2.0.
  7. CONSIDERS A LOCAL DEPRESSION PONDIING DEPTH OF 6 INCHES.
  8. STORAGE CAPACITY BASED ON THE BASKET HALF FULL.
  9. CONCRETE STRUCTURES SOLD SEPARATELY.





	MDDEL #	TREATMENT FLOW (CFS)	BYPASS FLOW (CFS)	SOLIDS STORAGE CAPACITY (CF)
	BID-GRATE-FULL 12-12-12	0.97	1.55	0.14
	BID-GRATE-FULL 18-18-12	1.86	3,68	0.35
•	BID-GRATE-FULL 26-26-12	2.78	4.83	0.60
	BID-GRATE-FULL 24-40-12	6.71	6.59	1.04
	BID-GRATE-FULL 26-26-24	9.49	4.83	1.80
۱.	BID-GRATE-FULL 24-40-24	13.53	6.59	3.12
	BID-GRATE-FULL 36-36-24	17.14	7.60	4.45

	DRAWING: BIO CLEAN GRA	TE INLET FILTER DETAILS	MEETS FULL CAPTURE	
	TYPICAL MODEL DETAIL WARRANTY: 1 YEAR MANUFACTURER'S		REQUIREMENTS	
			PRØJECT:	
	398 VIA EL CENTRO OCEANSIDE CA 92058		REVISIONS:	DATE:
			REVISIONS:	DATE:
	DATE: 10/12/17	SCALE: SF = 15	REVISIONS:	DATE:
	DRAFTER: M.C.P.	UNITS = INCHES	REVISIONS:	DATE:



A Forterra Company



# **Appendix C – Geotechnical Report and Percolation Test**